



SHINWA

Work Together

GENERAL CATALOG 2018.10~

Shinwa Rules Co., Ltd.



| ul. Złota 36 | 62-800 Kalisz | tel. 62 766 31 01 | www.jag-mar.pl | biuro@jag-mar.pl

SHINWA

Work Together

The words above are very important to us. They convey a crucial message: combine your strengths, come together, and perform as a single entity.

Our mission is to create measuring instruments and other products that are designed to help you and work together with you, on the job and in daily life.

The motto above serves as a constant reminder that we're here to listen to your ideas and work together with you.



Quantity of Packing Unit

The quantity listed is the packing unit per box. For the items with a case unit, the packing unit per case is listed in the parenthesis below the quantity.

The Difference Between Polish Finish and Hard Chrome Finish

Both are made of stainless steel, but the hard chrome finish model has a matte finish. This prevents the sun from causing glare on the scale, making it easier to read.

Shaku Scale

The shaku (尺) is a unit of length traditionally used in East Asian countries. 1shaku is equal to 10/33 meters (approximately 30.3 cm) in Japan. The shaku system has smaller units as following: 1shaku (尺)=10 sun (寸) =1,000 bu (分)=10,000 rin (厘)

P. 214 21. Parts List

P. 223 22. Japan Calibration Service System (JCSS)

P. 225 23. Etching


P. 226 24. Sheet Heaters

P. 227 25. Custom-Made Items

P. 228 26. Name Printing

P. 229 27. Index
Item Code →
Description

P. 251 28. Index
Description →
Item Code




P. 7 1. Carpenter's Squares
Carpenter's Square, HC Square Rigid, Large Square, Large Caliper, Dressmaking Square, Rafter Square



P. 26 2. Stainless Steel Rules/Machine Scale
Stainless Steel Rule, 6-Folding Stainless Steel Rule, Molding Rule, Precision Stainless Steel Rule



P. 37 3. Aluminum Rules
Aluminum Rule with Non-slip Pad, Aluminum Cutting Rule, Telescopic Measure, Shaku Measure



P. 44 4. Resin Folding Rules/Bamboo Rules
Folding Rule, Bamboo Rule



P. 46 5. Squares/Protractors
Japanese Try Square, Miter Gauge, Japanese Bevel, Try Square Aluminum Base



P. 53 6. Vernier Calipers/Micrometers
Vernier Caliper, Depth Gauge, Micrometer



P. 59 7. Tape Measures
Tape Measure, Flat Tape, Spring Tape Measure



P. 64 8. Surveying Products
Aluminum Leveling Rod, Construction Black Board



P. 80 9. Scales
Scale, Digital Scale, Spring Scale



P. 85 10. Levels
Level, Blue Slant, Water Level, Digital Level



P. 95 11. Lasers/Optical Equipment
Laser, Laser Range Finder, Auto Level



P. 114 12. Inklines/Chalklines/Plumbholders
Ink Line, Chalk Line, Plumb Holder



P. 131 13. Circular Saw Guides
Circular Saw Guide L Angle, Circular Saw Guide T-slide, Circular Saw Guide I Clamp, Circular Saw Guide Free Angle



P. 144 14. Construction Tools
Stud Finder, Measuring Instrument Set for Steel Fabrication, Log Scriber



P. 151 15. Industrial Tools
Scribing Needle, Caliper, Gauge, Counter, Inspection Mirror, Chuck Wrench



P. 163 16. Thermometers/Hygrometers/Environment Measuring Instruments
Thermometer, Hygrometer, Soil pH Meter, Lux Meters, UV Light Meter, Noise Meter



P. 186 17. Outdoor Products
Dry Compass, Map Measure



P. 189 18. Magnifying Glasses
Reading Glass, Power Magnifier, Sheet Magnifier, Binocular



P. 195 19. Drawing Tools
Rule, Erasing Shield, Template, Triangle Scale, Drawing Compass



P. 204 20. Magnets
Color Magnet, Pick-up, with Handle, Magnetic Sheet Mat

Key to the symbols

NEW New catalog items

JIS JIS mark

cm/shaku cm/shaku
(Upper side (or Front) metric/
Lower side (or Back) shaku)

shaku/cm shaku/cm
(Upper side (or Front) shaku/
Lower side (or Back) metric)

With non-slip pad

With red numbers

With grid scale

Vial with luminous sheet

With magnet

Thermometer/Hygrometer

Thermometer

Hygrometer

With hanging hole

Letters in English

Letters in Japanese

Japanese zodiac signs

With stopper

With direction arrow

Oil

With battery

With edge

Double-sided tape

Glass lens

Plastic lens

Packaging

S Shrink package

B Box

VH Vinyl package + header card

SP Sleeve package

B Bag

C Clear package

C Card

V Vinyl package

∅ No package

New Products

Laser Beam Level II 300 mm
with Magnet
[P. 93]



Tape Measure RIGHT GEAR
25-7.5 m/shaku
[P. 61]




Round Shape Vial
φ16 Blue 2 pc-pack
[P. 91]

Mini Level Revo
Clear Cube Model
[P. 90]




Large Square Polish Finish
60 x 30 cm with 8 Scales
[P. 21]



Carpenter's Square Flat Corner
White 1 shaku 5 sun
[P. 12]



Maximum and Minimum
Digital Thermometer D-10
Waterproof
[P. 171]




Inspection Scope B φ9
Wireless 3.5 Inch LCD
[P. 159]



Handy Ink Line Marker Pro Plus
Auto-rewind Sharp Line
Metal Blue
[P. 115]



Fiberglass Folding Rule
5-folding 1 m Black
[P. 45]



Construction White Board Mini
with Telescopic Arm
MCW 14 x 17 cm with Itemized
Magnetic Sheet
[P. 75]



Digital Thermo/Hygrometer
Home A with Clear Package
[P. 170]



Carpenter's Square Holder with Magnet
[P. 20]



Digital Moisture Meter for Wood with Maximum and Minimum Hold Function
[P. 146]

Laser ROBO X line-E Green
[P. 97]



Laser ROBO X line-E Red
[P. 97]



Vernier Caliper 450 mm
[P. 53]

Tripod with Handle B
[P. 113]




Tripod with Handle C
[P. 113]



Laser Range Finder L-Measure30 Metric/Shaku
[P. 111]



Wireless Thermometer with Remote Twin Probe A Maximum and Minimum External Antenna Type
[P. 173]




Circular Saw Guide L-Angle Plus Adjust 1 m/shaku
[P. 134]




Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 1 m/shaku
[P. 133]

Carpenter's Squares (P. 7)



Stainless Steel Rules/Machine Scale (P. 26) Aluminum Rules (P. 37) Resin, Bamboo Rules (P. 44)




Square/Protractors (P. 46) Vernier Calipers/Micrometers (P. 53) Tape Measures (P. 59)



Inklines/Chalklines/Plumbholders (P. 114)



Circular Saw Guides (P. 131)




Construction Tools (P. 144) Industrial Tools (P. 151)




*Not available in certain areas. Please contact us for details.

Surveying Products (P. 64) Scales (P. 80)



Levels (P. 85)



Lasers/Optical Equipment (P. 95)



*Not available in certain areas. Please contact us for details.

Thermometers/Hygrometers/ Environment Measuring Instruments (P. 163)



Outdoor Products (P. 186) Magnifying Glasses (P. 189)



Drawing Tools (P. 195) Magnets (P. 204)



1. Carpenter's Squares



The difference between Polish Finish and Hard Chrome Finish

Surface finish differs. The polish finish is regular stainless steel while the hard chrome type has been given a matte finish to prevent glare and give the scale high readability.

Carpenter's Square Thick Corner Hard Chrome Finish

Item Code	Front	Corner/Cross Section	Back
10030 10294			
10553 10561 10626			
10014			
10286			
10011 10012 10027			
10555 10556 10028			
34513			
34517			

Item Code	Description	Long Branch Width x Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10030	50 cm 12	520×15×1.4 (260)	91	4 960910 100305	10	
10294	30 cm 12	320×15×1.4 (160)	60	4 960910 102941		
10553	1 shaku 5 sun 12	485×15×1.4 (242.5)	86	4 960910 105539		
10561	1 shaku 6 sun 12	520×15×1.4 (260)	91	4 960910 105614		
10626	1 shaku 12	320×15×1.4 (160)	60	4 960910 106260		
10014	50 cm with Square Scale 12	520×15×1.4 (260)	91	4 960910 100145		
10286	30 cm with Square Scale 12	320×15×1.4 (160)	60	4 960910 102866		
10588	1 shaku 5 sun with Square Scale 12	485×15×1.4 (242.5)	86	4 960910 105881		
10596	1 shaku 6 sun with Square Scale 12	520×15×1.4 (260)	91	4 960910 105966		
10618	1 shaku with Square Scale 12	323×15×1.4 (161.5)	60	4 960910 106185		
10011	50 cm/1 shaku 5 sun 12	520×15×1.4 (260)	91	4 960910 100114		
10012	50 cm/1 shaku 6 sun 12	520×15×1.4 (260)	91	4 960910 100121		
10027	30 cm/1 shaku 12	320×15×1.4 (160)	60	4 960910 100275		
10555	1 shaku 5 sun/50 cm 12	520×15×1.4 (260)	91	4 960910 105553		
10556	1 shaku 6 sun/50 cm 12	520×15×1.4 (260)	91	4 960910 105560		
10028	1 shaku/30 cm 12	320×15×1.4 (160)	60	4 960910 100282		
34513	H-1475 20"/45 cm	520×15×1.4 (260)	91	4 960910 345133		
34517	H-1476 20" with Square Scale	520×15×1.4 (260)	60	4 960910 345171		

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens


Features

- Hard chrome finish (matte processed) on graduation to prevent glare and make it easy to see



Matte processed

- Easy-to-read, large scale marks
- Angled face prevents ink from bleeding while shape is designed to provide an easy grip



- Includes graduations for both metric and shaku, so each can be used as necessary
- Strong due to hardening process yet also has flexibility



Use

- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10030	10294	10553	10561
Scale on Front Side				
Outside	50 cm	30 cm	1 shaku 5 sun	1 shaku 6 sun
Inside				
Scale on Back Side				
Outside	25 cm	15 cm	7.5 sun	8 sun
Inside				
Shape of Corner	Thick			
Squareness	Less than 0.1 mm per 100 mm			
Length Tolerance	±0.2 mm			
Material	Stainless steel			

	10626	10014	10286	10588
Scale on Front Side				
Outside	1 shaku	50 cm	30 cm	1 shaku 5 sun
Inside				
Scale on Back Side				
Outside	5 sun	25 cm	15 cm	7.5 sun
Inside				
Shape of Corner	Thick			
Squareness	Less than 0.1 mm per 100 mm			
Length Tolerance	±0.2 mm			
Material	Stainless steel			

	10596	10618	10011	10012	10027
Scale on Front Side					
Outside	1 shaku 6 sun	1 shaku	50 cm	30 cm	
Inside					
Scale on Back Side					
Outside	8 sun	5 sun	25 cm	15 cm	
Inside					
Shape of Corner	Thick				
Squareness	Less than 0.1 mm per 100 mm				
Length Tolerance	±0.2 mm				
Material	Stainless steel				

	10555	10556	10028	34513	34517
Scale on Front Side					
Outside	1 shaku 5 sun	1 shaku 6 sun	1 shaku	20"	
Inside					
Scale on Back Side					
Outside	7.5 sun	8 sun	5 sun	10"	
Inside					
Shape of Corner	Thick				
Squareness	Less than 0.1 mm per 100 mm				
Length Tolerance	±0.2 mm				
Material	Stainless steel				

Carpenter's Squares
 Stainless Steel Rules / Machine Scale
 Aluminum Rules
 Resin Folding Squares / Protectors
 Vernier Calipers / Micrometers
 Tape Measures
 Surveying Products
 Scales
 Levels
 Lasers / Optical Equipment
 Inklines / Chalklines / Plumholders
 Circular Saw Guides
 Construction Tools
 Industrial Tools
 Thermometers / Hygrometers / Moisture Measuring Instruments
 Outdoor Products
 Magnifying Glasses
 Drawing Tools
 Magnets

Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale and Inside Scale

Item Code	Front	Corner/Cross Section	Back
10359			
10332			
10340			

Item Code	Description	Long Branch×Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10359	50 cm	520×15×1.4 (260)	91		10	
10332	1 shaku 5 sun	485×15×1.4 (242.5)	86			
10340	1 shaku 6 sun	520×15×1.4 (260)	91			

Refer to P. 2 about the shaku scale

Features

- Inner graduations based on the inner scale reference point are marked on short branch
- Hard chrome finish (matte processed) on graduation to prevent glare and make it easy to see
- Strong due to hardening process yet also has flexibility



Matte processed

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10359	10332	10340
Scale on Front Side			
Long Branch Outside	50 cm	1 shaku 5 sun	1 shaku 6 sun
Short Branch Inside	—	—	—
Scale on Back Side			
Long Branch Outside	25 cm	7.5 sun	8 sun
Short Branch Inside	23 cm	7 sun	7.5 sun
Scale on Front Side			
Long Branch Outside	—	SS	—
Short Branch Inside	CS MS	MS	MS
Scale on Back Side			
Long Branch Outside	25 cm	7.5 sun	8 sun
Short Branch Inside	—	CS	—
Shape of Corner	Thick		
Squareness	Less than 0.1 mm per 100 mm		
Length Tolerance	±0.2 mm		
Material	Stainless steel		

Carpenter's Square Thick Corner Hard Chrome Finish for Left-hander

Item Code	Front	Corner/Cross Section	Back
10677			
10650			
10669			

Item Code	Description	Long Branch×Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10677	50 cm with Square Scale	520×15×1.4 (260)	91		10	
10650	1 shaku 5 sun with Square Scale	485×15×1.4 (242.5)	86			
10669	1 shaku 6 sun with Square Scale	520×15×1.4 (260)	91			

Refer to P. 2 about the shaku scale

Features

- For left-handed users
- Hard chrome finish (matte processed) on graduation to prevent glare and make it easy to see
- Strong due to hardening process yet also has flexibility



Matte processed

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10677	10650	10669
Scale on Front Side			
Long Branch Outside	50 cm	1 shaku 5 sun	1 shaku 6 sun
Short Branch Inside	—	—	—
Scale on Back Side			
Long Branch Outside	25cm	7.5sun	8sun
Short Branch Inside	—	—	—
Scale on Front Side			
Long Branch Outside	—	SS	—
Short Branch Inside	CS MS	MS	MS
Scale on Back Side			
Long Branch Outside	25 cm	7.5 sun	8 sun
Short Branch Inside	—	CS	—
Shape of Corner	Thick		
Squareness	Less than 0.1 mm per 100 mm		
Length Tolerance	±0.2 mm		
Material	Stainless steel		

Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales

Item Code	Front	Corner/Cross Section	Back
10370			
10373			
10371			
10372			

Item Code	Description	Long Branch×Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10370	50 cm	520×15×1.4 (260)	91		10	
10373	50 cm with Square Scale	520×15×1.4 (260)	91			
10371	1 shaku 5 sun with Square Scale	485×15×1.4 (242.5)	86			
10372	1 shaku 6 sun with Square Scale	520×15×1.4 (260)	91			

Refer to P. 2 about the shaku scale

Features

- Inner graduations based on the outer scale reference point are marked on front side
- Hard chrome finish (matte processed) on graduation to prevent glare and make it easy to see
- Strong due to hardening process yet also has flexibility



Matte processed

Use

- For all types of inking, marking, and measuring right angles/length

Specifications





--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10370	10373	10371	10372
Scale on Front Side				
Long Branch Outside	50 cm	1 shaku 5 sun	1 shaku 6 sun	—
Short Branch Inside	45 cm	—	1 shaku	—
Scale on Back Side				
Long Branch Outside	25 cm	7.5 sun	8 sun	—
Short Branch Inside	20 cm	—	7 sun	—
Scale on Front Side				
Long Branch Outside	50 cm	SS	—	—
Short Branch Inside	MS	CS MS	MS	—
Scale on Back Side				
Long Branch Outside	25 cm	7.5 sun	8 sun	—
Short Branch Inside	—	CS	—	—
Shape of Corner	Thick			
Squareness	Less than 0.1 mm per 100 mm			
Length Tolerance	±0.2 mm			
Material	Stainless steel			

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Carpenter's Square Thick Corner Polish Finish

Item Code	Front	Corner/Cross Section	Back
11010			
11002			

Item Code	Description	Long Branch×Width×Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Package
11010	50 cm JIS 12	520×15×1.4 (260)	91	4 960910 110106	10	V
11002	50 cm with Square Scale JIS 12	520×15×1.4 (260)	91	4 960910 110021		

Features

- Leverages the luster of stainless
- Strong due to hardening process yet also has flexibility

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	11010	11002
Scale on front side	Outside 50 cm	—
	Inside —	—
Scale on back side	Outside 25 cm	—
	Inside —	—
Shape of Corner	Outside 50 cm	SS
	Inside —	CS MS
Squareness	Outside 25 cm	—
	Inside —	—
Length Tolerance	Less than 0.1 mm per 100 mm	
Material	Stainless steel	

Carpenter's Square Thick Corner Polish Finish Fluorescent

Item Code	Front	Corner/Cross Section	Back
11777			
11770			
11754 11762			

Item Code	Description	Long BranchxWidthxThickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
11777	50 cm JIS	520×15×1.4 (260)	91		10	
11770	50 cm with Square Scale JIS	520×15×1.4 (260)	91			
11754	1 shaku 5 sun with Square Scale	485×15×1.4 (242.5)	86			
11762	1 shaku 6 sun with Square Scale	520×15×1.4 (260)	91			

Refer to P. 2 about the shaku scale

Features

- Easy to read even in the dark
- Strong due to hardening process yet also has flexibility

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	11777	11770	11754	11762
Scale on front side	Outside 50 cm	1 shaku 5 sun	1 shaku 6 sun	—
	Inside —	—	—	—
Scale on back side	Outside 25 cm	7.5 sun	8 sun	—
	Inside —	—	—	—
Shape of Corner	Outside 50 cm	SS	—	—
	Inside —	CS MS	MS	—
Squareness	Outside 25 cm	7.5 sun	8 sun	—
	Inside —	—	CS	—
Length Tolerance	Less than 0.1 mm per 100 mm			
Material	Stainless steel			

Carpenter's Square Thick Corner Black Color

Item Code	Front	Corner/Cross Section	Back
10871			
10758			

Item Code	Description	Long Branch×Width×Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Package
10871	50 cm with Square Scale JIS 12	520×15×1.4 (260)	87	 4 960910 108714	10	
10758	1 shaku 5 sun with Square Scale 12	485×15×1.4 (242.5)	83	 4 960910 107588	10	

Refer to P. 2 about the shaku scale

Features

- Decorative gold graduation
- Luxury finish, great as a gift
- Strong due to hardening process yet also has flexibility



Luxurious black finish
+
Gold gilded graduation

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10871	10758
Scale on front side	Outside 50 cm	1 shaku 5 sun
	Inside —	—
Scale on back side	Outside 25 cm	7.5 sun
	Inside —	—
Shape of Corner	Outside 50 cm	SS
	Inside —	CS MS
Squareness	Outside 25 cm	7.5 sun
	Inside —	CS
Length Tolerance	Less than 0.1 mm per 100 mm	
Material	Stainless steel	

Carpenter's Square Flat Corner Hard Chrome Finish

Item Code	Front	Corner/Cross Section	Back
10640 10647			
10643 10646 10648			
10653			
10652			
10654 10655			
10657			
10638 10639 10642			
10644 10645 10649			

Item Code	Description	Long Branch×Width×Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
10640	50 cm	520×15×1.4 (260)	88		10	
10647	30 cm	320×15×1.4 (160)	56		10	
10643	1 shaku 5 sun	485×15×1.4 (242.5)	86		10	
10646	1 shaku 6 sun	520×15×1.4 (260)	88		10	
10648	1 shaku	320×15×1.4 (160)	56		10	
10653	50 cm with Square Scale	520×15×1.4 (260)	88		10	
10652	30 cm with Square Scale	320×15×1.4 (160)	56		10	
10654	1 shaku 5 sun with Square Scale	485×15×1.4 (242.5)	86		10	
10655	1 shaku 6 sun with Square Scale	520×15×1.4 (260)	88		10	
10657	1 shaku with Square Scale	323×15×1.4 (161.5)	56		10	
10638	50 cm/1 shaku 5 sun	520×15×1.4 (260)	88		10	
10639	50 cm/1 shaku 6 sun	520×15×1.4 (260)	88		10	
10642	30 cm/1 shaku	320×15×1.4 (160)	56		10	
10644	1 shaku 5 sun/50 cm	520×15×1.4 (260)	88		10	
10645	1 shaku 6 sun/50 cm	520×15×1.4 (260)	88		10	
10649	1 shaku/30 cm	320×15×1.4 (160)	56		10	

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens


Features

- Corner has the same thickness as the branches
- With inner graduations based on the outer scale reference point
- Hard chrome finish on entire surface (matte processed)



Matte processed

- Angled face prevents ink from bleeding while shape is designed to provide an easy grip



- Includes graduations for both metric and shaku, so each can be used as necessary
- Strong due to hardening process yet also has flexibility

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10640	10647	10643	10646
Scale on Front Side	Outside 50 cm	30 cm	1 shaku 5 sun	1 shaku 6 sun
	Inside 45 cm	25 cm	1 shaku	
Scale on Back Side	Outside 25 cm	15 cm	7.5 sun	8 sun
	Inside 20 cm	10 cm	7 sun	
Shape of Corner	Outside 50 cm	30 cm	1 shaku 5 sun	1 shaku 6 sun
	Inside 40 cm MS	20 cm MS	1 shaku MS	
Squareness	Outside 25 cm	15 cm	7.5 sun	8 sun
	Inside 20 cm	10 cm	7 sun	
Length Tolerance	±0.2 mm			
Material	Stainless steel			

	10648	10653	10652	10654
Scale on Front Side	Outside 1 shaku	50 cm	30 cm	1 shaku 5 sun
	Inside 7 sun	45 cm	25 cm	1 shaku
Scale on Back Side	Outside 5 sun	25 cm	15 cm	7.5 sun
	Inside 3 sun	20 cm	10 cm	7 sun
Shape of Corner	Outside 1 shaku	SS		
	Inside 7 sun MS	CS MS	CS	MS
Squareness	Outside 5 sun	25 cm	15 cm	7.5 sun
	Inside 3 sun	—		CS
Length Tolerance	±0.2 mm			
Material	Stainless steel			

	10655	10657	10638	10639
Scale on Front Side	Outside 1 shaku 6 sun	1 shaku	50 cm	
	Inside 1 shaku	7 sun	45 cm	
Scale on Back Side	Outside 8 sun	5 sun	25 cm	
	Inside 7 sun	3 sun	20 cm	
Shape of Corner	Outside SS	1 shaku 5 sun	1 shaku 6 sun	
	Inside MS	1 shaku	1 shaku MS	
Squareness	Outside 8 sun	5 sun	7.5 sun	8 sun
	Inside CS		7 sun	
Length Tolerance	±0.2 mm			
Material	Stainless steel			

	10642	10644	10645	10649
Scale on Front Side	Outside 30 cm	1 shaku 5 sun	1 shaku 6 sun	1 shaku
	Inside 25 cm	1 shaku	7 sun	
Scale on Back Side	Outside 15 cm	7.5 sun	8 sun	5 sun
	Inside 10 cm	7 sun	3 sun	
Shape of Corner	Outside 1 shaku	50 cm	30 cm	
	Inside 7 sun MS	40 cm MS	20 cm MS	
Squareness	Outside 5 sun	25 cm	15 cm	
	Inside 3 sun	20 cm	10 cm	
Length Tolerance	±0.2 mm			
Material	Stainless steel			

Carpenter's Square Flat Corner White

Item Code	Front	Corner/Cross Section	Back
11101 11100			
11108 11103 11102			
11109 11106 11104			
11110 11107 11105			

Item Code	Description	Long Branch Width x Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
11101	50 cm	520×15×1.4 (260)	105	4 960910 111011	10	
11100	30 cm	320×15×1.4 (160)	65	4 960910 111004	10	
11108	1 shaku 5 sun	485×15×1.4 (242.5)	100	4 960910 111080	10	
11103	1 shaku 6 sun	520×15×1.4 (260)	105	4 960910 111035	10	
11102	1 shaku	320×15×1.4 (160)	65	4 960910 111028	10	
11109	50 cm/1 shaku 5 sun	520×15×1.4 (260)	105	4 960910 111097	10	
11106	50 cm/1 shaku 6 sun	520×15×1.4 (260)	105	4 960910 111066	10	
11104	30 cm/1 shaku	320×15×1.4 (160)	65	4 960910 111042	10	
11110	1 shaku 5 sun/50 cm	520×15×1.4 (260)	105	4 960910 111103	10	
11107	1 shaku 6 sun/50 cm	520×15×1.4 (260)	105	4 960910 111073	10	
11105	1 shaku/30 cm	320×15×1.4 (160)	65	4 960910 111059	10	


Refer to P. 2 about the shaku scale

Features

● Easy-to-read black scale on white background



● Hard coating to prevent peeling



● Angled face prevents ink from bleeding while shape is designed to provide an easy grip
 ● Strong due to hardening process yet also has flexibility

Use

● For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

		11101	11100	11108	11103
Scale on front Side	Outside	50 cm	30 cm	1 shaku 5 sun	1 shaku 6 sun
	Inside	45 cm	30 cm	1 shaku 3 sun	
Scale on Back Side	Outside	25 cm	15 cm	7.5 sun	8 sun
	Inside	20 cm	10 cm	7 sun	
Scale on Back Side	Outside	50 cm	30 cm	1 shaku 5 sun	1 shaku 6 sun
	Inside	40 cm MS	20 cm MS	1 shaku 2 sun MS	1 shaku 3 sun MS
Scale on Back Side	Outside	25 cm	15 cm	7.5 sun	8 sun
	Inside	20 cm	10 cm	7 sun	
Shape of Corner		Flat			
Squareness		Less than 0.1 mm per 100 mm			
Length Tolerance		±0.4 mm	±0.3 mm	±0.4 mm	
Material		Stainless steel			

		11102	11109	11106	11104
Scale on front Side	Outside	1 shaku	50 cm		30 cm
	Inside	7 sun	45 cm		30 cm
Scale on Back Side	Outside	5 sun	25 cm		15 cm
	Inside	4 sun	20 cm		10 cm
Scale on front Side	Outside	1 shaku	1 shaku 5 sun	1 shaku 6 sun	1 shaku
	Inside	7 sun MS	1 shaku 2 sun MS	1 shaku 3 sun MS	7 sun MS
Scale on Back Side	Outside	5 sun	7.5 sun	8 sun	5 sun
	Inside	4 sun	7 sun		4 sun
Shape of Corner		Flat			
Squareness		Less than 0.1 mm per 100 mm			
Length Tolerance		±0.3 mm	±0.4 mm		±0.3 mm
Material		Stainless steel			

		11110	11107	11105
Scale on front Side	Outside	1 shaku 5 sun	1 shaku 6 sun	1 shaku
	Inside	1 shaku 3 sun	7 sun	
Scale on Back Side	Outside	7.5 sun	8 sun	5 sun
	Inside	7 sun		4 sun
Scale on front Side	Outside	50 cm		30 cm
	Inside	40 cm MS		20 cm MS
Scale on Back Side	Outside	25 cm		15 cm
	Inside	20 cm		10 cm
Shape of Corner		Flat		
Squareness		Less than 0.1 mm per 100 mm		
Length Tolerance		±0.4 mm		±0.3 mm
Material		Stainless steel		

Carpenter's Square High Quality Thick Corner Hard Chrome Finish

Item Code	Front	Corner/Cross Section	Back
10839 10876			
10847 10877 10855 10878			

Item Code	Description	Long Branch Width x Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10839	50 cm with Square Scale JIS	520×15×1.4 (260)	84	4 960910 108394	10	
10876	50 cm with Square Scale Flexible JIS	520×15×1.4 (260)	73	4 960910 108769	10	
10847	1 shaku 5 sun with Square Scale	485×15×1.4 (242.5)	80	4 960910 108479	10	
10877	1 shaku 5 sun with Square Scale Flexible	485×15×1.0 (242.5)	67	4 960910 108776	10	
10855	1 shaku 6 sun with Square Scale	520×15×1.0 (260)	84	4 960910 108554	10	
10878	1 shaku 6 sun with Square Scale Flexible	520×15×1.0 (260)	73	4 960910 108783	10	

Refer to P. 2 about the shaku scale

Features

● High-precision squareness
 ● Hand polished by master craftsmen
 ● Beautiful glossy finish on scale marks
 ● Packaged in high-quality raised fabric (10839/10847/10855)
 ● Thin and flexible (10876/10877/10878)
 ● Hard chrome finish (matte processed) on graduation to prevent glare and make it easy to see
 ● Angled face prevents ink from bleeding while shape is designed to provide an easy grip
 ● Strong due to hardening process yet also has flexibility



Use

● For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10839	10876	10847	10877	10855	10878
Scale on front side	Outside 50 cm	1 shaku 5 sun	1 shaku 6 sun			
	Inside 25 cm	7.5 sun	8 sun			
Scale on back side	Outside 25 cm	7.5 sun	8 sun			
	Inside 20 cm	10 cm	7 sun			
Shape of Corner Thick						
Squareness Less than 0.06 mm per 100 mm						
Length Tolerance ±0.2 mm						
Material Stainless steel						

Carpenter's Square High Quality Thin Corner Hard Chrome Finish

Item Code	Front	Corner/Cross Section	Back
10837			
10845			
10860			

Item Code	Description	Long Branch×Width×Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Package
10837	50 cm with Square Scale	520×15×1.4 (260)	80		10	
10845	1 shaku 5 sun with Square Scale	485×15×1.4 (242.5)	76		10	
10860	1 shaku 6 sun with Square Scale	520×15×1.4 (260)	80		10	

Refer to P. 2 about the shaku scale.

Features

- Finished squareness with high precision
- Individually hand polished by craftsmen
- Thin corner aids precision marking
- Glossy finish is beautifully applied on scale marks
- Packaged in high quality raised fabric
- Hard chrome finish on entire surface (matte processed)
- Angled face prevents ink from bleeding while shape is designed to provide an easy grip
- Strong due to hardening process yet also has flexibility

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10837	10845	10860
Scale on Front Side	Outside 50 cm	1 shaku 5 sun	1 shaku 6 sun
	Inside	—	—
Scale on Back Side	Outside 25 cm	7.5 sun	8 sun
	Inside	—	—
Shape of Corner	Outside	SS	
	Inside	CS/MS	MS
	Outside	25 cm	7.5 sun 8 sun
	Inside	—	CS
Squareness	Less than 0.06 mm per 100 mm		
Length Tolerance	±0.2 mm		
Material	Stainless steel		

Carpenter's Square Wide Hard Chrome Finish

Item Code	Front	Corner/Cross Section	Back
10405			
11487			
11481			
10421			
10450			
10451			
10424			
10456			
10464			
10414			

Item Code	Description	Long Branch×Width×Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Package
10405	50 cm with 6 Scales	520×20×2.0 (260)	240		10	
11487	50 cm with 4 Scales	520×20×2.0 (260)	240		10	
11481	50 cm with 8 Scales	520×20×2.0 (260)	240		10	
10450	50 cm with 8 Scales cm Notation	520×20×2.0 (260)	240		10	
10421	30 cm with 8 Scales	320×20×2.0 (160)	144		10	
10451	30 cm with 8 Scales cm Notation	320×20×2.0 (160)	144		10	
10424	15 cm with 8 Scales cm Notation	170×20×2.0 (85)	72.5		10	
10456	1 shaku 6 sun with 4 Scales	520×20×2.0 (260)	240		10	
10464	1 shaku with 4 Scales	320×20×2.0 (160)	144		10	
10414	50 cm/1 shaku 6 sun with 5 Scales	520×20×2.0 (260)	240		10	

Refer to P. 2 about the shaku scale

Features

- Heavy-duty
- Suitable for ironwork or engineering work
- Graduations marked on every edge (8-scale models)
- Strap hole on 10424, 10421, 10451
- Hard chrome finish on entire surface (matte processed)

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale


	10405	11487	11481	10450
Scale on Front Side	Outside 50 cm	—	50 cm	—
	Inside 45 cm	—	45 cm	—
Scale on Back Side	Outside 25 cm	—	25 cm	—
	Inside	—	20 cm	—
Shape of Corner	Outside 50 cm	—	50 cm	—
	Inside 45 cm	—	45 cm	—
Squareness	Outside 25 cm	—	25 cm	—
	Inside	—	20 cm	—
Squareness	Less than 0.1 mm per 100 mm			
Length Tolerance	±0.2 mm			
Material	Stainless steel			

	10421	10451	10424
Scale on Front Side	Outside 30 cm	15 cm	—
	Inside 25 cm	10 cm	—
Scale on Back Side	Outside 15 cm	7.5 cm	—
	Inside 10 cm	5 cm	—
Shape of Corner	Outside 30 cm	15 cm	—
	Inside 25 cm	10 cm	—
Squareness	Outside 15 cm	7.5 cm	—
	Inside 10 cm	5 cm	—
Squareness	Less than 0.1 mm per 100 mm		
Length Tolerance	±0.2 mm		
Material	Stainless steel		


	10456	10464	10414
Scale on Front Side	Outside 1 shaku 6 sun	1 shaku	50 cm
	Inside	—	45 cm
Scale on Back Side	Outside 8 sun	5 sun	25 cm
	Inside	—	—
Shape of Corner	Outside 1 shaku 6 sun	1 shaku	1 shaku 6 sun
	Inside	—	—
Squareness	Outside 8 sun	5 sun	8 sun
	Inside	—	—
Squareness	Less than 0.1 mm per 100 mm		
Length Tolerance	±0.2 mm		
Material	Stainless steel		

JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery cm/shaku (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Carpenter's Square Wide White



Item Code	Description	Long Branch×Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
11161	50 cm with 8 Scales	520×20×2.0 (260)	240	4 960910 111615	10	
11160	30 cm with 8 Scales	320×20×2.0 (160)	145	4 960910 111608	10	



Features

- Easy-to-read black scale on white background
- Hard coating to prevent peeling
- Heavy-duty
- Suitable for ironwork or engineering work
- Graduations marked on all 8 edges
- Strap hole on 11160


Use

- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale		
	11161	11160
Scale on Front Side	Outside	50 cm
	Inside	45 cm
	Outside	25 cm
	Inside	20 cm
Scale on Back Side	Outside	50 cm
	Inside	45 cm
	Outside	25 cm
	Inside	20 cm
Shape of Corner Flat		
Squariness Less than 0.1 mm per 100 mm		
Length Tolerance ±0.4 mm		
Material Stainless steel		

Carpenter's Square Wide Polish Finish



Item Code	Description	Long Branch×Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
11207	50 cm with 6 Scales	520×20×2.0 (260)	240	4 960910 112070	10	
11215	30 cm with 8 Scales	320×20×2.0 (160)	144	4 960910 112155	10	

Features

- Heavy-duty
- Suitable for ironwork or engineering work
- Graduations marked on every edge (8-scale models)
- Strap hole on 11215

Use


- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale		
	11207	11215
Scale on Front Side	Outside	50 cm
	Inside	45 cm
	Outside	25 cm
	Inside	20 cm
Scale on Back Side	Outside	50 cm
	Inside	45 cm
	Outside	25 cm
	Inside	20 cm
Shape of Corner Flat		
Squariness Less than 0.1 mm per 100 mm		
Length Tolerance ±0.2 mm		
Material Stainless steel		

Graduation rows on wide and large squares

- 4 types are available: 4-scale, 5-scale, 6-scale and 8-scale. Rows will differ due to the scale location on the long branch (long part) and the short branch (short part) of the carpenter's square.



- On squares with few scales the marks are larger for higher readability, while squares with many scales have many graduations for greater breadth of use.

Carpenter's Square Flat Hard Chrome Finish

Item Code	Front	Corner/Cross Section	Back
10032			
10297			
10007			
10592			
10595			
10620			
10008			
10016			
10590			
10598			
10044			
10033			
10047			
10037			
10045			
10046			
10048			
10038			

Item Code	Description	Long Branch Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10032	50 cm	520×15×1.0 (260)	87	4 960910 100329	10	
10297	30 cm	320×15×1.0 (160)	55	4 960910 102972		
10007	15 cm	160×15×1.0 (80)	26	4 960910 100077		
10592	1 shaku 5 sun	485×15×1.0 (242.5)	82	4 960910 105928		
10595	1 shaku 6 sun	520×15×1.0 (260)	87	4 960910 105959		
10620	1 shaku	320×15×1.0 (160)	55	4 960910 106208		
10008	5 sun	160×15×1.0 (80)	26	4 960910 100084		
10016	50 cm with Square Scale	520×15×1.0 (260)	87	4 960910 100169		
10590	1 shaku 5 sun with Square Scale	485×15×1.0 (242.5)	82	4 960910 105904		
10598	1 shaku 6 sun with Square Scale	520×15×1.0 (260)	87	4 960910 105980		
10044	50 cm/1 shaku 5 sun	520×15×1.0 (260)	87	4 960910 100442		
10033	50 cm/1 shaku 6 sun	520×15×1.0 (260)	87	4 960910 100336		
10047	30 cm/1 shaku	320×15×1.0 (160)	55	4 960910 100473		
10037	15 cm/5 sun	160×15×1.0 (80)	26	4 960910 100374		
10045	1 shaku 5 sun/50 cm	520×15×1.0 (260)	87	4 960910 100459		
10046	1 shaku 6 sun/50 cm	520×15×1.0 (260)	87	4 960910 100466		
10048	1 shaku/30 cm	320×15×1.0 (160)	55	4 960910 100480		
10038	5 sun/15 cm	160×15×1.0 (80)	26	4 960910 100381		

Refer to P. 2 about the shaku scale

JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery cm/shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

- Thin, flat surface makes it easy to use on smaller objects
- Includes inner graduations based on the outer scale reference point
- Hard chrome finish on entire surface (matte processed)



-Matte finish

- Strong due to hardening process yet also has flexibility

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

		10032	10297	10007	10592
Scale on Front Side	Outside	50 cm	30 cm	15 cm	1 shaku 5 sun
	Inside	45 cm	25 cm	10 cm	1 shaku
Scale on Back Side	Outside	25 cm	15 cm	7.5 cm	7.5 sun
	Inside	20 cm	10 cm	7 cm	7 sun
Shape of Corner	Outside	50 cm	30 cm	15 cm	1 shaku 5 sun
	Inside	40 cm	25 cm	10 cm	1 shaku
Squareness	Outside	25 cm	15 cm	7.5 cm	7.5 sun
	Inside	20 cm	10 cm	7 cm	7 sun
Length Tolerance		±0.2 mm			
Material		Stainless steel			

		10595	10620	10008	10016
Scale on Front Side	Outside	1 shaku 6 sun	1 shaku	5 sun	50 cm
	Inside	1 shaku	7 sun	3 sun	45 cm
Scale on Back Side	Outside	8 sun	5 sun	2.5 sun	25 cm
	Inside	7 sun	3 sun	2 sun	20 cm
Shape of Corner	Outside	1 shaku 6 sun	1 shaku	5 sun	SS
	Inside	1 shaku	7 sun	3 sun	CS MS
Squareness	Outside	8 sun	5 sun	2.5 sun	25 cm
	Inside	7 sun	3 sun	2 sun	—
Length Tolerance		±0.2 mm			
Material		Stainless steel			

		10590	10598	10044	10033
Scale on Front Side	Outside	1 shaku 5 sun	1 shaku 6 sun	50 cm	
	Inside	1 shaku		42 cm	
Scale on Back Side	Outside	7.5 sun	8 sun	25 cm	
	Inside	7 sun		20 cm	
Shape of Corner	Outside	SS		1 shaku 5 sun	1 shaku 6 sun
	Inside	MS		1 shaku	
Squareness	Outside	7.5 sun	8 sun	7.5 sun	8 sun
	Inside	CS		7 sun	
Length Tolerance		±0.2 mm			
Material		Stainless steel			

		10047	10037	10045
Scale on Front Side	Outside	30 cm	15 cm	1 shaku 5 sun
	Inside	25 cm	10 cm	1 shaku
Scale on Back Side	Outside	15 cm	7.5 cm	7.5 sun
	Inside	10 cm	7 cm	7 sun
Shape of Corner	Outside	1 shaku	5 sun	50 cm
	Inside	7 sun	3 sun	42 cm
Squareness	Outside	5 sun	2.5 sun	25 cm
	Inside	3 sun	2 sun	20 cm
Length Tolerance		±0.2 mm		
Material		Stainless steel		

		10046	10048	10038
Scale on Front Side	Outside	1 shaku 6 sun	1 shaku	5 sun
	Inside	1 shaku	7 sun	3 sun
Scale on Back Side	Outside	8 sun	5 sun	2.5 sun
	Inside	7 sun	3 sun	2 sun
Shape of Corner	Outside	50 cm	30 cm	15 cm
	Inside	40 cm	25 cm	10 cm
Squareness	Outside	25 cm	15 cm	7.5 cm
	Inside	20 cm	10 cm	7 cm
Length Tolerance		±0.2 mm		
Material		Stainless steel		

Carpenter's Square Flat White


Item Code	Front	Corner/Cross Section	Back
11172			
11171			
11170			
11175			
11176			
11174			
11173			
11181			
11183			
11179			
11177			
11182			
11184			
11180			
11178			

Item Code	Description	Long Branch/Width x Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
11172	50 cm	520×15×1.0 (260)	90	4 960910 111721	10	
11171	30 cm	320×15×1.0 (160)	54	4 960910 111714	10	
11170	15 cm	160×15×1.0 (80)	26	4 960910 111707	10	
11175	1 shaku 5 sun	485×15×1.0 (242.5)	85	4 960910 111752	10	
11176	1 shaku 6 sun	520×15×1.0 (260)	90	4 960910 111769	10	
11174	1 shaku	320×15×1.0 (160)	54	4 960910 111745	10	
11173	5 sun	160×15×1.0 (80)	26	4 960910 111738	10	
11181	50 cm/1 shaku 5 sun	520×15×1.0 (260)	90	4 960910 111813	10	
11183	50 cm/1 shaku 6 sun	520×15×1.0 (260)	90	4 960910 111837	10	
11179	30 cm/1 shaku	320×15×1.0 (160)	54	4 960910 111790	10	
11177	15 cm/5 sun	160×15×1.0 (80)	26	4 960910 111776	10	
11182	1 shaku 5 sun/50 cm	520×15×1.0 (260)	90	4 960910 111820	10	
11184	1 shaku 6 sun/50 cm	520×15×1.0 (260)	90	4 960910 111844	10	
11180	1 shaku/30 cm	320×15×1.0 (160)	54	4 960910 111806	10	
11178	5 sun/15 cm	160×15×1.0 (80)	26	4 960910 111783	10	

Refer to P. 2 about the shaku scale

Features

- Easy-to-read black scale on white background
- Hard coating to prevent peeling



Hard coating
Baked finish
Stainless steel

- Thin, flat surface makes it easy to use on smaller objects
- With inner graduations based on the outer scale reference point
- Rounded corners to protect clothing and pockets from damage



White

Hard chrome finish

- Has flexibility due to heat treatment

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale


	11172	11171	11170	11175
Scale on front side	Outside 50 cm	30 cm	15 cm	1 shaku 5 sun
	Inside 45 cm	30 cm	10 cm	1 shaku 3 sun
Scale on back side	Outside 25 cm	15 cm	7.5 cm	7.5 sun
	Inside 20 cm	10 cm	7 cm	7 sun
Shape of Corner	Outside 50 cm	30 cm	15 cm	1 shaku 5 sun
	Inside 45 cm	30 cm	10 cm	1 shaku 3 sun
Squareness	Outside 25 cm	15 cm	7.5 cm	7.5 sun
	Inside 20 cm	10 cm	7 cm	7 sun
Length Tolerance	±0.4 mm	±0.3 mm	±0.4 mm	
Material	Stainless steel			

	11176	11174	11173	11181
Scale on front side	Outside 1 shaku 6 sun	1 shaku	5 sun	50 cm
	Inside 1 shaku 3 sun	7 sun	3 sun	45 cm
Scale on back side	Outside 8 sun	5 sun	2.5 sun	25 cm
	Inside 7 sun	4 sun	2 sun	20 cm
Shape of Corner	Outside 1 shaku 6 sun	1 shaku	5 sun	1 shaku 5 sun
	Inside 1 shaku 3 sun	7 sun	3 sun	1 shaku 3 sun
Squareness	Outside 8 sun	5 sun	2.5 sun	7.5 sun
	Inside 7 sun	4 sun	2 sun	7 sun
Length Tolerance	±0.4 mm	±0.3 mm	±0.4 mm	
Material	Stainless steel			

	11183	11179	11177	11182
Scale on front side	Outside 50 cm	30 cm	15 cm	1 shaku 5 sun
	Inside 45 cm	30 cm	10 cm	1 shaku 3 sun
Scale on back side	Outside 25 cm	15 cm	7.5 cm	7.5 sun
	Inside 20 cm	10 cm	7 cm	7 sun
Shape of Corner	Outside 1 shaku 6 sun	1 shaku	5 sun	50 cm
	Inside 1 shaku 3 sun	7 sun	3 sun	45 cm
Squareness	Outside 8 sun	5 sun	2.5 sun	25 cm
	Inside 7 sun	4 sun	2 sun	20 cm
Length Tolerance	±0.4 mm	±0.3 mm	±0.4 mm	
Material	Stainless steel			

	11184	11180	11178
Scale on front side	Outside 1 shaku 6 sun	1 shaku	5 sun
	Inside 1 shaku 3 sun	7 sun	3 sun
Scale on back side	Outside 8 sun	5 sun	2.5 sun
	Inside 7 sun	4 sun	2 sun
Shape of Corner	Outside 50 cm	30 cm	15 cm
	Inside 45 cm	30 cm	10 cm
Squareness	Outside 25 cm	15 cm	7.5 cm
	Inside 20 cm	10 cm	7 cm
Length Tolerance	±0.4 mm	±0.3 mm	
Material	Stainless steel		

Carpenter's Square Wide and Flexible Hard Chrome Finish



Item Code	Description	Long Branch Width x Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10034	50 cm	520×20×1.0 (260)	115	4 960910 100343	10	
10600	1 shaku 6 sun	515×20×1.0 (258)	113	4 960910 106000	10	

Refer to P. 2 about the shaku scale

Features

- 1 mm-thickness, wide type
- Graduations starting from end face reference point lets you measure from both directions and even depth
- Thin, flat surface fits in tight places and makes it easy to mark
- Hard chrome finish on entire surface (matte processed)
- Strong due to hardening process yet also has flexibility



Use


- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

		10034	10600
Scale on Front Side	Long Branch Outside	50 cm	1 shaku 6 sun
	Inside	49 cm	1 shaku 6 sun
	Short Branch Outside	25 cm	8 sun
	Inside	23 cm	7.5 sun
Scale on Back Side	Long Branch Outside	50 cm	1 shaku 6 sun
	Inside	49 cm	1 shaku 6 sun
	Short Branch Outside	25 cm	8 sun
	Inside	23 cm	7.5 sun
Shape of Corner		Flat	
Squareness		Less than 0.1 mm per 100 mm	
Length Tolerance		±0.2 mm	
Material		Stainless steel	

Carpenter's Square for Two-by-Four Hard Chrome Finish



Item Code	Description	Long Branch Width x Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
10055	50 cm	520×19×1.0 (260)	115	4 960910 100558	10	
10056	1 shaku 5 sun	520×19×1.0 (260)	115	4 960910 100565	10	

Refer to P. 2 about the shaku scale

Features

- 19 mm width is suitable for two-by-four applications
- Incline graduation helps to find incline easily
A regular graduation is on the back (10055: 50 cm, 10056: 1 shaku 5 sun)
- Large and clear graduation letters
- Hard chrome finish on entire surface (matte processed)
- Strong due to hardening process yet also has flexibility



Use

- For all types of inking and measuring in two-by-four building


Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

		10055	10056
Scale on Front Side	Long Branch Outside	2×4	
	Inside	—	
	Short Branch Outside	25 cm incline	
	Inside	—	
Scale on Back Side	Long Branch Outside	50 cm	1 shaku 5 sun
	Inside	MS	
	Short Branch Outside	25 cm	7.5 sun
	Inside	—	
Shape of Corner		Flat	
Squareness		Less than 0.1 mm per 100 mm	
Length Tolerance		±0.2 mm	
Material		Stainless steel	


About 2x4 Graduations

2x4 graduations refer to the numbers often used when using 2x lumber, and the graduations can be used to quickly measure lumber of this size.



2x Lumber Dimensions

	2 × 4	2 × 6	2 × 8	2 × 10	2 × 12
Width	90	140	184	235	286
Width to Center	45	70	92	117.5	143
Thickness	38				
Thickness to Center	19				



JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

12 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Carpenter's Square Hard Chrome Finish with Magnet

Item Code	Front	Corner/Cross Section	Back
10175			
10181			
10445			
10425			
10435			

Item Code	Description	Long Branch×Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Package
10175	Flat Corner 50 cm	520×15×1.4 (260)	98		10	
10181	Flat Corner 1 shaku 6 sun	520×15×1.4 (260)	98		10	
10445	Wide 50 cm with 6 Scales	520×20×2.0 (260)	238		10	
10425	Wide 30 cm with 8 Scales	320×20×2.0 (160)	144		10	
10435	Wide 15 cm with 8 Scales cm Notation	170×20×2.0 (85)	72.5		10	

Refer to P. 2 about the shaku scale

Features

- Magnets prevent loss by sticking to the scaffolding
- Strap hole on 10425 and 10435
- Hard chrome finish on entire surface (matte processed)
- Strong due to hardening process yet also has flexibility (10175/10181)



Use

- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10175	10181
Scale on Front Side		
long Branch Outside	50 cm	1 shaku 6 sun
Inside	45 cm	1 shaku
Short Branch Outside	25 cm	8 sun
Inside	20 cm	7 sun
Scale on Back Side		
long Branch Outside	50 cm	1 shaku 6 sun
Inside	40 cm MS	1 shaku MS
Short Branch Outside	25 cm	8 sun
Inside	20 cm	7 sun
Shape of Corner	Flat	
Squareness	Less than 0.1 mm per 100 mm	
Length Tolerance	±0.2 mm	
Material	Stainless steel	

	10445	10425	10435
Scale on Front Side			
long Branch Outside	50 cm	30 cm	15 cm
Inside	45 cm	25 cm	10 cm
Short Branch Outside	25 cm	15 cm	7.5 cm
Inside	—	10 cm	5 cm
Scale on Back Side			
long Branch Outside	50 cm	30 cm	15 cm
Inside	45 cm	25 cm	10 cm
Short Branch Outside	25 cm	15 cm	7.5 cm
Inside	—	10 cm	5 cm
Shape of Corner	Flat		
Squareness	Less than 0.1 mm per 100 mm		
Length Tolerance	±0.2 mm		
Material	Stainless steel		

Carpenter's Square Rigid Hard Chrome Finish

Item Code	Front	Corner/Cross Section	Back
10634			
10545			
10510			
10529			
10511			

Item Code	Description	Long Branch×Width×Thickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Package
10634	30 cm	320×15×2.6 (160)	116		10	
10545	1 shaku	320×15×2.6 (160)	116		10	
10510	30 cm with Square Scale	320×15×2.6 (160)	116		10	
10529	1 shaku with Square Scale	320×15×2.6 (160)	116		10	
10511	30 cm/1 shaku	320×15×2.6 (160)	116		10	

Refer to P. 2 about the shaku scale

Features

- Thick and tough
- Small, handy mobile size
- Useful for finding right angles
- Hard chrome finish (matte processed) on graduation to prevent glare and make it easy to see
- Strong due to hardening process yet also has flexibility



Use

- For all types of inking, marking, and measuring right angles/length
- For production of fittings

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	10634	10545
Scale on Front Side		
long Branch Outside	30 cm	1 shaku
Inside	—	—
Short Branch Outside	15 cm	5 sun
Inside	—	—
Scale on Back Side		
long Branch Outside	30 cm	1 shaku
Inside	—	—
Short Branch Outside	15 cm	5 sun
Inside	—	—
Shape of Corner	Flat	
Squareness	Less than 0.1 mm per 100 mm	
Length Tolerance	±0.2 mm	
Material	Stainless steel	

	10510	10529	10511
Scale on Front Side			
long Branch Outside	30 cm	1 shaku	30 cm
Inside	—	—	—
Short Branch Outside	15 cm	5 sun	15 cm
Inside	—	—	—
Scale on Back Side			
long Branch Outside	SS	—	1 shaku
Inside	CS	—	—
Short Branch Outside	15 cm	5 sun	—
Inside	—	—	—
Shape of Corner	Flat		
Squareness	Less than 0.1 mm per 100 mm		
Length Tolerance	±0.2 mm		
Material	Stainless steel		

Small Square

Item Code	Front	Corner/Cross Section	Back
12130			
12017			
12325			
12114			
12435			
12416			
12476			
12101			
12102			
12103			
12104			

Item Code	Description	Long BranchxWidthxThickness (Short Branch)	Weight (g)	JAN Code	Packing Unit	Packaging
12130	Grooved Polish Finish 30 x 15 cm	330×15×1.1 (165)	57	4 960910 121300	10	
12017	Grooved Polish Finish 30 x 15 cm with Square Scale	330×15×1.1 (165)	57	4 960910 120174	10	
12325	Flat Polish Finish 30 x 15 cm	330×15×1.1 (163)	60	4 960910 123250	10	
12114	Flat Polish Finish 30 x 15 cm with Square Scale	330×15×1.1 (163)	60	4 960910 121140	10	
12435	Black 30 x 15 cm	330×15×1.3 (163)	67	4 960910 124356	10	
12416	Black 30 x 15 cm with Square Scale	330×15×1.3 (163)	67	4 960910 124165	10	
12476	White 30 x 15 cm with Square Scale	330×15×1.3 (163)	67	4 960910 124769	10	
12101	Polish Finish 10 x 5 cm	105×10×1.2 (55)	14	4 960910 121010	10 (100)	
12102	Polish Finish 3 x 1.5 sun	105×10×1.2 (55)	14	4 960910 121027	10 (100)	
12103	Polish Finish 15 x 7.5 cm	160×10×1.2 (80)	20	4 960910 121034	10 (60)	
12104	Polish Finish 5 x 2.5 sun	160×10×1.2 (80)	20	4 960910 121041	10 (60)	

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery cm/shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

【12130, 12017, 12325, 12114】

- Small, handy mobile size
- Stainless steel construction makes it strong and rust-resistant
- Etching + black chrome coating on graduations help them last long



Polish finish grooved



Polish finish

【12435, 12416, 12476】

- Small, handy mobile size
- Flat shape makes it easy to use on smaller objects
- White scale on black background, or black scale on white background makes scale and numbers easy to see



Black coating



White coating

【12101, 12102, 12103, 12104】

- Small, handy mobile size
- Stainless steel construction makes it strong and rust-resistant
- Convenient for simple marking and also as a rule

Polish finish
12101, 12102Polish finish
12103, 12104

Use

- For all types of inking, marking, and measuring right angles/length

Specifications

 --: No scale SS: Square scale CS: Circle scale
 MS: Mortise scale

	12130	12017	12325	12114
Scale on Front Side	Outside	30 cm		
	Inside	5 mm pitch 30 cm		
	Outside	15 cm		
	Inside	5 mm pitch 15 cm		
Scale on Back Side	Outside	30 cm		
	Inside	5 mm pitch 30 cm	SS	5 mm pitch 30 cm
	Outside	15 cm		
	Inside	5 mm pitch 15 cm	CS	5 mm pitch 15 cm
Shape of Corner	Flat			
Squareness	Less than 0.1 mm per 100 mm			
Length Tolerance	±0.2 mm			
Material	Stainless steel			

	12435	12416	12476
Scale on Front Side	Outside	30 cm	
	Inside	5 mm pitch 30 cm	
	Outside	15 cm	
	Inside	5 mm pitch 15 cm	
Scale on Back Side	Outside	30 cm	
	Inside	5 mm pitch 30 cm	SS
	Outside	15 cm	
	Inside	5 mm pitch 15 cm	CS
Shape of Corner	Flat		
Squareness	Less than 0.1 mm per 100 mm		
Length Tolerance	±0.3 mm		
Material	Iron		

	12101	12102	12103	12104
Scale on Front Side	Outside	10 cm	3 sun	15 cm
	Inside	—	1 cm pitch 15 cm	—
	Outside	5 cm	1.5 sun	7.5 cm
	Inside	—	1 cm pitch 7 cm	—
Scale on Back Side	Outside	10 cm	3 sun	15 cm
	Inside	1 cm pitch 10 cm	—	1 cm pitch 15 cm
	Outside	5 cm	1.5 sun	7.5 cm
	Inside	1 cm pitch 5 cm	—	1 cm pitch 7 cm
Shape of Corner	Flat			
Squareness	Less than 0.1 mm per 100 mm			
Length Tolerance	±0.2 mm			
Material	Stainless steel			

Holder

NEW



12427

Fastens with a click
Doesn't come off easily

Strong
neodymium
magnets

Easily attaches and
detaches while working



Features

- Easily attach and detach the square while working without shifting hands
- Uses a strong neodymium magnet so that the square fastens with a click and will not come off easily even crouching
- Features a belt holder that can be attached while wearing the belt
- With a hook hole for a safety cord. Square can be fitted into a holder with the safety cord attached (only for a square with a hole).
- Plate position can be changed according to square width

Use

- For carrying a square

Specifications

Attachable Belt Size	Width: Less than 50 mm Thickness: Less than 2.5 - 5 mm
Supported Square Size	Width: 10 mm, 15 mm, 20 mm Thickness: Less than 2 mm
Material	Body: ABS resin Magnet: Neodymium

Large Square

Item Code	Front	Corner/Cross Section	Back
63099			
63400			
63122			
63118			
63128			
63094			

Features

- Useful to measure and mark large objects such as building stone, lumber, and metal plates
- 63400 Hard chrome finish on entire surface (matte processed)



Use

- For all types of inking, marking, and measuring right angles/length

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale


	63099	63400	63122
Scale on Front Side	Outside	1 m	
	Inside		1 m
Scale on Back Side	Outside	60 cm	
	Inside		57 cm
Shape of Corner	Outside	1 m	
	Inside		1 m
Squareness	Outside	60 cm	
	Inside		57 cm
Length Tolerance	±0.5 mm		
Material	Stainless steel		

	63118	63128	63094
Scale on Front Side	Outside	1 m	3 shaku 3 sun
	Inside		1 m
Scale on Back Side	Outside	60 cm	2 shaku
	Inside		60 cm
Shape of Corner	Outside	1 m	3 shaku 3 sun
	Inside		1 m
Squareness	Outside	60 cm	2 shaku
	Inside		60 cm
Length Tolerance	±0.5 mm		
Material	Stainless steel		

Item Code	Description	Long Branch Width x Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
63099	Rigid Polish Finish 1 m x 60 cm	1,040×30×4.0 (630)	1,516	4 960910 630994	5	
63400	Hard Chrome Finish 1 m x 60 cm	1,040×35×2.5 (630)	1,102	4 960910 634008		
63122	Polish Finish 1 m x 60 cm with 8 Scales	1,040×35×2.5 (630)	1,102	4 960910 631229		
63118	Polish Finish 1 m x 60 cm	1,040×35×2.5 (630)	1,102	4 960910 631182		
63128	Polish Finish 3 shaku 3 sun x 2 shaku	1,040×35×2.5 (630)	1,102	4 960910 631281		
63094	Polish Finish 1 m/3 shaku 3 sun	1,040×35×2.5 (630)	1,102	4 960910 630949		

Refer to P. 2 about the shaku scale

Large Square



Item Code	Description	Long Branch×Width×Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
63053	Rigid Polish Finish 60 x 30 cm	630×25×3.0 (330)	543	4 960910 630536	5	
63402	Hard Chrome Finish 60 x 30 cm	630×30×2.0 (330)	432	4 960910 634022		
63413	Polish Finish 60 x 30 cm with 8 Scales	630×30×2.0 (330)	430	4 960910 634138		
63410	Polish Finish 60 x 30 cm	630×30×2.0 (330)	430	4 960910 634107		
63411	Polish Finish 2 x 1 shaku	638×30×2.0 (335)	440	4 960910 634114		
63412	Polish Finish 60 cm/2 shaku	638×30×2.0 (335)	440	4 960910 634121		

Refer to P. 2 about the shaku scale

Features

- Useful to measure and mark large objects such as building stone, lumber, and metal plates
- 63402 Hard chrome finish on entire surface (matte processed)
- 63413 has graduations on all 8 sides



Matte finish

Use

- For all types of inking, marking, and measuring right angles/length


Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	63053	63402	63413
Scale on Front Side	Outside	60 cm	
	Inside	—	55 cm
Scale on Back Side	Outside	30 cm	
	Inside	—	25 cm
Shape of Corner	Outside	60 cm	
	Inside	—	55 cm
Squareness	Outside	30 cm	
	Inside	—	25 cm
Length Tolerance			
±0.5 mm			
Material			
Stainless steel			

	63410	63411	63412
Scale on Front Side	Outside	60 cm	2 shaku
	Inside	—	60 cm
Scale on Back Side	Outside	30 cm	1 shaku
	Inside	—	30 cm
Shape of Corner	Outside	60 cm	2 shaku
	Inside	—	60 cm
Squareness	Outside	30 cm	1 shaku
	Inside	—	30 cm
Length Tolerance			
±0.5 mm			
Material			
Stainless steel			

Large Square with Brace



Item Code	Description	Long Branch×Width×Thickness (Short Branch) (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
63121	Polish Finish 1 m x 60 cm	1,040×35×2.5 (630)	1,710	4 960910 631212	1	

Features

- Useful to measure and mark large objects such as building stone, lumber, and metal plates



- With brace to protect vertical accuracy from shock when dropped or bumped

Use


- For all types of inking, marking, and measuring right angles/length

Specifications

--: No scale SS: Square scale CS: Circle scale MS: Mortise scale

Scale on Front Side	log bench	Outside	1 m
		Inside	—
	port bench	Outside	60 cm
		Inside	—
Scale on Back Side	log bench	Outside	1 m
		Inside	—
	port bench	Outside	60 cm
		Inside	—
Shape of Corner		Flat	
Squareness		Less than 0.1 mm per 100 mm	
Length Tolerance		±0.5 mm	
Material		Stainless steel	

Rafter/Flat Square



Item Code	Description	Long BranchxWidthxThickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
64548	Rafter Square 60 x 40 cm	610x51x2.3 (407)	806	4 960910 645486	5	
62359	Flat Square 30 x 20 cm	305x38x1.2 (204)	150	4 960910 623590	10	

Features

- Comes in handy for two-by-four building as width measure is in inches
- White scale on black background makes graduations and numbers easy to see

Use


- For all types of marking and measuring length in two-by-four building

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

	64548	62359
Scale on front side	Outside 60 cm	30 cm
	Inside 57 cm	27 cm
Scale on back side	Outside 40 cm	20 cm
	Inside 35 cm	16 cm
Shape of Corner	Outside 60 cm	30 cm
	Inside 57 cm	27 cm
Squareness	Outside 40 cm	20 cm
	Inside 35 cm	16 cm
Length Tolerance	Less than 0.1 mm per 100 mm	
Material	Iron	

Stainless Steel Rafter Square Polish Finish



Item Code	Description	Long BranchxWidthxThickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
32506	S-1401 24" x 16"	24x2x0.1 (16)	740	4 960910 325067	1	

*Made-to-order

Features

- With rafter length table
- With brace length table
- With octagon scale

Use


- Convenient for roof construction

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

Scale on front side	Outside 24"	
	Inside 22.5"	
Scale on back side	Outside 16"	
	Inside 14"	
Shape of Corner	Outside 24"	
	Inside 22.5"	
Squareness	Outside 16"	
	Inside 14"	
Length Tolerance	Less than 0.1 mm per 100 mm	
Material	Stainless steel	

Dressmaking Square



Item Code	Description	Long BranchxWidthxThickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
64009	Hard Chrome Finish 75 x 35 cm	785x30x1.5 (380)	396	4 960910 640092	5	

Features

- Convenient for taking measurements of fabric for dressmaking

Use


- For dressmaking

Specifications

—: No scale SS: Square scale CS: Circle scale MS: Mortise scale

Scale on front side	Outside 75 cm	
	Inside —	
Scale on back side	Outside 35 cm	
	Inside —	
Shape of Corner	Outside Dress making	
	Inside —	
Squareness	Outside Dress making	
	Inside —	
Length Tolerance	Less than 0.1 mm per 100 mm	
Material	Stainless steel	

Large Caliper



Item Code	Description	Caliper Length (mm)	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
63509	30 cm	160	420×15×3.0	278	4 960910 635098	1	V
63517	35 cm	200	480×15×3.0	326	4 960910 635173		
63525	45 cm	260	590×15×3.0	416	4 960910 635258		
63541	60 cm	330	770×17×3.0	597	4 960910 635418		
63568	75 cm	430	960×18.5×4.0	1,127	4 960910 635685		
63592	1 m	580	1,200×20×4.0	1,575	4 960910 635920		

Features


- Can easily measure diameter of trees and timber

Use


- To measure the diameter of timber
- To assort rounded objects by size like fruits



Specifications



Carpenter's Square with Fence



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77885	60 cm/shaku	630 (330) × 30 × 4 (edge 330 × 25 × 3)	1,000	4 960910 778856	2	V


Refer to P. 2 about the shaku scale

Features

- Edge holds to the material tightly and prevents sliding when cutting with an electric circular saw or marking
- All stainless steel made, heavy and tough
- Shaku graduation is marked inside of long branch

Use


- Use as a guide rule for electric circular saws
- For all types of marking and measuring length



Specifications

Squareness	Less than 0.1 mm per 100 mm
Length Tolerance	±0.5 mm
Material	Stainless steel

Ornamental Carpenter's Square



98760

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
98760	Gold and Silver with Frame	522×673×40	2,920	4 960910 987609	1	

Features

- History of the carpenter's square is engraved on metal plates, and the gold and silver color finish turns it into a beautiful, decorative framed piece

Use


- For an anniversary gift or occasional gift



Specifications

Material	Square: Stainless steel Frame: Aluminum, acrylic resin
----------	---

JAPANESE INDUSTRIAL STANDARD Carpenter's Square Part of B7534-2005 (abstract) as of July 2018




(A Type) : 10014

Division	Item	Standard		
Standard	JIS B7534-2005	-		
Material	Hardness	A type	B type	C type
		Hv320 min	Hv210 min	Hv210 min
Performance, Shapes and Dimensions	①Tolerances on Length	The tolerance on length of carpenter's squares shall be ± 0.2 mm for an arbitrary length from its outer or inner scale reference point and the length between arbitrary two graduation lines, taking the reference temperature at 20°C.		
	②Squareness of Scale Side Face	The squareness of the scale side face of the long branch in respect to that of the short branch shall not exceed 0.1 mm per 100 mm.		
	③Straightness of Scale Side Face	The straightness in horizontal direction of the scale side of carpenter's square shall be less than $(0.3 + \text{Overall length of long branch or short branch divided by } 2,500)$ mm.		
	④Flatness of Scale Face	For a carpenter's square of Type A. When it is bent so that the distance between both ends of long branch becomes 3/4 the "outer scale length of long branch" and returned, the flatness of scale face of the long branch shall not exceed 1/100 the "outer scale length of long branch".		
	⑤Scale	The graduation lines shall reach the ridge of the scaled surface, as well as the squareness in respect to the ridge of scaled surface shall be less than 0.2 mm per 5 mm. The thickness of the graduation lines shall be 0.2 to 0.45 mm. For those of the same nominal thickness, the minimum value of the actual thickness shall be at least 55% of the maximum value.		
	⑥Width	A type·B type 15.0 $\pm$ 0.3 mm/C type 20.0 $\pm$ 0.3 mm·15.0 $\pm$ 0.3 mm		
	⑦Thickness	A Type 1.4 $\pm$ 0.4 mm B type T:2.6 $\pm$ 0.3 mm t:2.0 $\pm$ 0.3 mm C type 2.0 $\pm$ 0.3 mm·1.0 $\pm$ 0.3 mm		
Shape	Cross Section	A type	B type	C type

About the Carpenter's Square

Part names




The angled face prevents ink from bleeding. The valley is designed to provide an easy grip for users.

About Special Scales


① Square Scale (SS)

A scale graduated in $\sqrt{2}$ times the actual length scale for measuring the largest square possible to be cut out from a circular material.



② Circle Scale (CS)

A scale graduated in $1/\pi$ times the actual length scale for measuring the circumference of a circular material.




③ Back Side Indicator


On both the front and back sides of the square, there are icons indicating frequently used scale marks (J). These icons allow users to know the value written on the back side without flipping the square.

④ Mortise Scale (MS)


Useful to measure the depth of a mortise.



2. Stainless Steel Rules/ Machine Scale



Stainless Steel Rule Hard Chrome Finish [Metric]



Item Code	Description	JIS	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
21010	H-101A 15 cm		175×15×0.5	10	4 960910 210103	50	
21085	H-101C 30 cm		335×25×1.0	65	4 960910 210851	10	
21028	H-101E 60 cm		640×30×1.2	180	4 960910 210288	5	
21107	H-101F 1 m		1,050×35×1.5	425	4 960910 211070	5	
21589	H-102G 1.5 m		1,565×40×2.0	950	4 960910 215894	5	
21607	H-102H 2 m		2,065×40×2.0	1,250	4 960910 216075	5	
21566	H-102I 3 m		3,065×40×3.0	2,865	4 960910 215665	5	

Features

- JIS Grade 1 (15 cm - 2 m)
- Hard chrome finish provides its surface with excellent durability and prevents glare on the scale for high readability
- Etching and plating finish maintains its performance even under harsh conditions
- English package
- Made in Japan

Use


- For measuring length, drawing lines and marking

Specifications

	21010	21085	21028	21107
Upper Graduation	1 mm pitch			
Lower Graduation	0.5 mm pitch			
Material	Stainless steel			

	21589	21607	21566
Upper Graduation	0.5 mm pitch for up to 10 cm		
	1 mm pitch for the rest		
Lower Graduation	1 mm pitch		
Material	Stainless steel		

Stainless Steel Rule Hard Chrome Finish [Metric/Inch]



Item Code	Description	JIS	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
22004	H-201A 15 cm/6"		175×15×0.5	10	4 960910 220041	50	
22012	H-201C 30 cm/12"		335×25×1.0	65	4 960910 220126	10	
22021	H-201E 60 cm/24"		640×30×1.2	180	4 960910 220218	5	
22039	H-201F 1 m/36"		1,050×35×1.5	425	4 960910 220393	5	

Features

- Metric scale on front side and inch scale on back side
- Hard chrome finish provides its surface with excellent durability and prevents glare on the scale for high readability
- Etching and plating finish maintains its performance even under harsh conditions
- English package
- Made in Japan


Use

- For measuring length, drawing lines and marking

Specifications

		22004	22012	22021	22039
Front Side	Upper	0.5 mm pitch			
	Lower	1 mm pitch			
Back Side	Upper	1/10", 1/20", 1/50" pitch			
	Lower	1/16", 1/32", 1/64" pitch			
Material		Stainless steel			

Stainless Steel Rule Hard Chrome Finish [Metric/Inch]



Item Code	Description	JIS	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
23001	H-301A 15 cm/6"		175×15×0.5	10	4 960910 230019	50	
23021	H-301C 30 cm/12"		335×25×1.0	65	4 960910 230217	10	
23029	H-301E 60 cm/24"		640×30×1.2	180	4 960910 230293	5	
23037	H-301F 1 m/36"		1,050×35×1.5	425	4 960910 230378	5	
23159	H-302G 1.5 m/60"		1,565×40×2.0	950	4 960910 231597	5	
23167	H-302H 2 m/78"		2,065×40×2.0	1,250	4 960910 231672	5	
23175	H-302I 3 m/118"		3,065×40×3.0	2,865	4 960910 231757	5	

Features

- Metric scale on upper side and inch scale on lower side
- Hard chrome finish provides its surface with excellent durability and prevents glare on the scale for high readability
- Etching and plating finish maintains its performance even under harsh conditions
- English package
- Made in Japan

Use

- For measuring length, drawing lines and marking

Specifications

		23001	23021	23029	23037
Front Side	Upper	0.5 mm,1 mm pitch			
	Lower	1/16",1/32",1/64"pitch			
Back Side		Conversion table			
Material		Stainless steel			

		23159	23167	23175
Front Side	Upper	0.5 mm,1 mm pitch		
	Lower	1/16",1/32",1/64"pitch		
Back Side		Plain		
Material		Stainless steel		


JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

The difference between Polish Finish and Hard Chrome Finish

Surface finish differs. The polish finish is regular stainless steel while the hard chrome type has been given a matte finish to prevent glare and give the scale high readability.

Stainless Steel Rule Hard Chrome Finish [Metric/Inch]



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
24007	H-401A 15 cm/6"	175×15×0.5	10		50	
24015	H-401C 30 cm/12"	335×25×1.0	65		10	
24023	H-401E 60 cm/24"	640×30×1.2	180		5	
24031	H-401F 1 m/36"	1,050×35×1.5	425		1	
24252	H-402G 1.5 m/60"	1,565×40×2.0	950		1	
24260	H-402H 2 m/78"	2,065×40×2.0	1,250		1	
49099	H-402I 3 m/118"	3,065×40×3.0	2,865		1	

Features

- Metric scale on upper side and inch scale on lower side
- Hard chrome finish provides its surface with excellent durability and prevents glare on the scale for high readability
- Etching and plating finish maintains its performance even under harsh conditions
- English package
- Made in Japan

Use


- For measuring length, drawing lines and marking

Specifications

		24007	24015	24023	24031
Front Side	Upper	0.5 mm, 1 mm pitch			
	Lower	1/16", 1/32", 1/64" pitch			
Back Side		Conversion table			
Material		Stainless steel			

		24252	24260	49099
Front Side	Upper	0.5 mm, 1 mm pitch		
	Lower	1/16", 1/32", 1/64" pitch		
Back Side		Plain		
Material		Stainless steel		

Stainless Steel Rule Polish Finish [Metric]



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
21148	S-101A 15 cm	175×15×0.5	10		50	
21156	S-101C 30 cm	335×25×1.0	65		10	
21164	S-101E 60 cm	640×30×1.2	180		5	
21172	S-101F 1 m	1,050×35×1.5	425		1	
21741	S-102G 1.5 m	1,565×40×2.0	950		1	
21768	S-102H 2 m	2,065×40×2.0	1,250		1	
23275	S-102I 3 m	3,065×40×3.0	2,865		1	
23276	S-102J 4 m	4,065×45×3.0	4,253		1	
23277	S-102K 5 m	5,065×45×3.0	5,299		1	
23278	S-102L 6 m	6,065×45×3.0	6,345		1	

Features

- JIS Grade 1 (15 cm - 2 m)
- Polish finish offers both fine metallic luster and reasonable price
- English package
- Made in Japan

Use

- For measuring length, drawing lines and marking

Specifications

	21148	21156	21164	21172
Upper Graduation	1 mm pitch			
Lower Graduation	0.5 mm pitch			
Material	Stainless steel			

	21741	21768	23275
Upper Graduation	0.5 mm pitch for up to 10cm 1 mm pitch for the rest		
Lower Graduation	1 mm pitch		
Material	Stainless steel		

	23276	23277	23278
Upper Graduation	1 mm pitch		
Lower Graduation	1 mm pitch		
Material	Stainless steel		

Stainless Steel Rule Hard Chrome Finish

Item Code	Front	Back
24777		
24540		
30451		
24737		
24580		
24621		
24785		
24548		
30459		
24742		
24591		
24629		

Features

- Hard chrome finish provides its surface with excellent durability and prevents glare on the scale for high readability
- Etching and plating finish maintains its performance even under harsh conditions
- English package
- Made in Japan

Use

- For measuring length, drawing lines and marking

Specifications

24777	24737	24785	24742
1/32", 1/64", 1/10", 1/50"			
24540	24580	24548	24591
1/64", 1/32", 1/16", 1/8"			
24621	24629		
1/10", 1/100", 1/64", 1/32"			
30451	30459		
1/32", 1/64", 1.0 mm, 0.5 mm			

Item Code	Description	Overall Length×Width× Thickness (mm)	Weight (g)	JAN Code	Packing Unit	packaging
24777	H-3302A 6"/6" Rigid 3R	6×0.75×0.03	17	4 960910 247772	25	
24540	H-3001A 6"/6" Rigid 4R	6×0.75×0.03	17	4 960910 245402		
30451	H-3412A 6"/15 cm Rigid EM	6×0.75×0.03	17	4 960910 304512		
24737	H-3301A 6"/6" Flexible 3R	6×0.5×0.02	7	4 960910 247376	50	
24580	H-3101A 6"/6" Flexible 4R	6×0.5×0.02	7	4 960910 245808		
24621	H-3102A 6"/6" Flexible 5R	6×0.5×0.02	7	4 960910 246218		
24785	H-3302C 12"/12" Rigid 3R	12×1.375×0.04	66	4 960910 247857	25	
24548	H-3001C 12"/12" Rigid 4R	12×1.375×0.04	66	4 960910 245488		
30459	H-3412C 12"/30 cm Rigid EM	12×1.375×0.04	66	4 960910 304598		
24742	H-3301C 12"/12" Flexible 3R	12×0.5×0.02	15	4 960910 247420	50	
24591	H-3101C 12"/12" Flexible 4R	12×0.5×0.02	15	4 960910 245914		
24629	H-3102C 12"/12" Flexible 5R	12×0.5×0.02	15	4 960910 246294		

Stainless Steel Rule Hard Chrome Finish



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
13005	15 cm	JIS (Red) 175×15×0.5	10	4 960910 130050	50	
13013	30 cm	JIS (Red) 335×25×1.0	65	4 960910 130135	10	
13021	60 cm	JIS (Red) 640×30×1.2	180	4 960910 130210	5	
13048	1 m	JIS (Red) 1,050×35×1.5	425	4 960910 130487	1	
13056	1.5 m	JIS (Red) 1,565×40×2.0	950	4 960910 130562	1	
13064	2 m	JIS (Red) 2,065×40×2.0	1,250	4 960910 130647	1	
13072	3 m	JIS (Red) 3,065×40×3.0	2,865	4 960910 130722	1	

Features

- JIS Grade 1 (15 cm - 2 m)
- Hard chrome finish (matte processed) to prevent glare and make graduation easy to see
- Etching and plating finish maintains its performance even under harsh conditions
- Inch conversion chart and tap drill size chart on back (15 cm - 1 m)

Use

- For measuring length, drawing lines and marking

Specifications

	13005	13013	13021	13048
Upper Graduation	1 mm pitch			
Lower Graduation	0.5 mm pitch			
Material	Stainless steel			

	13056	13064	13072
Upper Graduation	0.5 mm pitch for up to 10 cm 1 mm pitch for the rest		
Lower Graduation	1 mm pitch		
Material	Stainless steel		

Stainless Pickup Rule Hard Chrome Finish



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
13128	10 cm	120×15×0.5	7	4 960910 131286	50	
13131	15 cm	JIS (Red) 175×15×0.5	10	4 960910 131316	10	
13134	30 cm	JIS (Red) 335×25×1.0	65	4 960910 131347	5	
13137	60 cm	JIS (Red) 640×30×1.2	180	4 960910 131378	1	
13140	1 m	JIS (Red) 1,050×35×1.5	425	4 960910 131408	1	

Features

- JIS Grade 1 (15 cm - 1 m)
- Bent end of the scale makes it easy to pick up



- Big numbers make it easy to read off
- Conversion chart on the back

Use

- For measuring length, drawing lines and marking

Specifications

Graduation	1 mm pitch for both upper and lower
Material	Stainless steel

Stainless Steel Rule Polish Finish



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
14001	15 cm	JIS (Red) 175×15×0.5	10	4 960910 140011	50	
14028	30 cm	JIS (Red) 335×25×1.0	65	4 960910 140288	10	
14036	60 cm	JIS (Red) 640×30×1.2	180	4 960910 140363	5	
14044	1 m	JIS (Red) 1,050×35×1.5	425	4 960910 140448	1	
14052	1.5 m	JIS (Red) 1,565×40×2.0	950	4 960910 140523	1	
14060	2 m	JIS (Red) 2,065×40×2.0	1,250	4 960910 140608	1	
14079	3 m	3,065×40×3.0	2,865	4 960910 140790	1	
14087	4 m	4,065×45×3.0	4,253	4 960910 140875	1	
14095	5 m	5,065×45×3.0	5,299	4 960910 140950	1	
14109	6 m	6,065×45×3.0	6,345	4 960910 141094	1	

Features

- JIS Grade 1 (15 cm - 2 m)
- Polish finish offers both fine metallic luster and reasonable price
- Inch conversion chart and tap drill size chart on back (15 cm - 1 m)

Use


- For measuring length, drawing lines and marking

Specifications

	14001	14028	14036	14044
Upper Graduation	1 mm pitch			
Lower Graduation	0.5 mm pitch			
Material	Stainless steel			

	14052	14060	14079	14087	14095	14109
Upper Graduation	0.5 mm pitch for up to 10 cm 1 mm pitch for the rest			1 mm pitch		
Lower Graduation	1 mm pitch					
Material	Stainless steel					

Stainless Steel Rule Hard Chrome Finish Metric/Shaku



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
13202	15 cm Double-left Reference Point	175×15×0.5	10	4 960910 132023	10	
13203	30 cm Double-left Reference Point	330×25×1.0	64	4 960910 132030		
13204	60 cm Double-left Reference Point	635×30×1.2	175	4 960910 132047		
13205	1 m Double-left Reference Point	1,040×35×1.5	420	4 960910 132054		
13210	1 m Right Reference Point	1,050×35×1.5	425	4 960910 132108		

Refer to P. 2 about the shaku scale

Features

- Shaku graduation comes in handy for carpenters
- Double-left Reference Point model is such that when either the shaku or cm scale is on the upper level, that graduation's reference point reads from the left side edge. (13210, the reference point on both the upper and lower graduations reads from the right side edge.)
- Conversion chart on the back (13202/13203/13204/13205)
- Inch conversion chart and tap drill size chart on back (13210)

Use

- For measuring length, drawing lines and marking

Specifications

	13202	13203	13204	13205	13210
Upper Graduation	1 mm pitch				
Lower Graduation	Shaku				
Material	Stainless steel				

Stainless Steel Rule Hard Chrome Finish with Magnet



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
13501	15 cm	175×15×1.3	15	4 960910 135017	10	
13528	30 cm	335×25×1.8	81	4 960910 135284		
13536	60 cm	640×30×2.0	216	4 960910 135369		
13544	1 m	1,050×35×2.3	487	4 960910 135444		

Features

- JIS Grade 1
- Magnetic sheet attached on the back


Use

- For measuring length, drawing lines and marking

Specifications

	13501	13528	13536	13544
Upper Graduation	1 mm pitch			
Lower Graduation	0.5 mm pitch			
Material	Stainless steel			

Flexible Stainless Steel Rule Hard Chrome Finish



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
13250	30 cm	325×15×0.5	18	4 960910 132504	50	
13269	60 cm	630×15×0.5	35	4 960910 132696		
13277	1 m	1,030×15×0.5	60	4 960910 132771		
13285	1.5 m	1,530×15×0.5	87	4 960910 132856		
13293	2 m	2,030×15×0.5	115	4 960910 132931		

Features

- Narrower and thinner rule with flexibility
- Its quality is the same as JIS products
- Can be used to match curved surfaces

Use

- For measuring curves or attaching to machines


Specifications

	13250	13269	13277	13285	13293
Upper Graduation	1 mm pitch				
Lower Graduation	0.5 mm pitch				
Material	Stainless steel				

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Stainless Steel Rule Hard Chrome Finish 1 mm Dividing *Made-to-order



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
13404	15 cm JIS	175×15×0.5	10	4 960910 134041	50	
13463	30 cm JIS	335×25×1.0	65	4 960910 134638		
13412	60 cm JIS	640×30×1.2	180	4 960910 134126	10	
13498	1 m JIS	1,050×35×1.5	425	4 960910 134980		

Features

- JIS Grade 1
- Easy-to-read 1 mm pitch for a situation that does not require detailed graduations
- Inch conversion chart and tap drill size chart on back


Use

- For measuring length, drawing lines and marking

Specifications

	13404	13463	13412	13498
Upper Graduation	1 mm pitch			
Lower Graduation	1 mm pitch			
Material	Stainless steel			

Stainless Steel Rule Hard Chrome Finish with Stopper




Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76751	15 cm JIS	175×22 (15) ×5 (0.5)	20	4 960910 767515	10	
76752	30 cm JIS	335×35 (25) ×6 (1.0)	90	4 960910 767522		

Features

- JIS Grade 1
- Attached stopper enables it to hold and measure depth more easily and accurately

Use

- For marking, measuring length, depth and height of step



Specifications

Material	Rule: Stainless steel Stopper: Brass
----------	---

Rule Stopper



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76745	for 15 cm Rule	15×22×5	9	4 960910 767454	10	
76746	for 30 cm Rule	20×35×6	23.5	4 960910 767461		
76747	for 60 cm Rule	20×40×6	24	4 960910 767478		
76748	for 1 m Rule	20×50×6	30	4 960910 767485	5	
76749	for 1.5 and 2 m Rule	20×55×8	42.5	4 960910 767492		

Features

- Attaches to a ruler to make it easier to hold and measure depth more easily and accurately


Use

- For marking, or measuring length, depth and height of step

Specifications

	76745	76746	76747	76748	76749
Suitable Size (Width × Thickness)	15×0.5 mm	25×1.0 mm	30×1.2 mm	35×1.5 mm	40×2.0 mm
Material	Brass				

Stainless Steel Rule Mini



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
13242	Hard Chrome Finish 15 cm	160×26×0.5 Rule Width: 12	8	4 960910 132429	20	
14249	Polish Finish 15 cm	160×26×0.5 Rule Width: 12	8	4 960910 142497		

Features

- Clip for securing in a pocket
- It can also be used as a depth gauge by sliding the clip
- Easy to carry around
- Inch conversion chart on the back

Use

- For measuring length and depth

Specifications

	13242	14249
Upper Graduation	1 mm pitch	
Lower Graduation	1 mm pitch	
Material	Stainless steel	

6-folding Stainless Steel Rule Polish Finish



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
63770	1 m	1,000×15×0.5	64	4 960910 637702	10	

Features

- This 1 m scale can be folded into six parts to carry and store easily


Use

- For measuring length, drawing lines and marking


Specifications

Graduation	1 mm pitch
Material	Stainless steel

Precision Stainless Steel Rule Hard Chrome Finish with JCSS Certificate



14115



Graduations for Instrumental error

with JCSS Certificate *1

*1 Measuring points at every 100 mm (only bottom side scale)

Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
14113	30 cm *2	310×30×10	724	4 960910 141131	1	
14114	60 cm *2	610×30×10	1,425	4 960910 141148		
14115	1 m	1,010×30×10	2,360	4 960910 141155		

*2 30 cm and 60 cm models are made-to-order items.

Features

- Rules for examination or calibration
- Comes with a premium wooden box


Use

- For calibration of all types of measuring instruments

Specifications

Material	Stainless steel
Graduations for Instrumental Error	0.25 mm pitch (1 mm before and behind) on 30 cm, 60 cm, 1 m
Graduations	1 mm pitch except for graduations for instrumental error
Graduations Line Width	0.1 - 0.2 mm
Length Tolerance	±0.06 mm
Coefficient of Linear Expansion	10.3 × 10 ⁻⁶ /°C

Molding Rule



Features

- Handy for creating wood or metal molds for casting
- Hard chrome finish prevents glare on the scale, making it easier to read

Use

- For creating wood or metal molds for casting


Specifications

Material	Stainless steel
----------	-----------------

Description	Overall Length×Width×Thickness (mm)	Weight (g)	Packing Unit	Packaging
15 cm ○○/1000	182×15×0.5	11	10	
30 cm ○○/1000	345×25×1.0	66		
60 cm ○○/1000	651×30×1.2	185		
1 m ○○/1000	1,060×35×1.5	435		
2 m ○○/1000	2,085×40×2.0	1,275	1	

12/1000

This means that 1 cm measured on contraction rule is actually 1.012 cm



*The length and weight are based on 10/1000 model. They will vary depending on percent elongation.

Item Code list

* **Blue frames** indicate stock items. Others are made-to-order items including (—).

*We can provide a separate estimate for sizes and percent elongation other than those listed below.

Length ○/1000	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
15 cm	81738	46800	—	18003	18004	14932	—	18007	—	18015	19005	18023	18024	81657	18031
30 cm	—	15000	15296	15008	15016	15024	15032	15040	15059	15067	15261	15075	15083	15091	15105
60 cm	81737	16000	16381	16004	16012	16020	16039	16047	16055	16063	16365	16071	16098	16101	16128
1 m	—	17001	17345	17000	17019	17027	17035	17043	17051	17078	17353	17086	17094	17108	17116
2 m	—	18500	14050	—	73879	—	83803	18503	18686	18511	18499	18538	18678	18546	18554

Length ○/1000	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
15 cm	19006	14938	14939	67845	18058	—	18066	77785	77196	18074	—	14950	77673	—	18082
30 cm	15113	15121	15148	15334	15156	15288	15164	15172	15180	15199	15202	15210	15229	18090	15237
60 cm	16136	16144	16152	16160	16179	16373	16187	16195	16209	16217	16225	16233	16241	14900	16268
1 m	17124	17132	17140	17159	17167	17361	17175	17183	17191	17205	—	17221	17248	75416	17256
2 m	18562	18570	18589	18597	18600	—	18619	65204	15380	18627	—	14945	65205	—	18635

What are molding rules?

- These are ideal rules for creating wood or metal molds for casting. A casting is set by pouring melted cast metal into a mold. As the casted metal contracts as it cools, the mold is made with extra dimensions. Since the contraction percentage varies depending on metals, sizes and foundries, various molding rules with different enlargement ratios are required.



Rules Specifications

*Varies depending on length

Items	Base	Numerical Unit		Graduation Pitch				
				Upper Graduation		Lower Graduation		
	Zero Point at Edge	mm	cm	0.5 mm	1 mm	0.5 mm	1 mm	Shaku
Stainless Steel Rule Hard Chrome Finish	●	●			●	● *		
Stainless Steel Rule Hard Chrome Finish Metric x Shaku	●		●		●			●
Stainless Pickup Rule Hard Chrome Finish	●		●		●		●	
Stainless Steel Rule Polish Finish	●	●			●	● *		
Stainless Steel Rule Hard Chrome Finish with Scale Stopper	●	●			●	●		
Stainless Steel Rule Hard Chrome Finish with Magnet	●	●			●	●		
Stainless Steel Rule Hard Chrome Finish 1 mm Dividing	●	●			●		●	
Stainless Steel Rule Hard Chrome Finish Flex Ruler 15 mm Width	●	●			●	●		
Stainless Steel Rule Mini	●	●			●		●	
Molding Rule	●		●		●		●	

■ Material less than 2 m: Stainless steel SUS420J2 Over 3 m: Stainless steel SUS304


SUS420J2 has a baked finish. SUS304 doesn't have a baked finish.

Length tolerance over 3 m: 3 m±0.5 mm, 4 m±0.65 mm, 5 m±0.8 mm, 6 m±0.95 mm

(SUS means Stainless Steel—rust-resistant. HV refers to Vickers Hardness—a unit for hardness.)

Metal Rules Grade 1 of JIS B7516-2005 (abstract)

as of June, 2019

Standard	Grade 1 of JIS B7516—2005						
Material	SUS420 J2 of JIS G 4305 or that equivalent or superior to this in quality						
Hardness of Material	Hv400 min						
S i z e  (Unit : mm)	Nominal Size	Overall Length (L)		Thickness (T)		Width (W)	
		Size	Tolerance	Size	Tolerance	Size	Tolerance
	150	175	±5 mm	0.5	±10%	15	±2%
	300	335		1.0		25	
	600	640		1.2		30	
	1,000	1,050		1.5		35	
	1,500	1,565		2.0		40	
	2,000	2,065		2.0		40	
Flatness of Scale Face	The scale face shall be flat to a level of no hindrance to measurements						
Straightness of Scale Side Face (Unit : mm)	Nominal Size	Straightness		Nominal Size	Straightness		
	150	0.23 max		1,000	0.40 max		
	300	0.26 max		1,500	0.50 max		
	600	0.32 max		2,000	0.60 max		
Squareness of Scale End Face	The squareness of the scale end face of a rule in respect of its scale side shall be 0.035mm max per 10mm length of the end face						
Tolerance of Length (Unit : mm) *Temperature at 20°C	Length			Tolerance			
	500 max			±0.15			
	over 500 - 1,000 max			±0.20			
	over 1,000 - 1,500 max			±0.25			
	over 1,500 - 2,000 max			±0.30			

Conversion table

Items	Inch Conversion Chart (TAP DRILL W.W./UNC)	Measurement Conversion Chart			
		Length	Width	Weight	Volume
Hard Chrome Finish 15 cm	●				
30 cm	●				
60 cm	●				
1 m	●				
Metric x Shaku 15 cm left		●	●		
30 cm left		●	●		
60 cm left		●	●	●	
1 m left		●	●	●	●
1 m right	●				
Polish Finish 15 cm	●				
30 cm	●				
60 cm	●				
1 m	●				
Pickup 10 cm		●			
15 cm		●	●		
30 cm		●	●		
60cm		●	●	●	
1m		●	●	●	●
With Scale Stopper 15 cm	●				
30 cm	●				
1mm Dividing 15 cm	●				
30 cm	●				
60 cm	●				
1 m	●				
Mini 15 cm	●				

■ All of our stainless steel rules that are compatible with Japanese Industrial Standard (JIS) under the specifications above display a JIS mark. Although some of our rules do not have the JIS mark displayed because they exceed JIS specifications due to unusual graduations, shapes, or sizes, all of our products whether compatible or not have gone through strict product inspections based on the JIS specifications above to provide safe, high-quality products.

Machine Scale

Features

- Hard chrome finish (matte processed) to prevent glare and make graduation easy to see
- Can be installed on equipment to facilitate adjustments by graduation and size confirmation during processing, etc.
 *For installation separate double-sided tape or an adhesive will be necessary. We can make holes for screw-fastening. (Please see the table below.)




Use

- For attaching to machines

Specifications

Precision	The precision is based on "Metal Rules Grade 1 of JIS" from page (35)
Material	Stainless steel
Body Size	Machine Scale 15×0.5 mm Indicator Plate 20×15×0.5 mm



Without Holes

Graduation	Item Code	Description	Graduation	Item Code	Description
① Upper left	14127	50 mm	④ Lower left	14146	50 mm
	14128	100 mm		14147	100 mm
	14129	150 mm		14148	150 mm
	14130	200 mm		14149	200 mm
	14131	300 mm		14150	300 mm
	14132	500 mm		14151	500 mm
② Upper right	14134	50 mm	⑤ Lower right	14153	50 mm
	14135	100 mm		14154	100 mm
	14136	150 mm		14155	150 mm
	14137	200 mm		14156	200 mm
	14138	300 mm		14157	300 mm
	14139	500 mm		14158	500 mm
③ Upper central	14141	100 mm	⑥ Lower central	14160	100 mm
	14142	200 mm		14161	200 mm
	14143	300 mm		14162	300 mm
	14144	500 mm		14163	500 mm


Indicator Plate

Item Code	Description
14165	Indicator Plate for Machine Scale


Hole Making Fee (made-to-order)

Please ask us about our fees for hole-making. Hole positions are as shown in the figure below.

Hole Positions (hole diameter 3.5 mm)



3. Aluminum Rules




Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package



Since aluminum can be elastic due to change in temperatures, please do not use it for precisions other than the shown tolerance. Based on the temperature 20°C, a 10°C change generates 0.235 mm expansion or contraction per 1 m.

Aluminum Rule Rigid



Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65340	30 cm	310×35×5	90	4 960910 653405	20	
65363	45 cm	460×35×5	130	4 960910 653634		
65378	60 cm	610×35×5	180	4 960910 653788		
65387	1 m	1,010×35×5	300	4 960910 653870	10	

Features

- Tough aluminum rules with 50% more aluminum materials than the conventional model
- Bold, easy-to-read graduations
- Light, durable, rust-resistant
- Accessory: Cork strip with adhesive tape



to tape on the back if necessary

- Edge prevents ink from running off



Use

- For measuring the length, drawing lines, and cutting


Specifications

	65340	65363	65378	65387
Length Tolerance	±0.20 mm	±0.25 mm	±0.28 mm	±0.40 mm
Material	Aluminum			

*Length tolerance is the accuracy measured at normal temperature.

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Aluminum Rule with Non-slip Pad




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65331	30 cm	310×35×5	52	4 960910 653313	20	
65415	30 cm Blue	310×35×5	52	4 960910 654150	20	
65416	30 cm Pink	310×35×5	52	4 960910 654167	20	
65417	30 cm Gold	310×35×5	52	4 960910 654174	20	
65418	30 cm White	310×35×5	55	4 960910 654181	20	
65358	45 cm	460×35×5	79	4 960910 653580	20	
65423	45 cm Blue	460×35×5	79	4 960910 654235	20	
65424	45 cm Pink	460×35×5	79	4 960910 654242	20	
65425	45 cm Gold	460×35×5	79	4 960910 654259	20	
65426	45 cm White	460×35×5	85	4 960910 654266	20	
65374	60 cm	610×35×5	106	4 960910 653740	20	
65434	60 cm Blue	610×35×5	106	4 960910 654341	20	
65435	60 cm Pink	610×35×5	106	4 960910 654358	20	
65436	60 cm Gold	610×35×5	106	4 960910 654365	20	
65437	60 cm White	610×35×5	115	4 960910 654372	20	
65382	1 m	1,010×35×5	173	4 960910 653825	10	
65442	1 m Blue	1,010×35×5	173	4 960910 654426	10	
65443	1 m Pink	1,010×35×5	173	4 960910 654433	10	
65444	1 m Gold	1,010×35×5	173	4 960910 654440	10	
65445	1 m White	1,010×35×5	190	4 960910 654457	10	

Aluminum Rule

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65498	15 cm	160×35×5	28	4 960910 654983	20	
65501	30 cm	310×35×5	51	4 960910 655010	20	
65528	45 cm	460×35×5	76	4 960910 655287	20	
65536	60 cm	610×35×5	102	4 960910 655362	20	
65544	1 m	1,010×35×5	169	4 960910 655447	10	

Features

- Bold, easy-to-read graduations
- Light, durable, rust-resistant
- Non-slip foam
- Choose your favorite color



Safety wall


The safety wall is higher than the cutter edge to prevent a cutter from sliding over it.

Use

- For measuring length, drawing lines, and cutting

Drawing Guide Groove

Use it when you want to draw a line by using a marker or pen without touching the rule directly.



Drawing guide is not included.

Specifications

	65498
Length Tolerance*	±0.16 mm
Material	Main Part: Aluminum
	65331 65415 65416 65417 65418 65501
Length Tolerance*	±0.20 mm
Material	Main Part: Aluminum
	65358 65423 65424 65425 65426 65528
Length Tolerance*	±0.25 mm
Material	Main Part: Aluminum
	65374 65434 65435 65436 65437 65536
Length Tolerance*	±0.28 mm
Material	Main Part: Aluminum
	65382 65442 65443 65444 65445 65544
Length Tolerance*	±0.40 mm
Material	Main Part: Aluminum

*Length tolerance is the accuracy when measured at normal temperature.

Back (non-slip pad)



Aluminum Cutting Rule PROTECT



65065



65066

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65065	70 cm/shaku	720×80×15	650	4 960910 650657	2	
65066	1 m/shaku	1,020×80×15	920	4 960910 650664		
65067	1.25 m/shaku	1,270×80×15	1,150	4 960910 650671		
65068	2 m/shaku	2,030×80×15	1,800	4 960910 650688		

Refer to P. 2 about the shaku scale

Features

- Protector folds for easy carrying and storage
- 30 mm tall wall (35 mm from cutting surface) protects your hands
- Stainless steel edges prevent damage from a cutting blade
- Side cap protects materials from being scratched



Use


- For measuring length, drawing lines, cutting, guiding a circular saw

Specifications

	65065	65066	65067	65068
Length Tolerance	±0.51 mm	±0.60 mm	±0.68 mm	±0.90 mm
Straightness Tolerance	Below 0.34 mm	Below 0.4 mm	Below 0.45 mm	Below 0.6 mm
Material	Main Part: Aluminum Edge: Stainless steel Side-cap: Polyacetal resin Stopper: Rubber			

*Length tolerance is the accuracy when measured at normal temperature.
 *Straightness tolerance is the warpage of the sides.

How to measure straightness



Aluminum Cutting Rule EX



65030



65032

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65030	60 cm/shaku	625×88×11	500	4 960910 650305	2	
65032	1 m/shaku	1,020×88×11	800	4 960910 650329		
65034	1.5 m/shaku	1,535×88×11	1,240	4 960910 650343		
65036	2 m/shaku	2,020×88×11	1,580	4 960910 650367		
65038	2.5 m/shaku	2,540×88×11	1,990	4 960910 650381	1	

Refer to P. 2 about the shaku scale

Aluminum Cutting Rule EX with Handle




65033

Item Code	Description		Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
65031	60 cm/shaku	  	625×88×68	650		2	
65033	1 m/shaku	  	1,020×88×68	950			
65035	1.5 m/shaku	  	1,535×88×68	1,390		1	
65037	2 m/shaku	  	2,020×88×68	1,730			

Refer to P. 2 about the shaku scale

Features

- Stainless steel edges prevent damage from a cutting blade



- Fully-covered rubber stopper
- Elastomer resin handle makes it easy to hold (models with handle)



- Suitable for carpentry using shaku graduations
- Double-left Reference Point Model: When either the shaku or cm scale is on the upper level, that graduation's reference point reads from the left side edge
- Light, durable, rust-resistant
- Bold, easy-to-read graduations

Use

- For measuring length, drawing lines, and cutting
- For guiding a circular saw (without handle)

Specifications

	65030 65031	65032 65033	65034 65035	65036 65037	65038
Length Tolerance	±0.28 mm	±0.40 mm	±0.55 mm	±0.70 mm	±0.80 mm
Straightness Tolerance	Below 0.32 mm	Below 0.4 mm	Below 0.5 mm	Below 0.6 mm	Below 0.7 mm
Material	Main Part: Aluminum Edge: Stainless steel Handle: ABS resin, elastomer resin Stopper: Rubber				

*Length tolerance is the accuracy when measured at normal temperature.
 *Straightness tolerance is the warpage of the sides.

How to measure straightness



JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Aluminum Cutting Rule



Item Code	Description		Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging	
65086	60 cm/shaku	 	625×60×9	370	4 960910 650862	5		
65088	1 m/shaku Left Reference Point	 	1,020×60×9	579	4 960910 650886			
65090	1 m/shaku	 	1,020×60×9	579	4 960910 650909			
33421	1 m		1,020×60×9	579	4 960910 334212			
65094	1.5 m/shaku	 	1,535×60×9	912	4 960910 650947			
65091	2 m/shaku	 	2,020×60×9	1,250	4 960910 650916	1	5	
33422	2 m		2,020×60×9	1,250	4 960910 334229			
65092	2.5 m/shaku	 	2,540×60×9	1,560	4 960910 650923	1		

Refer to P. 2 about the shaku scale


Aluminum Cutting Rule with Handle



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65098	60 cm/shaku	625×60×60	520	4 960910 650985	2	
65093	1 m/shaku	1,020×60×60	730	4 960910 650930		
33423	1 m	1,020×60×60	730	4 960910 334236		
65096	1.5 m/shaku	1,535×60×60	1,060	4 960910 650961	1	
65097	2 m/shaku	2,020×60×60	1,400	4 960910 650978		
33424	2 m	2,020×60×60	1,400	4 960910 334243		


Refer to P. 2 about the shaku scale

Aluminum Cutting Rule Light



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65075	1 m	1,020×56×5.5	382	4 960910 650756	5	
65076	1 m with Handle	1,020×56×52	460	4 960910 650763	2	

Cut Rail




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65077	1 m/shaku	1,020×100×50	1,600	4 960910 650770	1	
65078	2 m/shaku	2,020×100×50	3,000	4 960910 650787		

Refer to P. 2 about the shaku scale

Features

- Stainless steel edges prevent damage from a cutting blade



- Rubber stopper on the back helps to position the rule better



- Unique shaped handle makes it easy to hold. (with Handle model)
- Suitable for carpentry using with shaku graduations
- Double-left Reference Point model: When either the shaku or cm scale is on the upper level, that graduation's reference point reads from the left side edge. (Item code 65088 is a Left Reference Point model that reads from the left side edge for both shaku [upper graduation] and cm [lower graduation].)
- Bold, easy-to-read graduations
- Light, durable, rust-resistant

Use


- For measuring length, drawing lines, and cutting
- For guiding a circular saw (without handle)

Specifications

	65086 65098	65088 65090 65093 33421 33423	65094 65096	65091 65097 33422 33424	65092
Length Tolerance	±0.28 mm	±0.4 mm	±0.55 mm	±0.7 mm	±0.8 mm
Straightness Tolerance	Below 0.32 mm	Below 0.4 mm	Below 0.5 mm	Below 0.6 mm	Below 0.7 mm
Graduations	33421, 33422, 33423, 33424 Scale Side: cm Cutter Side: cm 65088 Scale Side: shaku Cutter Side: cm Others Scale Side: cm Cutter Side: shaku				
Material	Main Part: Aluminum Edge: Stainless steel Handle: ABS resin, elastomer resin Stopper: Rubber				

*Length tolerance is the accuracy when measured at normal temperature.
 *Straightness tolerance is the warpage of the sides.

How to measure straightness



Features

- Lightweight design, easy-to-use for women
- Large and vivid numbered graduations
- Light, durable, rust-resistant
- With rubber stopper
- Stainless steel edges prevent damage from a cutting blade
- Narrower grip makes it easy to hold even with a small hand (with Handle model)

Use

- For measuring length, cutting
- For pasting wall paper

Specifications

Length Tolerance	±0.4 mm
Straightness Tolerance	Below 0.4 mm
Material	Main Part: Aluminum Edge: Stainless steel Handle: ABS resin Stopper: Rubber

*Length tolerance is the accuracy when measured at normal temperature.
 *Straightness tolerance is the warpage of the sides.

How to measure straightness



Features

- Aluminum cutting rule with safety features
- Safety wall prevents blade from sliding over

Use

- For measuring length, drawing lines, and cutting

Specifications

	65077	65078
Length Tolerance	±0.4 mm	±0.7 mm
Straightness Tolerance	Below 0.45 mm	Below 0.60 mm
Material	Main Part: Aluminum Stopper: Rubber	Edge: Stainless steel

*Length tolerance is the accuracy when measured at normal temperature.
 *Straightness tolerance is the warpage of the sides.

How to measure straightness



Telescopic Measure One Direction II

The one touch stopper lever locks easily

Hang by attached hook for outer dimension measurement



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65190	A 3 shaku 2 sun	Width×Thickness Tip end 33×22 47×23	300	4 960910 651906	5	
65191	AB 6 shaku 6 sun	Width×Thickness Tip end 33×22 47×23	530	4 960910 651913		
65192	B 9 shaku 3 sun	Width×Thickness Tip end 33×22 47×23	710	4 960910 651920		
65193	C 12 shaku	Width×Thickness Tip end 33×22 47×23	890	4 960910 651937		
65194	D 13 shaku 5 sun	Width×Thickness Tip end 33×22 47×23	990	4 960910 651944		
65195	E 15 shaku 5 sun	Width×Thickness Tip end 33×22 47×23	1,120	4 960910 651951		

Refer to P. 2 about the shaku scale

Features

- Expands three times in length and can be read off at hand. Easy one-person use.
- Plastic end will not scratch walls and ceilings
- Hang by attached hook for outer dimension measurement
- Bold, easy-to-read graduations
- Ideal for measuring ceiling height without switching hands
- One-touch stopper lever adopted to significantly improve durability and ease of locking
- Tape at the back can be used for marking and notes
- Large caps on both ends and graduation close to the edges are convenient for scribing

Use

- For interior finish work, installment of fittings, doors, stair works, plumbing work, masonry work, etc.
- A, AB types: For inner dimension measurement of areas with closet storage space, floor cupboards, and crown molding
- B, C, D, E types: For shaku measures and ken measures

Specifications

	65190	65191	65192
Length Tolerance	±1.0 mm up to 2 m, ±0.5 mm/m over 2 m		
Measuring Range	461 mm (1 shaku 5 sun 2 bu) 970 mm (3 shaku 2 sun)	810 mm (2 shaku 6 sun 7 bu) 2,017 mm (6 shaku 6 sun 6 bu)	1,078 mm (3 shaku 5 sun 6 bu) 2,821 mm (9 shaku 3 sun 1 bu)
Material	Tip End: ABS resin Main Body: Aluminum Stopper Lever: Polycarbonate resin Joint Part: Polyacetal resin Hook for Outer Dimension Measurement: Stainless steel		

	65193	65194	65195
Length Tolerance	±1.0 mm up to 2 m, ±0.5 mm/m over 2 m		
Measuring Range	1,351 mm (4 shaku 4 sun 6 bu) 3,640 mm (12 shaku 1 bu)	1,502 mm (4 shaku 9 sun 5 bu) 4,093 mm (13 shaku 5 sun 1 bu)	1,704 mm (5 shaku 5 sun 2 bu) 4,699 mm (15 shaku 5 sun 1 bu)
Material	Tip End: ABS resin Main Body: Aluminum Stopper Lever: Polycarbonate resin Joint Part: Polyacetal resin Hook for Outer Dimension Measurement: Stainless steel		

*Length tolerance is the accuracy when measured at normal temperature.

Telescopic Measure One Direction [Metric/Shaku]



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65183	A 3 shaku 2 sun	Width×Thickness Tip end 30×19 45×19	270	4 960910 651838	5	
65184	AB 6 shaku 3 sun	Width×Thickness Tip end 30×19 45×19	470	4 960910 651845		
65185	B 9 shaku 3 sun	Width×Thickness Tip end 30×19 45×19	660	4 960910 651852		
65186	C 12 shaku	Width×Thickness Tip end 30×19 45×19	830	4 960910 651869		
65187	D 13 shaku 5 sun	Width×Thickness Tip end 30×19 45×19	920	4 960910 651876		
65188	E 15 shaku 5 sun	Width×Thickness Tip end 30×19 45×19	1,050	4 960910 651883		

Refer to P. 2 about the shaku scale

Features

- Expands three times in length and can be read off at hand. Easy one-person use.
- Ideal for measuring ceiling height without switching hands
- One-touch stopper lever for efficient operation
- Tape at the back can be used for marking and notes

Use

- For interior finish work, installment of fittings, doors, stair work, plumbing work, masonry work, etc.
- A, AB types: For inner dimension measurement of areas with closet storage space, floor cupboards, and crown molding
- B, C, D, E types: For shaku measures and ken measures

Specifications


	65183	65184	65185	65186	65187	65188
Length Tolerance	±0.5 mm up to 1 m, ±0.5 mm/m over 1 m					
Measuring Range	45.5 cm (1 shaku 5 sun) 97.0 cm (3 shaku 2 sun)	77.3 cm (2 shaku 5 sun 5 bu) 190.9 cm (6 shaku 3 sun)	107.6 cm (3 shaku 5 sun 5 bu) 281.8 cm (9 shaku 3 sun)	134.8 cm (4 shaku 4 sun 5 bu) 363.6 cm (12 shaku)	150.0 cm (4 shaku 9 sun 5 bu) 409.1 cm (13 shaku 5 sun)	169.5 cm (5 shaku 5 sun 9 bu) 469.7 cm (15 shaku 5 sun)
Material	Main Part: Aluminum Stopper Lever: ABS resin					

*Length tolerance is the accuracy when measured at normal temperature.

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Telescopic Measure Two Directions [Metric/Shaku]



Item Code	Description of Product	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65160	A 3 shaku 2 sun	Width×Thickness 26×17	Tip end 26×17	230	4	5
65161	AB 6 shaku 3 sun	Width×Thickness 26×17	Tip end 26×17	410	4	
65162	B 9 shaku 3 sun	Width×Thickness 26×17	Tip end 26×17	560	4	
65163	C 12 shaku	Width×Thickness 26×17	Tip end 26×17	700	4	
65164	D 13 shaku 5 sun	Width×Thickness 26×17	Tip end 26×17	800	4	

Refer to P. 2 about the shaku scale

Telescopic Measure Two Directions [Metric]

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65107	A 95 cm	Width×Thickness 26×17	Tip end 26×17	230	4	5
65108	AB 190 cm	Width×Thickness 26×17	Tip end 26×17	410	4	
65109	B 280 cm	Width×Thickness 26×17	Tip end 26×17	560	4	
65105	C 360 cm	Width×Thickness 26×17	Tip end 26×17	700	4	
65106	D 400 cm	Width×Thickness 26×17	Tip end 26×17	800	4	

Features

- Expands three times in length and can be read off at hand. Easy one-person use.
- Plastic end will not scratch walls and ceilings
- Bold, easy-to-read graduations
- Center remains static as it expands in two directions. This makes it optimal particularly when extending the measure left and right for inner dimension measurement.



Use

- For interior finish work, installment of fittings, doors, stair work, plumbing work, masonry work, etc.
- A, AB types: For inner dimension measurement of areas with closet storage space, floor cupboards, and crown molding
- B, C, D, E types: For shaku measures and ken measures

Specifications

	65160	65161	65162	65163	65164
Length Tolerance	±0.4 mm	±0.6 mm	±0.8 mm	±0.9 mm	±1.0 mm
Measuring Range	36.4 cm (1 shaku 2 sun)	69.7 cm (2 shaku 3 sun)	100.0 cm (3 shaku 3 sun)	127.3 cm (4 shaku 2 sun)	142.4 cm (4 shaku 7 sun)
Material	Main Part: Aluminum Tape: Steel Stopper Screw: Polycarbonate resin				

	65107	65108	65109	65105	65106
Length Tolerance	±0.4 mm	±0.6 mm	±0.8 mm	±0.9 mm	±1.0 mm
Measuring Range	36.4 cm (1 shaku 2 sun)	69.7 cm (2 shaku 3 sun)	100.0 cm (3 shaku 3 sun)	127.3 cm (4 shaku 2 sun)	142.4 cm (4 shaku 7 sun)
Material	Main Part: Aluminum Tape: Steel Stopper Screw: Polycarbonate resin				

*Length tolerance is the accuracy when measured at normal temperature.

Shaku Measure



	65132	65133
1st Side	Metric graduation (1 mm pitch) + Shaku graduation (5 rin pitch)	
2nd Side	Shaku graduation (5 sun pitch)	
3rd Side	Stud (1 shaku 5 sun pitch)	Stud (1 shaku 6 sun 2 bu 5 rin pitch)
4th Side	This side lets you write down graduations with a pencil	

Item Code	Description	Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65132	12 shaku	23×19	950	4	1	
65133	13 shaku 5 sun	23×19	1,050	4		

Refer to P. 2 about the shaku scale

Features

- Tough aluminum product. Unlike wooden products, it will not warp under wet conditions.
- Having metric and shaku graduations reduces measurement errors
- Easy-to-read and fade-resistant graduations
- Graduations on all four sides
- Comes apart for better portability. Locks easily by sliding back together.
- Rubber caps on both ends prevent scratching
- Includes a tough nylon carry case

Use

- As shaku measure for laying out foundations
- As a template to make a disposable shaku measure stick

Specifications

	65132	65133
Length (split)	3,680 (1,840) mm	4,120 (2,060) mm
Length Tolerance	-0.8 - +1.3 mm	
Straightness Tolerance	Within 3 mm	Within 3.4 mm
Material	Main Part: Aluminum Edge: Rubber	

Ken Measure



65180

1st Side	Metric graduation (1 mm pitch) + Shaku graduation (5 rin pitch)
2/3/4th Side	This side lets you write down graduations with a pencil



Item Code	Description	Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65180	12 shaku	23×19	950	4 960910 651807	1	B


Refer to P. 2 about the shaku scale

Features

- Tough aluminum product. Unlike wooden products, it will not warp under wet conditions
- Having metric and shaku graduations reduces measurement errors
- Easy-to-read and fade-resistant graduations
- Comes apart for better portability. Locks easily by sliding back together.
- Rubber caps on both ends prevent scratching
- Includes a tough nylon carry case



- Special tape is pasted on the third side for notes and markings



- Can be cleaned with thinner

Use

- For carpenters Ideal for marking off pillars in the process of building a new house (For measurement of dimensions, pitches, dovetails, measurement for joining lumber, special pitches for studs 1shaku 2sun or 1m intervals, etc.)
- For roof tilers Ideal for marking intervals of crossbars on a rafter
- For construction workers Ideal for marking intervals for packing during installation of concrete boards or L-shape retaining walls

Specifications

Length (divided length)	3,680 (1,940) mm
Length Tolerance	−0.8 - +1.3 mm
Straightness Tolerance	Within 3 mm (for total length)
Material	Main Part: Aluminum Edge: Rubber

Aluminum Box Beam Straight Measure



65260 65262 65264 65266

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
65260	135 cm	1,350×60×20	990	4 960910 652606	1	B
65262	175 cm	1,750×60×20	1,270	4 960910 652620		
65264	195 cm	1,950×60×20	1,430	4 960910 652644		
65266	230 cm	2,300×60×20	1,680	4 960910 652668		

Features

- High precision for accurate check of straightness in base alignment of window frames, door frames and walls, etc.



- Scale side is broad to enable stable measurement without wobble
- Writeable tape so measurements and marks can easily be erased




Use

- For checking base alignment straightness of window frames, door frames and walls, etc.

Specifications

	65260	65262	65264	65266
Material	Main Part: Aluminum	Side-cap: ABS resin		
Straightness Tolerance	Less than 0.30 mm	Less than 0.35 mm	Less than 0.40 mm	Less than 0.45 mm

4. Resin Folding Rules/ Bamboo Rules




Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Bamboo Rule


71760



71919



71854



Item Code	Description	Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
71760	30 cm with Hole	300×23×4	22		10	
71765	50 cm with Hole	500×23×4	42			
71773	1 m with Hole	1,000×28×4	91			
71897	Kane 1 shaku	303×23×3	17			
71900	Kane 2 shaku	606×23×4	45			
71919	Kane 3 shaku	909×28×5	88			
71854	Kujira 2 shaku for Kimono	758×23×4	57			

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

- Made of bamboo to fit in the hands
- 1 mm pitch for both upper and lower graduations (71760)



Use

- Kane-shaku: For building work
- Kujira-shaku: For Japanese traditional dressmaking

Specifications

Length Tolerance	Less than 50 cm: ±0.5 mm 1 m: ±1 mm
Material	Bamboo

About the Graduations

Kane-shaku

The shaku of Kane-shaku was named after the brass-made scale in the Edo era. 1 shaku is equivalent to 8 sun of Kujira-shaku. (= 30.3 cm)

Kujira-shaku

It was originally made out of a barb of whale (Kujira). It is used for dressmaking. 1 shaku of Kujira shaku is defined as 1 shaku 2 sun 5 bu Kane - shaku.

Fiberglass Folding Rule




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78625	5-folding 1 m Black	1,000×15×3.2	67	4 960910 786257	5	
78605	5-folding 1 m	1,000×15×3.2	67	4 960910 786059		
78606	10-folding 1 m	1,000×13×2.2	44	4 960910 786066		
78833	10-folding 2 m	2,000×15×3.2	131	4 960910 788336		
78633	5-folding 1 m Black in Bulk	1,000×15×3.2	67	4 960910 786332	20	
78705	5-folding 1 m in Bulk	1,000×15×3.2	67	4 960910 787056		
78708	10-folding 1 m in Bulk	1,000×13×2.2	44	4 960910 787087		
78841	10-folding 2 m in Bulk	2,000×15×3.2	131	4 960910 788411	10	
78623	5-folding 1 m/shaku	1,000×15×3.2	67	4 960910 786233	5	
78624	5-folding 1 m/shaku in Bulk	1,000×15×3.2	67	4 960910 786240	20	

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

- Highly durable, as moving parts can withstand folding 25,000 times with little wear and no reduction in performance
- Glass fiber has been combined into nylon resin to provide high rigidity and superior straightness



- Joints are wire-reinforced to stay securely fastened and be resistant to breaking or bending




- Nylon resin construction makes it resistant to rust



- Easy-to-read, large numbers
- Does not conduct electricity well, and will not conduct electricity up to about 11,000 V



- Click stops at 90 and 180 degrees



- Folds up for portability


Use

- For measuring length, drawing lines and boning rod measurement

Specifications

Length	0 - 1,000 mm: ±1.0 mm
Tolerance	1,001 - 2,000 mm: ±1.4 mm
Material	Nylon resin with fiberglass

5. Squares/Protractors




Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Japanese Try Square



62006



62009

Item Code	Description	Base Length×Width×Thickness (mm)	Blade Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62014	13 cm with Square Scale	94×18×8	161×18×1.5	110	4 960910 620148	6	
62006	15 cm with Square Scale	94×18×8	177×18×1.5	114	4 960910 620063	6	
62009	15 cm	94×18×8	177×18×1.5	114	4 960910 620094	6	


Features

- 13 cm/15 cm with square scale can be used to work out the size of lumber you can cut from a log


Use

- For inspection of the right angle on material objects or products

Inspection of the angle



Square scribing




Specifications

Angle Tolerance	90°: Less than 0.1 mm per 100 mm
Length Tolerance	±0.3 mm
Material	Stainless steel

Miter Rule 45°/90°




62081



32674



62081/32674




62189

Item Code	Description	Base Length×Width×Thickness (mm)	Blade Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62081	Standard Model	163×15×5	170×100×1.5	177	4 960910 620810	6	
32674	Standard Model S-1462 Inch Graduations	163×15×5	170×100×1.5	177	4 960910 326743	6	
62189	with 40 mm Wide Fence	163×40×5	170×100×1.5	334	4 960910 621893	6	


Features

- Use as a Try Square and Miter Gauge
- Mark both left and right 45° angles with one side

As Miter Gauge



As Try Square



Use

- For testing accuracy of 45 and 90-degree angles

Specifications


Angle Tolerance	45°: Less than 0.2 mm per 100 mm 90°: Less than 0.1 mm per 100 mm
Length Tolerance	±0.3 mm
Material	Stainless steel

Miter Rule 45°

62103




62060



62110



62103
62060
62110




62162

Features

- Helps check and scribe 45 degrees easily
- Four different types available: Standard, With Graduations, With Right Angle, and With 40 mm Plate

Use

- For testing 45° angles, drawing lines, and scribing
- With Right Angle: Testing 90° angles, drawing lines, and scribing




Specifications

Angle Tolerance	45° and 90°: Less than 0.2 mm per 100 mm
Length Tolerance	±0.3 mm
Material	Stainless steel


Item Code	Description	Base Length×Width×Thickness (mm)	Blade Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62103	Standard Model	115×15×5	172×62×1.5	119	4 960910 621039	12	
62060	with Graduations	115×15×5	172×62×1.5	119	4 960910 620605	12	
62110	with Right Angle	115×15×5	172×62×1.5	133	4 960910 621107	12	
62162	with 40 mm Wide Fence	116×40×6	172×62×1.5	251	4 960910 621626	6	

Miter Rule 3D 45°90°

62113



62112




Features

- Can confirm 45 and 90-degree angles at the same time, and is easy to use for scribing line
- Can draw a 15mm wide line necessary for areas such as a crown molding
- Excellent stability

Use

- For testing precise 45 and 90-degree angles
- For marking the base layout of a 45-degree angle



Specifications

	62113	62112
Angle Tolerance	45° and 90°: Less than 0.2 mm per 100 mm	
Length Tolerance	±0.2 mm	
Material	Aluminum	Polycarbonate


Item Code	Description	Overall Length×Height×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62113	Aluminum	168×63×73	90	4 960910 621138	6	
62112	Polycarbonate	169×63×73	44	4 960910 621121	6	

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Miter Rule 3D 45°


62114



Features

- Mark precise 45-degree angles both left and right just by sliding the Miter Rule. No need to reverse the gauge itself.
- Excellent stability
- Convenient to work on baseboard corners

Use




- For testing precise 45 and 90-degree angles
- For marking the base layout of a 45-degree angle

Specifications

Angle Tolerance	45° and 90°: Less than 0.2 mm per 100 mm
Length Tolerance	±0.2 mm
Material	Aluminum

Item Code	Description	Overall Length×Height×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62114	Aluminum	200×63×73	100	4 960910 621145	6	

Sliding Bevel



Features

- Can be adjusted to any angle
- Lightweight and solid aluminum handle
- Fixing screw on the tail doesn't get in the way

Use

- Scribing and drawing of any angle
- For scribing dovetail or ink scribing

Specifications

Material	Blade: Stainless steel Handle: Aluminum
----------	---

Item Code	Description	Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
33919	SB-8 8"	235×22×17	120	4 960910 339194	6	
33921	SB-10 10"	285×25×17	160	4 960910 339217	6 (60)	

Japanese Bevel

62502



Features

- Can be adjusted to any angle

Use

- Scribing and drawing of any angle

Specifications

Material	Stainless steel
----------	-----------------

Item Code	Description	Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62502	25 cm	250(150)×15×2	91	4 960910 625020	12	
62510	30 cm	300(180)×15×2	109	4 960910 625105		
62529	45 cm	450(300)×15×2	171	4 960910 625297		
62532	60 cm	600(400)×15×2	235	4 960910 625327	5	

Japanese Sliding Bevel

62596




Features

- Can be adjusted to any angle
- Sliding bevel can be fixed at any angle with screw stoppers

Use

- Scribing and drawing of any angle
- For scribing dovetail or ink scribing



Specifications

Material	Body: Stainless steel Screw: Brass
----------	------------------------------------

Item Code	Description	Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62588	15 cm	180×14×5.5	111	4 960910 625884		
62596	25 cm	250×19×5.5	202	4 960910 625969	12	

Aluminum Sliding Bevel

62661




Angle Graduation



62570



Gradient Graduation




62540



Features


- Useful for checking angles on welded areas
- Blade can be on either side of the stock for symmetrical work
- Cross brace prevents any accidental change in angle
- Light aluminum material
- Thick blade can be used as a guide for a circular saw
- Angle scale is 1° pitch for 20° - 120°, and gradient scale is 1/10 pitch for 0 - 10
- Screw stopper easy to tighten and loosen



- Measured angles can be written on a specially installed tape with a pen or pencil. (An eraser works well on this if a pencil is used.)

Use

- For scribing or copying an angle such as a roof's gradient
- After measuring the gradient, it can be used as a guide for a circular saw
- Model with graduation can be used to measure length as well



Scribing



As a circular saw guide



Specifications

	62660	62569
Length Tolerance	±0.3 mm	
Material	Body: Aluminum	Screw: Polypropylene resin

	62661	62570	62540
Length Tolerance	±0.35 mm		—
Material	Body: Aluminum	Screw: Polypropylene resin	

	62662	62571	62541
Length Tolerance	±0.35 mm		—
Material	Body: Aluminum	Screw: Polypropylene resin	

	62572	62542
Length Tolerance	±0.4 mm	
Material	Body: Aluminum	Screw: Polypropylene resin

	62573
Length Tolerance	±0.4 mm
Material	Body: Aluminum Screw: Polypropylene resin

Item Code	Description	Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62660	30 cm with Angle Scale	355×30×28	265	4 960910 626607	5	
62661	45 cm with Angle Scale	505×30×28	380	4 960910 626614		
62662	60 cm with Angle Scale	655×30×28	480	4 960910 626621		
62569	30 cm with Gradient Scale	355×30×28	265	4 960910 625693		
62570	45 cm with Gradient Scale	505×30×28	380	4 960910 625709		
62571	60 cm with Gradient Scale	655×30×28	480	4 960910 625716	1	
62572	90 cm with Gradient Scale	955×30×28	680	4 960910 625723		
62573	1.2 m with Gradient Scale	1,255×30×28	880	4 960910 625730		
62540	45 cm without Scale	505×30×28	380	4 960910 625402	5	
62541	60 cm without Scale	655×30×28	480	4 960910 625419		
62542	90 cm without Scale	955×30×28	680	4 960910 625426		

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Mini Try Square Brass Base

62020

62021

62022

62023

Item Code	Description	Base Length×Width×Thickness (mm)	Blade Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62020	4.5 cm	35×12×6	45×11×1.5	26	4 960910 620209	12	
62021	6 cm	40×12×6	60×11×1.5	30	4 960910 620216		
62022	7.5 cm	48×15×6	75×13×1.5	45	4 960910 620223		
62023	9 cm	55×15×6	90×13×1.5	53	4 960910 620230		

Features

- Ideal small square for personal use



Use

- For testing a right angle and scribing

Specifications

	62020	62021	62022	62023
Angle Tolerance	Less than 0.04 mm per 45 mm	Less than 0.06 mm per 60 mm	Less than 0.07 mm per 75 mm	Less than 0.09 mm per 90 mm
Material	Base: Brass Blade: Stainless steel			


Try Square Aluminum Base without Graduations

74110

Item Code	Description	Base Length×Width×Thickness (mm)	Blade Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74110	20 cm	140×30×20	200×30×1.5	233	4 960910 741102	1	
74111	25 cm	140×30×20	250×30×1.5	249	4 960910 741119		
74112	30 cm	200×30×20	300×30×1.5	341	4 960910 741126		
74113	35 cm	200×30×20	350×30×1.5	357	4 960910 741133		
74114	40 cm	250×40×30	400×40×1.5	797	4 960910 741140		
74115	45 cm	250×40×30	450×40×1.5	825	4 960910 741157		
74116	50 cm	250×40×30	500×40×1.5	852	4 960910 741164		
74117	60 cm	300×40×30	600×40×1.5	1,015	4 960910 741171		
74118	70 cm	300×40×30	700×40×1.5	1,065	4 960910 741188		
74119	90 cm	450×40×30	900×40×2.0	1,395	4 960910 741195		
74120	1 m	450×40×30	1,000×40×2.0	1,404	4 960910 741201		

Features

- Ideal square for wood materials
- Variety of sizes from 20 cm to 1 m
- Long blade models come in handy to mark across multiple items
- Large base helps to test a right angle



Use

- For testing a right angle and scribing

Specifications

Angle Tolerance	Less than 0.1 mm per 100 mm
Material	Base: Brass Blade: Stainless steel

Miter Try Square

62286

Item Code	Description	Base Length×Width×Thickness (mm)	Blade Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62286	20 cm	130×40×14	200×40×1.5	205	4 960910 622869	1	
62294	25 cm	130×40×14	250×40×1.5	234	4 960910 622944		
62308	30 cm	130×40×14	300×40×1.5	250	4 960910 623088		
32255	S-1421 20 cm/8"	*	130×40×14	205	4 960910 322554		
32263	S-1422 25 cm/10"	*	130×40×14	234	4 960910 322639		
32271	S-1423 30 cm/12"	*	130×40×14	250	4 960910 322714		


*S-1421, 1422 and 1423 are made-to-order items.

Features

- Graduations on the blade enable to measure dimensions
- Large base helps to test a right angle

Use

- For testing a right angle and scribing
- For scribing 45°



Specifications

Angle Tolerance	45°: Less than 0.4 mm per 100 mm 90°: Less than 0.1 mm per 100 mm
Length Tolerance	±0.2 mm
Material	Base: Aluminum Blade: Stainless steel

Protractor Hard Chrome Finish



62995

- 10 cm compact size
- Pocket-sized portable



62480

- Classic protractor



62490



62901

- Center lock nut has a needle built-in to hold in the center



62928

- Square protractor board guides outside edge



62774



62868

- Groove on the protractor board allows the blade to be locked tightly



62952

- Trigonometric function chart on the back


Item Code	Description	Angle Plate			Blade			Weight (g)	JAN Code	Packing Unit	Packaging
		Diameter (mm)	Thickness (mm)	Angle pitch	Single 2blade	Length (mm)	Graduator (cm)				
62995	Mini 40 10 cm	40	1.0	2°	2	100	10	20	4 960910 629950	10	
62480	No.19 90 10 cm	90	1.2	1°	1	153	10	65	4 960910 624801	10	
62490	No.19 Double-blade 90 10 cm	90	1.2	1°	2	153	10	82	4 960910 624900	10	
62901	No.182 90 10 cm	90	1.2	1°	1	153	10	80	4 960910 629011	1	
62928	No.183 Square 10 cm	Square	1.2	1°	1	153	10	100	4 960910 629288	1	
62774	No.30 120	120	1.5	1°	1	245	—	150	4 960910 627741	5	
62868	No.101 120 15 cm with Groove	120	1.5	1°	1	245	15	150	4 960910 628687	5	
62898	No.300 210 30 cm	210	2.0	0.5°	1	385	30	500	4 960910 628984	1	
62839	No.300 Double-blade 210 30 cm	210	2.0	0.5°	2	385	30	660	4 960910 628397	1	
62855	No.600 320 60 cm	320	2.5	0.5°	1	650	60	1,350	4 960910 628557	1	
62944	No.600 Double-blade 320 60 cm	320	2.5	0.5°	2	650	60	1,900	4 960910 629448	1	
62847	No.1000 320 1 m	320	2.5	0.5°	1	1,050	100	1,600	4 960910 628472	1	
62952	No.1000 Double-blade 320 1 m	320	2.5	0.5°	2	1,050	100	2,400	4 960910 629523	1	

Features

- Etching + black chrome coating on graduations help to last long
- Bold, easy-to-read graduations
- Hard chrome finish provides its surface with excellent durability and prevents glare on the scale for high readability
- Double blade model firmly matches shapes that a regular protractor board can't match




Measures the angle on the edge of a blade



Measures any angles




Expands up to 20 cm




- No.300-No.1000 have a trigonometric function chart on the back

Use


- For measuring angles, scribing, and measuring length



Scribing



Length Measure




*Except 62774

Specifications

	62995
Material	Main Part: Stainless steel Fixing Pin: Stainless steel Metal Washer: Brass
	62480 62490 62901 62928 62774 62868
Material	Main Part: Stainless steel Screw: Brass
	62898 62839 62855 62944 62847 62952
Material	Main Part: Stainless steel Screw: Iron

Example of use



Protractor Polish Finish

62987



- 10cm compact size
- Pocket-sized portable

62499



- Polish finish offers both fine metallic luster and reasonable price

Item Code	Description	Angle Plate			Blade			Weight (g)	JAN Code	Packing Unit	Packaging
		Diameter (mm)	Thickness (mm)	Angle patch	1:Single 2:Double	Length (mm)	Graduation (cm)				
62987	Mini $\phi 40$ 10 cm	40	1.0	2'	2	100	10	20	4 960910 629875	10	
62499	No.19 $\phi 90$ 10 cm	90	1.2	1'	1	153	10	65	4 960910 624993	10	

Features


- Etching + black chrome coating on graduations help to last long
- Bold, easy-to-read graduations

Use

- For measuring angles, scribing, and measuring length

Specifications

	62987	62499
Material	Main Part: Stainless steel Fixing Pin: Stainless steel Metal Washer: Brass	Main Part: Stainless steel Screw: Brass



Digital Protractor



62495




Item Code	Description	Overall Length×Width×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62495	20 cm with Hold Function	217×35×20	162	4 960910 624955	5	
62496	30 cm with Hold Function	317×35×20	224	4 960910 624962	5	

Features

- Easy-to-read digital display
- Includes hold function
- Nob to fix angle



- Long-lasting, etched graduations
- Left end reference point and inside reference point at right angle are useful for measuring



- Can be fully straightened



Use

- Angle measurement, length measurement, scribing

Specifications


	62495	62496
Angle Tolerance	$\pm 0.3^\circ$	
Length Tolerance	Up to 200 mm: ± 0.2 mm (range when not connecting two rules)	Up to 300 mm: ± 0.3 mm (range when not connecting two rules)
Minimum Reading	Angle: 0.1° Length: 1 mm	
Measuring Range	Angle: $0 - 359.9^\circ$ Length: 0 - 395 mm	Length: 0 - 595 mm
Temperature and Humidity for Use	Temperature: $0 - 50^\circ\text{C}$, Humidity: Up to 85%	
Auto Power Off	Approximately 5 minutes	
Battery	1x Lithium battery CR2032 (Battery included is for trial use only and may not last as long)	
Material	Rule: Stainless steel	Module: ABS resin

6. Vernier Calipers/Micrometers



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Vernier Caliper




Features

- Easy-to-use standard vernier caliper
- Includes storage case (19920/19921/19922)

Use

- For measuring outside, inside, depth, and gap (19899/19912/19913)
- For measuring outside, inside, and gap (19920/19921/19922)

Specifications



	19899	19912	19913
Body Size	a 235 mm	a 296 mm	a 410 mm
	b 77 mm	b 90 mm	b 100 mm
	c 16 mm	c 18 mm	c 20 mm
	d 40 mm	d 50 mm	d 55 mm
	e 54 mm	e 55 mm	e 60 mm
	f 16 mm	f 16 mm	f 18 mm
	g 3.6 mm	g 3.6 mm	g 4.4 mm
	Product Weight 150 g	180 g	326 g
Material	Stainless steel		
Depth Probe	Attached		
Accuracy	±0.07 mm		±0.08 mm


	19920	19921	19922
Body Size	a 620 mm	a 770 mm	a 1,220 mm
	b 159 mm	b 159 mm	b 221 mm
	c 38 mm	c 38 mm	c 50 mm
	d 90 mm	d 90 mm	d 130 mm
	e 92 mm	e 92 mm	e 124 mm
	f 24 mm	f 24 mm	f 32 mm
	g —	g —	g —
	Product Weight 1,000 g	1,200 g	3,300 g
Material	Stainless steel		
Depth Probe	None		
Accuracy	±0.1 mm		±0.15 mm

Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Packaging
19899	150 mm	0.05 - 150	0.05	4 960910 198999	6	
19912	200 mm	0.05 - 200	0.05	4 960910 199125		
19913	300 mm	0.05 - 300	0.05	4 960910 199132		
19920	450 mm	0.05 - 450	0.05	4 960910 199200	1	
19921	600 mm	0.05 - 600	0.05	4 960910 199217		
19922	1000 mm	0.05 - 1000	0.05	4 960910 199224		



JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery cm/shaku (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Mini Vernier Caliper



19894



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Packaging
19892	70 mm	0.05 - 70	0.05	4 960910 198920	10	
19894	100 mm	0.05 - 100	0.05	4 960910 198944	10	

Features

- Small size, portable
- Same high precision as larger model


Use

- For measuring outside, inside, depth, and gap



Specifications

	19892	19894
Body Size	a 114 mm	a 160 mm
	b 39 mm	b 60 mm
	c 8.5 mm	c 14 mm
	d 18.5 mm	d 30 mm
	e 28 mm	e 37 mm
	f 8 mm	f 12 mm
	g 1.7 mm	g 2.3 mm
Weight	22 g	71 g
Material	Stainless steel	
Depth Probe	Attached	
Accuracy	±0.06 mm	

Pocket Vernier Caliper



19518



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Packaging
19518	100 mm	0.1 - 100	0.1	4 960910 195189	10	

Features

- Small size, portable


Use

- For measuring outside, inside, depth, and gap


Specifications

Body Size	a	157 mm
	b	52 mm
	c	12 mm
	d	28 mm
	e	37 mm
	f	12 mm
	g	3.5 mm
Weight	39 g	
Material	Stainless steel	
Depth Probe	Attached	
Accuracy	±0.1 mm	



Vernier Caliper Plastic Body



19514



19515



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Packaging
19514	70 mm	0.1 - 70	0.1	4 960910 195141	10	
19515	100 mm	0.1 - 100	0.1	4 960910 195158	10	

Features

- Light and compact, easy carrying
- Strap hole
- Polycarbonate is tough and stable. Rustproof and will not scratch other surfaces




Use

- For measuring outside, inside, depth, and gap

Specifications

	19514	19515
Body Size	a 114 mm	a 161 mm
	b 40 mm	b 58 mm
	c 8 mm	c 11 mm
	d 19 mm	d 27 mm
	e 30 mm	e 41 mm
	f 10.5 mm	f 15 mm
	g 2.7 mm	g 3.9 mm
Weight	6 g	15 g
Material	Polycarbonate	
Depth Probe	Attached	
Accuracy	±0.1 mm	

Fiberglass Dial Caliper



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Packaging
19932	150 mm	0.1 - 150	0.1	4 960910 199323	5	C

Features

- Easy-to-read scale
- Will not scratch other surfaces







Use

- For measuring outside, inside, depth, and gap

Specifications

Body Size	a	224 mm
	b	77 mm
	c	14 mm
	d	39 mm
	e	38 mm
	f	16 mm
	g	3.8 mm
Weight	44 g	
Material	Nylon resin (with fiberglass)	
Depth Probe	Attached	
Accuracy	±0.1 mm	

Digital Vernier Caliper with Hold Function



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Packaging
19974	Mini 100 mm	0.01 - 100	0.01	4 960910 199743	3	SP
19975	150 mm	0.01 - 150	0.01	4 960910 199750		
19976	200 mm	0.01 - 200	0.01	4 960910 199767		
19977	300 mm	0.01 - 300	0.01	4 960910 199774	1	B
19986	450 mm	0.01 - 450	0.01	4 960910 199866		
19987	600 mm	0.01 - 600	0.01	4 960910 199873		
19988	1000 mm	0.01 - 1,000	0.01	4 960910 199880		

Features

- Ideal for precision work with a minimum reading value of 0.01 mm
- Zero set function enables relative measurement or indirect measurement
- Hold function is useful when the screen cannot be seen
- Moisture resistant (19974/19975/19976/19977)
- Able to measure large objects (19986/19987/19988)
- Preset function enables to adjust zero point in 0.01 mm units (19986/19987/19988)



Use


- For measuring outside, inside, depth (19974/19975/19976/19977), and gap
- For relative measurement and indirect measurement

Specifications

	19974	19975	19976	19977	19986	19987	19988
Body Size	a 167 mm	a 235 mm	a 294 mm	a 400 mm	a 626 mm	a 776 mm	a 1233 mm
	b 60 mm	b 77 mm	b 90 mm	b 102 mm	b 169 mm	b 169 mm	b 216 mm
	c 12 mm	c 15 mm	c 19 mm	c 19 mm	c 38 mm	c 38 mm	c 50.8 mm
	d 30 mm	d 40 mm	d 50 mm	d 60 mm	d 100 mm	d 100 mm	d 125 mm
	e 50 mm	e 62 mm	e 62 mm	e 62 mm	e 100 mm	e 100 mm	e 130 mm
	f 13 mm	f 16 mm	f 16 mm	f 17 mm	f 24 mm	f 24 mm	f 31 mm
	g 3.6 mm	g 3.6 mm	g 3.6 mm	g 3.6 mm	g —	g —	g —
	Weight	92 g	155 g	179 g	280 g	980 g	1,100 g
Material	Body: Stainless steel Display Unit: ABS resin						
Depth Probe	Attached				None		
Accuracy	±0.03 mm			±0.04 mm	±0.05 mm		±0.1 mm
Minimum Reading	0.01 mm						
Repeatability	0.01 mm						
Use Temperature	0 - 40°C						
Storage Temperature	-10 - 60°C						
Storage Humidity	Below 80%						
Battery	1x Silver oxide battery SR44				1x Lithium battery CR2032		
	(Battery included is for trial use only and may not last as long)						

*Repeatability means the precision earned after repeated measurement.

Digital Vernier Caliper with Solar Panel



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Package
19983	150 mm	0.01 - 150	0.01	4 960910 199835	3	
19984	200 mm	0.01 - 200	0.01	4 960910 199842	3	

Features

- Ideal for precision work with a minimum reading value of 0.01 mm
- Dual power model with solar panel and lithium battery
- *Solar panel reduces the use of battery when surrounding illuminance is over 200 lux.
- Zero set function enables relative measurement or indirect measurement
- Auto power off function

Use


- For measuring outside, inside, depth, and gap
- For relative measurement and indirect measurement

Specifications

	19983	19984
Body Size	a 235 mm	a 286 mm
	b 76 mm	b 90 mm
	c 16 mm	c 19 mm
	d 40 mm	d 46 mm
	e 70 mm	e 70 mm
	f 16 mm	f 16 mm
	g 3.7 mm	g 3.7 mm
Weight	160 g	187 g
Material	Body: Stainless steel Display Unit: ABS resin	
Depth Probe	Attached	
Accuracy	±0.03 mm	
Minimum Reading	0.01 mm	
Repeatability	0.01 mm	
Use Temperature	0 - 40°C	
Storage Temperature	-10 - 60°C	
Storage Humidity	Below 80%	
Battery	Solar panel / 1x Lithium battery CR2016 (Battery included is for trial use only and may not last as long)	

*Always use the item with a battery installed.
 Using it without a battery may cause malfunction.
 *Repeatability means the precision earned after repeated measurement.

Digital Vernier Caliper Carbon Fiber Body



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Package
19978	100 mm	0.1 - 100	0.1	4 960910 199781	5	
19979	150 mm	0.1 - 150	0.1	4 960910 199798	5	

Features

- Automatically powered on/off just by sliding the module (19978/19979)
- With auto power off function
- Zero set function enables relative measurement or indirect measurement
- Will not scratch other surfaces
- Strap hole (19978)
- Dual power model with solar panel and lithium battery
- *Solar panel reduces the use of battery when surrounding illuminance is over 200 lux.

Use


- For measuring outside, inside, depth (19979/19981), and gap
- For relative measurement and indirect measurement

Specifications

	19978	19979	19981
Body Size	a 178 mm	a 237 mm	a 237 mm
	b 61 mm	b 77 mm	b 77 mm
	c 12 mm	c 16 mm	c 16 mm
	d 30 mm	d 40 mm	d 40 mm
	e 50 mm	e 63 mm	e 70 mm
	f 13 mm	f 16 mm	f 16 mm
	g —	g 3.9 mm	g 3.9 mm
Weight	34 g	56 g	59 g
Material	Body: Carbon fiber composite Display Unit: ABS resin		
Depth Probe	None	Attached	
Accuracy	Outside Measurement: ±0.3 mm Inside Measurement: ±0.5 mm		
Minimum Reading	0.1 mm		
Repeatability	0.1 mm		
Use Temperature	0 - 40°C		
Storage Temperature	-10 - 60°C		
Storage Humidity	Below 80%		
Battery	1x Silver oxide battery SR44		Solar panel / 1x Lithium battery CR2016
	(Battery included is for trial use only and may not last as long)		


*Always use the item with a battery installed.
 Using it without a battery may cause malfunction.
 *Repeatability means the precision earned after repeated measurement.

Digital Vernier Caliper Carbon Fiber Body with Solar Panel



Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	JAN Code	Packing Unit	Package
19981	150 mm	0.1 - 150	0.1	4 960910 199811	5	

Depth Gauge



Item Code	Description	Measurement Range (mm)	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
19300	Mini	0 - 20	60×55×10	32	4 960910 193000	10	

Features

- Small size, easy carrying
- Fixing screw

Use

- For measuring groove depth on tires


Specifications

Material	Body: Stainless steel Screw: Iron
Accuracy	±0.1 mm

[For Reference] Minimum Tire Groove Depth

Bicycle	0.8 mm
Passenger Car	1.6 mm
Small Truck	1.6 mm
Large Truck	1.6 mm
Bus	1.6 mm

Digital Depth Gauge



Item Code	Description	Measurement Range (mm)	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
19305	Mini 25 mm	0.1 - 25	112.5×60×15	43	4 960910 193055	10	

Features

- Resin construction makes it lightweight as well as rustproof, and will not scratch other surfaces
- Automatically turns on just by sliding the module
- Auto power off function

Use


- For measuring various depths

Specifications

Material	Body: Nylon resin (with fiberglass) Digital Module: ABS resin
Accuracy	±0.2 mm
Minimum Reading	0.1 mm
Repeatability	0.1 mm
Use Temperature	0 - 40°C
Storage Temperature	-10 - 60°C
Storage Humidity	Below 80%
Battery	1x Silver oxide battery SR44 (Battery included is for trial use only and may not last as long)

*Repeatability means the precision earned after repeated measurement.

Digital Depth Gauge with Hold Function



Item Code	Description	Measurement Range (mm)	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
19306	150 mm	0.01 - 150	232×100×15	166	4 960910 193062	3	
19307	200 mm	0.01 - 200	284×100×15	187	4 960910 193079		

Features

- Ideal for precision work with a minimum reading value of 0.01 mm
- Zero set function enables relative measurement or indirect measurement
- Hold function is useful when the screen cannot be seen
- Automatically turns on just by sliding the module
- Auto power off function



Use

- For measuring depth

Specifications

	19306	19307
Material	Body: Stainless steel Digital Module: ABS resin	
Accuracy	±0.03 mm	
Minimum Reading	0.01 mm	
Repeatability	0.01 mm	
Use Temperature	0 - 40°C	
Storage Temperature	-10 - 60°C	
Storage Humidity	Below 80%	
Battery	1x Silver oxide battery SR44 (Battery included is for trial use only and may not last as long)	

*Repeatability means the precision earned after repeated measurement.

Micrometer



78935



78936


Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78935	0 - 25 mm	0.01 - 25	0.01	52×128×20	205	4 960910 789357	3	
78936	25 - 50 mm	25 - 50	0.01	63×158×20	265	4 960910 789364		

Features

- Tough coating and plating for flake and rust-resistance
- Speedy adjustment to measurement base


Use

- For measuring thickness



Specifications

- Part names



Material	Anvil: Carbide alloy Spindle A: Carbide alloy Spindle B: Bearing steel
Accuracy	±0.01 mm (to measurement range)

Digital Micrometer





79523

○Front

- Part Name

○Back



Easy relative measurement with ZERO set switch

1. Measure the base



2. Push the ZERO set switch



3. The difference from the base is displayed



Features

- Digital display to read at a glance
- Speedy measurement with Thick Thimble + Ratchet knob
- Zero set function enables relative measurement or indirect measurement
- Auto power off function
- Spherical attachment, convenient to measure the thickness of pipe
- Superhard chip on measuring surface



Use

- For measuring thickness

Specifications

Material	Frame: SC steel Spindle: High-carbon chrome steel Measurement Surface: Superhard chip
Measuring Force	10 N
Accuracy	±0.003 mm
Minimum Reading	0.001 mm
Use Temperature	0 - 40°C
Storage Temperature	-20 - 60°C
Battery	1x Lithium battery CR2032 (Battery included is for trial use only and may not last as long)

Item Code	Description	Measurement Range (mm)	Minimum Measurement Value (mm)	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
79523	0 - 25 mm	0.001 - 25	0.001	61×156×28	201	4 960910 795235	2	

7. Tape Measures



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Tape Measure TOUGH GEAR HG



80821

Rust-resistant stainless tape and stainless spring
 Nylon-coated stainless tape for durability against friction and scratching

Nylon coating

Rust-resistant finish + baked finish

Stainless material



80818

- Models with Holder
- Strong cord with wire core
- Easily detachable belt holder



Features

- JIS Grade 1 (metric graduation model)
- Shock proof protector covers the body
- Shock absorber attached
- 455 mm pitch indication
- Zero point auto-correct hook
- All models come with a metal shaft strap as a standard. A safety cord can be attached.



- Models without Holder
- Safety cord included

- Magnetic Hook
- Strong neodymium magnet sticks well to steel frames



Use

- For measuring length

Specifications

Material	Body: ABS resin Cover: Elastomer resin Tape: Stainless steel
----------	--

● Tape pattern

80821 80823	25 mm	Front	2 3 4 5 6 7 8 9 10 1 2 3 4
	5.5 m	Back	2 3 4 5 6 7 8 9 10 1 2 3 4
80824	25 mm	Front	2 3 4 5 6 7 8 9 10 1 2 3 4
	7.5 m	Back	2 3 4 5 6 7 8 9 10 1 2 3 4
80822 80818	25 mm	Front	1 2 3 4 5 6 7 8 9 10 1 2 3 4
	5.5 m (shaku)	Back	2 3 4 5 6 7 8 9 10 1 2 3 4

Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
80821	HG 25-5.5 m	JIS	25	5.5	329	4	960910 808218
80822	HG 25-5.5 m/shaku	shaku/cm	25	5.5	329	4	960910 808225
80823	HG 25-5.5 m with Magnetic Hook	JIS	25	5.5	329	4	960910 808232
80824	HG 25-7.5 m	JIS	25	7.5	446	4	960910 808249
80818	HG 25-5.5 m/shaku with Holder	shaku/cm	25	5.5	385	4	960910 808188

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Tape Measure TOUGH GEAR SD



Features

- JIS Grade 1 (metric graduation model)
- Shock proof protector covers the body
- Shock absorber attached
- 455 mm pitch indication
- Zero point auto-correct hook
- All models come with a metal shaft strap as a standard. A safety cord can be attached.



- Models without Holder
- Safety cord included

- Magnetic Hook
- Strong neodymium magnet sticks well to steel frames


Use

- For measuring length

Specifications

Material	Body: ABS resin Cover: Elastomer resin Tape: Carbon tool steel
----------	--

Tape pattern



Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
80874	SD 25-5.5 m	JIS	25	5.5	314	4	(40)
80875	SD 25-5.5 m/shaku	shaku/cm	25	5.5	314	4	(40)
80876	SD 25-5.5 m with Magnetic Hook	JIS	25	5.5	314	4	(40)
80877	SD 25-7.5 m	JIS	25	7.5	440	4	(24)
80870	SD 25-5.5 m with Holder	JIS	25	5.5	376	4	(40)
80871	SD 25-5.5 m/shaku with Holder	shaku/cm	25	5.5	376	4	(40)
80872	SD 25-5.5 m with Magnetic Hook with Holder	JIS	25	5.5	376	4	(40)
80873	SD 25-7.5 m with Holder	JIS	25	7.5	510	4	(24)

Refer to P. 2 about the shaku scale

Tape Measure TOUGH GEAR Automatic Stop



Features

- JIS Grade 1 (metric graduation model)
- Automatic stopper locks the tape at any pulled position
- All models come standard with a shaft strap. A safety cord can be attached.
- Shock-proof protector covers the body
- Shock absorber attached
- 455 mm pitch indication
- Zero point auto-correct hook


Use

- For measuring length

Specifications

Material	Body: ABS resin, elastomer resin Tape: Carbon tool steel
----------	---

Tape pattern



Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
80814	19-5.5 m	JIS	19	5.5	258	4	(40)
80815	25-5.5 m	JIS	25	5.5	309	4	(40)
80816	25-5.5 m/shaku	shaku/cm	25	5.5	309	4	(40)
80813	25-5.5 m/shaku with Holder	shaku/cm	25	5.5	369	4	(40)

Refer to P. 2 about the shaku scale

Tape Measure RIGHT GEAR



80862




80863

Nylon-coated tape for durability against friction and scratching

Nylon coating

Baked finish

Carbon steel



80864



80866



80865



80867



80855



80868



Item Code	Description		Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
80862	19-5.5 m	JIS	19	5.5	222	4 960910 808621	12 (48)	C
80863	19-5.5 m/shaku	shaku/cl	19	5.5	222	4 960910 808638		
80864	25-5.5 m	JIS	25	5.5	268	4 960910 808645		
80866	25-5.5 m/shaku	shaku/cl	25	5.5	268	4 960910 808669		
80865	25-5.5 m with Magnetic Hook	JIS	25	5.5	268	4 960910 808652	6 (24)	C
80867	25-7.5 m	JIS	25	7.5	378	4 960910 808676		
80855	25-7.5 m/shaku	NEW! shaku/cl	25	7.5	378	4 960910 808553		
80868	25-7.5 m with Magnetic Hook	JIS	25	7.5	378	4 960910 808683		

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

● JIS Grade 1 (metric graduation model)




● Hook guard structure to protect hook from shocks due to drops, etc.



● Shock proof protector covers the body

● Convenient large hook hanger to attach a safety cord



● Shock absorber attached

● Belt clip

● Hand strap

● 455 mm pitch indication

● Zero point auto-correct hook

● Strong neodymium magnet sticks well to steel frames (80865/80868)

● Double-sided graduations (Metric graduations are vertical graduations on the reverse)



Use

● For measuring length

Specifications

Material	Body: ABS resin, elastomer resin Tape: Carbon tool steel
----------	---

● Tape pattern

80862	19 mm 5.5 m	Front	Back
80863	19 mm 5.5 m (shaku)	Front	Back
80864 80865	25 mm 5.5 m	Front	Back
80866	25 mm 5.5 m (shaku)	Front	Back
80855	25 mm 7.5 m (shaku)	Front	Back
80867 80868	25 mm 7.5 m	Front	Back

Tape Measure SMART GEAR



80882



80883

● Catchy POP box for retailers



Compact design



Large hook hanger



Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
80880	19-5.5 m	19	5.5	210	4 960910 808805	12 (48)	
80881	19-5.5 m/shaku	19	5.5	210	4 960910 808812		
80882	25-5.5 m	25	5.5	275	4 960910 808829		
80883	25-5.5 m/shaku	25	5.5	275	4 960910 808836		
72762	25-5.5 m with Magnetic Hook	25	5.5	275	4 960910 727625		

Refer to P. 2 about the shaku scale

Features

- Compact size easily fits in a pocket
- Convenient large hook hanger to attach a safety cord
- Shock absorber attached
- 455 mm pitch indication
- Zero point auto-correct hook
- Strong neodymium magnet sticks well to steel frames (72762)
- Double-sided graduations (Metric graduations are vertical graduations on the reverse)

Use

- For measuring length

Specifications

Material	Body: ABS resin, elastomer resin Tape: Carbon tool steel
----------	---

● Tape pattern

80880	19 mm 5.5 m	Front	
		Back	
80881	19 mm 5.5 m (shaku)	Front	
		Back	
80882 72762	25 mm 5.5 m	Front	
		Back	
80883	25 mm 5.5 m (shaku)	Front	
		Back	

Tape Measure



78002



78007

Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
78002	H-132 Free Type	JIS	13	2	70	4 960910 780026	12
78007	H-163 Free Type	JIS	16	3.5	128	4 960910 780071	

Features

- JIS Grade 1 (metric graduation model)
- Easy-to-hold, fits in the hand
- Zero point auto-correct hook
- Shock absorber attached (78007)
- 455 mm pitch indication
- Belt clip (78007)
- Hand strap
- Rust-resistant stainless spring

Use

- For measuring length

Specifications

Material	Body: ABS resin Tape: Carbon tool steel
----------	--

Holder



80825

Item Code	Description	JAN Code	Packing Unit	Packaging
80825	One-touch Holder for Measuring Tape	4 960910 808256	20	

Features

- Detachable with one touch
- Safety cord can be attached
- Detachable while belt is on

Use

- For tape measure holders

Specifications

- Attachable Belt: Less than 60 mm wide and less than 4 mm thick
- Attachable Tape Measure: Over 20 mm width of installing area and over 12 mm length of installation screw
- Installation stopper included

Material	Body: ABS resin, polycarbonate resin
----------	--------------------------------------

Spring Tape Measure

71005



Features

- Retract the tape by pushing the center button

Use

- For measurement in dressmaking and curved surfaces

Specifications

Body Size	φ54 × 20 mm
Length Tolerance	±1.4 mm
Material	Tape: Vinylchloride film with fiberglass Body/Tape End : ABS resin

Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
71005	1.5 m	8	1.5	25	4 960910 710054	10	

Flat Tape

71013



Front:
Vertical
graduations

Back:
Horizontal
graduations



Features

- For flexible measurement of various objects

Use

- For measurement in dressmaking and curved surfaces

Specifications

Length Tolerance	±1.9 mm
Material	Tape: Vinylchloride film with fiberglass Tape End: Steel Calking: Brass

Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
71013	1.5 m	15	1.5	15	4 960910 710139	10	


Fiberglass Tape Measure



78181



78184



Features

- JIS Grade 1
- Light and portable
- Graduations printed on both sides of the tape

Use

- For general measurement, road, railroad, or electric constructions

Specifications

- Standard Tension/Temperature: 10 N/20°C
- Front side (White) 2 mm pitch graduation
- Back side (Yellow) 5 mm pitch graduation


Material	Tape: Vinylchloride film with fiberglass Body: ABS resin
----------	---

Item Code	Description	Tape Width (mm)	Tape Length (m)	Weight (g)	JAN Code	Packing Unit	Packaging
78184	FW-30	JIS	12	30	450	4 960910 781849	1
78181	FW-50	JIS	12	50	700	4 960910 781818	


Zero Point Auto-correct Hook

The hook position automatically moves in order to correct the length error created by the thickness of the hook between the hook being pushed and pulled.

● Standard model



● Magnetic model



JIS B 7512 Steel Tape Measures

Tolerances on length for grade 1

{ L is a numerical value expressing the measured value in meters (rounding up the fraction less than 1 to an integer place) }

±{(0.2+0.1L) + 0.2} mm for tape measure whose reference point is its end face
 ±(0.2+0.1L) mm for tape measure whose reference point excludes its end face


JIS B 7522 Textile Tape Measures

Tolerances on length for grade 1 (Class 1 Line graduation)

{ L is a numerical value expressing the measured value in meters (rounding up a fraction less than 1 to an integer place) }


±(0.6+0.4L) mm

8. Surveying Products



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Aluminum Leveling Rod 60mm Wide



76931




76926

Item Code	Description	Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76931	30 cm	6	105	4 960910 769311	20	
76932	50 cm	6	175	4 960910 769328		
76933	70 cm	6	250	4 960910 769335		
76934	1 m	6	365	4 960910 769342		
76935	1.1 m	6	405	4 960910 769359		
77351	1.5 m	6	510	4 960910 773516	10	
77352	2 m	6	650	4 960910 773523		
76926	Cross Fitting for 60 mm Wide	70x25x68	126	4 960910 769267	5	

Leveling Rod

Features

- Light, thin aluminum material
- Center rib strengthens the structure against shock
- 100 mm of margin useful for joining with Cross Fitting or using inside as reference point (only 76935)



Use

- Photographic recording


Specifications

Material	Body: Aluminum End of Rods: Polypropylene resin
----------	--

Cross Fitting

Features

- Measure both vertically and horizontally by attaching to 60 mm width leveling rod




Use

- Attach to make a cross leveling rod

Specifications

Material	Body: Iron (chrome plating)
----------	-----------------------------

Aluminum Cross Leveling Rod 60mm Wide



76936

Item Code	Description	Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76936	1 x 1.1 m	25 (Metal)	900	4 960910 769366	5	

Features

- Includes two leveling rods and a cross metal fitting to measure both vertically and horizontally

Use

- For on-site record photography

Specifications

Material	Body: Aluminum End of Rods: Polypropylene resin Rods Fixture: Iron (chrome plating)
----------	---

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Plywood Leveling Rod 63 mm Wide with Aluminum Frame



Front




Back

76965



76980



76968

Item Code	Description	Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Package
76964	30 cm	12	152	4 960910 769649	1	B
76965	50 cm	12	253	4 960910 769656		
76966	70 cm	12	335	4 960910 769663		
76967	1 m	12	472	4 960910 769670		
76968	1 m 2 Folded	24	514	4 960910 769687	5	
76980	Cross Fitting for 63 mm Wide	73x73x34	215	4 960910 769809	1	VH

Leveling Rod

Features

- Veneer board is resistant to bending motion
- Numbers are marked every 1 cm on the vertical display side

Use

- For on-site record photography


Specifications

Material	Body: Veneer board Frame: Aluminum Tip End: Iron (chrome plating) Edge: Stainless (only folded type) Moveable Parts: Iron (chrome plating) (only folded type)
----------	---

Cross Fitting

Features

- Enables measuring both vertically and horizontally together by attaching to 63 mm width leveling rod



Use

- Attach to make a cross leveling rod

Specifications

Material	Body: Iron (chrome plating)
----------	-----------------------------

*Not compatible for 1 m folded type

Mini Telescopic Leveling Staff

Front · Metric graduation



Back · Metric + shaku graduation

76900




Item Code	Description	Size in Stored (mm)	Weight (g)	JAN Code	Packing Unit	Package
76863	2 m 2 Steps	1,085×26×14	370	4 960910 768635	6	VH
76900	3 m 3 Steps	1,140×30×20	670	4 960910 769007		

Features

- Convenient for measuring in rooms since graduations are measured in fine left and right 1 mm pitch
- Large end cap, graduations for inner measurement
- Drain holes for outdoor use

Use

- For horizontal, vertical, inner dimension and height measurements



Specifications

Material	Body: Aluminum
Length Tolerance	2 m 2 steps: ±1.5 mm per 1 m 3 m 3 steps: ±2 mm per 1 m

Telescopic Leveling Staff II

■Front Easy-to-read graduations every 10 mm
Red graduations every 50 mm



■Back 1 mm pitch graduations from the reference point

73266



73264



73265



73266



73267



73268

Item Code	Description	Size in Stored (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73264	3 m 3 Steps	1,188×50×27	1,100	4 960910 732643	2	
73265	5 m 3 Steps	1,893×50×27	1,700	4 960910 732650		
73266	5 m 4 Steps	1,489×50×27	1,650	4 960910 732667		
73267	5 m 5 Steps	1,244×50×27	1,600	4 960910 732674		
73268	7 m 5 Steps	1,645×50×27	2,100	4 960910 732681		


Features

- Front has easy-to-read graduation lines every 10 mm. There are also red graduation lines every 50 mm. Additionally, background color alternates every 1 m between white and yellow, so one can quickly identify the number of meters even from far away.
- Back side has 1 mm pitch graduations from the reference point to also enable use in measurements for landscaping construction, etc.
- In addition to the background color, the number of meters can also be determined by the number of ●



- ...2 m
- ...3 m
- x 1 indicates 1 m
- ...4 m

- Aluminum alloy, light weight, water-resistant
- One-touch detachable boards with the same button for each step make it easy to clean separately
- Convenient for measuring in areas with a large elevation difference such as hills or along the coast (73268)



Use

- For leveling horizontally and vertically

Specifications

Material	Body: Aluminum Joint: ABS resin
Length Tolerance	±L mm L=m unit's measuring length (fractions are rounded up)

Telescopic Leveling Staff

■Front Yellow color every 1 m Vertical numbers every 1 cm Center line



■Back Red and white graduations every 50 cm

76930

Item Code	Description	Size in Stored (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76973	5 m 3 Steps	1,900×49×22	1,427	4 960910 769731	5	
76930	5 m 4 Steps	1,495×50×27	1,750	4 960910 769304		

Features

- Aluminum alloy, light weight, water-resistant
- One-touch detachable boards with the same button for each step make it easy to clean separately


Use

- For leveling horizontally and vertically

Specifications

Material	Body: Aluminum
Length Tolerance	±3 mm per 1 m

Fiberglass Leveling Rod Tape



76970

Item Code	Description	Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76969	3 m	0.7	234	4 960910 769694	1	
76970	5 m	0.7	352	4 960910 769700		
76971	10 m	0.7	643	4 960910 769717		

Features

- Large numbered graduations for photography
- Fade resistant
- Fiberglass tape with little elasticity

Use

- For on-site record photography

Specifications

Material	Tape: Fiberglass Metal Fitting: Iron
Length Tolerance	3 m: 3 m±3.6 mm 5 m: 5 m±5.2 mm 10 m: 10 m±9.2 mm

Adhesive Leveling Rod Tape



78192

78193

78194

78195

78196

[78192 - 78195]

Thickness of graduation: 1 mm




... 5 cm mark

... 10 cm mark

[78196]


Thickness of graduation: 5 mm



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78192	50 mm x 25 m 20 cm Color Interval	φ107×50	210	4 960910 781924	5	
78193	50 mm x 25 m 30 cm Color Interval	φ107×50	210	4 960910 781931		
78194	75 mm x 25 m 20 cm Color Interval	φ107×75	310	4 960910 781948		
78195	75 mm x 25 m 30 cm Color Interval	φ107×75	310	4 960910 781955		
78196	60 mm x 26 m 20 cm Color Interval with Numbering	φ107×60	250	4 960910 781962		

Features

- With antireflective fabrication so objects will show clearly when photographed
- Will not peel even in temperatures from -10 to 40°C so it can be used reliably in summer or winter
- Can be written with an oil-based marker so a custom rule can easily be made



- Synthetic paper that does not release toxic gases even when burned
- With tape cutter to cut necessary length


Use

- For positioning in banking drainage, and foundation work, as well as for photography

Specifications

	78192	78193	78194	78195	78196
Material	Tape: Synthetic paper			Cutter: Iron	
Thickness	0.15 mm				
Length	25 m				26 m

Surveying Pole



76984


76985

76988-76996

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76984	Wood 2 m	φ28×2,095	1,000	4 960910 769847	20	
76985	Aluminum 2 m Steps	φ32(25)×1,195 (During storage)	415	4 960910 769854	30	
76988	Aluminum 2 m	φ29×2,061	468	4 960910 769885	10	
76996	Aluminum 2 m 10 pc-set	φ29×2,061	468 ×10	4 960910 769960	1	

Features

- Aluminum 2 m 2 steps model locks at a position just by turning right or left
- Highly weatherproof so it can be used repeatedly under various environments (76988/76996)
- About 50% lighter compared to wooden construction (76988/76996)
- End has a hard, steel tip (76988/76996)
- 10-item value set (76996)



Use

- For indicating position or direction while leveling


Specifications

	76984	76985	76988	76996
Material	Body: Wood Tip End: Iron	Body: Aluminum Tip End: Iron	Body: Aluminum Tip End: PP, Iron Cap: PP	

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Surveying Pin Pole (Steel)



76927

Item Code	Description	Diameter (mm)	Weight (g)	JAN Code	Packing Unit	Package
76927	30 cm ϕ 4	ϕ 4	40	4 960910 769274	10	
76928	60 cm ϕ 4	ϕ 4	74	4 960910 769281		
76976	30 cm ϕ 6	ϕ 6	102	4 960910 769762		
76977	50 cm ϕ 6	ϕ 6	147	4 960910 769779	5	
76978	60 cm ϕ 6	ϕ 6	168	4 960910 769786		
76979	1 m ϕ 8	ϕ 8	456	4 960910 769793		

Features

- Baked finish for fade-resistance

Use

- For indicating position or direction while leveling

Specifications

Material	Iron
----------	------

Traverse Surveying Pin Pole (Hard Steel)



76982

Item Code	Description	Diameter (mm)	Weight (g)	JAN Code	Packing Unit	Package
76982	50 cm ϕ 3.2	ϕ 3.2	40	4 960910 769823	30	

Features

- Baked finish for fade-resistance
- Hard steel material helps to penetrate into hard ground

Use

- For indicating position or direction while leveling

Specifications

Material	Iron
----------	------

Measuring Wheel



75421

75422

Come with soft case

Item Code	Description	Measuring Unit	Measurement Range	Weight (g)	JAN Code	Packing Unit	Package
75421	E10-S	1 cm	1 km	820	4 960910 754218	1	
75422	E20-S	10 cm	10 km	1,260	4 960910 754225		

Features

- Easy-to-read counter at hand level



- Easy-to-hold handle
- Triple extensions for compact packing



Use

- For construction, plumbing works, engineering works, measurement of properties, measurement of interior works, layout of golf course, landscaping, etc.

Specifications

	75421	75422
Maximum Size	980 mm	1,030 mm
Minimum Size	570 mm	620 mm
Wheel Diameter	119 mm	212 mm
Counter	Five-digit number	
Accuracy	± 1 cm per 100 cm	
Stand	Without	With
Material	Body: ABS resin, nylon resin, aluminum Wheel: Rubber, polypropylene resin	

Construction Flag

76955



Item Code	Description	Stick Size (mm)	Flag Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
76955	Fabric Pair of White and Red	ϕ 16.5x600	335x442	110	4 960910 769557	10	
76909	Nylon Pair of White and Red	ϕ 16.5x600	340x450	red: 100 white: 115	4 960910 769090		

Features

- Flags clearly visible from a distance

Use

- For controlling traffic at construction sites, etc.


Specifications

	76955	76909
Material	Wood, fabric	Wood, nylon


Construction Chalk Board Wood




76975




76956




76957




77059




77069




77057



77058



77067




77068



77088



77031




77087


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76975	A 45 x 60 cm	450x600x18	855	4 960910 769755	10	
77031	AS 30 x 45 cm	300x450x17	410	4 960910 770317	10	
76956	B 45 x 60 cm	450x600x18	855	4 960910 769564	10	
77057	B-2 60 x 45 cm	600x450x18	855	4 960910 770577	10	
76957	C 45 x 60 cm	450x600x18	855	4 960910 769571	10	
77058	C-2 60 x 45 cm	600x450x18	855	4 960910 770584	10	
77059	D 45 x 60 cm	450x600x18	855	4 960910 770591	10	
77067	D-2 60 x 45 cm	600x450x18	855	4 960910 770676	10	
77087	DS 30 x 45 cm	300x450x17	410	4 960910 770874	10	
77088	DS-2 45 x 30 cm	450x300x17	410	4 960910 770881	10	
77068	E-2 60 x 45 cm	600x450x18	855	4 960910 770683	10	
77069	F 45 x 60 cm	450x600x18	855	4 960910 770690	10	

Features

- Suitable for construction site photography



- Dark grid lined



- Eraser + 3 pc-pack chalks included




- Folding stand and storage for equipment at the back



Use

- For on-site record photography



Specifications

Material	Body: Wood
----------	------------

Construction Water-resistant Chalk Board



77061




78229



77328




77075




77322



78230



77074



78238


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77061	TA 45 x 60 cm	450×600×18	855	4 960910 770614	10	B
77328	TB 45 x 60 cm	450×600×18	855	4 960910 773288	10	B
77322	TC 45 x 60 cm	450×600×18	855	4 960910 773226	10	B
77074	TD 45 x 60 cm	450×600×18	855	4 960910 770744	10	B
78229	TDS 30 x 45 cm	300×450×17	430	4 960910 782297	10	B
77075	TD-2 60 x 45 cm	600×450×18	855	4 960910 770751	10	B
78230	TF 45 x 60 cm	450×600×18	855	4 960910 782303	10	B
78238	TG 45 x 60 cm	450×600×18	855	4 960910 782389	10	B

Features


●Water-resistant, weatherproof




●By using water-resistant chalk on a water-resistant chalkboard, letters will not be washed off. A construction record photo can be taken in rain.



●Dark grid lined



●Special eraser, 3 x water-resistant chalks included



●Folding stand and storage for equipment at the back



Use

●For on-site record photography

Specifications

Material	Body: Wood
----------	------------

Construction Chalk Board Steel



77510



77539



77533



77514



77511



77540



77513




77523

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77510	SA 45 x 60 cm	470x600x15	1,850	4 960910 775107	1 (5)	B
77533	SAS 30 x 45 cm	320x450x15	1,100	4 960910 775336		
77511	SC 45 x 60 cm	470x600x15	1,850	4 960910 775114		
77513	SD 45 x 60 cm	470x600x15	1,850	4 960910 775138		
77539	SDS 30 x 45 cm	320x450x15	1,100	4 960910 775398		
77514	SD-2 60 x 45 cm	620x450x15	1,850	4 960910 775145		
77540	SDS-2 45 x 30 cm	470x300x15	1,100	4 960910 775404		
77523	SG 45 x 60 cm	470x600x15	1,850	4 960910 775237		

Features


- Durable steel surface
- Aluminum frame increases durability
- Dark grid lined



- Eraser + 3 pc-pack chalks included



- Easy carrying handle



- Magnet compatible



- Storage for equipment



- Folding stand on the back




Use

- For on-site record photography


Specifications

Material	Front: Steel Back: Aluminum Frame: Aluminum Stand: Iron Handle, Corner: ABS resin
----------	---


Construction White Board




77357




77358




77331




77332



77385




77365



77333



77368



77366



77367

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77357	AW 45 x 60 cm	470×600×15	1,790	4 960910 773578	1	B
77365	ASW 30 x 45 cm	320×450×15	940	4 960910 773653	1	B
77358	BW 45 x 60 cm	470×600×15	1,790	4 960910 773585	1	B
77331	CW 45 x 60 cm	470×600×15	1,790	4 960910 773318	1	B
77366	CSW 30 x 45 cm	320×450×15	940	4 960910 773660	1	B
77332	DW 45 x 60 cm	470×600×15	1,790	4 960910 773325	1	B
77333	DW-2 60 x 45 cm	620×450×15	1,790	4 960910 773332	1	B
77367	DSW 30 x 45 cm	320×450×15	940	4 960910 773677	1	B
77368	DSW-2 45 x 30 cm	470×300×15	940	4 960910 773684	1	B
77385	FW 45 x 60 cm	470×600×15	1,790	4 960910 773851	1	B

Features

- Eraser + one white board marker (black) included



- Easy to carry



- Folding stand and storage for equipment at the back



- Magnet compatible



Use

- For on-site record photography




Specifications

Material	Front: Steel Back: Aluminum Frame: Aluminum Stand: Steel Handle, Corner: ABS resin
----------	--


JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens


Construction White Board



77359



77387



77369



77386

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77359	GW 45 x 60 cm	470×600×15	1,790	4 960910 773592	1 (5)	
77369	GSW 30 x 45 cm	320×450×15	940	4 960910 773691		
77386	HW 45 x 60 cm	470×600×15	1,790	4 960910 773868		
77387	JW 45 x 60 cm	470×600×15	1,790	4 960910 773875		

Features

- Eraser + one white board marker (black) included



- Easy to carry



- Folding stand and storage for equipment at the back



Use

- For on-site record photography
- For on-site safety control (77386)

Specifications

Material	Front: Steel Back: Aluminum Frame: Aluminum Stand: Steel Handle, Corner: ABS resin
----------	--


Folding Construction White Board




77741



77742



77743




77744

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77741	OAW 45 x 60 cm	470×600×15	1,660	4 960910 777415	1 (5)	
77742	OCW 45 x 60 cm	470×600×15	1,660	4 960910 777422		
77743	ODW 45 x 60 cm	470×600×15	1,660	4 960910 777439		
77744	OGW 45 x 60 cm	470×600×15	1,660	4 960910 777446		

Features

- Convenient for storage and preventing scratches
- Handle for better portability
- Durable aluminum frame



- Eraser + one white board marker (black) included

- Folding stand and storage for equipment at the back




Use

- For on-site record photography

Specifications

Material	Front: Steel Back: Aluminum Frame: Aluminum Stand: Aluminum Handle, Corner: ABS resin
----------	---

Construction White Board Mini with Telescopic Arm




77626

77627

78161

78162




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77626	MCSW 11 x 14 cm with Itemized Magnetic Sheet	198×146×30 (folded)	162	4 960910 776265	5	
77627	MCW 14 x 17 cm with Itemized Magnetic Sheet	198×176×30 (folded)	206	4 960910 776272		
78161	MCSW 11 x 14 cm	198×146×30 (folded)	162	4 960910 781610		
78162	MCW 14 x 17 cm	198×176×30 (folded)	206	4 960910 781627		

Features

- Does not reflect camera flash easily during photography so board will show clearly



- Magnetic sheet title is only stuck on so title can be changed easily



- Steel sheets with itemized magnetic sheets attached can be stuck to the back of Construction White Board Mini with Telescopic Arm for storage



- Can securely lock on any angle



- Includes a whiteboard eraser and marker

Use

- For on-site record photography

Specifications

Whiteboard

	77626/78161	77627/78162
Maximum Extension	Up to 725 mm	Up to 755 mm
Material	Board: Steel Frame, Joint, Fixing screw, Cap: ABS resin Telescopic Part: Brass Grip: Silicone rubber	

Itemized Magnetic Sheet

Material	Vinyl chloride synthetic rubber
Magnetic material	Isotropic
Adsorption power	0.09 N/cm ² , 9 gf/cm ²


Whiteboard Marking Pen

Material	Body: ABS resin Magnet: Vinyl chloride synthetic rubber Ink: Oil (Pigmented ink)
Body Size	135×13.5×16 mm
Weight	9 g

Whiteboard Eraser

Material	Polyurethane resin
Body Size	50×50×20 mm
Weight	1 g

Itemized Magnetic Sheet 6 item-set



78428




78427

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78428	For Construction White Board Mini MCSW 11 x 14 cm	62x55x0.6	7	4 960910 784284	5	
78427	For Construction White Board Mini MCW 14 x 17 cm	80x76x0.6	12	4 960910 784277		

Features

- Magnetic sheet title is only stuck on so title can be changed easily



- Steel sheet construction so they can be stuck to the back of the whiteboard for storage

Use

- For changing titles on the Whiteboard Mini Expandable Type Series

Specifications

Material	Vinyl chloride synthetic rubber
Magnetic Material	Isotropic
Adsorption Power	0.09 N/cm ² , 9 gf/cm ²

Whiteboard Marking Pen/Eraser



78503



78504



78506



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78503	Whiteboard Marking Pen Black	135x17x17	13	4 960910 785038	10	
78504	Whiteboard Marking Pen Red	135x17x17	13	4 960910 785045		
78506	Whiteboard Marking Pen Black Fine with Eraser and Magnet	135x13.5x16	9	4 960910 785069		

Features

- Smooth flowing alcohol-based ink
- Eraser and magnet
- Cap includes an eraser, so written letters can easily be erased
- Cap includes a magnet so it can attach to a whiteboard, etc.



(78503/78504)



(78506)

Use

- For writing on whiteboard

Specifications

	78503	78504	78506
Material	Body: Polypropylene resin Ink: Oil (Pigmented ink)		Body: ABS resin Magnet: Vinyl chloride synthetic rubber Ink: Oil (Pigmented ink)

Waterproof Chalkboard Marking Pen/Chalk



78505

*Not suitable for ordinal chalkboard



77064

*Not suitable for ordinal chalkboard



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78505	Waterproof Chalkboard Marking Pen White	130x20x17	20	4 960910 785052	10	
77064	Chalk for Waterproof Chalkboard	70x11x11	7	4 960910 770645		

Features

- Marking Pen
- Stays on even under wet conditions
- Smooth flowing bold round tip
- Erased easily by any fabric
- 3 mm-wide line shows up clearly in record photography



Oil-based

- Chalk
- Can be used under wet conditions
- Usable on asphalt or concrete as well as water-resistant chalkboard
- Each chalk is wrapped to keep your hand clean

Use

- For writing on water-resistant chalkboard

Specifications

	78505	77064
Material	Body: Polypropylene resin Ink: Oil (Pigmented ink)	Body: Oil (Pigment)

Eraser



77353



77045

*Not suitable for ordinal chalk

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
77353	Eraser for Chalkboard and Whiteboard	112×44×29	19		10	
77045	Eraser for Waterproof Chalkboard	98×55×30	1			

Features

- Eraser for Chalkboard and Whiteboard
- Eraser with magnet
- Eraser for Waterproof Chalkboard
- Just rub lightly to erase




Use

- For erasing on blackboard, whiteboard, and water-resistant chalkboard

Specifications

	77353	77045
Material	ABS resin, cotton	Melamine foam

KONOE MASTER LINE

76911
7691676912
7691776913
7691876914
7691976915
76920Stick-on type
backInsert type
back

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
76911	M-1 Stick-on Type	50×50×4	25		10	
76912	M-2 Stick-on Type	50×50×4	25			
76913	M-3 Stick-on Type	50×50×4	25			
76914	M-4 Stick-on Type	50×50×4	25			
76915	M-5 Stick-on Type	50×50×4	25			
76916	M-6 Insert Type	50×50×10	58			
76917	M-7 Insert Type	50×50×10	58			
76918	M-8 Insert Type	50×50×10	58			
76919	M-9 Insert Type	50×50×10	58			
76920	M-10 Insert Type	50×50×10	58			

Features


- Made of durable aluminum alloy
- Light, clear, easily seen design
- Two types available: stick-on and insert

Use

- For identification in a boundary survey (It can be attached with adhesives or bolts to places where concrete or plastic stakes cannot be used)

■ How to place KONOE MASTER LINE


● Stick-on type




Install by pasting concrete/metal adhesives

● Insert type

1. Make a hole that matches the position of the master line bolt




2. Insert after pouring concrete or metal adhesives



Specifications

Material	Body: Aluminum alloy Bolt (Insert type): Stainless steel
----------	---

KONOE NAIL



Item Code	Description	Body Size (mm)				Weight (g)	JAN Code	Packing Unit	Packaging
		D	d	H	L				
76986	No.01 100 pc-pack	6	4	2	27	2	4 960910 769861	5	
76987	No.1 50 pc-pack	9	5	3	43	6	4 960910 769878	5	
76989	No.2 20 pc-pack	15	7	4	55	20	4 960910 769892	5	
76990	No.3 20 pc-pack	15	7	5	80	30	4 960910 769908	5	
76991	No.4 10 pc-pack	20	9	5	105	50	4 960910 769915	5	
76992	No.5 10 pc-pack	20	9	5	130	65	4 960910 769922	5	

Features

- Made of special steel
- Various types available from paved road to gravel road use

Use



- As a benchmark nail (from paved road to gravel road use)

KONOE NAIL	Use	KONOE DOUBLE
No.01	Wood, plastic	2
No.1	Concrete	
No.2	Asphalt	3
No.3		
No.4		
No.5	Gravel road	

Specifications

Material	Steel
----------	-------

How to drive the KONOE NAIL



■ Standard size of pilot hole for the KONOE NAIL

Concrete	Asphalt
About 1.0 mm smaller than the KONOE NAIL diameter	About 1.5 mm smaller than the KONOE NAIL diameter

KONOE NAIL Mini Pack

Item Code	Description	Body Size (mm)				Weight (g)	JAN Code	Packing Unit	Packaging
		D	d	H	L				
76938	No.01 20 pc-pack	6	4	2	27	2	4 960910 769380	5	
76939	No.1 20 pc-pack	9	5	3	43	6	4 960910 769397	5	
76940	No.2 5 pc-pack	15	7	4	55	20	4 960910 769403	5	
76941	No.3 5 pc-pack	15	7	5	80	30	4 960910 769410	5	
76942	No.4 5 pc-pack	20	9	5	105	50	4 960910 769427	5	
76943	No.5 5 pc-pack	20	9	5	130	65	4 960910 769434	5	

KONOE DOUBLE



Item Code	Description	Body Size (mm)			Weight (g)	JAN Code	Packing Unit	Packaging
		D	d	H				
76993	2 Red 100 pc-pack	27	5	4	2	4 960910 769939	5	
76994	2 Yellow 100 pc-pack	27	5	4	2	4 960910 769946	5	
76995	2 Blue 100 pc-pack	27	5	4	2	4 960910 769953	5	

Features

- ABS resin material is durable and coloring lasts longer.

Use

- As a highlighted base of the bench mark nail (with KONOE NAIL)


KONOE DOUBLE	Use	KONOE NAIL
2	Wood, plastic	No.01
	Concrete	No.1
3	Asphalt	No.2
	Gravel road	No.3
		No.4
		No.5

Specifications

Material	ABS resin
----------	-----------

KONOE DOUBLE Mini Pack

Item Code	Description	Body Size (mm)			Weight (g)	JAN Code	Packing Unit	Packaging
		D	d	H				
76946	2 Red 20 pc-pack	27	5	4	2	4 960910 769465	5	
76947	2 Yellow 20 pc-pack	27	5	4	2	4 960910 769472	5	
76948	2 Blue 20 pc-pack	27	5	4	2	4 960910 769489	5	
76949	3 Red 5 pc-pack	47	10	7	6	4 960910 769496	5	
76950	3 Yellow 5 pc-pack	47	10	7	6	4 960910 769502	5	
76951	3 Blue 5 pc-pack	47	10	7	6	4 960910 769519	5	



Marking Tape



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74161	15 mm × 50 m Pink	φ82×15	77	4 960910 741614	10	
74162	15 mm × 50 m Yellow	φ82×15	77	4 960910 741621		
74163	15 mm × 50 m Orange	φ82×15	77	4 960910 741638		
74164	15 mm × 50 m Blue	φ82×15	77	4 960910 741645		
73798	30 mm × 50 m Pink	φ82×30	170	4 960910 737983		
73799	30 mm × 50 m Yellow	φ82×30	170	4 960910 737990		
73800	30 mm × 50 m Orange	φ82×30	170	4 960910 738003		
74125	30 mm × 50 m Blue	φ82×30	170	4 960910 741256		
73865	30 mm × 100 m Pink	φ106×30	320	4 960910 738652		
					5	

Features

- Highly visible fluorescent color
- Large rolls: 50 m or 100 m length
- Tear easily by hand
- Does not become bulky when used in large quantity

Use

- For survey work, construction work, tree planting, tree measurement, etc.



Specifications

Material	Polyvinyl chloride resin
Thickness	0.09 mm

*Not adhesive

Rebar Marker




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78529	Red 10 pc-pack	50	6	4 960910 785298	10	
78530	Orange 10 pc-pack	50	6	4 960910 785304		
78531	Yellow 10 pc-pack	50	6	4 960910 785311		
78532	White 10 pc-pack	50	6	4 960910 785328		
78533	Green 10 pc-pack	50	6	4 960910 785335		
78534	Blue 10 pc-pack	50	6	4 960910 785342		
78552	Pink 10 pc-pack	50	6	4 960910 785526		

Features

- Easy to install with soft material



- Highly visible marker



- Silicone rubber, heat-resistant, cold-resistant and weatherproof


Use

- For photography of rebar pitch arrangement, checking spaces of horizontal and vertical pitches, and classifying diameters of rebars by colors

Specifications

Material	Silicone rubber
Range of Use	About 13~30 mm diameters

Leveling Line



Item Code	Description	Weight (g)	JAN Code	Packing Unit	Packaging
78563	Yellow 3 mm 30 m	290	4 960910 785632	4	
78564	Pink 3 mm 30 m	290	4 960910 785649		

Features

- Highly visible fluorescent color
- Hard to break, 3 mm thickness

Use

- For record photography of basement construction or road construction



Specifications

Material	Coating: Polyethylene resin Roll Core: Rubber
Thickness	3 mm

9. Scales



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Digital Compact Scale



70163



100 g proofreading
counterweight included



Case included



Features

- Portable pocket size
- Able to show net weight without weight of container or bag
- Simple and highly visible white LCD display – visible even in the dark
- With auto power off function
- With back light



Use

- For weighing small parts, calculating number



Specifications

Not for commercial use

Capacity	200 g
Minimum Measurement	0.2 g
Scale Interval	0.1 g
Linearity	±0.2 g
Use Environment	10-30°C (lower than 85% of humidity)
Automatic Power Off	1 minute
Material	Platform: Stainless steel Cover: ABS resin
Digital Display	LCD Display, Character Height: 13 mm
Power Source	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70163	Mini 200 g	115×64×18	110		3	

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Carpenter's Scales
 Stainless Steel Rules / Machine Scale
 Aluminum Rules
 Resin Folding Rules / Bamboo Rules
 Squares / Protractors
 Vernier Calipers / Micrometers
 Tape Measures
 Surveying Products
 Scales
 Levels
 Lasers / Optical Equipment
 Inklines / Chalklines / Plumbers
 Circular Saw Guides
 Construction Tools
 Industrial Tools
 Thermometers / Hygrometers / Scales for Measuring Instruments
 Outdoor Products
 Magnifying Glasses
 Drawing Tools
 Magnets

Digital Scale for Commercial Use

70194



- Inspection certificate plate: serial number, assembly year, calibration month & year



Plastic tray included



70119

Sold separately



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70191	3 kg	281×259×148	2,050	4 960910 701915	1 (2)	
70192	6 kg	281×259×148	2,050	4 960910 701922		
70193	15 kg	281×259×148	2,060	4 960910 701939		
70194	30 kg	281×259×148	2,065	4 960910 701946		
70119	AC adapter	84×58×69	463	4 960910 701199	1	

Features

- Dustproof and waterproof
IP56 5 Protected from limited dust ingress
 6 Protected from high pressure water jets from any direction
- 30 mm character height large, back-lit screen
- Stainless steel plate accessory allows sanitary use. Detachable and washable
- Auto power off function: Turns off after about 9 minutes pass without operation
- Tare function that allows for the weight of the container and displays only the weight of the contents



Use

- For weighing various things from crops to fishery products, etc

Specifications

Suitable for commercial use

	70191	70192	70193	70194
Capacity	3 kg	6 kg	15 kg	30 kg
Minimum Measurement	50 g	100 g	200 g	500 g
Resolution	1/600	1/600	1/750	1/600
Scale Interval	5 g	10 g	20 g	50 g
Linearity	±5 g	±10 g	±20 g	±50 g
Reproducibility	±5 g	±10 g	±20 g	±50 g
Auto Power Off	Approximately 9 minutes			
Digital Display	LCD Display, Character Height: 30mm			
Dustproof/Waterproof	IP56 (when the battery is used)			
Plate Size	200 × 240 mm			
Material	Body: ABS resin			
Power Source	6x Alkaline batteries (not included) AC adapter (sold separately #70119)			
Rated Voltage	DC9V			

Digital Scale

70106



Plastic tray included



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70104	3 kg	281×259×148	1,910	4 960910 701045	1 (2)	
70105	6 kg	281×259×148	1,918	4 960910 701052		
70106	15 kg	281×259×148	1,924	4 960910 701069		
70107	30 kg	281×259×148	1,928	4 960910 701076		

Features

- Dustproof and waterproof
IP56 5 Protected from limited dust ingress
 6 Protected from high pressure water jets from any direction
- 30 mm character height large, back-lit screen
- Stainless steel plate accessory allows sanitary use. Detachable and washable
- Auto power off function: Turns off after about 9 minutes pass without operation
- With tare function that allows for the weight of the container and displays only the weight of the contents



Use

- For weighing various things from crops to fishery products, etc

Specifications

Not for commercial use

	70104	70105	70106	70107
Capacity	3 kg	6 kg	15 kg	30 kg
Minimum Measurement	20 g	40 g	100 g	200 g
Resolution	1/3000			
Scale Interval	1 g	2 g	5 g	10 g
Linearity	±1 g	±2 g	±5 g	±10 g
Reproducibility	±1 g	±2 g	±5 g	±10 g
Auto Power Off	Approximately 9 minutes			
Digital Display	LCD Display, Character Height: 30 mm			
Dustproof/Waterproof	IP56 (when the battery is used)			
Plate Size	200 × 240 mm			
Material	Body: ABS resin			
Power Source	6x Alkaline batteries (not included) AC adapter (sold separately #70119)			
Rated Voltage	DC9V			

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Digital Scale Remote-reading



70108



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70108	100 kg	276×291×33 Operating part 108×120×55	3,380	4 960910 701083	4	B

Features

- Visible display position - remote display
- Rust-resistant stainless steel platform
- Low height platform (33 mm) is convenient when weighing heavy goods
- Easy-to-read 15 mm character height LCD display
- Auto power off function
- Percentage mode for comparative measurement
- Convenient tare function
- AC adapter included (1x 9V Alkaline battery also included)



Use

- For weighing crops, etc.

Specifications

Not for commercial use

Capacity	100 kg
Minimum Measurement	0.5 kg
Scale Interval	0.05 kg
Accuracy	±0.5 kg
Use Environment	5 - 35°C (without condensation)
Automatic Power Off	4 minutes
Digital Display	LCD Display, Character Height: 15 mm
Material	Platform: Stainless steel Body: Glass Operating Part: ABS resin
Power Source	1x 9V Alkaline battery (Battery included is for trial use only and may not last as long) AC adapter

Scale



70008

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70026	50 kg	350×289×146	5,000	4 960910 700260	1	B
70008	100 kg	350×289×146	5,000	4 960910 700086		

Features

- Easy-to-read graduation plate




50 kg



100 kg

- Low height platform is convenient when weighing heavy goods



Use

- For weighing crops, etc.

Specifications

Not for commercial use

	70026	70008
Capacity	50 kg	100 kg
Scale Interval	200 g	500 g
Size of Platform	350 × 250 mm	
Material	Platform, Body: Steel Graduation Display Cover: AS resin Graduation Plate: Aluminum	

Scale for Commercial Use



70123



70124



70079



70084



70090



70093



70102



70101

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70123	200 g	240×190×210	1,800	4 960910 701236	1 (8)	
70124	400 g	240×190×210	1,800	4 960910 701243		
70079	1 kg	240×190×210	1,800	4 960910 700796		
70081	2 kg	270×220×270	3,400	4 960910 700819	1 (4)	
70084	4 kg	270×220×270	3,400	4 960910 700840		
70087	8 kg	270×220×270	3,400	4 960910 700871		
70090	12 kg	270×220×270	3,400	4 960910 700901		
70093	20 kg	270×245×270	4,000	4 960910 700932		
70102	30 kg	280×260×275	4,500	4 960910 701021		
70101	50 kg	380×320×355	11,000	4 960910 701014	1	

Features

- Easy-to-read scale with clear graduations
- Durable with robust design
- Dust and moisture proof (70101)

Use

- For weighing various things from crops to fishery products, etc.

Specifications

Suitable for commercial use

Type	Spring dial scale with standard matching verification		
Precision Grade	Grade 4		
	70123	70124	70079
Capacity	200 g	400 g	1 kg
Range of Use ^{*1}	20 g - 200 g	40 g - 400 g	100 g - 1 kg
Scale Interval	1 g	2 g	5 g
Number of Scales	200		
Tolerance ^{*2}	 ① 0 - 50 g ±1 g ② 50 g - 200 g ±2 g	 ① 0 - 100 g ±2 g ② 100 g - 400 g ±4 g	 ① 0 - 250 g ±5 g ② 250 g - 1 kg ±10 g
Dial Face	φ164 mm		
Platform Size	190 × 185 mm		
Platform Thickness	0.5 mm		
Material	Body: Copperplate Platform: Stainless steel Pointer: Aluminum Knob, Front Cover: Polyethylene resin		

	70081	70084	70087
Capacity	2 kg	4 kg	8 kg
Range of Use ^{*1}	100 g - 2 kg	200 g - 4 kg	400 g - 8 kg
Scale Interval	5 g	10 g	20 g
Number of Scales	400		
Tolerance ^{*2}	 ① 0 - 250 g ±5 g ② 250 g - 1 kg ±10 g ③ 1 kg - 2 kg ±15 g	 ① 0 - 500 g ±10 g ② 500 g - 2 kg ±20 g ③ 2 kg - 4 kg ±30 g	 ① 0 - 1 kg ±20 g ② 1 kg - 4 kg ±40 g ③ 4 kg - 8 kg ±60 g
Dial Face	φ196 mm		
Platform Size	220 × 210 mm		
Platform Thickness	0.5 mm		
Material	Body: Copperplate Platform: Stainless steel Pointer: Aluminum Knob, Front Cover: Polyethylene resin		


	70090	70093	70102
Capacity	12 kg	20 kg	30 kg
Range of Use ^{*1}	1 kg - 12 kg	2 kg - 20 kg	2 kg - 30 kg
Scale Interval	50 g	100 g	
Number of Scales	240	200	300
Tolerance ^{*2}	 ① 0 - 2.5 kg ±50 g ② 2.5 kg - 10 kg ±100 g ③ 10 kg - 12 kg ±150 g	 ① 0 - 5 kg ±100 g ② 5 kg - 20 kg ±200 g	 ① 0 - 5 kg ±100 g ② 5 kg - 20 kg ±200 g ③ 20 kg - 30 kg ±300 g
Dial Face	φ196 mm		
Platform Size	220 × 210 mm	245 × 230 mm	260 × 245 mm
Platform Thickness	0.5 mm		
Material	Body: Copperplate Platform: Stainless steel Pointer: Aluminum Knob, Front Cover: Polyethylene resin		

	70101
Capacity	50 kg
Range of Use ^{*1}	2 kg - 50 kg
Scale Interval	200 g
Number of Scales	250
Tolerance ^{*2}	 ① 0 - 10 kg ±200 g ② 10 kg - 40 kg ±400 g ③ 40 kg - 50 kg ±600 g
Dial Face	φ270 mm
Platform Size	320 × 320 mm
Platform Thickness	2 mm
Material	Body: Copperplate Platform: Stainless steel Pointer: Aluminum Knob, Front Cover: Polyethylene resin

*1 Range of use means the weight range suitable for commercial use.

*2 Tolerance required by the Japanese Measurement Act, Ordinance of METI (METI: Ministry of Economy, Trade Industry) for commercial use in Japan.

Spring Scale with Flat Scale Face



Item Code	Description	Minimum Scale Value (g)	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74451	500 g	5	290×30×25	126	4 960910 744516	5	
74452	1 kg	10	290×30×25	126	4 960910 744523	5	
74453	2 kg	20	290×30×25	126	4 960910 744530	5	
74459	5 kg	50	290×30×25	131	4 960910 744592	5	
74493	8 kg	100	290×30×25	133	4 960910 744936	5	
74460	10 kg	100	290×30×25	136	4 960910 744608	5	
74499	15 kg	200	290×30×25	142	4 960910 744998	5	
74461	20 kg	200	410×45×35	593	4 960910 744615	3	
74487	30 kg	500	410×45×35	618	4 960910 744875	3	
74488	50 kg	500	410×45×35	618	4 960910 744882	3	

Features

- Flat graduation plate makes it easy to read
- Zero point adjustment knob




- Flat surface allows accurate readings



Use

- For weighing various things such as parcels, crops, and fishery products



Specifications

Not for commercial use

Type	Spring Scale				
	74451	74452	74453	74459	74493
Capacity	500 g	1 kg	2 kg	5 kg	8 kg
Scale interval	5 g	10 g	20 g	50 g	100 g
Number of Scales	96				
Tolerance (less than half of capacity)	±5 g	±10 g	±20 g	±50 g	±100 g
	±10 g	±20 g	±40 g	±100 g	±200 g
Material	Body, Platform: Aluminum Handle, Hook: Iron Zero point adjustment knob, Platform Side: ABS resin				
	74460	74499	74461	74487	74488
Capacity	10 kg	15 kg	20 kg	30 kg	50 kg
Scale interval	100 g	200 g	500 g		
Number of Scales	96	75	98	60	96
Tolerance (less than half of capacity)	±100 g	±200 g	±500 g		
	±200 g	±400 g	±1,000 g		
Material	Body, Platform: Aluminum Handle, Hook: Iron Zero point adjustment knob, Platform Side: ABS resin		Body, Platform: Aluminum Handle, Hook: Iron Zero point adjustment knob, Platform Side: Zinc die casting		

Digital Spring Scale




70109

- Back light display (Front only)



Back light on while an object is hanging on the hook

- Big size display panel for easy reading



- Hold function



Stores the value on the display even after removing the object

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70109	20 kg	240×65×29	225	4 960910 701090	2	

Features

- With convenient tare function
- LCD display on the back as well



Use

- For weighing various things

Specifications

Not for commercial use

Capacity	20 kg
Scale Interval	10 g (0 - 10 kg) 20 g (10 - 20 kg)
Range of Use	0.2 - 20 kg
Use Environment	0 - 40°C (below 85% humidity)
Auto Power Off	0 - 19 minutes (adjustable by one minute)
Material	Body: ABS resin
Digital Display	Character Height: 14 mm on both sides of display
Power Source	2x Lithium batteries CR2032 (Batteries included are for trial use only and may not last as long)

10. Levels



Blue Level PRO

76391



Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76390	300 mm		65×27	295	4	
76391	380 mm		65×27	340	4	
76393	450 mm		65×27	395	4	
76394	600 mm		65×27	500	4	
76395	900 mm		65×27	690	4	
76396	1200 mm		65×27	885	4	
76398	1500 mm		65×27	1,075	4	
76400	1800 mm		65×27	1,285	4	

*Not available in certain areas. Please contact us for details.

Blue Level PRO with Magnet



76407

Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76403	300 mm		65×27	300	4	
76404	380 mm		65×27	345	4	
76405	450 mm		65×27	400	4	
76407	600 mm		65×27	510	4	
76408	900 mm		65×27	700	4	
76409	1200 mm		65×27	900	4	
76411	1500 mm		65×27	1,090	4	
76412	1800 mm		65×27	1,300	4	

*Not available in certain areas. Please contact us for details.

Blue Level Jr.



●Including a ball chain
(100 mm·
100 mm with magnet)

76331

76334

*Gradient cannot be measured with vial graduations

Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76330	100 mm		50×22	71	4	
76331	100 mm with Magnet		50×22	80	4	
76334	150 mm		50×22	110	4	
76336	150 mm with Magnet		50×22	115	4	
76335	200 mm		50×22	135	4	
76337	200 mm with Magnet		50×22	145	4	

*Not available in certain areas. Please contact us for details.

Shinwa's levels are made with accuracy within the specifications. Please use equipment with higher accuracy for work that requires greater specifications. Sensitivity means the gradient at which the air bubble starts moving. Accuracy means the tolerance of range that the air bubble indicates.


JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

- High-visibility vial with clear blue liquid and thick white line




- Luminous resin is added to the vial
- High precision of ± 1.0 mm/m for all vials
- Bright blue color-alumite finish



- Mix of H and box-shaped cross section and strong structure gives high accuracy and high durability

- Large vial, larger bubble for easy readings
- 45° vial
- Large side caps protect the level and material object
- V-shape groove on the measurement side for measuring pipes
- Measures 1/50 and 1/100 gradients
- Magnetic model is handy for steel frame work
- Comes with grip holes for models over 600 mm

Gradient Measurement



*The size of air bubble varies depending on temperature.

Use

- For verification of horizontal, vertical and 45° gradients in building, engineering, plumbing, electric and planting, etc.

Specifications

Sensitivity Precision	 Sensitivity 0.35 mm/m = 0.0201° Precision ± 1.0 mm/m = less than $\pm 0.0573^\circ$
Material	Body: Aluminum, ABS resin Vial: Acrylic resin Liquid: Petroleum liquid

Features

- High precision of ± 1.0 mm/m for all vials
- Bright blue color-alumite finish
- Luminous resin is added to the vial
- Mix of H and box shaped cross section and strong structure gives high accuracy and high durability
- V-shape groove on the measurement side for measuring pipes
- Magnetic model is handy for steel frame work
- High precision, high visibility



Use

- For verification of horizontal, vertical and 45° gradients in building, engineering, plumbing, electric and planting, etc.

Specifications

Sensitivity Precision	 Sensitivity 0.35 mm/m = 0.0201° Precision ± 1.0 mm/m = less than $\pm 0.0573^\circ$
Material	Body: Aluminum, ABS resin Vial: Acrylic resin Liquid: Petroleum liquid

Blue Level

76370



*Gradient cannot be measured with vial graduations

Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76370	300 mm	58×25	260	4 960910 763708	6	
76375	380 mm	58×25	305	4 960910 763753		
76371	450 mm	58×25	360	4 960910 763715		
76372	600 mm	58×25	470	4 960910 763722		
76373	900 mm	58×25	700	4 960910 763739		
76374	1200 mm	58×25	900	4 960910 763746		
76377	1500 mm	58×25	1,075	4 960910 763777	1	
76378	1800 mm	58×25	1,275	4 960910 763784		

Blue Level with Magnet

76380




*Gradient cannot be measured with vial graduations

Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76379	300 mm	58×25	360	4 960910 763791	6	
76384	380 mm	58×25	420	4 960910 763845		
76380	450 mm	58×25	460	4 960910 763807		
76381	600 mm	58×25	570	4 960910 763814		
76382	900 mm	58×25	860	4 960910 763821		
76383	1200 mm	58×25	1,060	4 960910 763838		
76385	1500 mm	58×25	1,315	4 960910 763852	1	
76389	1800 mm	58×25	1,490	4 960910 763890		

Features

- Large vial, larger bubble for easy readings
- 45° vial
- Large side caps protect the level and material object
- V-shape groove on the measurement side for measuring pipes
- Magnetic model is handy for steel frame work

Large vial



Large side cap



Strong magnets



V-shape groove

Use

- For verification of horizontal, vertical and 45° gradients in building, engineering, plumbing, electric and planting, etc.

Specifications


Sensitivity Precision	 Sensitivity 0.5 mm/m = 0.0286° Precision ±2.5 mm/m = less than ±0.1432°
Material	Body: Aluminum, ABS resin Vial: Acrylic resin Liquid: Petroleum liquid

Slope Level




- Fits pipes

76358



- Easy-to-read gradient as the bubble moves widely



76359

Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76358	300 mm	300×34×42	305	4 960910 763586	4	
76355	450 mm	450×34×42	390	4 960910 763555		
76359	600 mm	600×34×42	535	4 960910 763593		

*Not available in certain areas. Please contact us for details.

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

- Washable inner part
- Measures horizontality and five different gradients (0.5/100, 1/100, 1.5/100, 2/100, 2.5/100)
- These models can measure continuous gradients
- Can be used on flat surfaces as well
- Curved measurement side improves stability
- Vial with luminous sheet for better readability

Use

- For verification and adjustment of gradient in installation of drain pipes

Specifications

Precision	±1.5 mm/m
Material	Body: Aluminum Level Vial: Glass Side Cap: Rubber Liquid: Petroleum liquid Cover: ABS resin, polycarbonate resin

Precise I-Beam Level


76315



Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76315	150 mm	55×25	115	4 960910 763159	6	
76316	230 mm	55×25	170	4 960910 763166		
76318	300 mm	55×25	215	4 960910 763180		
76319	380 mm	55×25	270	4 960910 763197		
76320	450 mm	55×25	315	4 960910 763203		
76321	600 mm	55×25	415	4 960910 763210		
76322	750 mm	55×25	510	4 960910 763227	1	
76323	900 mm	55×25	610	4 960910 763234		
76324	1200 mm	55×25	805	4 960910 763241		

Precise I-Beam Level with Magnet


76301



Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76308	150 mm	55×25	140	4 960910 763081	6	
76310	230 mm	55×25	200	4 960910 763104		
76301	300 mm	55×25	280	4 960910 763012		
76302	380 mm	55×25	345	4 960910 763029		
76303	450 mm	55×25	395	4 960910 763036		
76304	600 mm	55×25	500	4 960910 763043		
76305	750 mm	55×25	600	4 960910 763050	6	
76306	900 mm	55×25	675	4 960910 763067		

Features


- Horizontal vial has three base lines on both sides to measure horizontal, 1/50 and 1/100 gradients
- Larger vial, larger bubble for easy readings
- Measures 45° besides horizontal and vertical *except for 150 mm model
- V-shape groove on the measurement side for measuring pipes
- Large vial with six-lined luminous sheet



- Magnetic model has strong covered magnets for steel frame work and welding work



Gradient Measurement



*The size of air bubble varies depending on temperature.

Use

- For verification of horizontal, vertical, 45°, 1/50 and 1/100 gradients in plumbing, building and engineering work, etc.

Specifications

Sensitivity Precision	(Horizontal) Sensitivity 0.35 mm/m = 0.0201° Precision ±1.0 mm/m = less than ±0.0573° (Vertical/45°) Sensitivity 0.5 mm/m = 0.0286° Precision ±2.5 mm/m = less than ±0.1432°
Material	Body: Aluminum Vial: Acrylic resin Liquid: Petroleum liquid

Handy Level MEGA-MAG with Magnet

73130



73133



- Fixed hook easily attaches to carabiner




- Safety cord can be attached to movable hook

*Gradient cannot be measured with vial graduations

Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73130	100 mm White	50×30	130	4 960910 731301	6	
73131	100 mm Black	50×30	130	4 960910 731318		
73132	150 mm White	50×30	150	4 960910 731325		
73133	150 mm Black	50×30	150	4 960910 731332		

Features

- Triple strength neodymium magnet holds well even if knocked (compared with our standard product)
- Stainless hook on both sides



Use

- For verification of horizontal, vertical and 45° (except 73130/73131) gradients in building, engineering, plumbing, electric and planting, etc.

Specifications

Sensitivity Precision	(Horizontal) Sensitivity 0.35 mm/m = 0.0201° Precision ±1.0 mm/m = less than ±0.0573°
Material	Body: Aluminum, ABS resin Hook: Stainless steel Vial: Acrylic resin Liquid: Petroleum liquid

*Not available in certain areas. Please contact us for details.

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Carpenter's Squares
 Stainless Steel Rules / Machine Scale
 Aluminum Rules
 Resin Folding Bamboo Rules
 Squares / Protractors
 Vernier Calipers / Micrometers
 Tape Measures
 Surveying Products
 Scales
 Levels
 Lasers / Optical Equipment
 Inklines / Chalklines / Plumblines
 Circular Saw Guides
 Construction Tools
 Industrial Tools
 Thermometers / Hygrometers / Humidity Measuring Instruments
 Outdoor Products
 Magnifying Glasses
 Drawing Tools
 Magnets

Handy Level Revo



*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76424	Single White	72.5×72.5×18	32	4 960910 764248	6	
76425	Single Blue	72.5×72.5×18	32	4 960910 764255		
76426	Double	95×45×22	36	4 960910 764262		
76427	Double with Magnet	95×45×22	44	4 960910 764279		
76428	Triple	120×53.5×16	58	4 960910 764286		
76429	Triple with Magnet	120×53.5×16	62	4 960910 764293		

*Not available in certain areas. Please contact us for details.

Features

- Clear blue high-precision large vial
- V-shape groove for measuring pipe
- Triple model has vials with luminous sheets
- Magnetic model has strong neodymium magnet. Convenient for steel frame work.
- Portable pocket size



Use

- For verification of horizontality, verticality, and 45° (except 76426/76427)

Specifications

	76424	76425	76426	76427	76428	76429
Sensitivity	Sensitivity 0.5 mm/m = 0.0286°					
Precision	Precision ±2.5 mm/m = less than ±0.1432°					
Material	Body: Aluminum Vial: Acrylic resin Liquid: Petroleum liquid			Body: ABS resin, aluminum Vial: Acrylic resin Liquid: Petroleum liquid		

Handy Level Light




*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76342	100 mm	100×50×19	39	4 960910 763425	10	

*Not available in certain areas. Please contact us for details.

Features

- Ultra lightweight and portable level
- Strap hole (76342)
- Ball chain convenient for carrying (76048)



Only on Light model

Use

- For verification of horizontality, verticality

Specifications

	76342	76048
Sensitivity	Sensitivity 0.5 mm/m = 0.0286°	
Precision	Precision ±2.5 mm/m = less than ±0.1432°	
Material	Body: ABS resin Vial: Acrylic resin Liquid: Petroleum liquid	Body: ABS resin, aluminum Vial: Acrylic resin Liquid: Petroleum liquid

Handy Level with Magnet



*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76048	B 100 mm	100×46×20	87	4 960910 760486	6	

Slim Level

76340



76332



*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
76340	200 mm White with Magnet	200×40×14	68		6	
76332	200 mm White with Magnet on Back Side	200×40×15	75		6	

*Not available in certain areas. Please contact us for details.

Features

- Portable and convenient slim shape level
- Magnet covers nearly all of the measurement side for secure fastening to metal surfaces, etc.



- Rear magnet convenient for adjusting position of wall mounts, etc. (76332)



- 45° vial
- Vial with luminous sheet



Use

- For verification of horizontal, vertical and 45° gradients in building, engineering, plumbing, electric and planting, etc.

Specifications

Sensitivity Precision	 Sensitivity 0.5 mm/m = 0.0286° Precision ±2.5 mm/m = less than ±0.1432°
Material	Body: ABS resin Vial: Acrylic resin Liquid: Petroleum liquid

Mini Level Revo

76416



76418



76417



76423



76387



*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
76416	Lineclip Model	100×19×26	15		10	
76417	for Rule and Square	71×19×25	17		10	
76418	T-shaped Model	80×55×15	21		10	
76423	Keyring Model	42×15×15	12		10	
76387	Clear Cube Model	75×30×15	38		10	

*Not available in certain areas. Please contact us for details.

Features

- Line clip model
- For measuring leveling string or pipe by using V-shape groove
- Can be used on flat surfaces as well
- Portable with pocket clip




- For rule and square
- Attachable on rule and square
- Can be used on flat surfaces as well
- Portable with pocket clip

- T-shape oval model
- Measures four directions at the same time
- Attach with screws to machine



- Key chain model
- Portable with large carabiner
- Clear Cube
- All 6 sides have been processed as measuring surfaces
- Place it flat to simultaneously measure two directions horizontally: front/back and left/right



Use

- For verifying horizontality

Specifications

	76416	76417	76418	76423	76387
Sensitivity Precision	Sensitivity 0.5 mm/m = 0.0286° Precision ±2.5 mm/m = less than ±0.1432°				
Material	Body: ABS resin Vial: Acrylic resin Liquid: Petroleum liquid			Body: Acrylic resin Liquid: Petroleum liquid	

Mini Level



76037



76046




76060


*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76037	A Circular Model	φ45×11	9	4 960910 760370	10	
76046	D Flat Model	75×25×15	30	4 960910 760462		
76060	H Cube Model	50×27×35	21	4 960910 760608		


Features



- A circular model
- Attach with screws to machine or equipment



- D flat model
- Whole surface can be used as measurement side. It can verify horizontal and perpendicular.



- H cube model
- Measures measurement pole with band

Use

- For verification of horizontality (76037)
- For verification of horizontality, verticality (76046/76060)

Specifications

Sensitivity Precision	Sensitivity 0.5 mm/m = 0.0286° Precision ±2.5 mm/m = less than ±0.1432°
Material	Body (A/D): Acrylic resin Body(H): ABS resin Vial: Acrylic resin Liquid: Petroleum liquid

Round Shape Vial



76328



76329



76530



76531

*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76328	A φ11 Clear 2 pc-pack	φ11×8.5	0.7×2	4 960910 763289	10	
76329	B φ16 Clear 2 pc-pack	φ16×8.5	1.7×2	4 960910 763296		
76530	φ11 Blue 2 pc-pack	φ11×8.5	0.8×2	4 960910 765306		
76531	φ16 Blue 2 pc-pack	φ16×8.5	1.4×2	4 960910 765313		

*Not available in certain areas. Please contact us for details.

Features

- Various uses such as leveling for part of machine, camera's tripod, and recorder's turntable

Use

- For verification of horizontality

Specifications


	76328	76329	76530	76531
Sensitivity Precision	14 mm/m = 0.80°	7 mm/m = 0.40°	1 mm/m = 0.0573°	0.5 mm/m = 0.0286°
Material	Body: Acrylic resin Liquid: Petroleum liquid			

*Sensitivity for Round Shape Vial indicates required gradient to move the air bubble by 1mm.

Level for Square



76503



*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76503	Level for Square	63×30×20	27	4 960910 765030	12	

Features

- Measures by attaching to square
- Can be used on flat surfaces as well

Use

- For verification of horizontality, verticality

Specifications

Sensitivity Precision	Sensitivity 0.5 mm/m = 0.0286° Precision ±2.5 mm/m = less than ±0.1432°
Material	Body: Aluminum Vial: Acrylic resin Liquid: Petroleum liquid

Post Level with Magnet



76339

With scales
Rubber stopper band


*Gradient cannot be measured with vial graduations.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76339	Post Level	128×90×90	74	4 960910 763395	6	

*Not available in certain areas. Please contact us for details.

Features

- Can be used to draw lines in right angle and 45°
- Attached magnets make it ideal for steel frame and steel-pipe work
- Stopper band included



With magnets



Use

- For marking vertical line on pillar or piling

Specifications

Sensitivity Precision	Sensitivity 0.5 mm/m = 0.0286° Precision ±2.5 mm/m = less than ±0.1432°
Material	Body: ABS resin Vial: Acrylic resin Liquid: Petroleum liquid

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Blue Level Digital



76343



76348




76327

Item Code	Description	Length×Thickness (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76343	350 mm	65×27	356	4 960910 763432	6	
76344	350 mm with Magnet	65×27	371	4 960910 763449	6	
76348	450 mm	65×27	467	4 960910 763487	6	
76349	450 mm with Magnet	65×27	473	4 960910 763494	6	
76326	600 mm	65×27	555	4 960910 763265	6	
76327	600 mm with Magnet	65×27	580	4 960910 763272	6	

*Not available in certain areas. Please contact us for details.

Features

- Backlit LCD display
- Glow blue with luminous resin
- Luxurious color-alumite finish
- Alarm goes off on horizontal and perpendicular
- Also measures rise, angle, gradient
- If the level body is used in reverse, the display automatically shows in reverse as well
- Calibration function
- Battery life indicator
- Convenient HOLD function
- Zero set function that enables a base angle to be set
- Auto power off function
- Attached magnets make it ideal for steel frame work



Use

Rise in 1 m	Angle	%
Mainly for building work and plumbing work	Mainly for engineering work	Mainly for reference of gradient for road work

*Choose from three displays

Specifications

Vial Sensitivity, Precision	Sensitivity Precision	0.35 mm/m = 0.0201° ±1.0 mm/m = less than ±0.0573°
Digital Display Precision	0°, 90°	Angle: ±0.1° Gradient: ±0.2% Rise: ±2 mm/m
	Other Degrees	Angle: ±0.2° Gradient: ±0.7% Rise: ±4 mm/m (300 mmUP: ±7 mm/m)
Minimum Unit for Digital Display		Angle: 0.1° Gradient: 0.1% Digital Level: 1 mm/m
Power Source		1x 9V battery (Battery included is for trial use only and may not last as long)
Use Temperature		0 - 50°C
Material		Body: Aluminum, ABS resin Vial: Acrylic resin Liquid: Petroleum liquid

Digital Angle Meter



76447




Neodymium magnet (three sides)
 ●Strong neodymium magnets on three sides



76825



76826



Neodymium magnet (base)
 ●Strong neodymium magnets on base

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76447	Mini with Magnet	56×56×30	189	4 960910 764477	1	
76825	Digital Angle Meter II Dust/Waterproof	151×60×31	280	4 960910 768253	1	
76826	Digital Angle Meter II Dust/Waterproof with Magnet	151×60×31	280	4 960910 768260	1	

Features

- Convenient for measuring from a reference point by setting the point from any angle
- Hold function allows measurement when display cannot be seen
- Mini magnet
- Strong neodymium magnet on three sides
- Switches indication for angle (°) or gradient (%)
- Digital Angle Meter II
- Dustproof and waterproof under IP65 specifications, making it useful for angle measurements in various places
- Switches digitally between display of degree, %, and mm/m. With backlight function for use in dark places.
- BEEPs when horizontal or vertical

Use

- For work installing machines or equipment

Specifications

	76447
Range	90° x 4 directions (360°)
Minimum Indication	Angle: 0.1° Inclination: 0.1%
Precision	±0.2°(±3.5 mm/m)
Use Temperature	0 - 40°C
Power Source	1x 9V battery (Battery included is for trial use only and may not last as long)
Auto Power Off	5 minutes
Material	Body: Zinc alloy Panel: Polycarbonate resin
Accessory	Screwdriver

	76825	76826
Range	90° × 4 directions (360°)	
Minimum Indication	Angle: 0.05° Gradient: 0.1% Rise: 1 mm/m	
Precision	0°-90°: ±0.05° Other Degrees: ±0.15°	
Use Temperature	-10 - 50°C	
Power Source	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)	
Auto Power Off	5 minutes	
Dust/water proof	IP65	
Material	Body: ABS resin, aluminum	
Accessory	Holder case	

Laser Beam Level II NEW




76165



76166

- Safe design in which laser beam is activated only when the contact sensor and laser switch are pressed



*Illustration



Contact sensor

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76164	300 mm	300×55×25	320	4 960910 761643	3	
76165	300 mm with Magnet	300×55×25	435	4 960910 761650		
76166	450 mm	450×55×25	430	4 960910 761667		
76167	450 mm with Magnet	450×55×25	540	4 960910 761674		

Rotating Table



76478




Image

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76478	for Laser Beam Level	φ108×100	800	4 960910 764781	1	

Features

- Laser point can be directed up to 10 m outdoors/30 m indoors to show horizontal level/gradient in a remote place
- Depends on usage environment such as brightness
- Horizontal vial LED lights up brightly when laser is irradiated, so you can see at a glance that laser light is coming out



- Measurement surface has a V-shaped groove to enable pipe measurement
- Can measure gradients of 1/50 and 1/100

Use

- For installation work in civil engineering, plumbing, electricity, masonry, interior finishing, and do-it-yourself carpentry, etc.

Specifications

Laser	Light Source	Visible light semiconductor laser
	Output	Less than 1 mW (JIS class 2 C6802: 2014)
	Wave Length	640 - 660 nm
	Display Accuracy	±2 mm per 5 m
Vial	Diameter *1	φ3 mm per 5 m
	*1 Distance Recognition	Outside: Approx. 10 m Inside: Approx. 30 m
	*2 Sensitivity	Horizontal: 0.35 mm/m=0.0201° Vertical: 0.5 mm/m=0.0286°
	Precision	Horizontal: ±1.0 mm/m = less than ±0.0573° Vertical: ±2.5 mm/m = less than ±0.1432°
Use Temperature		-10 - 50°C
Storage Temperature		-20 - 60°C
Power Source		2× AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)
Material	Body:	Aluminum, ABS resin, polypropylene resin
	Vial:	Acrylic resin
Liquid:		Petroleum liquid

*1 Depends on usage environment such as brightness
 *2 Sensitivity is the gradient when the bubble starts moving

Rotating Table

Features

- Smoothly rotates 360°
- Can be used for height adjustment such as positioning of a window frame by mounting a laser beam level and attaching to a tripod

Use

- For horizontal referencing by mounting a laser beam level


Specifications

Material	Rotating Plate Base: Aluminum die casting Level Stopper: ABS resin
Accessory	Hexagonal wrench (for adjusting circular vial)
Installation Screw	5/8 inch

Water Level



76644



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76644	A with 15 m Hose	290×290×67	1,130	4 960910 766440	1	

*Not available in certain areas. Please contact us for details.

Features

- Water level enables leveling a ceiling or over a long distance
- 15 cm-long hose with alarm function enables verification of the level from a distance without help from another person
- Easy-to-use compact size for tight spaces
- Comes with brush for washing the hose
- Enables precise adjustment by use of audible indicator
- Visually determine horizontal level

Use

- For suspended ceiling, basement, landscaping, grading, and fence work, etc.

Specifications

Precision	±1.5 mm/15 m
Material	Body: ABS resin Hose: Vinyl chloride resin
Hose Size	Outer Diameter: 11 mm Inner Diameter: 8 mm
Power Source	1x 9V Alkaline battery (Battery included is for trial use only and may not last as long)

Blue Slant



78546



78543



78544



78545



78551

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78546	Revolving Dial Model	120×240×20	120		5	
78543	Tube Vial Model	109×235×16	80			
78544	Dial Model	107×230×18.5	100			
78545	Dial Model with Magnet	107×230×18.5	115			
78551	Dial Model for Japanese Roof Slope	107×230×18.5	100			

*Not available in certain areas. Please contact us for details.

Features



●Dial can be raised for cleaning (Revolving Dial Model)



●Large vial (Revolving Dial Model)



●Easy-to-turn LOCK knob (Revolving Dial Model)

- Made of sturdy fiberglass ABS resin
- Both front and back sides can be used (Revolving Dial Model, Vial Model)
- Strong neodymium magnets on measurement side (Dial Type with Magnets Model)

Use

- For checking angle or slope

Specifications

	78546		
Sensitivity	Sensitivity 0.35 mm/m = 0.0201°		
Precision	Precision ±17.5 mm/m = less than ±1.0°		
Material	Body: ABS resin (with fiberglass) Vial: Acrylic resin Liquid: Petroleum liquid		
	78543		
Sensitivity	Sensitivity 0.7 mm/m = 0.0401°		
Precision	Precision ±17.5 mm/m = Less than ±1.0°		
Material	Body: ABS resin (with fiberglass) Vial: Glass Liquid: Petroleum liquid		
	78544	78545	78551
Sensitivity	Sensitivity 2.0 mm/m = 0.1146°		
Precision	Precision ±17.5 mm/m = less than ±1.0°		
Material	Body: ABS resin (with fiberglass) Clear Cover: Polyethylene resin Pointer: Aluminum		

Angle Level



78997



78996



78966

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78997	A-150	78×62×15	70		5	
78996	A-300	93×79×18	99			
78966	A-600	141×133×20	541			

Features

- Vernier scale measures angle faster and more accurately


Use

- For angle measurement

Specifications

	78997	78996	78966
Precision		±0.6°	
Minimum Measurement	0.2°	0.1°	5 mins (about 0.08°)
Material	Body: ABS resin		
Accessory	Stainless steel rule 15 cm		

How to read vernier scale



- ① Reading roughly at 0 on vernier scale. **26**
- ② Read where outside graduation matches by looking at vernier scale, which is located on the opposite side from the pointer. **26+4=26.4 degree**

11. Lasers/ Optical Equipment






Features of Laser ROBO Xline series

*Laser light depicted is an illustration.

360° irradiation with 1 light source

- Adoption of a cone mirror enables 360° irradiation with one light source. Greatly improves work efficiency since there is no need to rotate the main body.




Ceiling marking/ground marking lines cross

- The 360° full line crosses at 90°, forming the ceiling marking point/ground marking point



Easy-to-see Line/Bright Line

- Highly visible green-colored laser, bright and vivid red-colored laser



Inside corner 10 mm, outside corner 0 mm

- Can be used for inside corners from 10 mm* and outside corners from 0 mm since the ground marking cross lines can be irradiated



*When protective caps on the lasers have been

Body and rotary plate can be separated

- Separating makes it easier to mark in lower positions, easier to carry, and further improves usability



Fixed line mode

- All models feature a convenient fixed line mode for irradiating a line diagonally



IP54

- No concern about malfunction due to dust or water splashes, thanks to IP54 level dustproof and waterproof construction



Laser ROBO X line-E NEW

Electronic level sensor + motor

Full
Circumference
Accuracy
±1.5/7.5

Dust/
Water proof
IP54

For
Laser
Receiver

Dual Power
Source
Battery
AC

Do not stare into beam
Maximum Output 1 mW Frequency 5.5 kHz
Wavelength 510 - 538 nm
Class 2 Laser Product JIS C6802: 2014

High
Brightness
GREEN



71610





Do not stare into beam
Also, do not expose to a user of a telescopic optical system
Maximum Output 1 mW Frequency 5.5 kHz
Wavelength 635 - 638 nm
Class 2 Laser Product JIS C6802: 2014

High
Brightness
Twice More



71609



Item Code	Description	JAN Code	Packing Unit	Packaging
71610	X line-E Green	4 960910 716100	1	
71620	X line-E Green with Receiver and Tripod	4 960910 716209		
71609	X line-E Red	4 960910 716094		
71619	X line-E Red with Receiver and Tripod	4 960910 716193		

Laser ROBO X line NEW

Pendulum + magnetic damper

Full
Circumference
Accuracy
±1.5/7.5

Dust/
Water proof
IP54

For
Laser
Receiver


Dual Power
Source
Battery
AC

Do not stare into beam
Maximum Output 1 mW Frequency 5.5 kHz
Wavelength 510 - 538 nm
Class 2 Laser Product JIS C6802: 2014

High
Brightness
GREEN



71608




Do not stare into beam
Also, do not expose to a user of a telescopic optical system
Maximum Output 1 mW Frequency 5.5 kHz
Wavelength 635 - 638 nm
Class 2 Laser Product JIS C6802: 2014

High
Brightness
Twice More




71607



Item Code	Description	JAN Code	Packing Unit	Packaging
71608	X line Green	4 960910 716087	1	
71618	X line Green with Receiver and Tripod	4 960910 716186		
71607	X line Red	4 960910 716070		
71617	X line Red with Receiver and Tripod	4 960910 716179		

Features


- Adoption of a cone mirror enables 360° irradiation with one light source. Greatly improves work efficiency since there is no need to rotate the main body.



- 360° full line crosses the 90° line, forming ceiling marking/ground marking



- Since the ground marking cross lines can be irradiated, can be used for inside corners from 10 mm*, and outside corners from 0 mm




*When protective caps on, the lasers have been removed.

- Separating makes it easier to mark in lower positions, easier to carry, and further improves usability



- All models feature a convenient fixed line mode for shining a line diagonally



Use

- For all types of referencing

Specifications

- Mentioned on page 98

*Laser light depicted is an illustration.

Accessories



Receiver and Tripod Set Items




JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Differences in Braking Systems

Electronic level sensor + motor


Since inclination is sensed by the electronic level sensor and adjustment is done automatically by the two motors, the line is stabilized even in work sites with many vibrations, such as a high-rise building or a road with high traffic volume, and the line can be determined quickly.



— Work Sites with Many Vibrations —


Electronic level sensor + motor

Pendulum + magnetic damper




Pendulum + magnetic damper

Swinging can be quickly stopped by braking with pendulum and magnetic damper. Simple construction also makes it lightweight.



Xline-E
(Electronic level sensor + motor)

Xline
(Pendulum + magnetic damper)



Specifications Laser ROBO X line series

	71610	71609	71608	71607
Type	X line-E Green	X line-E Red	X line Green	X line Red
Light Source	Visible light semiconductor laser			
Output	1 mW Less than(Class2 JIS C6802: 2014)	2 mW Less than(Class2M JIS C6802: 2014)	1 mW Less than(Class2 JIS C6802: 2014)	2 mW Less than(Class2M JIS C6802: 2014)
Wave Length	510 - 538 nm	635 - 638 nm	510 - 538 nm	635 - 638 nm
Display Accuracy	±1.5 mm per 7.5 m			
Plumbpoint Accuracy	±1 mm per 3 m			
Vertical Accuracy	90°±0.03°			
Base Line Accuracy	±1.5 mm per 7.5 m			
Line Diameter	5 m About 2 mm(7.5 m About 3 mm)			
Automatic Correction Range	±4°		±3°	
Tilt Alam	Laser light blinks when it gets over automatic correction range(about a 1-second interval)			
Rotary Fine-Adjustment Range	360°			
Braking System	Sensor,motor system		Pendulum, Magnetic damper	
Power Source	4x AA Alkaline batteries or AC adapter *1			
Continuous Usage Time (1): 1 line *4 (2): 2 lines (3): 3 lines	(1)About 10 hrs (2)About 4 hrs (3)About 2 hrs	(1)About 14.5 hrs (2)About 6.5 hrs (3)About 3 hrs	(1)About 10.5 hrs (2)About 4.5 hrs (3)About 2 hrs	(1)About 17 hrs (2)About 8 hrs (3)About 4.5 hrs
Battery Usage Alarm	Power lamp flashes during use, laser light blinks for 8 secs. When turned on (at 0.5 sec. intervals), or when battery is nearly depleted, the device no longer does automatic leveling and laser light blinks for about 1 sec. intervals.		Power lamp blinks during use; laser line flashes for approximately 8 seconds (approximately 0.5-second intervals) when the power is ON; when multiple laser lines are irradiated and battery consumption continues, the device will automatically switch to irradiating only a horizontal line	
Maximum Range of Line	About 35 m (when with optical receiver) *5			
Dustproof/Waterproof	IP54 (when with battery) *6			
TriPod Screw	5/8 inch			
Size	Height 213 mm × Width 127 mm × Depth 182 mm		Height 188 mm × Width 127 mm × Depth 182 mm	
Approximate Weight (including batteries)	About 1,600 g		About 1,450 g	

*1 AA Ni-MH rechargeable batteries can also be used, but will not be recharged with the AC adapter. *2 When using for a long time at about 20°C, we recommend using the AC adapter instead of AA alkaline batteries. *3 This is based on the number of lines, so continuous usage time is the same with any combination. *4 When the power switch is turned ON, a horizontal line will be automatically irradiated. *5 Maximum reachable distance varies depending on the working environment and measurement position used. *6 Dustproof performance: Prevents dust from penetrating inside the device. A small amount of dust that has penetrated inside will not hinder normal operation. Waterproof performance: It will not be harmfully affected by a splash of water from any direction.

JIS JIS mark Red with red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Vibration-resistant Sensor + Motor

LASER ROBO NEO
GREEN
E-SENSOR

LASER ROBO NEO
E-SENSOR





Features of Laser ROBO Neo E Sensor series

*Laser depicted is an illustration.


Vibration resistant

- Quickly determine the line even in a work location with large vibrations and shaking




Easy-to-see Line/Bright Line

- Highly visible green-colored laser, bright and vivid red-colored laser




Fixed Line Mode

- Convenient when wanting to expose the line diagonally, etc.



Full Horizontal Line

- Emits laser lights in all 4 horizontal directions, spreading out in a full horizontal line (51 AR model)



AC adapter

- Continuous use possible over a long time



360° Rotary fine-adjustment


- Can be adjusted to a precise reference with rotary fine-adjustment knob capable of 360° rotation



Laser ROBO Green Neo E Sensor



- Full line type with full horizontal line and 4 vertical lines



71606



- High class type with full vertical lines



71605

- Reveals right angle to improve work efficiency






71603

- Basic vertical and horizontal line



71602




Features

- Uses a sensor + motor system that is resistant to strong vibrations



- With convenient Fixed Line Mode when wanting to expose line diagonally



Fixed Line

- Enables changing exposure only to necessary lines for horizontal circumference, full vertical and triangle-shape projection to reduce power consumption

71606 71616	① button to switch line patterns	
71606 71616 71605 71615	③ button to switch line patterns	
71603 71613	③ button to switch line patterns	

Use

- For all types of referencing

Specifications

- Mentioned on page 102

*Laser depicted is an illustration.

Item Code	Description	JAN Code	Packing Unit	Packaging
71606	Green Neo E Sensor 51 AR	4 960910 716063	1	B
71616	Green Neo E Sensor 51 AR with Receiver and Tripod	4 960910 716162	1	B
71605	Green Neo E Sensor 51	4 960910 716056	1	B
71615	Green Neo E Sensor 51 with Receiver and Tripod	4 960910 716155	1	B
71603	Green Neo E Sensor 31	4 960910 716032	1	B
71613	Green Neo E Sensor 31 with Receiver and Tripod	4 960910 716131	1	B
71602	Green Neo E Sensor 21	4 960910 716025	1	B
71612	Green Neo E Sensor 21 with Receiver and Tripod	4 960910 716124	1	B

Accessories



AC adapter



Level adjustment tripod adapter



Aluminum case
4x AA Alkaline batteries

Receiver and Tripod Set Items



Laser Receiver II Plus
for Laser ROBO Green
with Holder




Tripod with handle
Elevator A Lightweight type

Laser ROBO Neo E Sensor



- Full line type with full horizontal line and 4 vertical lines



71506

- High class type with full vertical lines



71505

- Reveals right angle to improve work efficiency






71503

- Basic vertical and horizontal line



71502




Features

- Uses a sensor + motor system that is resistant to strong vibrations



- Convenient Fixed Line Mode when wanting to expose line diagonally



- Includes Level Adjustment Tripod Adapter that makes it easy to adjust level when using a tripod



- Can be adjusted to a precise reference with rotary fine-adjustment knob capable of 360° rotation



Use

- For all types of referencing

Specifications

- Mentioned on page 102

*Laser depicted is an illustration.

Item Code	Description	JAN Code	Packing Unit	Packaging
71506	Neo 51 AR E Sensor	4 960910 715066	1	
71516	Neo 51 AR E Sensor with Receiver and Tripod	4 960910 715165		
71505	Neo 51 E Sensor	4 960910 715059		
71515	Neo 51 E Sensor with Receiver and Tripod	4 960910 715158		
71503	Neo 31 E Sensor	4 960910 715035		
71513	Neo 31 E Sensor with Receiver and Tripod	4 960910 715134		
71502	Neo 21 E Sensor	4 960910 715028		
71512	Neo 21 E Sensor with Receiver and Tripod	4 960910 715127		

Accessories	Receiver and Tripod Set Items
AC Adapter Laser Glasses Level Adjustment Tripod Adapter Aluminum Case 4x AA Alkaline batteries	Optical Receiver Laser Receiver II Plus with Holder Tripod with Handle Elevator A Lightweight Type

Specifications Laser ROBO Neo E Sensor series

	71606	71605	71603	71602
Type	Green Neo E Sensor 51AR	Green Neo E Sensor 51	Green Neo E Sensor 31	Green Neo E Sensor 21
Light Source	Visible light semiconductor laser			
Output	Less than 1 mW (JIS class 2 C6802: 2014)			
Wave Length	520 nm (Green) Ground Marking Point: 650 nm (Red)			
Display Accuracy	Vertical: ±1 mm per 7.5 m Horizontal Circumference: ±1.5 mm per 7.5 m	Vertical/ Horizontal Line ±1 mm per 7.5 m		
Plumb Point Accuracy	±1 mm per 3 m			—
Vertical Accuracy	±0.03° at 90°			—
Base Line Accuracy	±1 mm per 7.5 m		—	
Angle of Emergence	Vertical: About 120° Horizontal: About 100° (Front 115°)	Vertical: About 120° Horizontal: About 115°		
Line Diameter	About 1.8 mm at 5 m ahead (about 2 mm at 7.5 m ahead)			
Automatic Correction Range	±3°			
Tilt Alarm	Laser light blinks when it gets over automatic correction range (about a 1-second interval) *1			
Rotary Fine-Adjustment Range	360°			
Braking System	Sensor + motor system			
Power Source	4x AA Alkaline batteries or AC adapter *2			
Continuous Usage Time *3 (A), (B), (C), and (D) correspond to description in the previous pages *6	①Mode *4 (A)7.5 hrs (B)35 hrs ②Mode (A)12 hrs (B)2 hrs ③Mode (A)24 hrs (B)12 hrs (C)12 hrs (D)5.5 hrs	①Mode *5 (A)35 hrs ②Mode (A)12 hrs (B)4.5 hrs ③Mode (A)24 hrs (B)12 hrs (C)12 hrs (D)5.5 hrs	①Mode *5 (A)35 hrs ②Mode (A)12 hrs (B)9 hrs ③Mode (A)24 hrs (B)12 hrs	①Mode *5 (A)35 hrs ②Mode (A)12 hrs ③Mode (A)24 hrs
Battery Usage Alarm	Power lamp flashes during use, laser light blinks for 8secs. When turned on (at 0.5sec. intervals), or when battery is nearly depleted, the device no longer does automatic leveling and laser light blinks for about 1sec. intervals.			
Maximum Range of Line	About 35 m (when with optical receiver) *7			
Dustproof/Waterproof	IP54 (when with battery) *8			
Tripod Screw	5/8 inch			
Size	Diameter 128 mm × Height 190 mm (body 105 mm x 96 mm)			
Approximate Weight (including battery)	1,325 g	1,280 g	1,265 g	1,250 g

*1 All of the lines will turn off, and only the horizontal line will blink. Return to automatic correction range and it will return to the previous state. *2 AA nickel hydride batteries can be used, but the AC adapter will not charge the device. *3 When using AA alkaline batteries at 20°C. *4 With the AR Series, turning the power switch ON automatically goes into ① mode's full horizontal line. *5 Turning the power switch ON automatically goes into ① mode. *6 Hold down the ② button to turn on all the lines. Using an AC adapter is recommended when using full lines over a long period of time. *7 Depends on circumstance and position of use. Receiving over 20m ahead is possible but accuracy is not guaranteed. *8 Dustproof: Protected from limited dust ingress. Waterproof: Protected from water spray from any direction.

	71506	71505	71503	71502
Type	Neo E Sensor 51AR	Neo E Sensor 51	Neo E Sensor 31	Neo E Sensor 21
Light Source	Visible light semiconductor laser			
Output	Less than 1 mW (JIS class 2)			
Wave Length	635 nm Ground Marking Point: 650 nm (Red)			
Display Accuracy	Vertical : ±1 mm per 7.5 m Horizontal Circumference : ±1.5 mm per 7.5 m	Vertical/ Horizontal Line ±1 mm per 7.5 m		
Plumb Point Accuracy	±1 mm per 3 m			—
Vertical Accuracy	±0.03° at 90°			—
Base Line Accuracy	±1 mm per 7.5 m		—	
Angle of Emergence	Vertical: About 120° Horizontal: About 100° (Front 115°)	Vertical: About 120° Horizontal: About 115°		
Line Diameter	About 1.5 mm at 5 m ahead (about 2 mm at 7.5 m ahead)			
Automatic Correction Range	±3°			
Tilt Alarm	Laser light blinks when it gets over automatic correction range (about a 1-second interval) *1			
Rotary Fine-Adjustment Range	360°			
Braking System	Sensor + motor system			
Power Source	4x AA Alkaline batteries or AC adapter *2			
Continuous Usage Time *3 (1): ①Mode *4 (2): ②Mode (F): All Lines Mode *6 (3): ③Mode	(1)11.5 hrs *4 (2)22 hrs (F)3.5 hrs (3)9 hrs	(1)44.5 hrs *5 (2)22 hrs (F)7.5 hrs (3)9 hrs	(1)44.5 hrs *5 (2)22 hrs (F)14 hrs (3)22 hrs	(1)44.5 hrs *5 (2)22 hrs (3)35.5 hrs
Battery Usage Alarm	Power lamp flashes during use, laser light blinks for 8secs. When turned on (at 0.5sec. intervals), or when battery is nearly depleted, the device no longer does automatic leveling and laser light blinks for about 1sec. intervals.			
Maximum Range of Line	About 35 m (when with optical receiver) *7			
Dustproof/Waterproof	IP54 (when with battery) *8			
Tripod Screw	5/8 inch			
Size	Diameter 128 mm × Height 190 mm (body 105 mm x 96 mm)			
Approximate Weight (including battery)	1,325 g	1,280 g	1,265 g	1,250 g

*1 All of the lines will turn off, and only the horizontal line will blink. Return to automatic correction range and it will return to the previous state. *2 AA nickel hydride batteries can be used, but the AC adapter will not charge the device. *3 When using AA alkaline batteries at 20°C. *4 With the AR Series, turning the power switch ON automatically goes into ① mode's full horizontal line. *5 Turning the power switch ON automatically goes into ① mode. *6 Hold down the ② button to turn on all the lines. Using an AC adapter is recommended when using full lines over a long period of time. *7 Depends on circumstance and position of use. Receiving over 20m ahead is possible but accuracy is not guaranteed. *8 Dustproof: Protected from limited dust ingress. Waterproof: Protected from water spray from any direction.

Full Horizontal High-brightness Line Models

LASERROBO
GREEN Neo
AR
BRIGHT



LASERROBO
Neo AR
BRIGHT



High-brightness Line Standard Models

LASERROBO
GREEN Neo
BRIGHT



LASERROBO
Neo
BRIGHT




Features of Laser ROBO Green Neo AR BRIGHT series

*Laser depicted is an illustration.

Full Horizontal Line

- Emits laser lights in all 4 horizontal directions, spreading out in a full horizontal line

**Around
Horizon**



Outstanding visibility

- Green line visually easier to see than red line


Comparison of green line and red line



*Actual lines may look different.

Direct semiconductor laser

- Direct laser diode stable even under low or high temperature
- Compared to wavelength conversion type, direct type exposes a line with entirely uniform and stable width and strength




Level Adjustment Tripod Adapter

- Easy to turn and finely adjust level when using tripod
- Shinwa's original innovative adapter that allows leveling without adjusting tripod legs



Laser ROBO Green Neo AR BRIGHT



- Full line type with full horizontal line and 4 vertical lines




78279

- Full horizontal line and right angle




78278



- Full horizontal line and vertical line




78277



Features

- Emits laser lights in all 4 horizontal directions, spreading out in a full horizontal line






- Uses a direct type semiconductor laser which, compared to a wavelength conversion type, exposes a line with entirely uniform and stable width and strength

Direct type

Wavelength conversion type

- Enables changing exposure only to necessary lines for horizontal circumference, full vertical and triangle-shape projection to reduce power consumption



- Includes Level Adjustment Tripod Adapter that makes it easy to adjust level when using a tripod
- Can be adjusted to a precise reference with rotary fine-adjustment knob capable of 360° rotation

Use

- For all types of referencing

Specifications

- Mentioned on page 108

*Laser depicted is an illustration.

Accessories



AC Adapter



Level Adjustment Tripod Adapter



Aluminum Case
4x AA Alkaline Batteries

Receiver and Tripod Set Items



Laser Receiver II Plus
for Laser ROBO Green
with Holder



Tripod with Handle
Elevator A Lightweight Type

Item Code	Description	JAN Code	Packing Unit	Packaging
78279	Green Neo 51 AR BRIGHT	4 960910 782792	1	B
78289	Green Neo 51 AR BRIGHT with Receiver and Tripod	4 960910 782891	1	B
78278	Green Neo 31 AR BRIGHT	4 960910 782785	1	B
78288	Green Neo 31 AR BRIGHT with Receiver and Tripod	4 960910 782884	1	B
78277	Green Neo 21 AR BRIGHT	4 960910 782778	1	B
78287	Green Neo 21 AR BRIGHT with Receiver and Tripod	4 960910 782877	1	B

Laser ROBO Neo AR BRIGHT



- Full line type with full horizontal line and 4 vertical lines




78241

- Full horizontal line and right angle




78240



- Full horizontal line and vertical line




77508



- Full horizontal line only




77507




Features

- Emits laser lights in all 4 horizontal directions, spreading out in a full horizontal line



- Vivid line can easily be seen even in bright worksites



- Includes Level Adjustment Tripod Adapter that makes it easy to adjust level when using a tripod



- Can be adjusted to a precise reference with rotary fine-adjustment knob
- Dustproof, water-resistant construction for use even in dusty environments or during sudden rain



Use

- For all types of referencing

Specifications

- Mentioned on page 108

*Laser depicted is an illustration.

Item Code	Description	JAN Code	Packing Unit	Packaging
78241	Neo 51 AR BRIGHT	4 960910 782419	1	
78244	Neo 51 AR BRIGHT with Receiver and Tripod	4 960910 782440		
78240	Neo 31 AR BRIGHT	4 960910 782402		
78243	Neo 31 AR BRIGHT with Receiver and Tripod	4 960910 782433		
77508	Neo 21 AR BRIGHT	4 960910 775084		
78219	Neo 21 AR BRIGHT with Receiver and Tripod	4 960910 782198		
77507	Neo 01 AR BRIGHT	4 960910 775077		
78218	Neo 01 AR BRIGHT with Receiver and Tripod	4 960910 782181		

Accessories



Laser Glasses



Level Adjustment Tripod Adapter



Aluminum Case
4x AA Alkaline batteries

Receiver and Tripod Set Items




Optical Receiver
Laser Receiver II Plus
with Holder



Tripod with Handle
Elevator A Lightweight Type

Laser ROBO Green Neo BRIGHT



- High-class green type with full vertical lines



78276

- Multi-purpose green type that gives all required reference lines



78271

- Green type with right angle



78275

- Green type with ceiling marking point




78273

- Green type with basic vertical & horizontal line



78274



Item Code	Description	JAN Code	Packing Unit	Package
78276	Green Neo 51 BRIGHT	4 960910 782761	1	B
78286	Green Neo 51 BRIGHT with Receiver and Tripod	4 960910 782860	1	B
78271	Green Neo 41 BRIGHT	4 960910 782716	1	B
78291	Green Neo 41 BRIGHT with Receiver and Tripod	4 960910 782914	1	B
78275	Green Neo 31 BRIGHT	4 960910 782754	1	B
78285	Green Neo 31 BRIGHT with Receiver and Tripod	4 960910 782853	1	B
78273	Green Neo 21P BRIGHT	4 960910 782730	1	B
78283	Green Neo 21P BRIGHT with Receiver and Tripod	4 960910 782839	1	B
78274	Green Neo 21 BRIGHT	4 960910 782747	1	B
78284	Green Neo 21 BRIGHT with Receiver and Tripod	4 960910 782846	1	B

Features

- Uses a direct type semiconductor laser which, compared to a wavelength conversion type, exposes a line with entirely uniform and stable width and strength

Direct type

Wavelength conversion type

- Enables changing exposure only to necessary lines for horizontal circumference, full vertical and triangle-shape projection to reduce power consumption

78276 78286	③ button to switch line patterns
78271 78291	③ button to switch line patterns
78275 78285	③ button to switch line patterns
78273 78283	③ button to switch line patterns

- Includes Level Adjustment Tripod Adapter that makes it easy to adjust level when using a tripod
- Can be adjusted to a precise reference with rotary fine-adjustment knob capable of 360° rotation

Use

- For all types of referencing

Specifications

- Mentioned on page 108

*Laser depicted is an illustration.

Accessories AC Adapter Level Adjustment Tripod Adapter Aluminum Case 4x AA Alkaline batteries	Receiver and Tripod Set Items Laser Receiver II Plus for Laser ROBO Green with Holder Tripod with Handle Elevator A Lightweight Type
--	--

Laser ROBO Neo BRIGHT

 High Brightness
Twice More

 High Precision
±1mm/7.5m

 Dust/Water-proof
IP54

For Laser Receiver

 Do not stare into beam
Maximum Output 1 mW Frequency 5.5 kHz
Wavelength 635 - 638 nm
Class 2 Laser Product JIS C6802: 2014

Premium product with two full lines

Multi-purpose type that gives all required reference lines

Reveals right angle to improve work efficiency

Reveals ceiling marking point



77362







77361



77360



77355



Basic vertical and horizontal line

Reveals ceiling marking point

Horizontal line only






77354



77389




77388



Item Code	Description	JAN Code	Packing Unit	Packaging
77362	Neo 51 BRIGHT	4 960910 773622	1	
77625	Neo 51 BRIGHT with Receiver and Tripod	4 960910 776258	1	
77361	Neo 41 BRIGHT	4 960910 773615	1	
77609	Neo 41 BRIGHT with Receiver and Tripod	4 960910 776098	1	
77360	Neo 31 BRIGHT	4 960910 773608	1	
77608	Neo 31 BRIGHT with Receiver and Tripod	4 960910 776081	1	
77355	Neo 21P BRIGHT	4 960910 773554	1	
77606	Neo 21P BRIGHT with Receiver and Tripod	4 960910 776067	1	
77354	Neo 21 BRIGHT	4 960910 773547	1	
77605	Neo 21 BRIGHT with Receiver and Tripod	4 960910 776050	1	
77389	Neo 11P BRIGHT	4 960910 773899	1	
77388	Neo 01 BRIGHT	4 960910 773882	1	

Features

Vivid line can easily be seen even on bright worksites



Includes Level Adjustment Tripod Adapter that makes it easy to adjust level when using a tripod



Can be adjusted to a precise reference with rotary fine-adjustment knob capable of 360° rotation



Dustproof, water-resistant construction for use even in dusty environments or during sudden rain



Use

For all types of referencing

Specifications

Mentioned on page 108

*Laser depicted is an illustration.

Accessories



Laser Glasses



Level Adjustment Tripod Adapter

Aluminum Case
4x AA Alkaline batteries

Receiver and Tripod Set Items

Optical Receiver
Laser Receiver II Plus
with HolderTripod with Handle
Elevator A Lightweight Type

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Specifications Laser ROBO Neo BRIGHT Series

	78279	78278	78277	78276	78271	78275	78273	78274
Type	Green Neo 51 AR BRIGHT	Green Neo 31 AR BRIGHT	Green Neo 21 AR BRIGHT	Green Neo 51 BRIGHT	Green Neo 41 BRIGHT	Green Neo 31 BRIGHT	Green Neo 21P BRIGHT	Green Neo 21 BRIGHT
Light Source	Visible light semiconductor laser							
Output	Less than 1 mW (JIS class 2)							
Wave Length	520 nm (Green) Ground Marking Point: 650 nm (Red)							
Display Accuracy	Vertical: ±1 mm per 7.5 m Horizontal Circumference: ±1.5 mm per 7.5 m			Vertical/ Horizontal Line ±1 mm per 7.5 m				
Plumb Point Accuracy	±1 mm per 3 m		—	±1 mm per 3 m				—
Vertical Accuracy	±0.03° at 90°		—	±0.03° at 90°			—	
Base Line Accuracy	±1 mm per 7.5 m	—		±1 mm per 7.5 m		—		
Angle of Emergence	Vertical: About 130° Horizontal: About 105°			Vertical: About 130° Horizontal: About 120°				
Line Diameter	About 1.8 mm at 5 m ahead (about 2 mm at 7.5 m ahead)							
Automatic Correction Range	±2.5°							
Tilt Alarm	Laser light blinks when it gets over automatic correction range (about a 1-second interval)*1							
Rotary Fine-Adjustment Range	360°							
Braking System	Pendulum + Magnetic damper							
Power Source	4x AA Alkaline batteries or AC adapter *2							
Continuous Usage Time (A), (B), (C), and (D) correspond to description in the previous pages *4 *5	①Mode (A)7 hrs (B)27 hrs ②Mode (A)11 hrs (B)2 hrs ③Mode (A)19 hrs (B)11 hrs (C)11 hrs (D)4.5 hrs	①Mode (A)7 hrs (B)27 hrs ②Mode (A)11 hrs (B)3.5 hrs ③Mode (A)19 hrs (B)11 hrs	①Mode (A)7 hrs (B)27 hrs ②Mode (A)11 hrs (B)4 hrs ③Mode (A)19 hrs	①Mode (A)27 hrs ②Mode (A)11 hrs (B)4 hrs ③Mode (A)19 hrs (B)11 hrs (C)11 hrs (D)4.5 hrs	①Mode (A)27 hrs ②Mode (A)11 hrs (B)4.5 hrs ③Mode (A)19 hrs (B)11 hrs (C)11 hrs (D)7 hrs	①Mode (A)27 hrs ②Mode (A)11 hrs (B)7 hrs ③Mode (A)19 hrs (B)11 hrs	①Mode (A)27 hrs ②Mode (A)11 hrs (B)7 hrs ③Mode (A)19 hrs (B)11 hrs	①Mode (A)27 hrs ②Mode (A)11 hrs ③Mode (A)19 hrs
Battery Usage Alarm	Laser light blinks for 8secs when turned on. (at 0.5-sec intervals)							
Maximum Range of Line	About 35 m (when with optical receiver) *6							
Dustproof/Waterproof	IP54 *7							
Tripod Screw	5/8 inch							
Size(mm)	Diameter 128 × Height 190 (body φ110 mm)			Diameter 128 × Height 180 (body φ94 mm)				
Approximate Weight (including battery)	1,320 g	1,290 g	1,260 g	1,215 g	1,210 g	1,200 g	1,195 g	1,190 g

*1 All of the lines will turn off, and only the horizontal line will blink. Return to automatic correction range and it will return to the previous state. *2 AA nickel hydride batteries can be used, but the AC adapter will not charge the device. *3 When using AA alkaline batteries at 20°C. *4 With the AR Series, turning the power switch ON automatically goes into ① mode's full horizontal line. *5 Hold down the ② button to turn on all the lines. Using an AC adapter is recommended when using full lines over a long period of time. *6 Depends on circumstance and position of use. Receiving over 20m ahead is possible but accuracy is not guaranteed. *7 Dustproof: Protected from limited dust ingress. Waterproof: Protected from water spray from any direction.

	78241	78240	77508	77507	77362	77361	77360	77355	77354	77389	77388	
Type	Neo 51 AR BRIGHT	Neo 31 AR BRIGHT	Neo 21 AR BRIGHT	Neo 01 AR BRIGHT	Neo 51 BRIGHT	Neo 41 BRIGHT	Neo 31 BRIGHT	Neo 21P BRIGHT	Neo 21 BRIGHT	Neo 11P BRIGHT	Neo 01 BRIGHT	
Light Source	Visible Light Semiconductor Laser											
Output	Less than 1 mW (JIS class 2)											
Wave Length	635 nm (ground marking point: 650 nm)			635 nm	635 nm (ground marking point: 650 nm)						635 nm	
Display Accuracy	Vertical: ±1 mm per 7.5 m Horizontal circumference: ±1.5 mm per 7.5 m			Horizontal Circumference: ±1.5 mm per 7.5 m	Vertical/ Horizontal Line ±1 mm per 7.5 m					Vertical : ±1 mm per 7.5 m	Horizontal Circumference : ±1 mm per 7.5 m	
Plumb Point Accuracy	±1 mm per 3 m		—		±1 mm per 3 m				—	±1 mm per 3 m	—	
Vertical Accuracy	±0.03° at 90°		—		±0.03° at 90°			—				
Base Line Accuracy	±1 mm per 7.5 m	—			±1 mm per 7.5 m		—					
Angle of Emergence	Vertical: About 130°	Horizontal: About 105°		—	Vertical: About 130°				Horizontal: About 120°		Vertical: About 130°	Horizontal: About 105°
Line Diameter	About 1.5 mm at 5 m ahead (about 2 mm at 7.5 m ahead)											
Automatic Correction Range	±2.5°											
Tilt Alarm	Laser light blinks when it gets over automatic correction range (about a 1-second interval)											
Rotary Fine-Adjustment Range	About 5° (500 mm per 5 m)				360°							
Braking System	Pendulum + Magnetic damper											
Power Source	4x AA Alkaline batteries											
Continuous Usage Time *1 (1):①Mode (2):②Mode (F):All Lines Mode *2 (3):③Mode	(1)13 hrs (2)17.5 hrs (F)4 hrs (3)10 hrs	(1)13 hrs (2)17.5 hrs (F)5.5 hrs (3)24 hrs	(1)13 hrs (2)17.5 hrs (F)6.5 hrs (3)32 hrs	(1)13 hrs	(1)58 hrs (2)24 hrs (F)8 hrs (3)12 hrs	(1)58 hrs (2)24 hrs (F)12 hrs (3)16 hrs	(1)58 hrs (2)24 hrs (F)16 hrs (3)25 hrs	(1)58 hrs (2)24 hrs (F)24 hrs (3)37 hrs	(1)58 hrs (2)24 hrs (3)42 hrs	(1)37 hrs	(1)58 hrs	
Battery Usage Alarm	Laser light blinks for 8secs when turned on (at 0.5-sec intervals)											
Maximum Range of Line	About 35 m (when with optical receiver) *3											
Dustproof/Waterproof	IP54 *4											
Tripod Screw	5/8 inch											
Size(mm)	Diameter 128 × Height 190 (body ϕ110 mm)				Diameter 128 × Height 180 (body ϕ94 mm)							
Approximate Weight (including battery)	1,320 g	1,290 g	1,260 g	1,190 g	1,215 g	1,210 g	1,200 g	1,195 g	1,190 g	1,150 g	1,140 g	

*1 When using AA alkaline batteries at 20°C. *2 Hold down the ② button to turn on all the lines. *3 Depends on circumstance and position of use. Receiving over 20 m ahead is possible but accuracy is not guaranteed. *4 Dustproof: Protected from limited dust ingress. Waterproof: Protected from water spray from any direction.

Carpenter's Squares
Stainless Steel Rules / Machine Scale
Aluminum Rules
Resin Folding Rules / Bamboo Rules
Squares / Protectors
Vernier Calipers / Micrometers
Tape Measures
Surveying Products
Scales
Levels
Lasers / Optical Equipment
Inklines / Chalklines / Plumbholders
Circular Saw Guides
Construction Tools
Industrial Tools
Thermometers / Hygrometers / Humidity Measuring Instruments
Outdoor Products
Magnifying Glasses
Drawing Tools
Magnets

Laser ROBO Fine BRIGHT




- Multi-purpose type that gives all required reference lines

- Reveals right angle to improve work efficiency


- Basic vertical and horizontal line




77467



77466



77465



Item Code	Description	JAN Code	Packing Unit	Packaging
77467	Fine 41 BRIGHT	4 960910 774674	1	B
77466	Fine 31 BRIGHT	4 960910 774667	1	B
77465	Fine 21 BRIGHT	4 960910 774650	1	B

Features

- High precision and bright high-grade model
- Compact size for single-hand operation

Use

- For all types of referencing

Specifications

	77467	77466	77465
Light Source	Visible light semiconductor laser		
Output	Less than 1 mW (JIS class 2)		
Wavelength	635 nm (ground marking point: 650 nm)		
Display Accuracy	Vertical/ Horizontal Line ±1 mm per 10 m		
Plumb Point Accuracy	±1 mm per 5 m		
Vertical Accuracy	±0.012" at 90°		
Base Line Accuracy	±1 mm per 10 m		
Angle of Emergence	Vertical: About 135° Horizontal: About 120°		
Line Diameter	1.5 mm at 5 m ahead		
Automatic Correction Range	±2.5°		
Tilt Alarm	Light turns off when over automatic correction range		
Rotary Fine-Adjustment Range	About 5° (500 mm per 5 m)		
Braking System	Magnetic damper		
Power Source	3x AA alkaline batteries		
Continuous Usage Time *1	(1): ① Mode	(1): 35 hrs	(1): 35 hrs
	(2): ② Mode *2	(2): 17 hrs	(2): 17 hrs
	(F): All Lines Mode	(F): 9 hrs	(F): 11 hrs
	(3): ③ Mode	(3): 11 hrs	(3): 17 hrs
Battery Usage Alarm	Laser light blinks for 8 secs when turned on		
Maximum Range of Line	About 35 m (with laser receiver) *3		
Dustproof/Waterproof	IP54 *4		
Tripod Screw	5/8 inch		
Size	Diameter 106 mm × Height 180 mm (body ø88 mm)		
Approximate Weight (including battery)	950 g	930 g	910 g


*1 When using AA alkaline batteries at 20°C. *2 Any combination of the same number of V1, V2, and H lines yields the same approximate continuous usage time. *3 Hold down the ② button to turn on all the lines. *4 Depends on circumstance and position of use. Receiving over 20m ahead is possible but accuracy is not guaranteed.

Accessories

Laser Glasses
4x AA Alkaline batteriesLevel Adjustment
Tripod Adapter

Aluminum Case

Laser ROBO Fine 3C



77096



Accessories

- Spanner (for removing and replacing of tripod installation adapter)
- Laser glasses (improves visibility of laser)

- Quality aluminum case
- Exclusive AC adapter
- 4x AA Alkaline batteries
- Tripod installation adapter for 5/8 inch (already installed to lower part of unit)



Item Code	Description	JAN Code	Packing Unit	Packaging
77096	Fine 3C1	4 960910 770966	1	B

*Laser depicted is an illustration.

Features

- The world's first corn prism - due to 360° line with no joints, the unit does not have to be turned to level. Greatly increases workability.
- Auto-leveling function performed by electronic level sensor helps to expose stable laser line even at a place where strong vibration occurs.



Use

- For all types of referencing

Specifications

	77096
Light Source	Visible light semiconductor laser
Output	Less than 1 mW (JIS class 2)
Wavelength	620 - 660 nm
Line Accuracy	±1 mm per 14 m
Repeat Precision	±1 mm per 14 m
Plumb Point Accuracy	±1 mm per 10 m
Vertical Accuracy	±0.0086" at 90°
Angle of Emergence	±1 mm per 14 m
Line Diameter	less than 3 mm at 5 m ahead
Automatic Correction Range	±4°
Tilt Alarm	Light turns off when over automatic correction range
Rotary Fine-Adjustment Range	About 2°(300 mm per 10 m)
Braking System	Auto-leveling function by electronic level sensor and motor
Power Source	3x AA Alkaline batteries / attached AC adapter
Continuous Usage Time *1	(1)10 hrs
	(2)6 hrs
(1):1 Line *2	(3)4 hrs
(2):2 Lines	
(3):3 Lines	
Battery Usage Alarm	—
Maximum Range of Line	About 14 m (with laser receiver) *3
Dustproof/Waterproof	IP54 *4
Tripod Screw	M35 (5/8 inch when using tripod installation adapter)
Size	Diameter 195 mm × Height 230 mm (body ø150 mm)
Approximate Weight (including battery)	2,000 g

*1 When using AA alkaline batteries at 20°C. *2 Any combination of the same number of V1, V2, and H lines yields the same approximate continuous usage time. *3 Hold down the ② button to turn on all the lines. *4 Depends on circumstance and position of use. Receiving over 20m ahead is possible but accuracy is not guaranteed.

Laser Receiver II

Dust/
Water-proof
IP56



71500



71501



77398



77399


Compatible models

71500-77398	71501-77399
X line Red Series Neo BRIGHT Series Neo E Sensor Series	Fine 3C Series Fine BRIGHT Series X line Green Series Green Neo BRIGHT Series Green Neo E Sensor Series

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
71500	Plus with Holder	150×67×34	190	4 960910 715004	1	
71501	Plus for Laser ROBO Green with Holder	150×67×34	190	4 960910 715011	1	
77398	with Holder	150×67×34	190	4 960910 773981	1	
77399	for Laser ROBO Green with Holder	150×67×34	190	4 960910 773998	1	


Features

- Uses narrow mode during regular operation, and can be switched to wide mode for use on a site with vibrations (71500/71501)



(Centered receiving light width is just an illustration.)


- The alarm sound will be different when higher or when lower than the center, so the position of the laser line can be understood by hearing the sound (71500/71501)



(Alarm can also be turned off when not needed.)

- Dust/Waterproof structure IP56
- 5 Dustproof performance: Protected from limited dust ingress
- 6 Waterproof performance: Protected from high pressure water jets from any direction

- Confirm power-on/off with buzzer and LED light



- Holder provided as standard

Use

- For marking on bright worksites and places where the laser line can be hard to see

Specifications

	71500	71501	77398	77399
Receiving Distance	1.5 - 20 m*1	1.5 - 20 m*2	1.5 - 20 m*2	1.5 - 20 m*2
Receiving Accuracy	—	—	Within ±1.0 mm from the #2 center of laser line	Within ±1.0 mm from the #2 center of laser line
Centered*3 Receiving Light Width	Narrow mode: Within 1.0 mm from the centered receiving light line Wide mode: Within 2.0 mm from the centered receiving light line	—	—	—
Auto Power Off	Power automatically turns off 7 minutes after turning on.			
Battery Usage Alarm	Power LED blinks when turned on			
Power Source	1x 9V battery (Battery included is for trial use only and may not last as long)			
Continuous Usage Time	About 20 hrs			

*1 Receiving distance upper limit of 20 m is a reference value. Receiving over a farther distance depends on circumstance and position of use.
 *2 Depends on circumstance and position of use. Receiving over 20 m ahead is possible but accuracy is not guaranteed.
 *3 Depends on circumstance and position of use

Rotating Table for Fine 3C



77099

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77099	Rotating Table for Fine 3C	150×120×120	1,050	4 960910 770997	1	

Features

- Movable system allows easy position adjustment
- Tripod legs are foldable to enable work near walls

Use

- For Fine 3C Series position adjustment

Specifications

Material	Body: Aluminum, stainless steel
Installation Screw	M35
Compatible Models	Fine 3C Series

Laser Safety Glasses



76793

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76793	Laser Safety Glasses	150×55×60	32	4 960910 767933	5	

Features

- Red laser light is easier to see

Use

- Red laser light can be spotted even in a bright environment

Specifications

Material	Polycarbonate resin
Compatible Models	X line Red Series Neo BRIGHT Series Neo E Sensor Series Fine 3C Series Fine BRIGHT Series

Laser Holder for Light Weight Steel Framing



76923

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	packaging
76923	with Rising/Lowering Motion	125×180×170	920	4 960910 769236	1	

Features

- Improves workability with fine-adjustment of 40 mm up and down
- Using together with Level Adjustment Tripod Adapter makes it easy to adjust level when using Laser Holder for Lightweight Steel Framing

Use

- For base material leveling and adjusting height with laser line generator in lightweight steel framing

Specifications

Material	Body: Aluminum
	Fixing Screw for Laser Holder: Brass Fixing Screw for Holder: Iron Top Plate/Bottom Plate/Moveable Knob: Polyacetal resin
Attachable Post Width	40 - 120 mm
Installation Screw	5/8 inch
Compatible Models	X line Series Green Neo BRIGHT Series Green Neo E Sensor Series Neo BRIGHT Series Neo E Sensor Series Fine BRIGHT Series

Laser Range Finder

PSC
compatible product

Shaku
Measurement value changeable

Continuous distance measurement

Specified measurement recording

99
Recalls 99 readings

+

−

Addition/Subtraction

Timer mode

Equal interval notification mode

2-year
2-year warranty



78174

Shaku
Measurement value changeable

Continuous distance measurement

2-year
2-year warranty



78190

Class 2 laser product
Maximum Output 1 mW
Wavelength 620 - 690 nm
IEC60825-1: 2014
JIS C6802: 2014

Warning
● Do not stare into beam
● Do not point laser light at others
● Keep away from children

Accessories



- Soft case (78174)
- Strap (78174/78190)
- 2x AAA Alkaline batteries (78174/78190)

Class 2 laser product
Maximum Output 1 mW
Wavelength 620 - 690 nm
IEC60825-1: 2014
JIS C6802: 2014

Warning
● Do not stare into beam
● Do not point laser light at others
● Keep away from children


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	packaging
78174	L-Measure40 II Metric/Shaku	122×46×26	140	4 960910 781740	1	
78190	L-Measure30 Metric/Shaku	112×38×24	94	4 960910 781900	4	



The picture shown is a concept image. A laser dot is actually projected.

Features

- Convenient shaku display function for measuring in carpentry such as finding length of studs, length of braces, and length of baseboards and crown molding
- Can measure the area and volume of a room
- Can measure height from a distant location with Pythagoras measurement



- Packaged in a size that catches the eyes of a wide range of users when displayed on a tape measure display rack (78190)
- Automatically records measured values (78174)
- Can add or subtract measured values (78174)
- Comes with equal interval notification function that uses a sound to notify each preset distance (78174)
- Comes with timer mode to measure at a set time like a camera's self-timer. Handy when measuring lengths of desks, etc. by oneself. (78174)

Use

- For measuring distance on construction sites and renovation sites

Specifications


	78174	78190
Material	Body: ABS resin, elastomer resin	Body: ABS resin
Measuring Range	0.1 - 40 m	0.1 - 30 m
Accuracy	±2.0 mm*1	±3.0 mm*2
Output	Less than 1 mW (JIS class 2 C6802: 2014)	
Wavelength	620 - 690 nm	
Operating Temperature	0 - 40°C	
Storage Temperature	-20 - 70°C	-10 - 50°C
Dustproof, Waterproof	IP40*3	
Continuous Use Count	5,000 times or more when using new alkaline batteries*4	
Power Source	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)	
Auto Power Off	3 minutes*5	

- *1 0.1 - 10 m: ±2.0 mm
More than 10 m: ±2.0±0.05×(D-10) mm (D=measurement distance Unit: m)
Measurement conditions
① Illuminance of less than 3,000 Lux ② Reflectivity is 90% of white target
③ Measurement temperature 25°C
- *2 0.1 - 10 m: ±3.0 mm
More than 10 m: ±3.0±0.05×(D-10) mm (D=measurement distance Unit: m)
Measurement conditions
① Illuminance of less than 3,000 Lux ② Reflectivity is 90% of white target
③ Measurement temperature 25°C
- *3 Dustproof performance: particles larger than 1.0 mm will not penetrate the device
Waterproof performance: No special protection
When the backlight is off (78174)
- *4 The laser light being irradiated will turn off after a certain period of time passes without operation.
(78174: about 1 minute, 78190: about 30 seconds)
A beep will also sound when the device auto powers off.



Rotating Laser



(Accessory)



76496



- Equipped with wall mount system for remote control by hanging on a wall

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76497	HV-2 with Tripod	178x182x253	-	4 960910 764972	1	
76496	HV-2	178x182x253	2,260	4 960910 764965		

*Laser depicted is an illustration

Features

- Receiver unit: Dust/waterproof structure (IP66)
- Tilt mode that automatically stops when the unit is moved abruptly
- Manual mode allows incline of X-axis to Y-axis in the range of $\pm 5.7^\circ$
- Can be used as a line laser

Use

- For all types of referencing

Specifications

Unit	76497	76496
Measuring Range (diameter)	300 m (150 m radius) with Laser Receiver	
Horizontal Accuracy	± 10 mm/100 m	
Vertical Accuracy	± 10 mm/100 m	
Auto Leveling Range	$\pm 5.7^\circ$	
Alarm for Out of Auto Leveling Range	Rotating head stops, laser light blinks.	
Rotating Speed	600 rpm/450 rpm/300 rpm 150 rpm/90 rpm/0	
Scanning Range	2°-36°	
Light Source	Visible-light diode laser (Class2) Output: less than 1 mW Wavelength: 635 nm	
Power Source	2x D batteries or charging type battery, AC adapter	
Continuous Usable Hours	60 hrs (2x D batteries) 40 hrs (charging type battery)	
Battery Usage Alarm	ON/OFF LED blinks	
Tripod Screw	5/8 inch	
Dustproof/Waterproof	IP64*	
Operating Temperature	-20 ~ 80°C	

*6 Dustproof: Protected from total dust ingress

6 Waterproof: Protected from water spray from any direction

Laser Receiver

Receiving Distance	150 m
Volume Control	Switching in 3 stages, Silent, Low, High
Display	LCD (front and back)
Power Source	1x 9V Alkaline battery
Continuous Usable Hour	50 hours
Dust/Waterproof	IP66
Size	80(H) x 150(W) x 35(L) mm
Weight	260 g (including battery)

*6 Dustproof: Protected from total dust ingress

6 Waterproof: Protected from high pressure water jets from any direction

Accessories



Auto Level



Magnification 32x
Waterproof IPX4

77055

Magnification 28x
Waterproof IPX4

76901

Magnification 24x
Waterproof IPX4

76653



(77055)

(76901-76653)

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77055	SA-32A with Tripod	209x130x142	1,308	4 960910 770553	1	
76901	SA-28A with Tripod	208x130x135	1,247	4 960910 769014		
76653	SA-24A with Tripod	208x130x135	1,241	4 960910 766532		

Features

- Waterproof structure (IPX4)
- Comes with a domed-head tripod

Use

- For leveling in construction work

Specifications

	77055	76901	76653
Standard Deviation (km)	±1.0 mm	±1.5 mm	±2.0 mm
Telescope	Correct image		
Magnification	32X	28X	24X
Effective Diameter	40 mm	30 mm	
Field Angle	1°30'	1°20'	
Shortest Focus Distance	0.5 m	0.6 m	
Stadia Multiplier	100		
Stadia Addend	0		
Sensitivity of Vial	8/2 mm		
Minimum Horizontal Measurement	1°		
Auto Leveling System	Magnet damper		
Auto Leveling Range	±15°		
Repeat Precision	0.3"	0.5"	
Tripod Screw	5/8 inch		
Bottom Plate Type	Plane/ spherical		
Waterproof	IPX4*		

*IPX4 Waterproof: Protected from water spray from any direction

Accessories

- Plumb bob, Allen key wrench, Correction needle
- Domed-head tripod
- Special carrying case



Tripod



76629



76827



76866



76676



76952



77304



76690



76654

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76629	A with Handle	655×117×112	1,348	4 960910 766297	1	
76827	B with Handle	210×75×75	270	4 960910 768277	1	
76866	C with Handle	585×115×115	1,550	4 960910 768666	1	
76676	1.5 m with Handle	931×185×185	5,100	4 960910 766761	1	
76952	3 m with Handle	1,280×180×180	6,670	4 960910 769526	1	
77304	Short Model	560×180×180	4,580	4 960910 773042	1	
76690	Flat Head	1,025×180×180	3,695	4 960910 766907	1	
76654	Spherical Head	1,040×180×180	3,815	4 960910 766549	1	

Features

■76629

- Lightweight, with handle making it convenient for portability
- Comes with special case



■76827

- Can irradiate the ground marking point of a laser line generator
- Enables low-level marking
- With vial
- With storage case



■76866

- Features a strong design with nearly 1 mm-thick aluminum part, and a handle made of alloy, so it is resistant to breaking from impacts due to drops or falls



1 mm



Made of alloy

*Cannot irradiate the ground marking point

- With hard tip that can be extended by turning the rubber cover
- With vial
- With storage case



■76952

- 2 level elevating model for a height of up to 3 m



2nd level

1st level

■77304

- Easy fine-adjustment with 77304 Short Model Adjust up to 30 mm diameter

- Ground marking point can be exposed



Use

- Find the level in a variety of work sites

Specifications

	76629	76827	76866	76676
Material	Body: Aluminum, ABS resin			Body: Aluminum, iron
Elevator Ascent and Descent Width	300 mm	60 mm	320 mm	350 mm
Range of Use in Height	630 - 1,710 mm	180 - 400 mm	530 - 1,600 mm	710 - 1,500 mm
Ground Marking Point Exposure	×	○	×	×
Installation Screw	5/8 inch			

	76952	77304	76690	76654
Material	Body: Aluminum, iron			
Elevator Ascent and Descent Width	1,160 mm	285 mm	—	
Range of Use in Height	1,060 - 3,000 mm	535 - 920 mm	930 - 1,560 mm	
Ground Marking Point Exposure	×	○	×	×
Installation Screw	5/8 inch			

*Laser depicted is an illustration.

12. Inklines/ Chalklines/ Plumbholders



Carpenter's Squares	Stainless Steel Rules/ Machine Scale	Aluminum Rules	Resin Folding Rules/ Bamboo Rules	Squares/ Protractors	Vernier Calipers/ Micrometers	Tape Measures	Surveying Products	Scales	Levels	Lasers/ Optical Equipment	Inklines/ Chalklines/ Plumbholders	Circular Saw Guides	Construction Tools	Industrial Tools	Thermometers/ Hygrometers/ Suction Measuring Instruments	Outdoor Products	Magnifying Glasses	Drawing Tools	Magnets
---------------------	--------------------------------------	----------------	-----------------------------------	----------------------	-------------------------------	---------------	--------------------	--------	--------	---------------------------	------------------------------------	---------------------	--------------------	------------------	--	------------------	--------------------	---------------	---------

Handy Ink Line Marker Pro/Jr. Plus Tough Line

 AUTO
rewind
10 m
Tough Line
Thin Thread 15 m


73287

 AUTO
rewind
8 m
Tough Line
Thin Thread 10 m


73289


 Uses tough
reinforced fiber

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73287	Pro Plus Auto-rewind Tough Line Metal Red	200×81×40	194	4 960910 732872	6	(SP)
73289	Jr. Plus Auto-rewind Tough Line Metal Red	175×70×38	156	4 960910 732896	6 (36)	(SP)

Features

- Tough thread used in fishing net that is resistant to chafing and hard to break
- Thread's water retention ability is high (1.2 times conventional thread), enabling continuous marking of lines without having to re-ink



- New lock function enables smooth opening of tank lid, and without replacement of thread
- One-touch line guide helps to easily mark up to a corner
- Angled mouth helps to fix thread easily as it reduces strain on the hand when pressing down on it
- "Marking button" that creates a thick, bold line
- Sealed ink tank with rubber gasket prevents leaking
- Compact size, can be carried in a nail pouch
- Can be stowed in special holder sold separately

Use

- For all types of marking

Specifications

	73287	73289
Material	Body: ABS resin, polyacetal resin, silicon rubber, rubber, stainless steel Anchor Pin: ABS resin, rubber Pin: Spring steel Line: Nylon Sponge: Cellulose	
Thread	φ0.7 mm × 15 m	φ0.7 mm × 10 m
Ink Capacity	Approx. 15 ml	Approx. 10 ml

Handy Ink Line Marker Pro/Jr. Plus Sharp Line

NEW

 AUTO
rewind
10 m
Sharp Line
Ultra-fine
thread 20 m


73297

 AUTO
rewind
8 m
Sharp Line
Ultra-fine
thread 15 m


73298

 AUTO
rewind
8 m
Sharp Line
Ultra-fine
thread 30 m


73299

Sharp Line φ 0.4 mm

Conventional thin thread φ 0.6 mm

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73297	Pro Plus Auto-rewind Sharp Line Metal Blue	200×81×40	192	4 960910 732971	6	(SP)
73298	Jr. Plus Auto-rewind Sharp Line Metal Blue	175×70×38	154	4 960910 732988	6 (36)	(SP)
73299	Jr. Plus Hand-rewind Sharp Line Metal Blue	162×70×39	107	4 960910 732995	6	(SP)

Features

- Enables marking of thin lines thanks to φ 0.4 mm ultra-fine thread
- Thread has sufficient durability for marking despite thin size



- New lock function enables smooth opening of tank lid, and without replacement of thread
- One-touch line guide helps to easily mark up to a corner
- Angled mouth helps to fix thread easily as it reduces strain on the hand when pressing down on it
- "Marking button" that creates a thick, bold line
- Sealed ink tank with rubber gasket prevents leaking
- Compact size, can be carried in a nail pouch
- Folding handle that does not get in the way (73299)
- Can be stowed in special holder sold separately

Use

- For all types of marking

Specifications

	73297	73298	73299
Material	Body: ABS resin, polyacetal resin, silicon rubber, rubber, stainless steel Anchor Pin: ABS resin, rubber Pin: Spring steel Line: Nylon Sponge: Cellulose		
Thread	φ0.4 mm × 20 m	φ0.4 mm × 15 m	φ0.4 mm × 30 m
Ink Capacity	Approx. 15 ml	Approx. 10 ml	

Handy Ink Line Marker Pro Plus

AUTO
rewind
10 m
Thin Thread
20 m



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73280	Auto-rewind Black	200×81×40	190	4 960910 732803	6	
73281	Auto-rewind Royal Blue	200×81×40	190	4 960910 732810	(36)	
73290	Auto-rewind Black with Holder	—	—	4 960910 732902	4	
73291	Auto-rewind Royal Blue with Holder	—	—	4 960910 732919	(24)	

Features

- New lock function enables smooth opening of tank lid and easy replacement of thread
- One-touch line guide helps to mark to a corner easily



- Angled mouth helps to fix thread easily
- Bold line at the push of a button even when ink level is low
- Sealed ink tank with rubber gasket prevents leaking
- Can be stowed in Holder (73286) sold separately



Use

- For all types of marking

Specifications

Material	Body: ABS resin, polyacetal resin, silicon rubber, rubber, stainless steel Anchor Pin: ABS resin, rubber Pin: Spring steel Line: Nylon Sponge: Cellulose Holder: ABS resin
Thread	φ0.6 mm × 20 m
Ink Capacity	Approx. 15 ml

Handy Ink Line Marker Jr. Plus

AUTO
rewind
8 m
Thin Thread
15 m



HAND
rewind
Thin Thread
30 m



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73282	Auto-rewind Black	175×70×38	155	4 960910 732827	6	
73283	Auto-rewind Coral Red	175×70×38	155	4 960910 732834	(36)	
73292	Auto-rewind Black with Holder	—	—	4 960910 732926	4	
73293	Auto-rewind Coral Red with Holder	—	—	4 960910 732933	(24)	
73284	Hand-rewind Black	160×70×38	110	4 960910 732841	6	
73285	Hand-rewind Turquoise Blue	160×70×38	110	4 960910 732858	(36)	

Features

- New lock function enables smooth opening of tank lid and easy replacement of thread
- One-touch line guide helps to mark to a corner easily



- Angled mouth helps to fix thread easily
- Bold line at the push of a button even when ink level is low
- Compact size, can be carried in a nail pouch
- Sealed ink tank with rubber gasket prevents leaking
- Folding handle (73284/73285)



- Can be stowed in Holder (73286) sold separately

Use

- For all types of marking

Specifications

	73282	73283	73292	73293
Material	Body: ABS resin, polyacetal resin, silicon rubber, rubber, stainless steel Anchor Pin: ABS resin, rubber Pin: Spring steel Line: Nylon Sponge: Cellulose Holder: ABS resin			
Thread	ø0.6 mm × 15 m			
Ink Capacity	Approx. 10 ml			

	73284	73285
Material	Body: ABS resin, polyacetal resin, silicon rubber, rubber, stainless steel Anchor Pin: ABS resin, rubber Pin: Spring steel Line: Nylon Sponge: Cellulose	
Thread	ø0.6 mm × 30 m	
Ink Capacity	Approx. 10 ml	

Holder

 Pro Plus
Jr. Plus
Compatible


73286

 Handy Ink Line Marker
Pro Plus shown here

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
73286	Holder for Handy Ink Line Marker Pro/Jr. Plus	222×66×63	65	4 960910 732865	6	

Features

- Prevents dropping and misplacement; convenient for carrying at work site
- Able to store Pro Plus or Jr. Plus (including Tough Line/Sharp Line) without any spacers by just sliding
- No need to take off belt to attach the holder
- Ink pan prevents contamination of your clothing from leaked ink



Specifications

- For carrying Ink Line Marker

Specifications

Material	Body: ABS resin
Compatible models	Handy Ink Line Marker Pro-Jr. Plus, Tough Line Handy Ink Line Marker Pro-Jr. Plus Sharp Line Handy Ink Line Marker Pro-Jr. Plus
Attachable Belt Size	Width within 50 mm, thickness between 2.5 - 5 mm

Handy Ink Line Marker Pro/Jr. LITE

 AUTO
rewind
10 m
Thin Thread
20 m


73300



73301

 AUTO
rewind
7.5 m
Thin Thread
15 m


73302



73303


 HAND
rewind
30 m
Thin Thread


73307

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
73300	Pro LITE Auto-rewind Blue	180×82×40	197	4 960910 733008	6 (36)	
73301	Pro LITE Auto-rewind Red	180×82×40	197	4 960910 733015		
73302	Jr. LITE Auto-rewind Green	153×71×38	155	4 960910 733022		
73303	Jr. LITE Auto-rewind Orange	153×71×38	155	4 960910 733039		
73307	Jr. LITE Hand-rewind Mint Green	153×71×39.5	110	4 960910 733077		

Features

- Easy-to-use simple design
- Wide opening for easy thread replacement
- Sealed ink tank with rubber gasket prevents leaking



- Each series has been developed with pop colors
- Anchor Pin with rubber gasket prevents ink leaking
- Easy-to-ink thread



- Folding handle (73307)



Use

- For all types of marking

Specifications

	73300	73301	73302	73303	73307
Material	Body: ABS resin, polyacetal resin, silicon rubber, rubber, stainless steel Anchor Pin: ABS resin, rubber Pin: Spring steel Line: Nylon Sponge: Cellulose				
Thread	φ0.6 mm × 20 m	φ0.6 mm × 15 m	φ0.6 mm × 30 m		
Ink Capacity	Approx. 15 ml	Approx. 10 ml			

Motorized Handy Ink Line Marker

 ELECTRIC
rewind
Thin Thread
15 m


77480

Internal Structure



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
77480	Motorized Black	150×70×40	190 (batteries included)	4 960910 774803	6 (36)	

Features

- Motor turns drum to rewind thread

Use

- For all types of marking

Specifications

Material	Body: ABS resin, polyacetal resin, silicon rubber, rubber, stainless steel Anchor Pin: ABS resin Pin: Spring steel Line: Nylon Sponge: Cellulose
Thread	φ0.6 mm × 15 m
Power Source	2x AAA Alkaline batteries

Handy Ink Line Marker Self-stop

AUTO
rewind
5 m
Thin Thread
10 m



77450

● Compact size



Features

- Trigger starts retraction of thread. Will not retract unless the trigger is pulled. Even if anchor line comes off accidentally, it is safe and will not fly back.

Use

- For all types of marking

Specifications

Material	Body: ABS resin, polyacetal resin, elastomer resin, rubber, silicon rubber Spring: Stainless steel Anchor Pin: ABS resin Pin: Spring steel Line: Nylon Sponge: Cellulose
Thread	φ0.6 mm × 10 m

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77450	Auto-rewind Black	130×60×33.5	120	4 960910 774506	6	

Handy Ink Line Marker SUMIWAZA

AUTO
rewind
10 m
Thin Thread
18 m



77845

● With large sealed ink tank that is easy to fill



Features

- "Marking button" that releases more ink
- Thread hold guide clicks in every 90°
- 80 ml capacity ink tank
- Threader is set on the back



Use

- For all types of marking

Specifications

Material	Body: ABS resin, polyacetal resin Spring: Stainless steel Anchor Pin: ABS resin Pin: Spring steel Line: Nylon Cotton: Chemical fiber Threader: Polyacetal resin
Thread	φ0.6 mm × 18 m

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77845	Auto-rewind Brown	226×85×86	280	4 960910 778450	4	

Ink/Disappearing Ink



77475

77476

77477

77478

77587

77588

77589

77837

77838

77839


77649

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77475	Black 200 ml	150×70×35	265	4 960910 774759	6 (36)	
77476	Red 200 ml	150×70×35	255	4 960910 774766		
77477	White 200 ml	150×70×35	320	4 960910 774773		
77478	Blue 200 ml	150×70×35	260	4 960910 774780		
77587	Black 200 ml for Wet Condition	150×70×35	285	4 960910 775879		
77588	Red 200 ml for Wet Condition	150×70×35	270	4 960910 775886	6 (12)	
77589	Black 500 ml	200×80×50	610	4 960910 775893		
77837	Black 15 ml 2 pc-pack	56.5×27×18.5	19×2	4 960910 778375		20
77838	Red 15 ml 2 pc-pack	56.5×27×18.5	19×2	4 960910 778382		
77839	White 15 ml 2 pc-pack	56.5×27×18.5	19×2	4 960910 778399		
77649	Disappearing Ink 50 ml	97×35×35	70	4 960910 776494	12	

Features

- Ideal for building and construction work
- Wet Condition Black and Red Ink
- Will not run on wet conditions

Black Ink



Black Ink for Wet Condition



- 15 ml bottle
- Fully usable size

Disappearing Ink

- Ink disappears immediately after surface is wiped with a wet cloth and dries
- Ink lines disappear naturally in about 2 weeks



*Do not use when the ink must completely disappear

Use

- For marking lines on plaster board, wooden material, concrete, etc.

Specifications

Material	77649 Water, glycerin, phenolphthalein, etc.
----------	---

Handy Chalk Line Neo



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77493	Auto-rewind Thick Thread Yellow	180×76×45.5	185	4 960910 774933	6 (36)	
77494	Hand-rewind Thick Thread Blue	160×76×45.5	120	4 960910 774940		
77963	Auto-rewind Thin Thread Orange	180×76×45.5	185	4 960910 779631		
77964	Hand-rewind Thin Thread Purple	160×76×45.5	120	4 960910 779648		

Features

- Clear body allows you to check for remaining powder and lumps
- Sealed tank prevents powder leaking and humidity entering
- Special yarn holds more chalk powder
- Safety Anchor Pin II for both thick and thin lines (77493/77963)
- Wide opening for easier thread replacement



Thick Thread: Thread diameter 1 mm for steel frame, construction, sheet metal work
 Thin Thread: Thread diameter 0.5 mm for building and interior work

Use

- For marking lines with chalk

Specifications

	77493	77494	77963	77964
Material	Body: ABS resin, polyacetal resin, silicon rubber Anchor Pin: ABS resin Pin: Spring steel Thread: Nylon Spring (Auto-rewind): Stainless steel Metal Hook, Thread Mouth Ring: Stainless steel Felt: Chemical fiber			
Thread	φ1.0 mm × 10 m		φ0.5 mm × 15 m	

Handy Chalk Line



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77560	5x Speed Hand-rewind	165×88×58	162	4 960910 775602	6	
77927	Hand-rewind Red	185×90×40	138	4 960910 779273		

Features

- 5x Speed Hand-rewind
- 5 times faster rewinding with geared reel
- Clear body allows you to check for remaining powder and lumps
- Wide opening tank mouth enables to pour chalk powder directly from bottle
- The handle lock allows better handling and thread is retracted just by pushing back the handle
- Special yarn holds 3 times more chalk powder
- Hand-rewind Red
- Clear body allows you to check for remaining powder and lumps
- Sealed tank prevents powder leaking and humidity entering



Use

- For marking lines with chalk

Specifications

	77560	77927
Material	Body: ABS resin, polycarbonate resin Anchor: ABS resin Anchor Needle: Spring steel Thread: Polyester Thread Mouth: Stainless steel Threader: Brass, iron Metal Hook: Stainless steel Felt: Chemical fiber	Body: ABS resin, polyacetal resin Thread Mouth Ring: Stainless steel Anchor: ABS resin Anchor Needle: Spring steel Thread: Nylon Threader: Polyacetal resin
Thread	φ1.0 mm × 20 m	φ0.5 mm × 20 m

Chalk Line BIG



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77580	Hand-rewind Blue	440×140×95	830	4 960910 775800	3	

Features

- Improved work efficiency when marking lines, since the tank can slide along the thread and apply powder without requiring the thread to be wound up
- Soft tank can be kneaded to break up powder blocks inside and make continuous application of powder to the line possible
- Attached line guide allows thread to pass through even if powder is in the tank. Thread replacement is simple since the drum can be separated from the device without using a tool
- Wear-resistant and hard-to-cut coarse thread



Use

- Suitable in line drawing for roads, parking lots, etc.

Specifications

Material	Body: Polycarbonate resin, ABS resin, brass, stainless steel Tank: Elastomer resin, polypropylene resin, ABS resin, brass Thread: Polyester Threader: Stainless steel, brass, steel Felt: Wool (natural fiber)
Thread	φ3 mm × 50 m

Chalk Powder



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77938	300 g White	φ66×178	355	4 960910 779389	6 (36)	
77935	300 g Yellow	φ66×178	355	4 960910 779358		
77936	300 g Red	φ66×178	355	4 960910 779365		
77937	300 g Blue	φ66×178	355	4 960910 779372		
78029	300 g Pink	φ66×178	355	4 960910 780293		
78030	300 g Green	φ66×178	355	4 960910 780309		
77954	200 g White for Outdoor	φ66×178	255	4 960910 779549	6	
77968	500 g White for Outdoor	φ90×223	565	4 960910 779686		
77976	1 kg White for Outdoor	254×124×95	1,100	4 960910 779761	1	
78096	150 g Blue for Outdoor	φ66×178	205	4 960910 780965	6 (36)	
77962	375 g Blue for Outdoor	φ90×223	440	4 960910 779624	6	
77965	750 g Blue for Outdoor	254×124×95	850	4 960910 779655	1	

Features

- Ultra fine powder helps to draw vivid lines
- Angled inlet makes it easy to pour
- Outdoor models are suitable on wet surface



Use

- For marking lines with chalk
- *Do not use if the line needs to be erased completely

Specifications

	77938			
Material	Calcium carbonate			
	77935	77937	78029	78030
Material	Calcium carbonate, pigment			
	77936			
Material	Calcium carbonate, dye			
	77954	77968	77976	
Material	Calcium carbonate, titanium oxide			
	78096	77962	77965	
Material	Calcium carbonate, titanium oxide, pigment			

Thread Reel



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77446	II Auto-rewind Red	110×69×31	90	4 960910 774469	6	
77456	II Hand-rewind Green	110×69×31	65	4 960910 774568		

Features

- Thin, lightweight size that fits in the palm of the hand
- Needle and thread replacements are simple since no tools are needed to take apart
- Main body's fixed needles can be stored safely with the needle cover
- Needle cover can be smoothly pushed down with one hand during use
- Since the needle interval is wide, the device is stable when needles are pinned



Use

- For leveling of lintel, finding length of rafter edge, and adjusting height of joist

Specifications

	77446	77456
Material	Body: ABS resin, polyacetal resin, stainless steel Spring: Stainless steel (Auto-rewind) Anchor: ABS resin, spring steel, rubber Needle: ABS resin, spring steel Thread: Nylon	
Thread	φ0.6 mm × 15 m (Auto-rewind 8 m)	φ0.6 mm × 30 m

Replacement Anchor Pin

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77453	Anchor Pin 2 pc-pack for Thread Reel II	37×5×9	1	4 960910 774537	15	

Replacement Anchor Pin/Hook



Can be hung by driving in a concrete nail

77843

- Needle can retract even if anchor pin unexpectedly detaches
- Can use both thick and thin thread
- Easy-to-hold and easily removable shape

77433

- Elastomer resin absorbs shock to the hand
- Can use commercially available concrete nails (concrete nail #12 × 50 mm)
- Includes 2 replacement nails

77849

77486

77862

77880

77452

77932

◎: Standard equipment ○: Compatible △: Compatible (Incompatible with holder use) —: Incompatible

Item Code	C.D.	Description	Pro Plus Tough Line	Jr. Plus Tough Line	Pro Plus Auto-rewind	Jr. Plus Auto-rewind	Pro Plus Hand-rewind	Pro LITE Auto-rewind	Jr. LITE Auto-rewind	Jr. LITE Hand-rewind	Mini α Auto-rewind	Motorized	Self Stop Auto-rewind	SUMIWAZA Auto-rewind	Chalk 5x Speed	Neo Auto Orange	Neo Hand Purple	Neo Auto Yellow	Neo Hand Blue	Chalk Hand-rewind	Thread Reel	Thread Reel II	Chalk BIG	Packing Unit
77843	6	Safety Anchor Pin with Magnet	△	△	△	△	△	△	△	△	○	○	○	○	○	○	○	○	○	○	○	—	—	
77433	9	Anchor Pin for Concrete	△	△	△	△	△	△	△	△	○	○	○	○	○	○	○	○	○	○	○	—	—	
77849	8	Safety Anchor Pin	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	—	—	
77486	5	Safety Anchor Pin II	◎	◎	◎	◎	○	◎	◎	○	○	○	○	◎	◎	○	◎	○	◎	○	○	—	—	10
77862	7	Anchor Pin Red 3 pc-pack	△	△	△	△	△	△	△	△	○	○	○	○	○	○	○	○	○	○	○	—	—	
77880	1	Anchor Pin Mini Red 3 pc-pack	○	○	○	○	○	○	○	○	○	○	○	○	○	○	◎	○	◎	◎	○	—	—	
77452	0	Anchor Pin Mini Black 3 pc-pack	○	○	○	○	◎	○	◎	◎	◎	◎	◎	○	○	◎	○	○	○	○	◎	—	—	
77932	7	Hook 3 pc-pack for Chalk Line	—	—	—	—	—	—	—	—	—	—	—	—	—	◎	◎	◎	◎	◎	◎	—	—	1

Replacement Cotton/Sponge/Felt

◎: Standard equipment ○: Compatible △: Compatible (Incompatible with holder use) —: Incompatible

Item Code	C.D.	Description	Pro Plus Tough Line	Jr. Plus Tough Line	Pro Plus Auto-rewind	Jr. Plus Auto-rewind	Pro Plus Hand-rewind	Pro LITE Auto-rewind	Jr. LITE Auto-rewind	Jr. LITE Hand-rewind	Mini α Auto-rewind	Motorized	Self Stop Auto-rewind	SUMIWAZA Auto-rewind	Chalk 5x Speed	Neo Auto Orange	Neo Hand Purple	Neo Auto Yellow	Neo Hand Blue	Chalk Hand-rewind	Thread Reel	Thread Reel II	Chalk BIG	Packing Unit
77848	1	Cotton 3 pc-pack for Ink Line Marker	○	—	○	—	—	○	—	—	○	—	—	—	—	—	—	—	—	—	—	—	—	
77484	1	Sponge 3 pc-pack for Ink Line Marker Pro	○	—	○	—	—	◎	—	—	○	—	—	—	—	—	—	—	—	—	—	—	—	
77485	8	Sponge 3 pc-pack for Motorized Ink Line Marker and Jr.	—	○	—	○	○	—	◎	◎	—	○	◎	—	—	—	—	—	—	—	—	—	—	
77451	3	Sponge 2 pc-pack for Ink Line Marker Self-stop	—	—	—	—	—	—	—	—	—	—	—	◎	—	—	—	—	—	—	—	—	—	10
77381	3	Sponge 3 pc-pack for Ink Line Marker Jr.	—	○	—	○	○	—	○	○	—	○	—	—	—	—	—	—	—	—	—	—	—	
77846	7	Sponge 3 pc-pack for Ink Line Marker SUMIWAZA	—	—	—	—	—	—	—	—	—	—	—	—	◎	—	—	—	—	—	—	—	—	
77578	7	Felt 4 pc-pack for Chalk Line BIG	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	◎	

Replacement Thread

◎: Standard equipment ○: Compatible △: Compatible (Incompatible with holder use) —: Incompatible

Item Code	C.D.	Description	Thickness of Thread (mm)	Pro Plus Tough Line	Jr. Plus Tough Line	Pro Plus Auto-rewind	Jr. Plus Auto-rewind	Pro Plus Hand-rewind	Pro LITE Auto-rewind	Jr. LITE Auto-rewind	Jr. LITE Hand-rewind	Mini α Auto-rewind	Motorized	Self Stop Auto-rewind	SUMIWAZA Auto-rewind	Chalk 5x Speed	Neo Auto Orange	Neo Hand Purple	Neo Auto Yellow	Neo Hand Blue	Chalk Hand-rewind	Thread Reel	Thread Reel II	Chalk BIG	Packing Unit
77594	7	Thread φ0.8 mm × 15 m for Ink Line Marker	φ0.8	○	○	○	○	○	○	○	○	○	○	○	○	○	—	—	—	—	—	—	○	—	
77864	1	Thread φ0.6 mm × 20 m for Ink Line Marker	φ0.6	○	○	○	○	○	◎	◎	◎	◎	◎	◎	◎	◎	—	—	—	—	—	—	◎	—	
77879	5	Thread φ0.7 mm × 15 m for Ink Line Marker Tough Line	φ0.7	◎	◎	○	○	○	○	○	○	○	○	○	○	○	—	—	—	—	—	—	○	—	
77882	5	Thread φ0.4 mm × 20 m for Ink Line Marker Sharp Line	φ0.4	○	○	◎	◎	◎	○	○	○	○	○	○	○	○	—	—	—	—	—	—	○	—	10
77562	6	Thread 3x Chalk Retentive φ1.0 mm × 20 m for Chalk Line Marker	φ1.0	—	—	—	—	—	—	—	—	—	—	—	—	—	◎	○	○	○	○	○	—	—	
77495	7	Thread φ1.0 mm × 20 m for Chalk Line Marker	φ1.0	—	—	—	—	—	—	—	—	—	—	—	—	—	○	○	○	◎	◎	○	—	—	
77929	7	Thread φ0.5 mm × 20 m for Chalk Line Marker	φ0.5	—	—	—	—	—	—	—	—	—	—	—	—	—	○	◎	◎	○	○	◎	—	—	
77577	0	Thread Super Thick 50 m for Chalk Line BIG	φ3.0	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	◎	—	3

JAN Code No.= [4960910+Item Code+CD]

*Differs from standard equipment's thread length


JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Screw Pitch Marking Tool

■Screw Pitch Marking Tool Multi Available pitches


100 mm
150 mm
200 mm
250 mm
300 mm



Item Code	Description	JAN Code	Packing Unit	Packaging
77315	Multi 5-pitch Switch	4 960910 773158	4	
77320	Main Block for Screw Pitch Marking Tool Multi	4 960910 773202		
77390	Screw Pitch Marking Tool 100	4 960910 773905		
77391	Screw Pitch Marking Tool 150	4 960910 773912		
77392	Main Block 100 for Screw Pitch Marking Tool	4 960910 773929		
77393	Main Block 150 for Screw Pitch Marking Tool	4 960910 773936		

Refer to P. 2 about the shaku scale

Screw Pitch Marking Tool Accessory




Item Code	Description	JAN Code	Packing Unit	Packaging
77394	Guide Rule for Screw Pitch Marking Tool/Multi	4 960910 773943	6	
77395	Stopper for Guide Rule for Screw Pitch Marking Tool/Multi	4 960910 773950	10	
67618	Cartridge 100/150 for Screw Pitch Marking Tool Multi	4 960910 676183		
67619	Cartridge 200/250/300 for Screw Pitch Marking Tool Multi	4 960910 676190	1	
90943	Ink Tank for Screw Pitch Marking Tool Multi	4 960910 909434		
77323	Replacement Belt 100/150 for Screw Pitch Marking Tool Multi	4 960910 773233		
77324	Replacement Belt 200/250/300 for Screw Pitch Marking Tool Multi	4 960910 773240		
77326	Replacement Cotton 2 pc-pack for Screw Pitch Marking Tool Multi	4 960910 773264		
77396	Replacement Lead 10 pc-pack for Screw Pitch Marking Tool	4 960910 773967	10	
77397	Replacement Cotton 4 pc-pack for Screw Pitch Marking Tool	4 960910 773974		

Features

■Screw Pitch Marking Tool Multi

- One unit can mark five different pitches

*In recent years, pitches for screws have been strictly controlled in building for some house builders. The pitch can vary depending on building structure. This tool can cover most cases.



- Easy-to-replace cartridge



- Easy-to-refill ink tank



■Screw Pitch Marking Tool 100 & 150

- Makes mark at equal intervals by spinning




■Screw Pitch Marking Tool Multi 100/150

- Using this tool with Stopper (77395) and Guide Rule (77394), pitches can be marked on the center of board.



Fix the stopper in one of the holes depending on the width of board, then slide the main block to the stopper. The marking position is 455 or 500 mm, and can mark the center of a 3 shaku/1000 mm wide board.




Use

- For marking screw pitch on boards such as plywood, plaster board, etc.

Specifications

	77315	77390	77391
Material	ABS resin, polyacetal resin, elastomer resin, stainless steel, aluminum, silicone rubber (multi)		
Size	Main Block 159 x 79 x 80 mm	Main Block 100 x 80 x 43 mm	Main Block 100 x 80 x 56 mm
	Guide Rule: 200 x 663 x 15mm		
Weight	Main Block 300 g	Main Block 170 g	Main Block 190 g
	Guide Rule: 110 g		
Accuracy	77315	100 mm Pitch: 95 - 100 mm 150 mm Pitch: 145 - 150 mm 200 mm Pitch: 195 - 200 mm 250 mm Pitch: 245 - 250 mm 300 mm Pitch: 295 - 300 mm	
	77390	95 ± 5 mm	
	77391	145 ± 5 mm	

Wind-resistant Plumb/Holder/Dial Plumb



■Wind resistant Plumb

Features

- Spring-loaded reel completely reduces the load on special dual thread and makes it hard to break



- Use when temporary braces are on the supports is also possible since the ends are long (about 40 mm)



- Rubber strap to secure plumb to an object
- Includes a useful carry case

Use

- For verifying perpendicularity of pillars

Specifications

	77554	77524
Accuracy*	±1 mm	
Material	Rod: Aluminum Drum Cover: ABS resin Plumb: Brass, phosphor bronze, bronze (iron for 77554) End: Aluminum	

*Accuracy determines the difference between the distance from the upper part end portion to the line in the accuracy confirmation window's position and the distance from the lower part end portion to the center of the indicator plate.

■Holder

Features

- Fixing to the pillar is easy and hassle-free



- Attaching and detaching to wind-resistant plumb can be done without tools using the fixing screw

Use

- Fixing the wind-resistant plumb to a pillar

Specifications

Products	Wind-resistant Plumb Basic (77554) Wind-resistant Plumb II with Magnetic Damper (77524)
Compatible Pillar Size	3.5 - 5.5 sun
Material	Stainless steel, aluminum, vinyl chloride resin

■Dial Plumb

Features

- Dial model allows one to see fine graduations in slope. No influence of wind.



- Slide arm (end part) is attached, allowing use even when temporary braces, etc. are on the support
- 240 cm when using an extension (77575)
- Includes a useful carry case

Use

- For checking listing of formwork and sash frames
- For setting up of house framework and checking listing supports

Specifications

	77548	77549	77550	77575
Accuracy*	Less than 0.5 mm/1 m			
Lean Tolerance to the Front-back Direction*	±20 mm	±40 mm		
Material	Main Rod, Sliding Arm, Scale Plate, Indicator Fixing Lever: Aluminum Unit Cover: ABS resin Indicator: Steel			

*Lean tolerance to the front-back direction is the maximum lean in the front-back direction in regards to the entire length of the main scale that can guarantee the accuracy during measurement.

Wind-resistant Plumb

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77554	Basic	61×134× 1,515~3,333	3,060	4 960910 775541	1	
77524	II with Magnetic Damper	64×112× 1,515~3,333	3,120	4 960910 775244		

Holder

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77599	for Wind-resistant Plumb with Quick Arm	336×110×122	370	4 960910 775992	1	

*For Wind-resistant Plumb

Dial Plumb

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77548	110 cm	63×39×1,100	1,500	4 960910 775480	1	
77549	175 cm	63×39×1,750	2,050	4 960910 775497		
77550	200 cm	63×39×2,000	2,300	4 960910 775503		
77575	240 cm	63×39×2,400	3,150	4 960910 775756		

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Handy Plumb Holder



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77375	Pro Auto-rewind Red	125×100×35	225	4 960910 773752	5	
77376	Pro Auto-rewind Red with Plumb Bob 400 g	—	—	4 960910 773769		
77377	Pro Hand-rewind Blue	125×100×45	185	4 960910 773776		
77501	Jr. Auto-rewind Red	87×82×27	120	4 960910 775015		
77502	Jr. Auto-rewind Red with Plumb Bob 200 g	—	—	4 960910 775022		

Replacement Needle/Thread

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77378	Needle for Handy Plumb Holder Pro	120×47×20	20	4 960910 773783	1	
77504	Needle for Handy Plumb Holder Jr.	81×29×20	8	4 960910 775046		
77598	Thread 15 m for Handy Plumb Holder	φ1.0×15m	—	4 960910 775985	10	

Features

- Can be hit with a hammer



- Pin can be changed by hand
- Spring drum is made of rust-resistant stainless steel
- Neodymium magnet sticks strongly
- Unit is covered with elastomer resin for shock-resistance

- Pro Hand-rewind Blue
- Folding handle for Pro Hand-rewind Blue
- Jr. Auto-rewind Red
- Lightweight, compact and portable



About 40% Less
Compared to size of Pro model

Use

- For verifying perpendicularity of pillars, walls, and frames

Specifications

	77375	77376	77377	77501	77502
Material	Body: ABS resin, elastomer resin Spring: Stainless steel Pointer: Spring steel Thread: Nylon Magnet: Neodymium magnet				
Thread Length	5 m	10 m	3.5 m		
Usable Plumb	100 g - 850 g (1 kg with drum stopper)	100 g - 1 kg	100 g - 400 g		


Plumb Bob



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77974	100 g with Damper	φ32×96	100	4 960910 779747	5	
77981	150 g with Damper	φ32×108	150	4 960910 779815		
77982	200 g with Damper	φ32×121	200	4 960910 779822		
77983	300 g with Damper	φ33×148	300	4 960910 779839		
77979	400 g with Damper	φ36×156	400	4 960910 779792		
77975	600 g with Damper	φ42×167	600	4 960910 779754		
77951	800 g with Damper	φ42×196	800	4 960910 779518		
77991	1000 g	φ42×213	1,000	4 960910 779914		


Features

- Highly visible yellow colored tip
- Rubber cover to protect from scratching
- Rubber cap



Stops in 1/20 of the time of conventional products

- Full lineup offers a choice from lightweight and easy to carry, to heavy items that are not affected by wind
- Great stability against wind and durable integrated structure (77991)



Use

- For verifying perpendicularity of pillars, walls, and frames

Specifications

Material	Tip of Body: Iron Double Ring: Stainless steel Cover/Protective Cap: Rubber
----------	---

Polyester Leveling Line Reel



78483



78478



78482




78499

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78477	0.5 mm 500 m Yellow	φ79×48	120	4 960910 784772	10	
78479	0.5 mm 500 m Pink	φ79×48	120	4 960910 784796		
78481	0.5 mm 500 m Orange	φ79×48	120	4 960910 784819		
78483	0.5 mm 500 m Green	φ79×48	120	4 960910 784833		
78478	0.8 mm 270 m Yellow	φ79×48	126	4 960910 784789		
78480	0.8 mm 270 m Pink	φ79×48	126	4 960910 784802		
78482	0.8 mm 270 m Orange	φ79×48	126	4 960910 784826		
78485	0.8 mm 270 m Green	φ79×48	126	4 960910 784857		
78498	1.2 mm 120 m Yellow	φ79×48	127	4 960910 784987		
78499	1.2 mm 120 m Pink	φ79×48	127	4 960910 784994		

Features

- Vivid coloring
- Polyester does not absorb water nor stretch as much as nylon. It can be pulled tight with less stretch
- Runs freely when held at the center



- Reel comes with cutter blade



With cutter blade

Use

- For basement construction, surveying, craft, and gardening

Specifications

Material	Polyester
----------	-----------

Cotton Leveling Line



78491



78494



78495


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78488	No.3 0.7 mm 100 m	154×90	39	4 960910 784888	10	
78489	No.4 0.8 mm 100 m	154×90	48	4 960910 784895		
78490	No.5 0.9 mm 100 m	154×90	60	4 960910 784901		
78491	No.6 1.0 mm 100 m	154×90	65	4 960910 784918		
78493	No.7 1.1 mm 100 m	154×90	75	4 960910 784932		
78494	No.8 1.2 mm 100 m	154×90	88	4 960910 784949		
78495	No.10 1.4 mm 100 m	154×90	106	4 960910 784956		

Features

- Environmentally-friendly 100% cotton
- Easy-to-tie pure cotton yarn
- Can be used for many applications from general work to surveying
- Abundant variations in thickness

Use

- For measuring, gardening, and kite-flying



Specifications

Material	Cotton
----------	--------

Paint Marker Wide Bullet-tip



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78541	Black	150×25×25	65	4 960910 785410	10	
78542	Red	150×25×25	65	4 960910 785427		
78547	White	150×25×25	65	4 960910 785472		
78548	Pink	150×25×25	65	4 960910 785489		

Features

- Writes clearly on a variety of surfaces
- Pigment ink helps to write clearly even on dark-colored surfaces
- Four colors available
- Dries quickly
- 4 mm line width



Use

- For marking on steel material, alloy, glass, plastic, concrete, PVC pipe, etc.

Specifications

Material	Body: Aluminum Cap: Polypropylene resin Ink: Oil-based (pigment ink)
----------	--

Paint Marker Fine Bullet-tip



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78414	Black	144×15×15	22	4 960910 784147	10	
78415	Red	144×15×15	22	4 960910 784154		
78416	Yellow	144×15×15	22	4 960910 784161		
78418	White	144×15×15	22	4 960910 784185		
78419	Pink	144×15×15	22	4 960910 784192		
78420	Gold	144×15×15	22	4 960910 784208		
78515	Blue	144×15×15	22	4 960910 785151	6	
78516	Silver	144×15×15	22	4 960910 785168		
78510	Holder for Paint Marker Fine	90×28×46	21	4 960910 785106		

Paint Marker

Features

- Writes clearly on a variety of surfaces
- Pigment ink helps to write clearly even on dark-colored surfaces
- Eight colors available
- Dries quickly
- 2 mm line width



Use

- For marking on steel material, alloy, glass, plastic, concrete, PVC pipe, etc.

Specifications

Material	Body: Aluminum Cap: Polypropylene resin Ink: Oil-based (pigment ink)
----------	--

Holder for Paint Marker Fine

Features

- Hole for safety strap. This allows a safety cord or strap to be attached
- Clips easily onto a belt being worn. The hook on the clip prevents it from detaching.



Use

- For carrying paint marker



Specifications

Material	Body: Nylon resin
Attachable Belt	Less than 60 mm wide and less than 4 mm thick

*Specially made for Shinwa's fine point paint marker

Oil-based Marking Pen Fine



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78424	Bullet-tip Black	132×17×21	20	4 960910 784246	10	
78429	Bullet-tip Red	132×17×21	20	4 960910 784291		
78430	Chisel-tip Black	132×17×21	20	4 960910 784307		
78431	Chisel-tip Red	132×17×21	20	4 960910 784314		

Replacement Cartridge for Oil-based Marking Pen

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78432	Black 2 pc-pack	78×13×13	6	4 960910 784321	10	
78434	Red 2 pc-pack	78×13×13	6	4 960910 784345		

Features

- Available in bullet-tip and chisel-tip
- Reusable by changing cartridge after ink runs out
- Dries quickly



Use


- For marking on steel material, alloy, glass, plastic, concrete, PVC pipe, etc.



Specifications

Material	Body, Cap: Polypropylene resin Ink: Oil-based (dye ink)
----------	--

Marking Crayon Retractable 7.0 mm



● Protector case included

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78463	Black	145×14×17	17	4 960910 784635	10	
78464	Red	145×14×17	17	4 960910 784642		
78465	White	145×14×17	17	4 960910 784659		

Refill for Marking Crayon Retractable 7.0 mm

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78466	Black 2 pc-pack	142×17×17	16	4 960910 784666	10	
78467	Red 2 pc-pack	142×17×17	16	4 960910 784673		
78469	White 2 pc-pack	142×17×17	16	4 960910 784697		

Features

- Knock type keeps your hands clean



- Easy to write



Use

- For marking on steel material, alloy, glass, plastic, concrete, PVC pipe, etc.

Specifications

Material	Body / Case: Polypropylene resin, ABS resin Crayon: Oil-based (pigment ink)
----------	--

Marking Crayon Retractable 4.0 mm



●Protector case included

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78445	Black	135×12×15	11	4 960910 784451	10	
78446	Red	135×12×15	11	4 960910 784468		
78447	Yellow	135×12×15	11	4 960910 784475		
78448	White	135×12×15	11	4 960910 784482		
78449	Pink	135×12×15	11	4 960910 784499		

Features

- Retractable type keeps your hands clean



- Easy to write



Use

- For marking on steel material, alloy, glass, plastic, concrete, PVC pipe, etc.

Specifications

Material	Body / Case: Polypropylene resin, ABS resin Crayon: Oil-based (pigment ink)
----------	--

Refill for Marking Crayon Retractable 4.0 mm

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78458	Black 4 pc-pack	142×17×17	10	4 960910 784581	10	
78459	Red 4 pc-pack	142×17×17	10	4 960910 784598		
78460	Yellow 4 pc-pack	142×17×17	10	4 960910 784604		
78461	White 4 pc-pack	142×17×17	10	4 960910 784611		
78462	Pink 4 pc-pack	142×17×17	10	4 960910 784628		

Marking Mechanical Pencil 2.0 mm



●Protector case included

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78470	Black	142×9×12	13	4 960910 784703	10	
78471	Red	142×9×12	13	4 960910 784710		
78472	White	142×9×12	13	4 960910 784727		

Features

- Writes smoothly, hard to break



Use

- For marking on steel material, alloy, concrete, etc.

Specifications

	78470	78471	78472
Material	Body: ABS resin, steel Crayon: Oil-based (pigment ink)		
	78473	78474	78475
Material	Case: Polypropylene resin, ABS resin Crayon: Oil-based (pigment ink)		

Replacement Lead for Marking Mechanical Pencil 2.0 mm

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78473	Black 6 pc-pack	150×9×9	6	4 960910 784734	10	
78474	Red 6 pc-pack	150×9×9	6	4 960910 784741		
78475	White 6 pc-pack	150×9×9	6	4 960910 784758		

Marking Mechanical Pencil Type 2.0 mm



78511



78508

●Protector case included



78507



78509

●Protector case included

Features

- Easy-to-write mechanical pencil with lead
- Comes with 1x lead

Use

- For marking lumber and plasterboard

Specifications

	78511	78507
Material	Body: ABS resin, steel Center: Graphite	
	78508	78509
Material	Case: Polypropylene resin, ABS resin Center: Graphite	

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78511	2H	143×9×12	12	4 960910 785113	10	
78507	HB	143×9×12	12	4 960910 785076		

Replacement Lead for Marking Mechanical Pencil Type 2.0 mm

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78508	2H 6 pc-pack	150×9×9	7	4 960910 785083	10	
78509	HB 6 pc-pack	150×9×9	7	4 960910 785090		

Marking Pencil PRO



78524



78517



78518



78519



78520



78521



78523

●Actual products are not sharpened.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78524	4H 3 pc-pack	177×7.5×7.5	4	4 960910 785243	10	
78517	2H 3 pc-pack	177×7.5×7.5	4	4 960910 785175		
78518	H 3 pc-pack	177×7.5×7.5	4	4 960910 785182		
78519	HB 3 pc-pack	177×7.5×7.5	4	4 960910 785199		
78520	2B 3 pc-pack	177×7.5×7.5	4	4 960910 785205		
78521	Red Hard 3 pc-pack	177×7.5×7.5	4	4 960910 785212		
78523	Red Soft 3 pc-pack	177×7.5×7.5	4	4 960910 785236		

Features

- Five different regular pencils available - 4H, 2H, H, HB, 2B
- Two different red pencils available - hard and soft
- Writes smoothly for professional use

Use

- For marking lumber and plasterboard



Specifications

	78524	78517	78518	78519	78520
Material	Body: Wood		Center: Graphite		
Shaft Type	Hexagonal shaft				
	78521		78523		
Material	Body: Wood		Center: Pigment, wax		
Shaft Type	Hexagonal shaft				

Marking Crayon Pencil Type



● Actual products are not sharpened.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78435	Black 3 pc-pack	φ8×175	6		10	
78440	Red 3 pc-pack	φ8×175	6			
78442	Yellow 3 pc-pack	φ8×175	6			
78443	White 3 pc-pack	φ8×175	6			

Features

- Usable on a variety of surfaces

Use

- For marking on steel material, alloy, glass, plastic, concrete, PVC pipe, etc.

Specifications

Material	Body: Wood Crayon: Oil-based (pigment ink)
Shaft Type	Cylindrical shaft

Chalk Holder



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78501	White	131×25×21	24		10	
78527	Red	131×25×21	24			
78528	Yellow	131×25×21	24			
78597	Blue	131×25×21	24			

Features

- Protects chalk from breaking or getting wet
- The magnetic cap will stick on steel chalkboard



- Clear cap shows color of chalk
- Keeps your hands clean



- Retractable type makes insertion and removal of chalk easy

Use

- As protector case for chalk

Specifications

Material	Body: Polypropylene resin Cap: Acrylic resin
Usable Chalk	φ11 - 12 mm

*Hold chalk as you move it in and out. Otherwise the chalk may fall or break.

Chalk



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74141	White 10 pc-pack with Plastic Case	φ12×82	5.5		10	
74142	Red 10 pc-pack with Plastic Case	φ12×82	5.5			
74143	Yellow 10 pc-pack with Plastic Case	φ12×82	5.5			

Features

- Plastic case protects chalks from breaking or getting wet
- Compact size convenient for carrying
- Clear case shows color of chalk



- Writes smoothly and erases easily
- Not only for blackboard, also for various materials such as wood, stone, metal, or concrete
- Highly visible vivid color makes work easier

Use

- For writing on chalkboards, wood, stone, iron and concrete

Specifications

Material	Calcium carbonate
----------	-------------------

Carpenter's Squares
Stainless Steel Rules/ Machine Scale
Aluminum Rules
Resin Folding Rules/ Bamboo Rules
Squares/ Protractors
Vernier Calipers/ Micrometers
Tape Measures
Surveying Products
Scales
Levels
Lasers/ Optical Equipment
Inclines/ Chalklines/ Plumbholders
Circular Saw Guides
Construction Tools
Industrial Tools
Thermometers/ Hygrometers/ Environment Measuring Instruments
Outdoor Products
Magnifying Glasses
Drawing Tools
Magnets

13. Circular Saw Guides



Circular Saw Guide L-Angle EX



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78054	45 cm/shaku	620×330×77	1,150		2	
78055	60 cm/shaku	750×330×77	1,250		2	
78032	1 m/shaku	1,150×400×77	2,000		1	

Refer to P. 2 about the shaku scale

Features

- 130 mm wide guide prevents accidental swinging
- Strong cross-sectional shape
- Light weight
- Easy-to-read vertical graduation (with red numbers)
- Slide block that prevents an electric circular saw from coming off included
- Attach the slider guide to the base of the electric circular saw. By sliding the saw on the guide's groove, it will cut without slipping
- Large and easy-to-hold handle made of non-slip elastomer resin. 1 m model comes with an extra handle at the center point of the guide.
- Guide edge has a stainless steel plate

Use

- As a guide rule when making square cuts on boards with an electric circular saw
- For dimension measurements

Specifications

	78054	78055	78032
Perpendicularity	Less than 0.1 mm per 100 mm		
Graduation	Shaku 1 shaku 6 sun 5 bu	2 shaku	3 shaku 3 sun
	Metric 50 cm	60 cm	1 m
Edge Height	15 mm		
Material	Body: Aluminum Handle: ABS resin, elastomer resin Guide Edge: Stainless steel		
Accessories	Slider, Cutout positioning stick		

Slider




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78236	for Circular Saw Guide with Groove	230×167×6	130		5	

Features

- Enables straight cuts without deviation after attaching to the electric circular saw and sliding it according to the groove of the corresponding circular saw guide

Use by inserting into the base of the electric circular saw




Use

- As a guide when using an electric circular saw with a circular saw guide

Specifications

Material	Stainless steel
----------	-----------------

Circular Saw Guide L-Angle Plus Shift **NEW**

79054



79052



79053



79055


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
79052	45 cm/shaku with Gradient Scale Cutting Function	687×390×85	1,300	4 960910 790520	2	
79053	60 cm/shaku with Gradient Scale Cutting Function	817×390×85	1,400	4 960910 790537		
79054	1 m/shaku with Gradient Scale Cutting Function	1,217×390×85	1,600	4 960910 790544	1	
79055	1.2 m/shaku with Gradient Scale Cutting Function	1,417×390×85	1,700	4 960910 790551		

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features


- Square cuts and angular cuts can be shifted by moving the movable edge pin and changing the edge position




- Since the fixed edge pin and movable edge pin are circular, they will not dig into the material even when pressed against it



- Features a slide/stop system which can slide easily and fix securely. Since the rubber stopper is usually floating, it is able to slide smoothly. When the handle is pressed, the rubber stopper moves down and closely adheres to the material, fixing it firmly.



- Wide Hex Grip handle that can be held firmly is adopted



- Includes both metric graduations and shaku graduations convenient for carpentry
- Aluminum construction makes guide both light and sturdy. Features white graduations on a blue background.
- Groove for slider
- Non-slip rubber pad achieves high non-slip performance thanks to the use of the high-performance microcellular polymer sheet PORON, which has a high-density, delicate and uniform cell structure



Use

- As a guide rule when making square or angular cuts with an electric circular saw
- As a guide rule when making cuts based on scribed angles from other materials
- For dimension measurements

Specifications

	79052	79053	79054	79055
Perpendicularity	Less than 0.1 mm per 100 mm			
Graduation	Shaku 1 shaku 6 sun 5 bu	2 shaku	3 shaku 3 sun	4 shaku
Metric	50 cm	60 cm	1 m	1.2 m
Gradient Adjustment Range	Gradient graduation from 1 sun to 10 sun			
Angle Adjustment Range	45° - 90°			
Edge Height	15 mm			
Material	Body: Aluminum Guide Surface, Fixed Edge Pin, Movable Edge Pin, Indicator arrow: Stainless steel Protection end cap: ABS resin Handle: ABS resin, elastomer resin Angle Fine Adjustment Screw: Phenol resin, brass			


Circular Saw Guide L-Angle Plus Adjust NEW



- Includes an angle fine adjustment screw which is easy to rotate even while wearing gloves




73182



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73180	45 cm/shaku	632×350×83	1,200		2	
73181	60 cm/shaku	762×350×83	1,300			
73182	1 m/shaku	1,162×400×83	1,700		1	
73183	1.2 m/shaku	1,362×400×83	1,800			

Features

- Combination of angle fine adjustment mechanism and slide/stop system enables smooth fine adjustment in mm units



- Angular fine adjustment secures edge firmly even on thin boards such as veneer



- Straight heel shape keeps the screw from directly contacting the ground or snagging the electric circular saw's cord



- Includes both metric graduations and shaku graduations convenient for carpentry

- Aluminum construction makes guide both light and sturdy. Features white graduations on a blue background.

- Groove for slider

- Non-slip rubber pad achieves high non-slip performance thanks to the use of the high-performance microcellular polymer sheet PORON, which has a high-density, delicate and uniform cell structure



Use

- As a guide rule when making square or angular cuts with an electric circular saw
- As a guide rule when making finishing cuts along a scribed line
- For dimension measurements

Specifications

	73180	73181	73182	73183
Perpendicularity	Less than 0.1 mm per 100 mm			
Graduation	Shaku	1 shaku 6 sun 5 bu	2 shaku	3 shaku 3 sun
	Metric	50 cm	60 cm	1 m
Angle Fine Adjustment Range (Guide Blade Tip)	To the left approx. 20 mm	To the left approx. 24 mm	To the left approx. 34 mm	To the left approx. 40 mm
	To the right approx. 18 mm	To the right approx. 21 mm	To the right approx. 30 mm	To the right approx. 36 mm
	15 mm			
	5 mm			
Edge Height	15 mm			
Cutout Positioning Stick Storage Height	5 mm			
Material	Body: Aluminum Guide Surface: Stainless steel Protection End Cap: ABS resin Angle Fine Adjustment Screw: Aluminum, polypropylene resin Handle: ABS resin, elastomer resin			
Accessories	1x Cutout positioning stick			

Circular Saw Guide L-Angle Plus




- Slides in easily and secures tightly with Slide-Stop System. It slides smoothly since the non-slip rubber is normally floating above the surface. Pressing down on the handle causes the rubber portion to move down and adhere to the material, securing it tightly.



73152



73150



73151



73153


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73150	45 cm/shaku	632×350×83	1,100		2	
73151	60 cm/shaku	762×350×83	1,200			
73152	1 m/shaku	1,162×400×83	1,600		1	
73153	1.2 m/shaku	1,362×400×83	1,700			

Refer to P. 2 about the shaku scale

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

- Wide Hexa Grip that grips securely. Pressing down on the handle causes the rubber portion to move down and adhere to the material, securing it tightly.




- Heel shape that stands completely straight. The product will not become diagonal when stood upright since the guide and the handle mounting board have the same height.



- Enables square cuts just by aligning base plate of electric circular saw along the edge of the guide
- Features both shaku and metric graduations to come in handy for carpenters
- Durable design with lightweight aluminum construction
- Groove for slider



- Non-slip rubber is made of high-performance microcellular polymer sheet (PORON), which is comprised of a high-density, delicate, and uniform cell structure to provide excellent non-slip performance



Use

- As a guide rule when making square cuts on boards with an electric circular saw
- For dimension measurements

Specifications

	73150	73151	73152	73153
Perpendicularity	Less than 0.1 mm per 100 mm			
Graduation	Shaku	1 shaku 6 sun 5 bu	2 shaku	3 shaku 3 sun
	Metric	50 cm	60 cm	1 m
Edge Height	15 mm			
Material	Body: Aluminum Guide Surface: Stainless steel Protective End Cap: ABS resin Wide Handle: ABS resin, elastomer resin, polypropylene resin			
Accessories	1x Cutout positioning stick			

Circular Saw Guide L-Angle with Horizontal Graduations



Features

- Easily mark where to cut
- Wide base for better grip

Measure and scribe as you go

50 cm
1 shaku 6 sun 5 bu

Outside edge of the long branch is the base point.

Use

- As a guide rule when making square cuts on boards with an electric circular saw
- For dimension measurements

Specifications

Perpendicularity	Less than 0.1 mm per 100 mm	
Blade Graduation	Shaku	3 shaku 3 sun
	Metric	1 m
Horizontal Graduation	Shaku	1 shaku 6 sun 5 bu
	Metric	50 cm
Edge Height	15 mm	
Material	Body: Aluminum Guide Surface: Stainless steel Handle: ABS resin, elastomer resin	
Accessories	1x Cutout positioning stick 1x Bracing fitting	


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78570	1 m/shaku	1,150×524×70	1,600		1	

Refer to P. 2 about the shaku scale

Circular Saw Guide L-Angle with Support Plate



- Support plate protects material from scratching and allows uneven surfaces to be cut
- Support plate can be adjusted for different sizes of electric circular saws



Features

- Just by aligning it on an object, it helps an electric circular saw cut perpendicularly
- Features both shaku and metric graduations to come in handy for carpenters
- Durable, lightweight aluminum material
- Stainless steel plate on guide edge
- Replacement support plate is available (sold separately)

Use

- As a guide rule when making square cuts on boards with an electric circular saw
- For dimension measurements

Specifications

	77899	77883	77901
Perpendicularity	Less than 0.1 mm per 100 mm		
Graduation	Shaku	1 shaku 6 sun 5 bu	2 shaku
	Metric	50 cm	60.5 cm
Edge Height	15 mm		
Material	Body: Aluminum Guide Surface: Stainless steel Handle: ABS resin, elastomer resin		
Accessories	1x Cutout positioning stick 1x Cutout positioning stick 1x Bracing fitting		

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77899	45 cm/shaku	580×335 - 380×70	1,360		2	
77883	60 cm/shaku	750×365 - 410×70	1,650			
77901	1 m/shaku	1,150×435 - 480×70	2,550		1	

Refer to P. 2 about the shaku scale

Circular Saw Guide L-Angle without Handle



77858

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77858	50 cm/shaku	500(40)×330(35)×20(5)	560	4 960910 778580	4	

Refer to P. 2 about the shaku scale

Features

- Find the square by aligning it to the edge



- Strong and lightweight thanks to aluminum and stainless steel bond

Use

- As a guide rule when making square cuts on boards with an electric circular saw
- For dimension measurements

Specifications

Perpendicularity	Less than 0.1 mm per 100 mm	
Graduation	Shaku	1 shaku 6 sun 4 bu
	Metric	46 cm
Edge Height	8.8 mm	
Material	Body: Aluminum, stainless steel	

Circular Saw Guide L-Angle for Left-hander



77803

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77803	45 cm/shaku	580×300×70	900	4 960910 778030	2	
77805	60 cm/shaku	750×330×70	1,100	4 960910 778054		
77807	1 m/shaku	1,150×400×70	1,500	4 960910 778078	1	

Refer to P. 2 about the shaku scale

Features

- L-Angle for a left-handed person


Use

- As a guide rule when making square cuts on boards with an electric circular saw
- For dimension measurements

Specifications

	77803	77805	77807
Perpendicularity	Less than 0.1 mm per 100 mm		
Graduation	Shaku	1 shaku 6 sun 5 bu	2 shaku
	Metric	50 cm	60.5 cm
Edge Height	15 mm		
Material	Body: Aluminum Guide Surface: Stainless steel Handle: ABS resin, elastomer resin		
Accessories	1x Cutout positioning stick 1x Brace fitting		

Circular Saw Guide L-Angle Light



77966



77967



77919

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77966	45 cm	580×276×78	600	4 960910 779662	2	
77967	60 cm	750×276×78	700	4 960910 779679		
77919	1 m	1,150×355×78.5	1,200	4 960910 779198	1	

Features

- Lightweight circular saw guide is made of aluminum, stainless steel, and polycarbonate resin
- Easy-to-grip handle
- Stainless steel plate on guide edge

Use

- As a guide rule when making square cuts on boards with an electric circular saw

Specifications

	77966	77967	77919
Perpendicularity	Less than 0.1 mm per 100 mm *at ordinary temperature		
Material	Body: Aluminum, polycarbonate resin Guide Surface: Stainless steel Reinforcing Metal Fitting: Stainless steel (77919)		
Edge Height	15 mm		
Accessories	1x Cutout positioning stick		

*The cutout positioning stick cannot be used for 45, 60 cm model.

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Circular Saw Guide L-Angle Fit



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78034	15 cm	220×220×24	250	4 960910 780347	4	
78036	23 cm	304×280×24	440	4 960910 780361		
78052	30 cm	380×280×24	535	4 960910 780521		

Features

- 9 mm high fence fixes it tightly even to chamfered two-by-four lumber or floorboards



- Extended long grip can be gripped tightly without causing interference to circular saw motor
- 15 cm and 23 cm models are suitable for cutting two-by-four lumber. 30 cm model is suitable for floorboards.



- Rubber sheet on back side prevents slipping and scratching of material (78034/78052)



- 5 mm pitch graduations


Use

- As a guide rule when making straight cuts on lumber with an electric circular saw

Specifications

	78034	78036	78052
Perpendicularity	Less than 0.2 mm per 100 mm		
Edge Height	9 mm		
Material	Body: Aluminum Guide Surface: Stainless steel		


Circular Saw Guide Triangle



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78108	AL 15 cm	238×238×25	275	4 960910 781085	4	
78280	PC 30 cm	372×372×25	340	4 960910 782808		

Features

- Can be used for square and 45° cuts
- Rubber is attached to the reverse side of the position where the hand presses down, allowing stable cutting at right angles and 45° angles



- Light and durable due to polycarbonate resin. This light weight comes from 44% aluminum, while strength is approximately 30x greater than acrylic. Will not scratch materials since it is made of resin. (78280)
- Long introduction part makes for stable cutting



- 9 mm high fence fixes it tightly even to chamfered two-by-four lumber or floorboards



- Stainless steel plate to protect against wear


Use

- As a guide rule when making square or 45° cuts on lumber with an electric circular saw

Specifications

	78108	78280
Angle Tolerance	Less than 0.2 mm per 100 mm at 45° and 90°	
Edge Height	9 mm	
Material	Body: Aluminum Guide Surface: Stainless steel	Body: Polycarbonate resin Guide Surface: Stainless steel

Circular Saw Guide T-Slide Slim-shift




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73312	15 cm/shaku	325×275×20	250	4 960910 733121	6	
73313	30 cm/shaku	460×275×20	287	4 960910 733138		
73314	45 cm/shaku	610×275×20	326	4 960910 733145		
73315	60 cm/shaku	760×275×20	370	4 960910 733152		
73316	90 cm/shaku	1,060×275×20	451	4 960910 733169		

Refer to P. 2 about the shaku scale

Features

- Can be used for both thin board and narrow width cuts. Bring edge up to cut thin boards without them moving into the T-slide itself. Or, fold the edge down for narrow width cuts.

Thin board mode



Narrow width mode



- Provides optimum end height so that even when cutting with 9 mm boards stacked on each other, it will not interfere with the second board




Use

- As a guide rule when cutting thin wooden boards into smaller, long strips with an electric circular saw
- As a guide rule when cutting wooden boards into smaller, long strips with an electric circular saw

Specifications

Material	Beam, Joint: Stainless steel End: Aluminum, UHPE tape Protective Cap, Stopper Screw: Polycarbonate resin (end) Mounting Position Adjustment Screw: Polyacetal resin (Guide stabilization metal fitting)
----------	--

Circular Saw Guide T-Slide II



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73711	15 cm/shaku	327×275×30	368	4 960910 737112	4	
73712	30 cm/shaku	462×275×30	405	4 960910 737129		
73713	45 cm/shaku	612×275×30	448	4 960910 737136		
73714	60 cm/shaku	762×275×30	490	4 960910 737143		
73715	90 cm/shaku	1,062×275×30	575	4 960910 737150		

Refer to P. 2 about the shaku scale

Features

- Newly designed stabilizer



Stabilizer prevents arm from shaking in any direction

- Quick-shift lock mechanism fixes arm easily and tightly



- Fence high enough for 3 pieces of 9 mm thick material



Use

- As a guide rule when cutting wooden boards into smaller, long strips with an electric circular saw

Specifications

Material	Arm: Iron Slider: Aluminum, UHPE tape Protective Cap, Edge Guide, Edge Clamping Plate: ABS resin Clamp Lever: Polyacetal resin
----------	---

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Circular Saw Guide T-Slide Basic



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73591	15 cm/shaku	280×220×15	164	4 960910 735910	8	
73592	30 cm/shaku	430×220×15	207	4 960910 735927		
73593	45 cm/shaku	580×220×15	249	4 960910 735934		
73594	60 cm/shaku	730×220×15	292	4 960910 735941		

Refer to P. 2 about the shaku scale

Features

- Since the arm comes out directly from the slider, it can be fixed securely to thin boards even less than 5 mm without any risk of the board penetrating the space between the arm and slider



- Hard-to-rust, rigid construction due to all stainless steel material (SUS304)



- 3D structure formed from a single sheet of stainless steel material makes it both strong and lightweight

- Includes holes for attaching wood as spacer with wood screws, which enables cutting to a narrow width


Use

- As a guide rule when cutting wooden boards into smaller, long strips with an electric circular saw

Specifications

Material	Stainless steel
----------	-----------------

Circular Saw Guide T-Slide Double




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73701	15 cm/shaku	327×425×30	650	4 960910 737013	4	
73702	30 cm/shaku	462×425×30	730	4 960910 737020		
73703	45 cm/shaku	612×425×30	830	4 960910 737037		
73704	60 cm/shaku	762×425×30	920	4 960910 737044		
73705	90 cm/shaku	1,062×425×30	1,090	4 960910 737051		

Refer to P. 2 about the shaku scale

Features

- Combined double slider




Interval between the two arms and the position of slider can be adjusted separately

- Newly designed stabilizer



Stabilizer prevents arm from shaking in any direction

- Quick-shift lock mechanism fixes arm easily and tightly



- Fence high enough for 3 pieces of 9 mm thick material



Use

- As a guide rule when cutting wooden boards into smaller, long strips with an electric circular saw

Specifications

Material	Arm: Iron Slider: Aluminum, UHPE tape Protective Cap/Edge Guide/ Edge Clamping Plate: ABS resin Clamp Lever: Polyacetal resin
----------	---

Circular Saw Guide I-Clamp One-touch


77822



Fix it by pulling the one-touch lever



One-touch operation for fixing and releasing (back side)



Features

- Fixes the rule on material with one touch. Not necessary to hold down the rule.
- Convenient not only for an electric circular saw but also as a cutter guide
- 2.4 m model can hold up to 8shaku board
- One-touch operation for fixing and releasing
- Fastens rule securely without scratching materials
- Durable and lightweight, made of aluminum and stainless steel
- Comes with both shaku and metric graduations
- Stainless steel plate on both guide edges

Use

- As a guide rule when making straight cuts of wooden boards such as 3x6 boards and 4x8 boards with an electric circular saw
- As a cutter guide
- For dimension measurements

Specifications

	77822	77821	77823	77824
Material	Body: Aluminum Mounting Part: Aluminum, urea resin, stainless steel Holding Lever, Edge Cap: ABS resin			
Clamping Size	Minimum 25 mm			
Maximum	1,010 mm	1,240 mm	2,010 mm	2,445 mm
Straightness Tolerance	Less than 0.45 mm	Less than 0.5 mm	Less than 0.6 mm	Less than 0.7 mm
Accessory	2x Cutout positioning stick (6 x 6 x 160 mm)			

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
77822	1 m/shaku	1,172x60x30	1,200	4 960910 778221	1	
77821	1.2 m/shaku	1,402x60x30	1,300	4 960910 778214		
77823	2 m/shaku	2,172x60x30	2,000	4 960910 778238		
77824	2.4 m/shaku	2,590x60x30	2,500	4 960910 778245		

Refer to P. 2 about the shaku scale

Circular Saw Guide Free Angle Neo



73160



73166



73161



73162



73163

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
73160	30 cm	465x142x20	630	4 960910 731608	1 (5)	
73166	37 cm	535x142x20	650	4 960910 731660		
73161	45 cm	615x142x20	700	4 960910 731615		
73162	60 cm	765x170x20	880	4 960910 731622	1	
73163	1 m	1,165x170x20	1,080	4 960910 731639		

Features

- Strong metal screw replaces the plastic one. Will not break
- Folds flat
- Easy to turn



Stainless + Brass



Flap type

- Rigid 3-D structure



More Strength

- Hollow, wide, aluminum guide makes it light and durable



65 mm



With protector caps to protect material from getting scratched

- Groove for Slider (sold separately, Item Code 78236): Just slide it in the groove to prevent shifting during cutting



Use after installing on the base of an electric circular saw

Use

- As a guide rule when making angular cuts on lumber with an electric circular saw
- As a guide rule when making cuts based on scribed angles from other materials

Specifications

	73160	73166	73161	73162	73163
Perpendicularity (at 90°)	Less than 1 mm per 300 mm	Less than 1.3 mm per 370 mm	Less than 1.6 mm per 450 mm	Less than 2.1 mm per 600 mm	Less than 3.5 mm per 1000 mm
Material	Body: Stainless steel, aluminum Stopper Screw: Stainless, brass Protector Cap: Polyacetal resin				
Accessory	1x Cutout positioning stick				

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Circular Saw Guide Free Angle Multi



78232

HOW TO USE

Fix slider to an electric circular saw and slide it in the groove to cut straight.



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78232	Free Angle Multi with Guide Rule 30 cm	455×145×23	750	4 960910 782327	4	
78233	Guide Rule 30 cm for Free Angle Multi	455×30×5	130	4 960910 782334	5	
78234	Guide Rule 45 cm for Free Angle Multi	605×30×5	171	4 960910 782341		
78235	Guide Rule 60 cm for Free Angle Multi	755×30×5	213	4 960910 782358		

Features

- Slider comes as standard
- Easily adjust length and angles
- Replacement guides enable length adjustment




30 cm (Standard equipment)
 45 cm (Optional)
 60 cm (Optional)

*30 cm guide comes as standard. 45 cm and 60 cm guides (sold separately) can be used to extend length.

- Aluminum guide can be locked at any position



- Longer guide helps to cut at an acute angle



Use

- As a guide rule when making angular cuts on lumber with an electric circular saw
- As a guide rule when making cuts based on scribed angles from other materials

Specifications

Perpendicularity (at 90°)	Less than 1 mm per 300 mm
Material	Body: Stainless steel, aluminum Stopper Screw: Aluminum, brass
Accessory	Slider, cutout positioning stick, stopper screw (flat)

Circular Saw Guide Free Angle One-touch



Securely lock guide onto material with one-touch lever

(Back)

78450

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78450	1 m	1,230×425×30	2,200	4 960910 784505	1	
78451	1.2 m	1,460×425×30	2,500	4 960910 784512		

Features

- Fixes rule on material with one touch
- One-touch operation for fixing and releasing
- An electric circular saw can be operated with both hands

Easy-to-read gradient graduation



Clear polycarbonate board helps to see cutting point



Pin can be used to fix on soft material such as plaster board



Use

- As a guide rule when making angular cuts on lumber with an electric circular saw

Specifications

	78450	78451
Perpendicularity (at 90°)	Less than 3.5 mm per 1,000 mm	
Material	Body: Stainless steel, aluminum Stopper Screw: Aluminum, brass	
Accessory	Assist plate (polycarbonate resin)	

Circular Saw Guide Mini Free Angle Justy

78079



78176



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78079	Quick Adjust 23 cm	350×105×26	360	4 960910 780798	4	
78176	II 23 cm	350×105×26	360	4 960910 781764	5	

Circular Saw Guide Mini Free Angle

78217



78179



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78217	Quick Adjust 30 cm	439×100×26	460	4 960910 782174	4 (24)	
78179	II 30 cm	439×112×23	450	4 960910 781795	5	

Features

- Adjustable to any angles from 20° - 160°
- Gradient graduation from 3 sun to 8 sun
- Turn over to use on wider material

■ Quick Adjust

- Easily lock at certain angles (45°, 90°, 135°)



■ Justy II/Mini Free Angle II

- Easy-to-read white graduation board
- Hard-to-break, new metal type stopper screw
- Flat folding screw



Use

- As a guide rule when making square cuts on lumber with an electric circular saw
- As a guide rule when making cuts based on angles scribed from other materials

Specifications

■ 23 cm

	78079	78176
Perpendicularity (at 90°)	Less than 1 mm per 300 mm	
Material	Body: Stainless steel Stop Switch: ABS, polyacetal resin Stopper Screw: Stainless steel, brass Stopper Screw (flat): ABS resin	Body: Stainless steel Stopper Screw: Stainless steel, brass
Accessory	1x Cutout positioning stick Stopper screw (flat) —	

■ 30 cm

	78217	78179
Perpendicularity (at 90°)	Less than 1 mm per 300 mm	
Material	Body: Stainless steel, aluminum Stop Switch: ABS, polyacetal resin Stopper Screw: Stainless steel, brass Stopper Screw (flat): ABS resin	Body: Stainless steel, aluminum Stopper Screw: Stainless steel, brass
Accessory	1x Cutout positioning stick Stopper screw (flat) —	

14. Construction Tools



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Stud Finder Smart

Needle : Wall thickness up to **25 mm**

78585



Needle : Wall thickness up to **35 mm**

78586



Needle : Wall thickness up to **35 mm**

Magnet : Wall thickness up to **13 mm** / ceiling thickness up to **12 mm**

78592



*When finding steel material behind plaster board, the usable area of magnet can vary depending on conditions.

Needle : Wall thickness up to **45 mm**

78574



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78585	25 mm	113x21x17.5	18	4 960910 785854	10	
78586	35 mm	133x21x17.5	20	4 960910 785861	10	
78592	35 mm with Magnet	161.5x21x17.5	28	4 960910 785922	10	
78574	45 mm	153x21x17.5	22	4 960910 785748	10	

Features





- Needle-type stud finder for plasterboard
- Handy carrying size
- Finds studs behind wall panel easily and accurately
- Graduations to measure the thickness of the wall material approximately
- Includes two replacement needles inside
- Safety lock feature prevents needle from coming out accidentally
- Keeps clean with Antibacterial body

Magnetic model

- Can detect location of both metal and wooden studs
- Can detect location of nails or metal studs (steel) under the cross without scratching the wall

Detection with magnet
Metal studs can be found from sounds without needle

Detection with needle
Wooden studs can be found by using needle



Use

- For finding studs behind plaster board

Specifications

Material	Body: ABS resin (with antibacterial agent) Movable Needle Cover: Polycarbonate resin Needle: Stainless steel
----------	--

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Carpenter's Squares
Stainless Steel Rules / Machine Scale
Aluminum Rules
Resin Folding Rules / Bamboo Rules
Squares / Protractors
Vernier Calipers / Micrometers
Tape Measures
Surveying Products
Scales
Levels
Lasers / Optical Equipment
Inklines / Chalklines / Plumbholders
Circular Saw Guides
Construction Tools
Industrial Tools
Thermometers / Hygrometers / Weather Measuring Instruments
Outdoor Products
Magnifying Glasses
Drawing Tools
Magnets

Replacement Needle for Stud Finder Smart

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	SP
78594	10 pc-pack for Stud Finder Smart 25 mm	φ0.7×70	—	4 960910 785946	10	
78595	10 pc-pack for Stud Finder Smart 35/45 mm	φ0.7×80	—	4 960910 785953	10	

Use

- For Stud Finder Smart series only (Not compatible with Stud Finder series)

Stud Sensor

Easy-to-use simple design



With wire detection alarm



78575

78576



Deep mode equipped



Detect the center of stud instantly




Multi-function all-purpose model



78577

78578

78657



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	SP
78575	Basic	136×56×35	101	4 960910 785755	5	
78576	Super	153×61×42	134	4 960910 785762	5	
78577	HG	169×71×45	159	4 960910 785779	5	
78578	HG-Center Finder	159×78×34	155	4 960910 785786	5	
78657	EX	160×80×30	230	4 960910 786578	5	

*Not available in certain areas. Please contact us for details.

Features

- Detects metal, wood, plastic, and rebar in concrete (only 78657) with light and alarm
- Sensor mode can be changed depending on material and thickness of wall (78577/78578/78657)
- Easy-to-hold and non-slip rubber grip (78577/78578/78657)

Use

- For finding studs behind walls

Specifications

Object	Material Model	Veneer + Plaster Board	ALC Board	Concrete	Mortar	Metal
Wood	Basic					
	Super					
	HG	○	×	×	×	×
	HG-Center	*				
Metal	EX	○	○	○	○	×
	Basic					
	Super	○	×	×	×	×
	HG	*				


*It is not possible to determine the metal and wood.

	78575	78576	78577
Material	Body: ABS resin		
Power Source	1x 9V Alkaline battery (Battery included is for trial use only and may not last as long)		
Object Detection Depth (approximate)	19 mm	19 mm	Shallow 19 mm Deep 35 mm
Wire Detection Alarm	×	○	○
Center Detection	×	×	×

	78578	78657
Material	Body: ABS resin	
Power Source	1x 9V Alkaline battery (Battery included is for trial use only and may not last as long)	
Object Detection Depth (approximate)	Regular 19 mm Deep 25 mm	Wood 25 mm Metal 40 mm
Wire Detection Alarm	○	○
Center Detection	○	×

Stud sensor's mechanism

- Detects changes in electrostatic capacity



Inside the stud sensor are two electrodes, shown above as ① and ①', and the sensor detects changes in electrostatic capacity among each electrode when an object with higher density than the wall comes between them, as shown in ②.

Concept of electrostatic capacity

Electrostatic capacity refers to the amount of electric charge that is stored in the two electrodes when a DC current is run between them, and this electrostatic capacity changes when an object approaches one of the electrodes.

Metal Stud Finder



78674

Wall thickness up to **15 mm**



Features

- Strong magnetic pendulum helps to find metal studs behind a wall or the position of nails or screws without scratching the wallpaper
- Easily detects with magnetic reaction
- Compact and lightweight. Great portability
- Reacts to magnetic pull from any direction with 360° rolling system



Use

- For detecting metal studs behind a wall

Specifications

Material	Body: ABS resin Windshield Cover: Acrylic resin Magnet: Neodymium
----------	---

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78674	Mini	30×30×31.5	13	4 960910 786745	10	

Tile Percussion Hammer

74102



74103



74104



74105

74106



With strap
(except 74106)

Features

- Contracts to pocket size for great portability

Use

- For inspecting integrity of tiles



Specifications

	74102	74103	74104
Material	Shaft: Stainless steel Grip: Rubber Globe Part: Tool steel Strap: Nylon		
Size	Min - Max 130 - 435 mm	Min - Max 165 - 725 mm	Min - Max 220 - 1,170 mm
Globe Part	ϕ17.5 mm		

	74105	74106
Material	Shaft: Stainless steel Globe Part: Tool steel Grip: Rubber Strap: Nylon	Shaft: Stainless steel Globe Part: Tool steel
Size	Min - Max 300 - 990 mm	Min - Max 147 - 605 mm
Globe Part	ϕ17.5 mm	

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
74102	A-1	130×18×18	71	4 960910 741027	5	
74103	A-2	165×18×18	90	4 960910 741034		
74104	A-3	220×18×18	111	4 960910 741041		
74105	A-4	300×18×18	126	4 960910 741058		
74106	B-1	147×17.5×17.5	61	4 960910 741065		


Digital Moisture Meter for Wood

NEW

With protective cap



78636



Know at a glance the numerical value's increase or decrease on the moisture content bar graph

Features

- Can easily measure the moisture of wood, and supports a wide variety from building materials to firewood
- Backlight function to make LCD screen easy to see even in dark places
- Holds the measured value so the numerical value can be checked even when the LCD screen is hard to see
- Can display the highest/lowest moisture content during measurement



Use

- For measuring the moisture content of wood

Specifications

Measurement Method	Electrical resistance
Measurement Range	Moisture content: 6.8 - 60% Temperature: -10 - 50°C*1 Humidity: 10 - 90%*1
Accuracy	Moisture Content: ±2%
Use Temperature	-10 - 50°C
Storage Temperature	-40 - 60°C
Resolution	Moisture Content: 0.1% Temperature: 0.1°C Humidity: 0.1%
Auto Power Off	Approx. 10 min.*2
Power Source	2x AAA batteries (Batteries included are for trial use only and may not last as long)
Material	Body: ABS resin, elastomer resin Measuring Probes: Stainless steel Button: Silicone rubber
Accessory	Storage case, 2x AAA batteries

*1 Since the accuracy of the temperature/humidity measurement function cannot be guaranteed, please use as an approximation.
 *2 When the device turns off due to the Auto Power Off function, the power button must be pressed twice to turn it on again.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78636	with Maximum and Minimum Hold Function	130×55×29	144	4 960910 786363	1	

Fabric Safety Cord



Features

- Cloth-made bellows structure resists tangling
- Swivel rotates 360°
- Resists spreading out when worn on the waist for greater comfort during work



Resists spreading

Use

- To prevent dropping and losing various tools

Specifications

	80858	80859	80860	80861
Material	Cord: Nylon Swivel: Zinc alloy			
Cord Size	Natural Length	Approx. 660 mm	Approx. 680 mm	
	Stretched Length	Approx. 1,430 mm	Approx. 1,450 mm	
	Width	12 mm	15 mm	
Working Load	Under 1 kg		Under 3 kg	


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
80858	A Black	660×12×15	42	4 960910 808584	10	
80859	A Orange	660×12×15	42	4 960910 808591		
80860	B Black	680×15×17	72	4 960910 808607		
80861	B Orange	680×15×17	72	4 960910 808614		

Safety Cord



Features

- Stainless steel wire is used as a core material for better durability, and polyurethane resin provides flexibility
- Comes with wire and ring-attaching tool



Use

- To prevent tools falling

Specifications

	80890	80891
Cord Size	Diameter	φ1.65 mm
	Core Diameter	φ0.6 mm
	Length	Approx. 340 mm
	Maximum Extension	Approx. 1,200 mm
Working Load	Under 500 g	Under 1 kg
Material	Cord: Stainless steel, polyurethane resin Wire-attaching Tool: Stainless steel (nylon coating), brass Saddle Snap: Zinc alloy Ring: Iron	

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
80890	A	340×22×10	25	4 960910 808904	10	
80891	B	500×30×11	73	4 960910 808911		

Folding Square



77840

Legs are detachable.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
77840	1.8 m	1,823×80×20 (excluding legs)	4,300 (including legs)		1	


Refer to P. 2 about the shaku scale

Features

- Angle and gradient graduations. Convenient for setting and reading of angle (gradient)



- Detachable legs allow use for layout of leading frames with legs and for marking on foundations or as a bevel without legs. The leg expansion from 50cm to 80 cm helps use with high ground foundations
- Storage case




Use

- For layout of leading frames and getting a right angle when marking on foundations
- For marking angle and gradient as a sliding bevel

Specifications

Accuracy	90°: Less than 1 mm per 1,000 mm (±1.8 mm at 1,800 mm) Other than 90°: No guaranteed accuracy. Please use as a guide.
Graduation	Angle: 30 - 90°, Gradient: 0 - 9/10 (9 sun gradient) Flat Gradient: 6/10 - 9/10 (6 sun - 9 sun gradient)
Material	Body: Aluminum Legs: Aluminum, stainless steel
Body Size (excluding legs)	At 90 degrees: 1,823 × 1,823 × 20 mm

Welding Guide Rule



77888




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
77888	1 m with Magnet	1,010×550×54 (at 90° degree)	1,500		1	

Refer to P. 2 about the shaku scale

Features

- Insulating coating on the rule surface. This prevents sparks even if welding rods touch it.
- Body is made out of aluminum for light weight and easy use
- Angles can be changed easily. Angle/gradient graduations eliminate the need to make a mold for each building.



- Strong magnet fixes it tightly on a surface With strong magnet




Use

- For tack welding
- For measuring and setting of angle and gradient


Specifications

Accuracy	Perpendicular: 1 mm or less per 1,000 mm
Graduation	Angle: 45 - 135° Gradient: Up to 5/10 (5 sun gradient)
Material	Body: Aluminum Rivet: Stainless steel

Measuring Instrument Set for Steel Fabrication



97575



97794

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
97575	5 Items	234×195×40	870	4 960910 975750	1	
97794	7 Items	425×375×70	3,600	4 960910 977945	1	

(As a set)

Item Code	C.D.	Description	Example Usage
97784	6	① Bevel Angle Measuring Gauge 9 Leaves (30° - 50°)	Measuring oxygen cutting in manufacture process inspection, bevel angle inspection in beveling edge preparation
97786	0	② Route Interval Measuring Gauge 9 Leaves (4 - 12 mm)	Measuring oxygen cutting in manufacture process inspection, route side inspection in beveling edge preparation
* 58691	8	③ Welding Gauge A	For various welding inspections such as leg length and reinforcement welding
* 62600	3	④ Taper Gauge No.700A 1 - 15 mm	Measuring various gap spaces
* 58695	6	⑤ Undercut Gauge	Measuring depth of overlay undercut
97788	4	⑥ Joint Offset Measuring Gauge	Measuring joint offset
97790	7	⑦ Flange Bend, Gradient Measuring Gauge	Measuring gap space of flange

*Listed separately

Features

- Convenient gauges for appraisal of steel fabrication are packed into handy kit. Helps to have better productivity and prevents loss.

Use

- For accuracy confirmation of steel frames

Specifications

■ Case

	97575	97794
Material	Polypropylene resin	ABS resin

■ Gauge

- ① Bevel Angle Measuring Gauge
9 Leaves (30° - 50°)



	97784
Material	Stainless steel
Accuracy	±1°
Pitch	2.5°
Body Size	30 × 65 × 18 mm
Weight	226 g

- ② Route Interval Measuring Gauge 9 Leaves (4 - 12 mm)



	97786
Material	Stainless steel
Accuracy	±0.1 mm
Pitch	1 mm
Body Size	20 × 65 × 18 mm
Weight	134 g

- ③ Welding Gauge (Refer to P. 149)

- ④ Taper Gauge (Refer to P. 154)

- ⑤ Undercut Gauge (Refer to P. 149)

- ⑥ Joint Offset Measuring Gauge




	97788
Material	Stainless steel
Accuracy	Gap of less than 0.5 mm
Body Size	65 × 230 × 35 mm
Weight	620 g

- ⑦ Flange Bend Gauge



	97790
Material	Stainless steel
Accuracy	Straightness of less than 0.2 mm, squareness of less than 0.5 mm/140 mm
Body Size	217 × 335 × 12 mm
Weight	794 g

Welding Gauge



58691

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
58691	A	70.5×48×7	85	4 960910 586918	5	

Features

- Compact size convenient for carrying
- Able to measure easily, swiftly, and accurately

Use

- For various welding inspections such as leg length and reinforcement welding

Specifications

Accuracy	Gap /Length: Less than ±0.2 mm (in 20 mm, 40 mm) Angle: ±1.5° or less
Material	Stainless steel

Undercut Gauge



58695

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
58695	Undercut Gauge	115×58×18	86	4 960910 586956	1	

Features

- Stable foundation for easy readout

Use

- For undercut depth measurement of weld overlay

Specifications

Accuracy	±0.05 mm (1.0 mm or less)
Material	Stainless steel, brass, iron

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Crack Scale



58699



58697



Front Back
58698

Features

- Card and 15 cm rule models are made of stainless steel for rigidity and durability
- Clear model allows easy matching (or measuring) of cracks

Use

- For inspection of concrete cracks in walls and foundations

Specifications

	58699	58698	58697
Measuring Range	Clearance: 0.10 - 1.40 mm Length: 0 - 80 mm	Clearance: 0.10 - 2.20 mm Length: 0 - 150 mm	Clearance: 0.03 - 2.20 mm Length: 0 - 80 mm
Accuracy	±0.05 mm		±0.02 mm
Material	Stainless steel		Polyester

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
58699	Card Type	55×91×0.3	12	4 960910 586994	10 (50)	
58698	Rule Type 15 cm	175×15×0.5	10	4 960910 586987		
58697	Clear Type	55×91×0.2	1	4 960910 586970		

Profile Gauge



77970



77971




77984

Features


- Gauge adapts to any shape
- Rust-resistant stainless steel pins

Use


- For shaping the angles of carpets/mats and curves in wood or steel



Fit the item into the object



Draw a line along the shape



Cut the object along the line

Specifications

	77970	77971	77984
Usable Range	Approx. 148 × 49 mm (width × depth)	Approx. 293 × 106 mm (width × depth)	Approx. 190 × 81 mm (width × depth)
Numbers of Strings	Approx. 185 pcs	Approx. 280 pcs	Approx. 195 pcs
String Size	φ0.8 × 84 mm	φ1.0 × 150 mm	φ1.0 × 120 mm
Material	Pins: Stainless steel		

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77970	A 150 mm	150×84×18	230	4 960910 779709	6	
77971	B 300 mm	300×150×31	977	4 960910 779716	4	
77984	C 200 mm	203×120×22	465	4 960910 779846	5	

Log Scribe



77590

1 pc Scribing Ink Pencil included



77597


Features

- Essential compass for scribing to build a log house
- Works as double scribe by replacing the needle with a Scribe Ink Pencil
- Level on the front for better visibility when scribing
- Line drawn by a Scribe Ink Pencil is black and can be erased. If it gets wet, the line turns to blue and cannot be erased.
- Fine adjustment simple even after fixing scribe width

Use

- For scribing around lumber when building a log house

*Scribe the roundness of lower log to upper log. Scribe on A with needle and draw a line to B by holding Double Scribe horizontally.



Specifications

Material	Body: Stainless steel Level Body: ABS resin
Level	Sensitivity: 0.5 mm/m = ±0.0286° Accuracy: ±2.5 mm/m = less than ±0.1432°

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77590	Log Scribe	250×55×70	350	4 960910 775909	1	
77597	Replacement Scribing Ink Pencil 2 pc-pack for Log Scribe	φ75×183	7	4 960910 775978		

15. Industrial Tools



Packaging **S** Shrink package **B** Box **V** Vinyl package + header card **C** Card **☐** No package
SP Sleeve package **BP** Bag **CP** Clear package **VP** Vinyl package

Scribing Needle



Features

- A
● Comes with superhard chip
- B
● Comes with superhard chip
- C
● Comes with superhard chip
● Needle can retract for good portability
● Needle can be replaced
- D
● Compact and can be stored easily in a tool box
● Needle can be replaced
- E
● Needle can retract for good portability
● Needle can be replaced
● Needle retracts by turning body



Use

- For scribing on general metal material, plastic, and wood



Specifications

	78638	78646	78654
Material	Body: Iron		Body: ABS resin
	Tip: Superhard chip		
	74444	74445	
Material	Body: Brass		
	Tip: Tungsten steel		


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78638	A	155×6×6	36	4 960910 786387	10	SP
78646	B	217×24×7	38	4 960910 786462		
78654	C	140×11×8	12	4 960910 786547		
74444	D	128×10×10	31	4 960910 744448		
74445	E	131×9.5×7.5	11	4 960910 744455		

Replacement of Scribing Needle

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78650	2 pc-pack for C	40×2×2	1	4 960910 786509	10	SP
74468	1 pc for D	64×3.5×3.5	4	4 960910 744684		
74469	1 pc for E	118×5×5	2	4 960910 744691		

JIS JIS mark **SP** With red numbers **cm/shaku** (Upper side (or Front) metric / Lower side (or Back) shaku) **M** With magnet **V** Vial with luminous sheet **T** Thermometer **DS** Double-sided tape **JP** Letters in Japanese **WS** With stopper **Oil** Oil **G** Glass lens **E** With edge
12 Japanese zodiac signs **B** With battery **cm/shaku** (Upper side (or Front) shaku / Lower side (or Back) metric) **NS** With non-slip pad **TH** Thermometer/Hygrometer **H** Hygrometer **L** With hanging hole **EN** Letters in English **DA** With direction arrow **GS** With grid scale **PL** Plastic lens

Divider



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77518	A 15 cm	150×18×12.5	112	4 960910 775183	5	
77526	B 20 cm	200×19×12.5	180	4 960910 775268	5	
77517	C 10 cm	100×17×12.5	70	4 960910 775176	5	
77536	D 25 cm	250×21×12.5	240	4 960910 775367	5	
77537	E 30 cm	300×21×12.5	290	4 960910 775374	5	
73059	A 15 cm with Spring	195×80×17.5	90	4 960910 730595	5	
73067	B 20 cm with Spring	250×94×17.5	112	4 960910 730670	5	
33950	SD-6 15 cm with Spring*	200×85×20	90	4 960910 339507	1	
33951	SD-8 20 cm with Spring*	250×100×20	112	4 960910 339514	1	
33952	SD-10 25 cm with Spring*	310×120×25	161	4 960910 339521	1	
33953	SD-12 30 cm with Spring*	360×120×25	184	4 960910 339538	1	

*SD-6, 8, 10 and 12 are made-to-order items

Features

- Hard coating is applied on the tip
- Spring models allow easy fine-adjustment with screw

Use

- For scribing circles or copying measurement of items



Specifications

Divider

	77518	77526	77517	77536	77537
Material	Carbon steel (superhard chip tip)				
Usable Range	150 mm (Radius)	200 mm (Radius)	100 mm (Radius)	250 mm (Radius)	300 mm (Radius)

Divider with Spring

	73059	73067
Material	Carbon steel (Hardened tip)	
Usable Range	150 mm (Radius)	200 mm (Radius)

	33950	33951
Material	Carbon steel (Hardened tip)	
Usable Range	150 mm (Radius)	200 mm (Radius)

	33952	33953
Material	Carbon steel (Hardened tip)	
Usable Range	250 mm (Radius)	300 mm (Radius)

Divider with Super Hard Chip



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77520	A-2 15 cm	150×22×19	130	4 960910 775206	5	
77521	B-2 20 cm	200×22×22.5	230	4 960910 775213	5	
77516	C-2 10 cm	100×17×16	70	4 960910 775169	5	
77543	D-2 25 cm	250×23×24	320	4 960910 775435	5	
77545	E-2 30 cm	300×28×23	460	4 960910 775459	3	
77546	F-2 40 cm	400×27×25	785	4 960910 775466	1	

Features


- Scribes on hard metal even with hard chrome plate finish or heat treatment
- Long-lasting tip



Superhard chip tip

Use

- For scribing circles or copying measurement of items



Specifications

	77520	77521	77516	77543	77545	77546
Material	Carbon steel (Hardened tip)					
Usable Range	150 mm (Radius)	200 mm (Radius)	100 mm (Radius)	250 mm (Radius)	300 mm (Radius)	400 mm (Radius)

One-side Caliper




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73250	A 15 cm	160×18×12	46	4 960910 732506	10	

Features

- Tip of one leg is shaped as needle
- Scribe on a uneven surface

Use

- As a scribing tool




Specifications

Material	Carbon steel (Hardened tip)
Usable Range	150 mm (Radius)

Outside Caliper



33958



73318

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73318	A 15 cm	165×100×12	62	4 960910 733183	10	
73326	B 20 cm	213×120×12	77	4 960910 733268	1	
33958	OC-6 15 cm with Spring *	175×100×20	83	4 960910 339583	1	
33959	OC-8 20 cm with Spring *	225×130×20	98	4 960910 339590		
33960	OC-10 25 cm with Spring *	285×160×25	153	4 960910 339606		
33961	OC-12 30 cm with Spring *	340×160×25	178	4 960910 339613		


*OC-6, 8, 10 and 12 are made-to-order items.

Features

- For outer dimension measurement that cannot be measured by vernier caliper

Use

- For taking readings of outer dimensions, etc.



Specifications

	73318	73326
Material	Carbon steel	
Usable Range	150 mm (Radius)	200 mm (Radius)
	33958	33959
Material	Carbon steel	
Usable Range	150 mm (Radius)	200 mm (Radius)
	33960	33961
Material	Carbon steel	
Usable Range	250 mm (Radius)	300 mm (Radius)

Inside Caliper



33954



73253

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73253	A 15 cm	165×20×11.5	51	4 960910 732537	10	
73261	B 20 cm	210×18×11.5	60	4 960910 732612	1	
33954	IC-6 15 cm with Spring *	175×85×20	94	4 960910 339545	1	
33955	IC-8 20 cm with Spring *	225×100×20	123	4 960910 339552		
33956	IC-10 25 cm with Spring *	285×120×25	178	4 960910 339569		
33957	IC-12 30 cm with Spring *	340×120×25	209	4 960910 339576		


*IC-6, 8, 10 and 12 are made-to-order items.

Features

- For inner dimension measurement of a pipe or hole

Use


- For taking readings of inner dimensions, etc.




Specifications

	73253	73261
Material	Carbon steel	
Usable Range	150 mm (Radius)	200 mm (Radius)
	33954	33955
Material	Carbon steel	
Usable Range	150 mm (Radius)	200 mm (Radius)
	33956	33957
Material	Carbon steel	
Usable Range	250 mm (Radius)	300 mm (Radius)

Radius Scale



73570



Front



73571



Front


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73570	A-1 R 0.5 - 7	175×15×0.5	7.5	4 960910 735705	10	
73571	A-2 R 8 - 15	175×15×0.5	7.5	4 960910 735712		

Features

- 1 scale can be used as an R gauge, diameter gauge, and as a rule
- Easy to pull out and measure due to its compact size

Use

- Measurement of R, measurement of diameter and sheet thickness, and measurement of length




Specifications

	73570	73571
Material	Stainless steel	
Accuracy	Radius Gauge: ±0.1 mm Diameter Gauge: ±0.05 mm Straight Rule: ±0.15 mm	
Measuring Range	Radius Gauge: R 0.5 - 7 mm Diameter Gauge: 0.5 - 6 mm Straight Rule: 0 - 150 mm	Radius Gauge: R 8 - 15 mm Diameter Gauge: 0.5 - 6 mm Straight Rule: 0 - 150 mm

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Taper Gauge



62600

62605

62610


62615




Easy carrying



62603



62612



Front



Back

62620

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
62600	No.700 A 1 - 15 mm	148×17×1.2	11	4 960910 626003	10	
62605	No.700 B 15 - 30 mm	154×31×1.2	29	4 960910 626058	10	
62610	No.700 C 30 - 45 mm	160×46×1.2	50	4 960910 626102	1	
62615	No.700 D 45 - 60 mm	162×60×1.2	70	4 960910 626157	1	
62603	1 - 15 mm with Metal Case	155×20×6 (During storage)	25	4 960910 626034	10	
62612	1 - 15 mm with Rule	160×26×4.5 (During storage)	21	4 960910 626126	10	
62620	Double 1 - 15 mm for Clearance, Hole Diameter, Length	144×16.3×5.5	25	4 960910 626201	10	

Taper Gauge No.700 and with Metal Case

Features

- Error occurs with the thickness of the gauge itself when measuring a circular hole. Inner diameter revision chart is on the back for better accuracy (62600/62603)


- Formula for revision
 Inner diameter = $\sqrt{\text{reading value}^2 + 1.44}$
 (B) (A)

Thickness of
Taper Gauge
(1.2 mm)



Use

- For measurement of inner diameter or dimension of gap



Inner dimension measurement



Clearance gap measurement

Specifications

	62600	62605	62610	62615	62603
Thickness	1.2 mm				
Accuracy	±0.05 mm				
Measuring Range	1 - 15 mm	15 - 30 mm	30 - 45 mm	45 - 60 mm	1 - 15 mm
Material	Stainless steel				
Hardness	Hv400 or more				

Taper Gauge with Rule

Features

- Error occurs with the thickness of the gauge itself when measuring a circular hole. Inner diameter revision chart is on the back for better accuracy.
- Convenient portable tool combines taper gauge and rule
- Clip comes in handy for measuring depth or hanging in a pocket

Use

- For measurement of inner diameter or dimension of gap
- For measuring length and depth

Specifications

	Taper Gauge	Rule
Accuracy	±0.05 mm	±0.15 mm
Measuring Range	1 - 15 mm	0 - 150 mm
Material	Stainless steel	
Hardness	Hv400 or more	


Taper Gauge Double

Features

- Thickness when the two blades are aligned together enables stable vertical insertion that keeps measurement reference side from slipping



Gap



Unstable and wobbly with one blade



Stable with two blades

- With graduations that can be easily read simply by aligning along one side of the gap
- Hole diameter measurement graduations already compensate for error in the sheet thickness, making tedious conversion unnecessary



Precise!

Use


- For measurement of inner diameter or dimension of gap
- For measuring length and depth

Specifications

Accuracy	Clearance: ±0.05 mm* Hole Diameter: ±0.05 mm
Measuring Range	Clearance: 1 - 15 mm Hole Diameter: φ2 - 15 mm
Material	Stainless steel
Hardness	Hv400 or more

*Precision is ±0.1 mm when the two blades are together.


Bolt and Nut Gauge



*Easily measures the length as well

Features

- Easily measure size of nut bolt just by putting on the gauge
- Measures different shapes of screws
- Inch/mm converting chart



Use


- For measuring size of bolt and nut

Specifications

Material	ABS resin
----------	-----------

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73773	Bolt and Nut Gauge	107×237×6	55	4 960910 737730	10	

Pitch Gauge



Features

- Finds pitch by aligning to screw thread

Use

- For pitch measurement of general screws


Inch	Indicates the number of threads per 1 inch on leaf	4 - 60
Metric	Indicates pitch in between two threads on leaf	0.25 - 2.5 mm

Specifications

	73794	73795
Material	Carbon tool steel	
Angle	55° (for whitworth screw thread)	60°
Leaf	26 leaves (Number of threads per 1 inch) 4, 4 1/2, 5, 6, 7, 8, 9 10, 11, 12, 13, 14, 16 18, 19, 20, 22, 24, 25 26, 28, 30, 32, 40, 48 60	28 leaves (mm) 0.25, 0.3, 0.35, 0.4 0.45, 0.5, 0.55, 0.6 0.65, 0.7, 0.75, 0.8 0.85, 0.9, 1.0, 1.1, 1.2 1.25, 1.3, 1.4, 1.5, 1.6 1.7, 1.75, 1.8, 1.9, 2.0 2.5

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73794	A-2 for Inch Screw Thread 26 Leaves	68×18×15	42	4 960910 737945	10	
73795	B-2 for Metric Screw Thread 28 Leaves	68×18×15	44	4 960910 737952		

Feeler Gauge



Features

- Variety of different length and leaves available

Use

- For clearance gap measurement

Specifications

	73776	73780	73781	73782	73796	73797
Material	Carbon tool steel					
Thickness Tolerance	Over 0.03 mm below 0.15 mm: ±0.005 mm Over 0.15 mm below 0.50 mm: ±0.012 mm Over 0.50 mm below 3.00 mm: ±0.020 mm					
Leaf Thickness (mm)	0.30 0.06 0.10	0.04 0.07 0.15	0.05 0.08 0.20	1.00 0.05 0.11 0.12 0.13 0.14 0.15 0.20 0.25 0.40 0.60 0.90	0.03 0.06 0.09 0.12 0.15 0.30 0.45 0.75	0.04 0.07 0.10 0.13 0.20 0.35 0.50 0.80

*Thickness tolerance is the tolerance for one leaf. In the case of use with multiple leaves, the tolerance is added together.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73776	A 75 mm 9 Leaves	81×13×5	20	4 960910 737761	10	
73780	B 100 mm 9 Leaves	109×13×5	27	4 960910 737808		
73781	C 150 mm 9 Leaves	156×13×5	40	4 960910 737815		
73782	D 65 mm 25 Leaves	70×14×15	63	4 960910 737822	5	
73796	E 100 mm 25 Leaves	105×13×17	95	4 960910 737969		
73797	F 150 mm 25 Leaves	153×13×17	140	4 960910 737976		

Digital Thickness Caliper



73746



Features

- Digital display for quick reading
- Easy-to-read 12 mm character height LCD
- ZERO set switch gives a reference point and makes comparison measurement
- Large handle makes easy holding
- Special case included

Use

- For measuring thin objects such as cloth or leather

Specifications

Measuring Range	0 - 10 mm
Graduation	0.01 mm
Indication Error	±0.02 mm
Maximum Insert Depth	30 mm
Measuring Force	1.1 N or less
Parallelism between Gauge Head and Anvil	±8 μm
Diameter of Gauge Head and Anvil	φ10 mm
Power Source	1x Silver oxide Battery SR44 (Battery included is for trial use only and may not last as long)
Auto Power Off	Approximately 5 min.
Material	Body: ABS resin Lever: Iron Spindle, Gauge Head, Anvil: Stainless steel

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73746	A 0.01 mm/10 mm with Handle	125×100×26	216	4 960910 737464	1	

Dial Gauge



73750



With lug
Hole diameter φ6.5 mm



Accessory: Flat lid

Features

- Convenient lug to install on magnetic stand

Use

- To measure flatness
- To measure parallelism
- To measure irregularity

Specifications

Graduation	0.01 mm
Measuring Range	0 - 10 mm
Outer Diameter	φ55 mm
Dial Reading	±0 - 50 - 100
Whole Measuring Range Indication Error	±18 μm
Retrace Error	5 μm
Adjacent Pitch Error	8 μm
Measuring Force	1.5 N or less
Material	Outer frame: ABS resin Graduation Plate, Stem: Aluminum Graduation Plate Cover: Acrylic resin Clamp, Gauge Head: Brass Limiter: ABS resin Spindle: Stainless steel

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73750	0.01 mm/10 mm	107×55×44	100	4 960910 737501	3	

Dial Indicator



73751



Holds onto magnet stand by installing stem (included)

φ2.0 mm

φ8 mm

φ6 mm

Accessory: Stem with dovetail × 2 Gauge head spanner

Features

- Two convenient stems are included

Use

- To measure flatness
- To measure parallelism
- To measure irregularity

Specifications


Graduation	0.01 mm
Measuring Range	0 - 0.8 mm
Outer Diameter	φ38.5 mm
Dial Reading	0 - 40 - 0
Wide Range Accuracy	13 μm
Retrace Error	3 μm
Adjacent Pitch Error	5 μm
Measuring Force	0.4 N or less
Material	Outer Frame: Aluminum Graduation Plate: Aluminum Graduation Plate Cover: Acrylic resin Stem: Brass, stainless steel Gauge Head: Stainless steel

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73751	0.01 mm/0.8 mm	77×39×25	44	4 960910 737518	3	

Magnetic Stand



73752



73753

Fine-adjust angle by turning the screw

Item Code	Description	Weight (g)	JAN Code	Packing Unit	Packaging
73752	A Standard	1,340	4 960910 737525	1	
73753	A-2 Fine adjustment	1,365	4 960910 737532		

Features

- Strong magnet to enable stable measurement

Use

- For holding Dial Gauge/Dial Indicator



Specifications

	73752	73753
Magnet Base	L58 × W50 × H55 mm	
Central Pillar	φ12 × 176 mm	
Supportive Pillar	φ10 × 165 mm φ10 × 150 mm	
Installation Hole	φ6.0/8.1 mm	
Adsorption Force	600 N (60 kgf) *	
Material	Body: Iron Lever, Screw: ABS resin	

*Please take extra care because absorption force varies greatly depending on thickness and material of object

Large Inspection Mirror



C-1

75796



75797



C-2


The knob easily fixes the position of the mirror

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75796	C-1 1.2 m Oval 80 x 120 mm	0.5 - 1.2	500	4 960910 757967	1	
75797	C-2 2.5 m Oval 120 x 150 mm	0.95 - 2.5	750	4 960910 757974		

Features

- Light and durable acrylic resin mirror
- Easy-to-hold elastomer resin grip
- Three-step telescopic function makes it easy to store

Use



For inspection under a car body



For inspection in ceiling



For inspection of machines




For inspection of sewer pipes

Specifications

Material	Body: Aluminum, iron, ABS resin, nylon resin, elastomer resin Mirror: Acrylic resin
----------	--

Inspection Mirror



Item Code	Description	Shaft Length (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75758	A-1 Circle 60 mm	530	53	4 960910 757585	10	
75759	A-2 Circle 36 mm	600	40	4 960910 757592		
75756	A-3 Oval 50 x 80 mm	530	56	4 960910 757561		
75757	A-4 Oval 25 x 50 mm	600	42	4 960910 757578		

Features

- Mirror angle can be easily adjusted
- Telescopic handle gives access to hard-to-see places

Use

- For inspection or observation of car engines, inside and behind machines, etc.



Specifications

Material	Shaft: Brass Mirror Frame: ABS resin Mirror: Glass
----------	--


Magnifying Mirror



Item Code	Description	Shaft Length (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75790	B-1 Circle 60 mm 2x	530	53	4 960910 757905	10	
75791	B-2 Circle 36 mm 2x	600	40	4 960910 757912		
75788	B-3 Oval 50 x 80 mm 2x	530	56	4 960910 757882		
75789	B-4 Oval 25 x 50 mm 2x	600	42	4 960910 757899		

Features

- Mirror angle can be easily adjusted
- Telescopic handle gives access to hard-to-see places



Use

- For inspection or observation of car engines, inside and behind machines, etc.

Specifications

Material	Shaft: Brass Mirror Frame: ABS resin Mirror: Glass
----------	--

Inspection Mirror with LED Light



Item Code	Description	Shaft Length (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74155	D-1 Circle 60 mm	530	70	4 960910 741553	10	
74156	D-2 Circle 36 mm	530	55	4 960910 741560		
74157	D-3 Oval 50 x 80 mm	530	73	4 960910 741577		
74158	D-4 Oval 25 x 50 mm	530	57	4 960910 741584		

Features

- Clear vision even in a dark and tight place
- High brightness LED light shines a light on inspection point by reflecting light in the mirror
- Compact for easy carrying
- Shaft can be extended in seven steps



Folded Approx.
160 mm
D-1



Use

- For inspection or observation of car engines, inside and behind machines, etc.

Specifications

Material	Shaft: Brass Mirror: Glass, ABS resin Light: ABS resin
Power Source	3x Alkaline batteries LR44 (included) (Batteries included are for trial use only and may not last as long)
Luminosity	30,000 mcd *Varies depending on usage situation

Inspection Scope **NEW**



Carry case



*Product is based on Japan domestic radio law (compatible with technical regulation conformity specification.) Cannot be used outside of Japan.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74172	A ϕ 5.8 Wireless 3.5 Inch LCD	200×105×215 (Excluding cable)	564	4 960910 741720	1	
74173	B ϕ 9 Wireless 3.5 Inch LCD	200×105×215 (Excluding cable)	663	4 960910 741737		

Inspection Scope Option **NEW**



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74175	Camera head ϕ 5.8 x 1 m	ϕ 19×1,000	92	4 960910 741751	1	
74176	Camera head ϕ 9 x 1 m	ϕ 19×1,000	191	4 960910 741768		
74178	Extension Cable 2 m	ϕ 19×2,060	550	4 960910 741782		
74179	Extension Cable 5 m	ϕ 19×5,060	1,360	4 960910 741799		

Features

- For inspection/checking in places that are narrow or difficult to see

Use

- Video can be sent to the monitor wirelessly for viewing close at hand



- Videos and still images can be saved to a MicroSD card (sold separately) and transferred to a computer, etc.



- Features a zoom function that can magnify at 5 levels, actual size, 1.5x, 2x, 2.5x, and 3x
- Cable can be bent freely and inserted into the inspection area regardless of how it is bent
- Features a high-brightness LED light with the ability to variably adjust illuminance using the switch at hand
- 74173 comes with tip tools that can be used for various purposes, such as attaching a hook or magnet to pick up fallen objects, or checking reverse sides with a side view mirror



Specifications

	74172	74173
Camera Head Diameter	5.8 mm	9 mm
Cable System	Inter-lock model	
Cable Diameter	4.8 mm	7.5 mm
Cable Length	1 m	
Lens Focal Distance	30 - 80 mm	80 - 150 mm
Lens Viewing Angle	40°	43°
Wireless Transmission Function	Transmission Frequency: 2468 MHz Bandwidth: 18 MHz Communication Range: Maximum of 10 m (Line-of-sight distance*1)	
Zoom Function	1x, 1.5x, 2x, 2.5x, 3x	
Record Function	Still image, movie	
Video Output Format	NTSC*2	
Recording Memory	MicroSD card up to 32 GB (sold separately)	
Illumination	High-brightness White LED (Light amount can be variably adjusted)	
Camera Resolution	640 X 480 pixel*3	
Monitor	3.5 inch (Color LCD), 320 X 240 pixel definition*4	
Interface	AV output (NTSC), USB output (Recorded video, still image playback)	
Dustproof/Waterproof	Camera head to cable: IP67*5 Main body: Not dustproof/waterproof	
Operating Temperature	0 - 40°C	
Operating Humidity	15 - 85% (No bedewing)	
Power Source (Main Unit)	4X AA Alkaline batteries (sold separately)	
LED Continuous Lighting Time	About 2 hours	
Power Source (Monitor)	DC rechargeable (time required for full charge: about 4 hours)	
Tip Tool	Unsupported	Hook, Magnet, Side view mirror
Material	Handle/Monitor: ABS resin, elastomer resin Camera Cable: Stainless steel, glass	

*1 This is the maximum distance for communication in an unobstructed environment where there is a straight line between the main unit and the LCD monitor. *2 An abbreviation for the video signal standard named after the National Television System Committee *3 Resolution density of the camera itself *4 Number of pixels on the display *5 Dustproof/Waterproof Performance Dustproof performance 6: Dust will not penetrate. Waterproof performance 7: Even if temporarily (within 30 minutes) submerged at a constant water depth (within 1 m), water will not enter inside.

Chuck Wrench




78582



78596



78587



Item Code	Description	Handle Length (mm)	Head Diameter (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78582	A 3 mm	60	6	17	4 960910 785823	10	
78596	A-2 3 mm	32	6	18	4 960910 785960		
78584	B 5 mm	65	4	36	4 960910 785847		
78587	C 6.5 mm	75	5.5	46	4 960910 785878		
78590	D 10 mm	90	6.5	62	4 960910 785908		
78593	E 13 mm	110	8	83	4 960910 785939		

Features

- Choose from a variety of types for each model

Use

- For opening and closing the chuck of an electric drill



Please securely tighten the drill chuck with the correct chuck wrench before using electric drill

Specifications



	78582	78596	78584	78587	78590	78593
Drill Chuck Size	3 mm for hobby use		0 - 3/16 inch 5 mm	0 - 1/4 inch 6.5 mm	0 - 3/8 inch 10 mm	0 - 1/2 inch 13 mm
Material	Iron					

Auto Punch




Features

- Easily marks a surface by pushing it down with one hand
- Accurately punches even on ceiling because no hammer is needed
- Head turns to adjust punching pressure
- Durable superhard chip on the tip



- Flat grip faces to prevent rolling over (77317/77318)



Use

- For marking steel metals, aluminum, or other materials that are not hardened

Specifications

Material	Body: Brass Tip: Superhard chip Grip: ABS resin
----------	---

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77317	M with Flat Grip to Prevent Rolling	130×30×24	80	4 960910 773172	10	
77318	L with Flat Grip to Prevent Rolling	155×35×28	150	4 960910 773189	5	
77259	M	133×30×30	80	4 960910 772595	10	
77258	L	160×35×35	181	4 960910 772588	5	

Deburring Tool



78665



78666

Features

- Compatible with three kinds of high-speed steel replacement blades for plastic, aluminum, brass, cast metal, and steel, etc.

Use

- For chamfering and deburring of metal parts

Specifications

Material	Body: Plastic Edge: High-speed steel
----------	---

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78665	with Replacement Blade for S-10/S-20/S-35	147×23×23	36		3	
78666	Replacement Blade 2pc-pack for S-10	48×12×3	2		10	

Suction Lifter

 Max
25
kg


74481

 Max
25
kg


74482

 Max
70
kg


74483

 Max
25
kg


74484

Features

- Convenient for transportation of items without handles

Use

- For transportation of refrigerators, furniture, and glass panels, etc.



74481



74482



74483



74484

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74481	Single A	123×123×104	472		6	
74482	Single B	213×156×74	780		4	
74483	Double A	390×115×70	984		4	
74484	Double B One-touch	244×100×125	735		4	

Specifications

	74481	74482	74483	74484
Adsorption Force*	25 kg		70 kg	25 kg
Material	Body: Aluminum Lever: Aluminum Adsorption Face: Rubber		Body: Aluminum Lever: Plastic Adsorption Face: Rubber	Body: Aluminum Lever: Iron Adsorption Face: Rubber
Adsorption Face Size	φ123 mm		φ115 mm	φ100 mm

*Indicated adsorption force is based on use for mirror surfaces.

Digital Counter



73310

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73310	Digital Counter	63×52×35	50		6	

Features

- Easy-to-hold
- Easy-to-read large numbers
- Measures from -9,999 to 99,999
- Switch to multiple functions by pushing a button



Count-down Button

Count-up Button

Use

- For counting the number of visitors, vehicles, bird-watching, etc.

Specifications


Measurement Range	-9,999 - 99,999
Material	Body: ABS resin, AS resin, silicone, polyacetal resin, stainless steel
Power Source	2x Alkaline batteries LR44 (included) (Batteries included are for trial use only and may not last as long)
Auto Power Off	30 seconds

*"FULL" sign will be displayed if it counts over 99,999.
 "-FULL" sign will be displayed if it counts below -9,999.

Counter



75078



75086



75090



75089

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75078	A Metallic Model with Stand	62×56×56	93		5	
75086	B Metallic Model	50×40×53	67			
75090	C Blue Plastic Model	50×41×54	34			
75089	C Yellow Plastic Model	50×41×54	34			

Features

- Counts numbers simply by pushing the button
- Model A is used screwed onto a mount

Use

- For counting the number of visitors, vehicles, bird-watching, etc.



Specifications

	75078	75086	75090	75089
Measurement Range	0 - 9,999			
Material	Body: Iron Others: Synthetic resin		Body: ABS resin Others: Synthetic resin	

16. Thermometers/ Hygrometers/ Hourglasses



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Thermo/Hygrometer



70494



70497



70498



72591



72605



72691



72669

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70494	Q-1 15 cm Blue	φ167×35	180	4 960910 704947	5	
70495	Q-1 15 cm Gray	φ167×35	180	4 960910 704954	5	
70496	Q-2 10 cm Blue	φ120×33	95	4 960910 704961	5	
70497	Q-2 10 cm Gray	φ120×33	95	4 960910 704978	5	
70498	Q-3 6.5 cm Blue	φ88×26	50	4 960910 704985	5	
70499	Q-3 6.5 cm Gray	φ88×26	50	4 960910 704992	5	
72591	F 15 cm	φ156×30	140	4 960910 725911	5	
72605	G 15 cm	φ156×30	140	4 960910 726055	5	
72691	U-1 10 cm	φ106×30	70	4 960910 726918	5	
72669	U-3 6.5 cm	φ71×21	30	4 960910 726697	5	

Features

- Measures both temperature and humidity for health management and energy saving
- Variety of sizes available from large easy-reading displays to small sizes for tight places

Use


- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

	70494	70495	70496	70497	70498	70499
Accuracy	Temperature: -20 - 40°C ±2°C Other values: ±4°C Humidity: 35 - 75% ±5% Other values: ±10%					
Measuring Range	Temperature: -30 - 50°C Humidity: 10 - 90%					
Each Graduation	Temperature: 2°C Humidity: 5%					
Material	Body, Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum					

	72591	72605	72691	72669
Accuracy	Temperature: -20 - 40°C ±2°C Other values: ±4°C Humidity: 35 - 75% ±5% Other values: ±10%			
Measuring Range	Temperature: -30 - 50°C Humidity: 10 - 100% Humidity: 0 - 100% Humidity: 10 - 90%			
Each Graduation	Temperature: 2°C Humidity: 5%			
Material	Body: Polystyrene resin, ABS resin Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum			

*It can be used as a wall-mounted unit by removing the stand.
(70494/70495/70496/70497/70498/70499)



JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Thermo/Hygrometer for Room Conditioning

Features

- Ideal for saving energy with displays of suggested temperature and comfortable humidity



Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

	70501	70506	70514
Accuracy	Temperature: -20 - 40°C ±2°C Other values: ±4°C		Temperature: -20 - 40°C ±2°C
	Humidity: 35 - 75% ±5% Other values: ±10%		±5%
Measuring Range	Temperature: -24 - 44°C		Temp. -20 - 40°C
Each Graduation	Humidity: 5 - 95%		Humidity: 10 - 90%
Material	Body: Polystyrene resin, ABS resin Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum		



70501



70506



70514

With hook hole



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
70501	F-2L 15 cm Blue	φ156×30	142	4 960910 705012	5	
70506	F-2M 10 cm Blue	φ106×30	70	4 960910 705067		
70514	F-2S 6.5 cm Blue	φ71×21	30	4 960910 705142		

Thermo/Hygrometer for Heatstroke Warning

Features

- Shows five levels of warning for heatstroke



Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

	70505	70507	70515
Accuracy	Temperature: -20 - 40°C ±2°C		
	Humidity: 35 - 75% ±5% Other values: ±10%		
Measuring Range	Temperature: -20 - 40°C		
Each Graduation	Humidity: 10 - 90%		
Material	Temperature: 2°C Humidity: 5%		
	Body: Polystyrene resin, ABS resin Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum		



70505



70507



70515

With hook hole



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
70505	F-3L II 15 cm White	φ156×30	150	4 960910 705050	5	
70507	F-3M 10 cm White	φ106×30	73	4 960910 705074		
70515	F-3S 6.5 cm White	φ71×21	33	4 960910 705159		

Thermo/Hygrometer for Environmental Safety

Features

- Shows various warnings for each temperature range, such as risk of mold or health warnings



Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

	70503	70508	70516
Accuracy	Temperature: -20 - 40°C ±2°C		
	Humidity: 35 - 75% ±5% Other values: ±10%		
Measuring Range	Temperature: -20 - 40°C		
Each Graduation	Humidity: 10 - 90%		
Material	Temperature: 2°C Humidity: 5%		
	Body: Polystyrene resin, ABS resin Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum		



70503



70508



70516

With hook hole



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
70503	F-4L 15 cm Blue	φ156×30	142	4 960910 705036	5	
70508	F-4M 10 cm Blue	φ106×30	70	4 960910 705081		
70516	F-4S 6.5 cm Blue	φ71×21	30	4 960910 705166		

Thermo/Hygrometer and Discomfort Index Meter



70480



70500

What is the discomfort index?

It is calculated with temperature and humidity to measure the degree of discomfort experienced by an individual. Keeping comfortable conditions can prevent heatstroke or flu.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70480	R-1 Green	φ167×35	193	4 960910 704800	5	
70500	R-2 Green	φ156×30	145	4 960910 705005		

Features

- Shows discomfort index to help health management at home

Use


- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

	70480	70500
Accuracy	Temp.: -20 - 40°C ±2°C Other values ±4°C	Temp.: -20 - 40°C ±2°C
	Humidity: 35 - 75% ±5% Discomfort Index: 60 - 80 ±2	Other values: ±10% Other values: ±4
Measuring Range	Temperature: -30 - 50°C	Temperature: -20 - 40°C
	Humidity: 10 - 90%	Discomfort Index: 45 - 95
Each Graduation	Temperature: 2°C	Humidity: 5%
	Discomfort Index: 2	
Material	Body: Polystyrene resin Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum	Body: Polystyrene resin, ABS resin Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum

Thermo/Hygrometer

Antibacterial agent compounded



70380



With stand on the back

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70380	P-2 12 cm White	120×120×30	100	4 960910 703803	5	

Features

- Measures both temperature and humidity and displays comfortable zones in colors for health management or energy saving

Use


- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

Accuracy	Temperature: -20 - 40°C ±2°C Humidity: 35 - 75% ±5% Other values: ±4°C Other values: ±10%
Measuring Range	Temperature: -28 - 48°C Humidity: 15 - 100%
Each Graduation	Temperature: 2°C Humidity: 5%
Material	Body: ABS resin (Antibacterial agent compounded) Scale Plate Cover: Polystyrene resin Pointer: Aluminum Scale Plate: Iron

Thermo/Hygrometer

70510



With hook hole

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70510	W-1 White	165×120×20	145	4 960910 705104	5	

Features

- Thin wall-mounted type


Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

Accuracy	Temperature: -20 - 40°C ±2°C Humidity: 35 - 75% ±5% Other values: ±4°C Other values: ±10%
Measuring Range	Temperature: -30 - 50°C Humidity: 0 - 100%
Each Graduation	Temperature: 2°C Humidity: 2%
Material	Body, Scale Plate Cover: Polystyrene resin Scale Plate: Iron Pointer: Aluminum

Thermo/Hygrometer



48927 48929 72615 48932 48975

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
48927	White and White	295×67×19	100	4 960910 489271	5	
48929	Black and White	295×67×19	100	4 960910 489295		
72615	Green	295×67×19	100	4 960910 726154		
48932	Blue	295×67×19	100	4 960910 489325		
48975	ECO White	295×67×19	100	4 960910 489752		

Features

- Measures both temperature and humidity to help health management or energy saving
- Choose from various colorful designs to match any rooms
- ECO White model also displays suggested air-conditioning temperature




Use

- For temperature and humidity control at home, in classroom, office, etc.

Specifications

Accuracy	Temperature: $\pm 2^{\circ}\text{C}$
	Humidity: 35 - 75% $\pm 5\%$ Other values: $\pm 10\%$
Measuring Range	Temperature: $-30 - 50^{\circ}\text{C}$
	Humidity: 0 - 100%
Each Graduation	Temperature: 2°C
	Humidity: 5%
Material	Body: Polystyrene resin

Thermometer



72689 72667 72675

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72689	S-1 10 cm	$\phi 106 \times 30$	70	4 960910 726895	5	
72667	S-3 6.5 cm	$\phi 71 \times 21$	30	4 960910 726673		
72675	S-5 3.5 cm	$\phi 36 \times 14$	5	4 960910 726758		

Features

- Lightweight, circular thermometer
- Easy-to-read graduations
- S-5 model comes with double-sided tape for installation

Use

- For temperature control in the home, classroom, or office, etc.

Specifications

	72689	72667	72675
Accuracy	$-20 - 40^{\circ}\text{C}$: $\pm 2^{\circ}\text{C}$ Other values: $\pm 4^{\circ}\text{C}$		
Measuring Range	$-30 - 50^{\circ}\text{C}$		
Each Graduation	2°C		
Material	Body: Polystyrene resin, ABS resin		Body: Polystyrene resin
	Scale Plate: Iron Pointer: Aluminum		Scale Plate: Iron Pointer: Aluminum

Hygrometer



72690 72668

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72690	T-1 10 cm	$\phi 106 \times 30$	70	4 960910 726901	5	
72668	T-3 6.5 cm	$\phi 71 \times 21$	30	4 960910 726680		

Features

- Lightweight, circular hygrometer
- Easy-to-read graduations


Use

- For humidity control in the home, classroom, or office, etc.

Specifications

Accuracy	35 - 75%: $\pm 5\%$ Other values: $\pm 10\%$
Measuring Range	0 - 100%
Each Graduation	2%
Material	Body: Polystyrene resin, ABS resin Scale Plate: Iron Pointer: Aluminum

Thermometer and Hygrometer Pair



72674

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72674	ST-4 4.5 cm	φ48×17	11	4 960910 726741	5	SP

Features

- Pair of compact thermometer and hygrometer
- Color indicates comfort zone
- Double-sided tape included for installation

Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

Accuracy	Temp.: -20 - 40°C ±2°C Other values ±4°C
	Humidity: 35 - 75% ±5% Other values ±10%
Measuring Range	Temperature: -30 - 70°C
	Humidity: 0 - 100%
Each Graduation	Temperature: 2°C
	Humidity: 2%
Material	Body: Polystyrene resin Scale Plate: Iron Pointer: Aluminum

Thermometer



Features

- V-1
 - Insert into food to measure temperature while cooking
 - Use the holder to measure the temperature of liquid
 - 75°C stands out in red for heat sterilization of O-157 strain
 - *Measurement Range: 0 - 100°C
 - Do not use to measure oil for deep-frying
 - Rust-resistant stainless steel
- V-2
 - Insert into the ground or pots to measure soil temperature
 - Different colors for each temperature range for easy reading
 - Rust-resistant stainless steel
- V-3
 - 90 cm-long thermo-sensitive probe makes it ideal for temperature control of compost in organic farming
 - Rust-resistant stainless steel
- V-4
 - Easy-to-read, large scale face (available in white and black)
 - Rust-resistant stainless steel
 - Wide measuring range enables use in many situations

Use

- V-1
 - As a cooking thermometer to measure the temperature of food, etc.
- V-2
 - For temperature control of raising seedlings and gardening, etc.
- V-3
 - For temperature control of compost
- V-4
 - For temperature control of asphalt and soil



For measuring temperature of asphalt For measuring temperature of soil

Specifications


	72960	72610	72611	73012 73013
Accuracy	±2°C			±5°C
Measuring Range	0 - 100°C	-20 - 60°C	-20 - 100°C	0 - 200°C
Each Graduation	2°C			5°C
Material	Body: Stainless steel			

Item Code	Description		Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72960	V-1 0 - 100°C φ3.5 x 13 cm		φ35×145	22		5	
72610	V-2 -20 - 60°C φ3.5 x 13 cm		φ35×140	15		10	
72611	V-3 -20 - 100°C φ6 x 90 cm		φ62×920	165		2	
73012	V-4 0 - 200°C White φ8 x 20 cm		φ83×215	111		1	
73013	V-4 0 - 200°C Black φ8 x 20 cm		φ83×215	111			

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) cm) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Thermometer



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72524	C	252×43×18	55		10	SP
72526	C-2	250×42×17	55		10	SP
72590	C-5	252×40×16	59		10	SP
48481	Wood M-023	270×50×10	90		5	SP
75919	Wood 45 cm	450×80×12	210		1	SP
75920	Wood 60 cm	600×85×12	380		1	SP
72571	Wood 90 cm	900×120×15	1,050		1	SP
72991	Aluminum 45 cm	465×80×20	320		1	SP
72992	Aluminum 60 cm	615×80×20	420		1	SP
72993	Aluminum 75 cm	765×80×20	520		1	SP

Features

- C/C-2
- Standard thermometer
- C-5
- Beautiful pine wood finish
- M-023
- Shows suggested air-conditioning temperatures
- Wood 45 - 90 cm/Aluminum 45 - 75 cm
- Large size and clear numbers make it easy to read even from a distance

With hook hole



Use

- For temperature control in the home, classroom, or office, etc.


Specifications

	72524	72526	72590
Accuracy	±1℃		
Measuring Range	-30 - 50℃		
Each Graduation	1℃		
Material	Body: Wood	Body: Polystyrene resin	Body: Wood

	48481	75919	75920	72571
Accuracy	±2℃	±1℃		
Measuring Range	-30 - 50℃	-40 - 50℃		
Each Graduation	2℃	1℃		
Material	Body: Wood			

	72991	72992	72993
Accuracy	-29 - 50℃: ±1℃ Other values: ±2℃		
Measuring Range	-40 - 50℃		
Each Graduation	1℃		
Material	Body: Aluminum		

Plastic Thermometer



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
48351	20 cm Blue	200×43×15	38		10	SP
48352	20 cm Yellow	200×43×15	38		10	SP
48356	25 cm Blue	250×40×15	48		10	SP
48357	25 cm Yellow	250×40×15	48		10	SP
48361	30 cm Blue	300×60×17	86		10	SP
48362	30 cm Yellow	300×60×17	86		10	SP

Features

- Easy-to-read graduations
- Colorful design adds an accent to a room.
- Available in various colors and sizes.

With hook hole




Use

- For temperature control in the home, classroom, or office, etc.

Specifications

Accuracy	±1°C
Measuring Range	-30 - 50°C
Each Graduation	1°C
Material	Body: Polystyrene resin


Thermometer "Petit Thermo Square"



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
48705	Vertical 12 cm White	120×28×7	13	4 960910 487055	10	SP
48706	Vertical 12 cm Yellow	120×28×7	13	4 960910 487062	10	SP
48707	Vertical 12 cm Blue	120×28×7	13	4 960910 487079	10	SP
48715	Vertical 13.5 cm with Magnet White	135×30×7	12	4 960910 487154	10	SP
48716	Vertical 13.5 cm with Magnet Yellow	135×30×7	12	4 960910 487161	10	SP
48717	Vertical 13.5 cm with Magnet Blue	135×30×7	12	4 960910 487178	10	SP
48785	Horizontal 13.5 cm with Magnet White	135×30×7	12	4 960910 487857	10	SP
48786	Horizontal 13.5 cm with Magnet Yellow	135×30×7	12	4 960910 487864	10	SP
48787	Horizontal 13.5 cm with Magnet Blue	135×30×7	12	4 960910 487871	10	SP
48795	Vertical 20 cm White	200×34×7	28	4 960910 487956	10	SP
48796	Vertical 20 cm Yellow	200×34×7	28	4 960910 487963	10	SP
48797	Vertical 20 cm Blue	200×34×7	28	4 960910 487970	10	SP

Features

- Small, affordable thermometer
- Choose from various colors and sizes
- Vertical 12 cm and 20 cm models come with a hook hole
- Double-sided tape on the back
- Vertical 13.5 cm and horizontal 13.5 cm have magnets




Use

- For temperature control in the home, classroom, or office, etc.

Specifications

	48705	48706	48707
Accuracy	±2°C		
Measuring Range	-30 - 50°C		
Each Graduation	2°C		
Material	Body: Polystyrene resin		
	48715	48716	48717
Accuracy	±2°C		
Measuring Range	-30 - 50°C		
Each Graduation	2°C		
Material	Body: Polystyrene resin		
	48785	48786	48787
Accuracy	±2°C		
Measuring Range	-30 - 50°C		
Each Graduation	2°C		
Material	Body: Polystyrene resin		
	48795	48796	48797
Accuracy	±1°C		
Measuring Range	-30 - 50°C		
Each Graduation	1°C		
Material	Body: Polystyrene resin		


Thermometer "Petit Thermo Twin" for Outside and Inside



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72957	Petit Thermo Twin	134×48×22	46	4 960910 729575	5	SP

Features

- Displays both inside and outside temperature



Use

- For temperature control inside and outside

Specifications

Accuracy	±2°C
Measuring Range	-30 - 50°C
Each Graduation	2°C
Material	Body: Polystyrene resin

*Not usable on double glazing and frosted glass

Digital Thermo/Hygrometer, Thermometer Smart



73115



73116



73117



73118

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73115	Digital Thermo/Hygrometer Smart A	103×102×18	135		5	
73116	Digital Thermometer Smart A	70×102×18	95		5	
73117	Digital Thermometer Smart B for Indoor and Outdoor with Waterproof Outside Sensor	70×102×18	115		5	
73118	Digital Thermometer Smart C Maximum and Minimum for Indoor and Outdoor with Waterproof Outside Sensor	103×102×18	150		5	

Features

- Bright, low-glare liquid crystal display with wide-viewing angle and clear font
- Folding stand and hole for hook to use on a wall or desk
- Flat surface model with stylish exterior. Ideal for temperature control in a space where appearance is important.
- External sensor is water-resistant for worry-free use even on a rainy day



Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

	73115	73116	73117	73118
Accuracy	Temp.: 0 - 40°C ±1°C Other values ±2°C Humidity: 40 - 80% ±10% Other values ±15%	0 - 40°C: ±1°C Other values: ±2°C		
Measuring Range	Temperature: -5 - 49°C Humidity: 30 - 95%	-5 - 50°C	Internal sensor: -5 - 50°C External sensor: -49 - 70°C	Internal sensor: -5 - 50°C External sensor: -50 - 70°C
Minimum Display	Temperature: 0.1°C Humidity: 1%	0.1°C		
Measuring Interval	20 seconds	6 seconds	10 seconds	
Power Source	1x AAA Alkaline battery (Battery included is for trial use only and may not last as long)			
Waterproof	—		External sensor: IPX7	
Material	Body: ABS resin		Body: ABS resin External Sensor: Stainless steel vinyl chloride resin	
Cord Length	—		3 m	

*Waterproof: Protected from immersion between 15 centimeters and 1 meter in depth

Digital Thermo/Hygrometer Home A NEW



73030/73044



73048



73049

With stand



With hook hole on the back



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73030	A Maximum and Minimum White	80×70×20	65		10	
73044	White with Clear Package	80×70×20	65		10	
73048	Blue with Clear Package	80×70×20	65		10	
73049	Green with Clear Package	80×70×20	65		10	

Features

- Bright, low-glare liquid crystal display with wide-viewing angle and clear font
- Display can switch between maximum temperature/humidity and minimum temperature/humidity
- Can be used in a wide range of locations thanks to its compact and simple design that suits any interior
- Can be propped up with its folding stand, or hung on a wall with its hook hole



On the table



On the wall



Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

Accuracy	Temp.: 0 - 40°C: ±1°C Other Values: ±2.5°C Humidity: 40 - 80%: ±10% Other Values: ±15%
Measuring Range	Temp.: -5 - 49°C Humidity: 30 - 95%
Minimum Display	Temp.: 0.1°C Humidity: 1%
Measuring Interval	10 seconds
Material	Body: ABS resin
Power Source	1x AAA Alkaline battery (Battery included is for trial use only and may not last as long)

Digital Thermo/Hygrometer



72989



72985

What is discomfort index?
It is calculated with temperature and humidity to measure the degree of discomfort experienced by an individual. Keeping conditions comfortable can prevent heatstroke or flu.



Based on the discomfort index, you can easily see if the current temperature and humidity are in a comfortable zone



73054



73055



73056



73057

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72989	B Maximum and Minimum with Solar Panel	155×112×23	185	4 960910 729896	5	SP
72985	C with Discomfort Index Meter	108×102×20	137	4 960910 729858	5	SP
73054	D-1 Blue	138×113×24	175	4 960910 730540	5	SP
73055	D-1 Orange	138×113×24	175	4 960910 730557	5	SP
73056	D-2 Blue	138×113×24	175	4 960910 730564	5	SP
73057	D-2 Orange	138×113×24	175	4 960910 730571	5	SP

Features

- Displays both temperature and humidity in a room
- Folding stand and hole for hook to use on a wall or desk
- B
- Displays temperature and humidity with a built-in sensor
- Records maximum and minimum temperatures and humidity for a set period of time by pushing "MAX/MIN" button. "RESET" button will reset the record.
- Solar panel reduces battery use
- C
- Displays in five levels
- D-1/D-2
- Alarm can be set for certain temperature or humidity
- Clear, easy-to-read heatstroke warning level icon
- Measures the highest/lowest temperature and humidity (73056/73057)

Use

- For temperature and humidity control in the home, classroom, or office, etc.

Specifications

	72989	72985
Accuracy	Temperature: 0 - 40°C ±1°C Other values ±2°C	Temperature: 0 - 40°C ±1°C Other values ±2°C
Measuring Range	Humidity: 30 - 95% ±10% *The others are just for reference	Humidity: 30 - 95%
Power Source	Solar Panel/1x Lithium battery CR2032 *Solar panel - above 150 lux *Battery - below 150 lux	1x AAA Alkaline battery
Material	Body: ABS resin	
	73054	73055
Accuracy	Temperature: 0 - 40°C ±1°C Humidity: 30 - 80% ±5% Other values: ±10%	Temperature: 0 - 40°C ±1°C Humidity: 30 - 80% ±5% Other values: ±10%
Measuring Range	Temperature: -5 - 50°C Humidity: 25 - 95%	Temperature: -5 - 50°C Humidity: 25 - 95%
Measuring Interval	10 seconds	10 seconds
Alarm Sound Interval	1 second	1 second
Alarm Volume	Approx. 75 dB (10 cm apart)	Approx. 75 dB (10 cm apart)
Heatstroke Levels	5 Level Icons Attention/Caution/Severe Caution/Danger, etc.	5 Level Icons Attention/Caution/Severe Caution/Danger, etc.
Power Source	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)
Material	Body: ABS resin	

Digital Thermometer




72947



73043



Folding stand and hole for hook to use on a desk or wall



Maximum temp. indicator
Current temp. indicator
Minimum temp. indicator

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72947	E for Indoor & Outdoor	74×102×20	91	4 960910 729476	5	SP
73043	D-10 Waterproof	217×64×19	108	4 960910 730434	5	SP

Features

- E
- Easy-to-read digital display with large display height (30 mm) is simple and easy to use
- Display switches between indoor and outdoor temperature
- D-10
- Simultaneously displays digital numbers and temperature bars.
- Temperature bars can be used to see current temperature/maximum temperature/minimum temperature at a glance.
- Water-resistant for worry-free use even if it gets slightly wet at warehouses or greenhouses

Use

- For temperature control in the home, classroom, or office, etc.

Specifications

	72947	73043
Accuracy	0 - 40°C: ±1°C Other values: ±2.5°C	0 - 40°C: ±1°C Other values: ±2°C
Measuring Range	Inside Sensor: -5°C - 50°C Outside Sensor: -50°C - 70°C	-10 - 50°C
Minimum Display	0.1°C	Numbers: 0.1°C Single Bar Graduation: 1°C
Measurement Interval	10 sec	10 sec*1
Cord Length	About 3 m	—
Material	Body: ABS resin	Body: ABS resin LCD: Glass
Power Source	1x AAA Alkaline battery (Battery included is for trial use only and may not last as long)	
Waterproof	—	IPX4*2

*1 Numbers and bars are updated simultaneously.

*2 Waterproof: Protected from water spray from any direction

Waterproof Digital Thermometer



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73045	G-1 Maximum and Minimum Remote-reading	129x117x24.5	215	4 960910 730458	5	
73046	G-2 Remote-reading for 2 points	129x117x24.5	245	4 960910 730465	5	

Features

- Waterproof
- Insert into the ground to measure soil temperature (Main unit does not contain temperature sensor)
- User-friendly digital thermometer with a large display
- G-1
 - Displays maximum, minimum, and current temperature together
- G-2
 - Two temperature sensors enable simultaneous measurement at two separate points

Use

- For temperature control in agricultural work or at home

Specifications

	73045	73046
Accuracy	0 - 40°C: ±1°C	Other temperature: ±2°C
Measuring Range	-50 - 90°C	
Minimum Display	0.1°C	
Operating Temperature	Main Unit: -5 - 50°C, Temperature Sensor: -50 - 90°C	
Measurement Interval	10 sec	
Material	Main Unit: ABS resin, acrylic resin Temperature Sensor: Stainless, vinyl chloride resin	
Power Source	1x AAA Alkaline battery (Battery included is for trial use only and may not last as long)	
Waterproof	Main Unit: IPX4*1 Temperature Sensor: IPX7*2	
Size	Temperature Sensor: ø5 x 50 mm Cord Length: 3 m	
Number of Cord	1	2

- *1 Waterproof: Protected from water spray from any direction
 *2 Waterproof: Protected from immersion between 15 centimeters and 1 meter in depth

Waterproof Digital Thermometer with Remote Probe



Probes for H-2 sold separately



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73080	H-1	103x66x25	105	4 960910 730809	5	
73081	H-2	172x77x46	360	4 960910 730816	1	
73087	Remote Probe Thin Model ø2.0 x 185 mm for Digital Thermometer H-2	ø2.0x185	80	4 960910 730878	1	
73088	Remote Probe Standard Model ø3.5 x 110 mm for Digital Thermometer H-2	ø3.5x110	80	4 960910 730885		
73089	Remote Probe Long and Thick Model ø5.0 x 275 mm for Digital Thermometer H-2	ø5.0x275	92	4 960910 730892		
73090	Remote Probe Surface Model ø3.5 x 110 mm for H-2	ø3.5x110	83	4 960910 730908		

Features

- IPX7 waterproof (*2)
- Enables user to read temperature remotely
- Includes hold function
- H-1
 - HI/LOW alarm beeps at set temperature
 - Probe sensor to measure internal temperature
 - Includes clip and stand for use in various settings
 - Includes cap to protect tip of probe
- H-2
 - Able to display maximum and minimum temperature during measurement
 - Replacement probes are available for various purposes
 - HI/LOW alarm beeps at set temperature
 - Memory records previous 10 measured values
 - Backlight function

Use

- For various uses such as cooking, facility management, or experiments, etc.

Specifications

	73080	73081
Accuracy	-20 - 150°C: ±1°C -30 - -21°C: ±2°C*1 151 - 250°C: ±1°C	±1°C
Measuring Range	-30 - 250°C *1	
Minimum Display	0.1°C	-19.9 - 199.9°C 0.1°C Other temperature 1°C
Operating Temperature	Temperature: 0 - 50°C Humidity: Less than 80% (no bedewing)	
Measurement Interval	1 sec	
Material	Main Unit, Cap: ABS resin Probe: Stainless steel	Main Unit, Cap: ABS resin Protecting Cover: Vinyl chloride resin Probe: Stainless steel
Auto Power Off	1 hour after operation stops	
Power Source	1x AAA Alkaline battery (Battery included is for trial use only and may not last as long)	2x AAA Alkaline batteries
Waterproof	IPX7 *2	
Size	Probe: ø3.5 x 100 mm Cord Length: 1 m	Probe: ø3.5 x 110 mm Cord Length: 1.4 m

- *1 -50 - -31°C and 251 - 300°C can be indicated but the accuracy is not guaranteed.
 *2 Waterproof: Protected from immersion between 15 centimeters and 1 meter in depth

Wireless Thermometer A



73441



Transmission
improved by utilizing
an external antenna

Max 5
Remote Sensors
(sold separately)
can communicate
with Base Unit

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73441	Maximum and Minimum External Antenna Type with Remote Twin Probe	175×85×28 (Base Unit)	180 (Base unit)	4 960910 734418	5	
73442	Additional Remote Sensor External Antenna Type	155×86×35	220	4 960910 734425		

*Item Code 73441 is a base unit and remote sensor set. Item Code 73442 is only a remote sensor.



73241



Max 5
Remote Sensors
(sold separately)
can communicate
with Base Unit

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73241	Maximum and Minimum Waterproof with Remote Twin Probe	125×68×28 (Base unit)	180 (Base unit)	4 960910 732414	5	
73242	Additional Remote Sensor	110×70×35	220	4 960910 732421		

Item code 73241 is base unit and additional remote sensor set
Item code 73242 is only the additional remote sensor

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Features

- Base unit can receive and check the temperature of the remote sensor that is in a remote location
- High-sensitivity type (73441/73442) with improved communication sensitivity thanks to external antenna
- Waterproof (73441/73242)
- Required operation is easy with few buttons
- Both base unit and remote sensor can measure temperature
- Individual alarms for each remote sensor can be set on the base unit
- With folding stand on the back of base unit to use on a desk

Use

- Measure temperature from a remote location

Specifications

73441/73442

	Base Unit	Remote Sensor
Accuracy	0 - 50°C: ±1°C Other temperature: ±2°C	
Measuring Range	-5 - 50°C	-40 - 90°C
Minimum Display		0.1°C
Operating Temperature	-5 - 50°C	
Measuring Interval		1 min
Material	Main Unit: ABS resin Display Cover: Polycarbonate resin Display: Glass	Main Unit: ABS resin Display Cover: Polycarbonate resin Display: Glass Temperature Sensor: Stainless steel, vinyl chloride resin
Power Source	4x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)	3x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)
Battery Life	About 6 months*1	About 6 months
Waterproof	—	Main Unit: — Temperature Sensor: IPX7*2
Type of Radio Equipment	—	Specified low-power equipment
Radio Wave Frequency	—	313.625 MHz
Communication Distance	—	Up to 150 m (line-of-sight distance)*3
Transmission Interval	—	4 min
Size	—	Main Unit: φ 5 x 50 mm Cord Length: 3 m

*1 Battery life can be reduced due to the sounding of the buzzer in the alarm function.

*2 IPX7 Waterproof: Protected from immersion between 15 centimeters and 1 meter in depth

*3 The line-of-sight distance is the maximum distance of transmission in an unobstructed environment on a straight line connecting the base unit and a remote sensor. In some cases, the distance of transmission may decline considerably due to obstructions between the base unit and the remote sensor or other structures that inhibit the radio waves.

73241/73242

	Base Unit	Remote Sensor
Accuracy	0 - 50°C: ±1°C Other temperature: ±2°C	
Measuring Range	-5 - 50°C	-40 - 90°C
Minimum Display		0.1°C
Operating Temperature	-5 - 50°C	
Measurement Interval		1 min
Material	Main Unit: ABS resin Display Cover: Polycarbonate resin Display: Glass	Main Unit: ABS resin Display Cover: Polycarbonate resin Display: Glass Temperature Sensor: Stainless steel, vinyl chloride resin
Power Source	4x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)	3x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)
Battery Life	About 6 months*1	About 6 months
Waterproof*2	IPX4*3	Main Unit: IPX4*3 Temperature Sensor: IPX7*4
Type of Radio Equipment	—	Specified low-power equipment
Radio Wave Frequency	—	313.625 MHz
Communication Distance	—	Up to 150 m (line-of-sight distance)*5
Transmission Interval	—	4 min
Size	—	Main Unit: φ 5 x 50 mm Cord Length: 3 m

*1 Battery life can be reduced due to the sounding of the buzzer in the alarm function.

*2 Please place a cap on the jack of the temperature sensor when probe is not in use to maintain the water-resistance feature of the additional remote sensor

*3 IPX4 Waterproof: Protected from water spray from any direction

*4 IPX7 Waterproof: Protected from immersion between 15 centimeters and 1 meter in depth

*5 Line-of-sight distance is the maximum distance of transmission in an unobstructed environment on a straight line connecting the base unit and a remote sensor. In some cases, the distance of transmission may decline considerably due to obstructions between the base unit and the remote sensor or other structures that inhibit the radio waves.

*Product is based on Japan domestic radio law (compatible with technical regulation conformity specification). Cannot be used outside of Japan.

Digital Thermometer for Refrigerator

73042



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73042	A Maximum and Minimum Remote-reading	65×65×19	75	4 960910 730427	10	

Features

- Can switch between display of temperature inside and outside the refrigerator
- Displays maximum, minimum, and current temperature together
- Waterproof
- Stand magnet and hook, making it possible to install in a variety of places

Use

- For temperature measuring inside and outside refrigerator

Specifications

Accuracy	Outside Refrigerator (OUT): ±1°C for 0 - 40°C, ±2°C for the other temperature Inside Refrigerator (IN): ±1°C for -10 - 40°C, ±2°C for the other temperature
Measuring Range	Outside Refrigerator (OUT): -5 - 50°C Inside Refrigerator (IN): -50 - 70°C
Minimum Display	IN/OUT: 1°C MAX/MIN: 1°C
Cord Length	3 m
Material	Body: ABS resin, polycarbonate
Power Source	1x Alkaline battery LR44 (Battery included is for trial use only and may not last as long)
Waterproof	IPX4*1 (for both main unit and sensor)

*1 IPX4 Waterproof: Protected from water spray from any direction

Thermometer for Refrigerator

Antibacterial agent compounded



72532

Antibacterial agent compounded



72703

72692



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72532	A with Magnet	135×24×7	20	4 960910 725324	10	
72703	A-3 5 cm	φ50×20	17	4 960910 727038	5	
72692	A-4 Remote-reading with Magnet	144×41×26	70	4 960910 726925	5	

Features

- A
- Magnet and double-sided mount tape on the back
- A-3
- Measure by installing aluminum base and setting up thermometer on it. Two aluminum bases are included to position two different places such as refrigerator and freezer. Optimum range indicator sticker is included.
- A-4
- Sensor inside refrigerator measures temperature which is read on unit attached to the outside of the refrigerator (cord length: 70 cm, sensor part: 5 cm)

Use

- For measuring temperature inside of refrigerator

Specifications

	72532	72703	72692
Accuracy	±2°C		
Measuring Range	-30 - 50°C	-34 - 50°C	-40 - 50°C
Each Graduation	1°C	2°C	
Material	Body: Polystyrene resin (Antibacterial agent compounded) Scale Plate Cover: Polystyrene resin	Body: ABS resin (Antibacterial agent compounded) Scale Plate Cover: Polystyrene resin	Body: ABS resin Scale Plate Cover: Aluminum
Accessories	Double-sided tape	2x Aluminum bases Optimum range indicator seal	Holder

Digital Thermometer for Refrigerator T

72980



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72980	Round-shape	φ50×20	38	4 960910 729803	10	

Features

- Magnet on the back
- Store excess cord around unit
- Position extra long cord with suction cups

Use

- For measuring temperature inside of refrigerator

Specifications

Accuracy	-10 - 30°C: ±1°C Other values: ±2.5°C
Measuring Range	-30 - 50°C
Cord Length	1.2 m
Material	Body: ABS resin
Power Source	1x Alkaline battery LR1130 (included) (Battery included is for trial use only and may not last as long)

Digital Thermometer for Cooking

72978



72979



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72978	T-Pink	213×25×15	21	4 960910 729780	5	
72979	T-Green	213×25×25	21	4 960910 729797		

Features

- Measures temperature with ON/OFF switch operation
- Long probe helps safe measurement
- Drip-proof design

Use

- For measuring temperature of food or oil for deep frying

Specifications

Accuracy	0 - 100°C: ±1°C Other values: ±2°C
Measuring Range	-30 - 250°C
Minimum Measurement	0.1°C
Display	4 digits character height 11 mm
Material	Display, Cap: ABS resin Thermometer: Stainless steel
Power Source	1x Alkaline battery LR44 (included) (Battery included is for trial use only and may not last as long)
Auto Power Off	Approximately 30 minutes after turning on power
Accessories	Cap

Thermometer for Frying Oil



72967

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72967	Chopstick Model	φ26×350	50	4 960910 729674	10	SP

Features

- Specifically designed to measure oil for deep-frying. The chopstick shape allows temperature measurement while using as cooking chopsticks.
- Lightweight and non-slip aluminum, easy to clean

Use

- For measuring oil temperature when cooking fried foods

Specifications

Accuracy	±5°C
Measuring Range	100 - 200°C
Each Graduation	5°C
Material	Body: ABS resin, aluminum

Digital Thermometer for Bath



73098

Turns on with a simple bump



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73098	B	95×75×30	55	4 960910 730984	5	SP

Features

- Cute thermometer that make bath time fun
- Ideal for temperature control of a baby bath with warning display function that notifies of high/low temperature

Use

- For health management and baby bath temperature control

Specifications

Accuracy	25 - 45°C: ±1°C Other values: ±2°C
Measuring Range	0 - 50°C
Minimum Display	1°C
Measurement Interval	5 sec
Power Source	1x Lithium battery CR2032 (Battery included is for trial use only and may not last as long)
Auto Power Off	Approximately 1 hour after turning on power
Material	Body: Vinyl chloride resin, ABS resin Temperature Sensor: Stainless steel

Thermometer for Bath



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72648	B Blue	160×63×23	48	4 960910 726482	10	
72760	B Pink	160×63×23	48	4 960910 727601		
72651	B-3	φ25×215	48	4 960910 726512		
72725	B-8	125×87×23	45	4 960910 727250		
73051	B-9 Green and White	94×78×28	40	4 960910 730519	5	SP
73052	B-9 White and Pink	94×78×28	40	4 960910 730526		
73095	B-10 Pink	96×91×26	48	4 960910 730953		
73096	B-10 Purple	96×91×26	48	4 960910 730960		
73097	B-10 White	96×91×26	48	4 960910 730977		

Features

- Cute thermometers that make bath time fun
- Antibacterial agent compounded body keeps it clean (except for 72651)
- B-10 model has a receptacle for essential oils so the aroma can be enjoyed at bath time

*Essential oils not included



Use

- Temperature control for baby's bath
- For heat shock prevention



Specifications

	72648	72760	72651
Accuracy	±2℃		±1℃
Measuring Range	20 - 60℃		-5 - 55℃
Each Graduation	2℃		1℃
Material	Body: Polystyrene resin (Antibacterial agent compounded)		Body: Polystyrene resin Weight: Lead


	72725	73051	73052
Accuracy	±2℃		
Measuring Range	20 - 50℃	10 - 50℃	
Each Graduation	2℃		
Material	Body: Polystyrene resin (Antibacterial agent compounded)		

	73095	73096	73097
Accuracy	±2℃		
Measuring Range	10 - 50℃		
Each Graduation	2℃		
Material	Body: Polypropylene resin (Antibacterial agent compounded)		

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric) / (Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku) / (Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Maximum and Minimum Thermometer



72709



72715

*Mercury products will be discontinued at the end of 2020.

Features


- Measures highest and lowest temperatures and current temperature at the same time

Use

- For temperature control in various situations

Specifications


	72709	72715
Accuracy	±2°C	
Measuring Range	-40 - 50°C	
Each Graduation	1°C	2°C
Material	Body: ABS resin Thermometric Material: Mercury, creosote, alcohol	Body: Polystyrene resin



How to use

- ① Pull down the index to the mercury column by pushing the reset button.
- ② Index will be pushed up and stopped by the change in temperature.

The mercury column may split during shipping. This condition will not allow accurate measuring. Simple steps will easily restore.



How to fix


1. Turn it upside down and push the reset button. Separate the mercury column and the index as far as possible.
2. Turn the unit back and knock it lightly on a rubber plate or shake it down multiple times.

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72709	D-7	220×65×22	110	4 960910 727090	5	
72715	D-9	φ106×43	80	4 960910 727151	5	

Psychrometer



72706



How to use

- ① Move the measuring plate and match the arrow to the 16°C indication on WET side.
- ② Read off the value on the arrow which is pointed out from the 26°C indication on DRY side.

WET: 16°C
 DRY: 26°C → 38%

Features

- Two thermometers are combined to measure humidity by finding difference in temperature between the wet bulb and the dry bulb
- Special lens makes the humidity table easy to read

Use

- For humidity control at home, in classroom, and office (also shows room temperature)

Specifications


Accuracy	Temperature: ±1°C Humidity: ±10%
Measuring Range	Temperature: -10 - 50°C Humidity: 10 - 94%
Each Graduation	Temperature: 1°C Humidity: -
Material	Body: Polystyrene resin Movable Plate, Water Tank: AS resin

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72706	E-2	285×84×26	100	4 960910 727069	5	

Thermometer for Aquarium



72583



Features

- High, low, and moderate temperatures are color coded for easy reading
- Suction cap and the lead weight stabilize the thermometer so it can be read from outside the tank

Use

- For temperature control in a fish tank

Specifications

Accuracy	±1°C
Measuring Range	0 - 40°C
Each Graduation	1°C
Material	Body: Glass Weight: Lead

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72583	L	φ13×150	18	4 960910 725836	10	


Infrared Thermometer




73038



73009




With stand
Clock function
*Displays the room temperature during the clock mode



D (Distance) : S (Spot) = 1:1

Example: 10 cm distance to the object being measured → 10 cm spot
*Measuring range minimum diameter: 7 mm





D (Distance) : S (Spot) = 1:1

Example: 10 cm distance to the object being measured → 10 cm spot
*Measuring range minimum diameter: 8 mm



73017





D (Distance) : S (Spot) = 2.5:1

Example: 5 cm distance to the object being measured → 2 cm spot
1 m distance to the object being measured → 40 cm spot
*Measuring range minimum diameter: 10 mm



73010



D (Distance) : S (Spot) = 12:1

Example: 36 cm distance to the object being measured → 3 cm spot
6 m distance to the object being measured → 50 cm spot
*Measuring range minimum diameter: 20 mm

Item Code	Description		Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73038	F	 	91×36×15	31	 4 960910 730380	5	
73009	A Emissivity Adjustable Model with Clock Function	 	68×37×18		 4 960910 730090		
73017	D Emissivity Adjustable Model with Probe	 	165×20×46	92	 4 960910 730175	2	
73010	B with Laser Pointer	 	185×46×143	240	 4 960910 730106		

Features

- Non-contact operation makes it safe and sanitary
- F
- Portable, compact size
- Measure quickly with simple design

■ A

- Infrared thermometer to measure temperature without touching
- Portable, ultra-compact size
- Continuous measuring mode enables temperature to be displayed in a series
- Min/Max measuring mode displays the lowest and highest temperature while the key is pressed
- Adjustable emissivity

■ D

- Two Measuring Methods: Non-contact (infrared), and contact (probe)

- Infrared

Able to safely measure a high-temperature object such as an engine or motor
*Adjustable emissivity according to the object to be measured



- Probe

Check cooked meat with the probe to see if the temperature reaches the point that kills E. coli



- IP54 dust and water proof

5 Dustproof: Protected from limited dust ingress
4 Waterproof: Protected from water spray from any direction

■ B

- Laser helps to find the measuring point at a glance

* Center of the measuring range diameter is approximately 2 cm from the laser point.

- Backlight function



Use

- For various temperature measurements

Specifications

	73038	73009
Accuracy	0°C or more: ±2.5% or ±2.5°C (higher value) -33 - 0°C: ±1-2.5°C+(displayed value×0.05)°C	±2% or ±2°C (higher value)
Measuring Range	-33 - 199°C	-55 - 220°C
Resolution	-9.9 - 199°C: 0.5°C Other values: 1°C	-9.9 - 199°C: 0.1°C Other values: 1°C
Measuring Interval	1 sec	
Measurement Wavelength	8 - 14 μm	
Operating Temperature	0 - 50°C	
Emissivity	0.95 (fixed)	Adjustable 0.05 - 1 (default as 0.95)
Auto Power Off	15 seconds after stopped operation	
Battery Life	40 hours (continuous use)	
Power Source	1x Lithium battery CR2032 (Batteries included is for trial use only and may not last as long)	
Material	Body: ABS resin	

	73017	73010
Accuracy	±2% or ±2°C (higher value) Probe 65°C up: ±1% -5 - 65°C: ±0.5°C -5°C or less: ±1°C	0 - 500°C: ±2% or ±2°C (higher value) -60 - 0°C: ±1-2°C+(displayed value×0.05)°C
Measuring Range	-33 - 220°C	-60 - 500°C
Resolution	-9.9 - 199.9°C: 0.1°C Other values: 1°C	
Measuring Interval	1 sec	
Measurement Wavelength	8 - 14 μm	
Operating Temperature	0 - 50°C	
Emissivity	Adjustable 0.1 - 1 (default as 0.95)	0.95 (fixed)
Auto Power Off	15 seconds after stopped operation	
Battery Life	40 hours (continuous use)	14 hours (continuous use)
Power Source	1x Lithium battery CR2450	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)
Laser Wavelength	—	635 - 660 nm
Output	—	1 mW or less (JIS Class2)
Dust/Waterproof	IP54	—
Material	Body: ABS resin	


Infrared Thermometer



73036




73014



D (Distance) : S (Spot) = 12:1

Example: 24 cm distance to the object being measured → 2 cm spot
6 m distance to the object being measured → 50 cm spot
*Measuring range minimum diameter: 20 mm



D (Distance) : S (Spot) = 16:1


Example: 48 cm distance to the object being measured → 3 cm spot
8 m distance to the object being measured → 50 cm spot
*Measuring range minimum diameter: 20 mm



73063




73100



D (Distance) : S (Spot) = 30:1

Example: 90 cm distance to the object being measured → 3 cm spot
15 cm distance to the object being measured → 50 cm spot
*Measuring range minimum diameter: 20 mm



D (Distance) : S (Spot) = 75:1

Example: 2 m 25 cm distance to the object being measured → 3 cm spot
7 m 50 cm distance to the object being measured → 10 cm spot
*Measuring range minimum diameter: 25 mm

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73036	E Emissivity Adjustable Model with Dual Laser Pointer	144×43×117	180	4 960910 730366		
73014	C Emissivity Adjustable Model	185×46×143	245	4 960910 730144	2	SP
73063	G Shock-resistant Emissivity Adjustable Model with Dual Laser Pointer	172×46×119	252	4 960910 730632		
73100	H Emissivity Adjustable Model with Dual Laser Pointer for High Temperature	204×58×179	370	4 960910 731004	1	B

Features

- Non-contact operation makes it safe and sanitary
- Adjustable emissivity according to the object to be measured
- Can show temperature simultaneously with maximum temperature, minimum temperature, difference between max/min temperature, or average temperature
- HI/LOW alarm function beeps and displays a notification when a set temperature is reached
- Backlight function

E

- IP54 dust and water proof

5 Dustproof: Penetration by a little dust will not disturb normal operation

4 Waterproof: Drops of water from any direction do not affect normal operation

C

- Laser helps to find the measuring point at a glance
- *Center of the measuring range diameter is approximately 2 cm from the laser point.

G

- Shock-resistant model
- Color bars indicating temperature change (Max/Min temperature mode)

H

- Model for high temperature measurements. Measurement range is -35 - 1,500°C to give the widest-possible range of temperature measurements.
- With memory function that records a maximum of 24 readings
- High distance coefficient of D:S=75:1 enables measurement of a narrow range even from a distant position
- Comes with convenient protector case for storage and portability

E/G/H

- Dual-laser points show both sides of the measuring range diameter

G/H

- Tripod socket screw for fixed point measurement

Use

- For various temperature measurements


Specifications

	73036	73014
Accuracy	0 - 550°C: ±2% or 2°C (higher value) -60 - 0°C: ±1 - 2°C + (displayed value × 0.05)°C	0 - 625°C: ±2% or 2°C (higher value) -60 - 0°C: ±1 - 2°C + (displayed value × 0.05)°C
Measuring Range	-60 - 550°C	-60 - 625°C
Resolution	-9.9 - 199°C: 0.1°C Other values: 1°C	
Measuring Interval	1 sec	
Measurement Wavelength	8 - 14 μm	
Operating Temperature	0 - 50°C	
Emissivity	Adjustable 0.1 - 1 (default as 0.95)	
Auto Power Off	60 seconds after stopped operation	
Battery Life	14 hours (continuous use)*1	
Power Source	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)	
Laser Wavelength	635 - 660 nm	
Output	1 mW or less (JIS Class2)	
Dust/Waterproof	IP54	—
Material	Body: ABS resin, elastomer resin	Body: ABS resin

	73063	73100
Accuracy	0 - 760°C: ±2% or ±2°C (higher value) -60 - 0°C: ±1 - 2°C + (displayed value × 0.05)°C	0 - 1,500°C: ±2% or ±2°C (higher value) -35 - 0°C: ±1 - 2°C + (displayed value × 0.05)°C
Measuring Range	-60 - 760°C	-35 - 1,500°C
Resolution	0.1°C	-35 - 999.9°C: 0.1°C Other values: 1°C
Measuring Interval	1 sec	
Measurement Wavelength	8 - 14 μm	
Operating Temperature	0 - 50°C	
Emissivity	Adjustable 0.1 - 1 (default as 0.95)	
Auto Power Off	60 seconds after stopped operation	
Battery Life	7 hours (continuous use)*2	12 hours (continuous use)*1
Power Source	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)	
Laser Wavelength	635 - 660 nm	
Output	1 mW or less (JIS Class2)	
Tripod Screw	1/4 inch	
Material	Body: ABS resin	

*1 140 hours of continuous use when not using the laser pointer and backlight
*2 30 hours of continuous use when not using the laser pointer

Stick Thermometer Alcohol/Mercury Individually Packaged



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72508	H -20 - 105°C 30 cm	300×6×6	21	4 960910 725089	10	SP
72510	H-2 0 - 200°C 30 cm	300×6×6	21	4 960910 725102	10	SP
72511	H-3 -20 - 105°C 30 cm	300×6×6	21	4 960910 725119	10	SP
72514	H-4 0 - 100°C 15 cm	153×6×6	11	4 960910 725140	10	SP
72547	H-5 0 - 100°C 30 cm	300×6×6	21	4 960910 725478	10	SP
72574	H-6 -30 - 50°C 30 cm	300×6×6	21	4 960910 725744	10	SP
72577	H-7 -10 - 65°C 30 cm	300×6×6	21	4 960910 725775	10	SP
72579	H-8 -20 - 50°C 15 cm	153×6×6	11	4 960910 725799	10	SP
72581	H-9 -10 - 50°C 15 cm x 2 pc-set	347×15×9	68	4 960910 725812	10	SP
72604	H-10 -20 - 105°C 45 cm	480×14×12	93	4 960910 726048	10	SP
72516	I -20 - 105°C 30 cm	300×6×6	23	4 960910 725164	10	SP

Features

- Alcohol model is easy to read
- Mercury model is watertight. Due to its high boiling point, it is good for measuring high temperature.
- Can be used inside its transparent protective case (72581)
- Can simultaneously measure ground temperature + air temperature, or water temperature + air temperature, etc. Can be used inside its metal protective case. (72511)
- Rubber stopper to prevent rolling (except 72511/72581/72604)

Use



For melting chocolate over hot water in cooking



For measuring temperature of solution, etc.



For measuring ground temperature



For measuring temperature of cooking oil, etc. (72510)

Specifications


	72508	72510	72511
Accuracy	±1℃		
Each Graduation	1℃		
Material	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene Case: Polyethylene resin		Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene Case: Polypropylene resin

	72514	72547	72574
Accuracy	±1℃		
Each Graduation	1℃		
Material	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene Case: Polyethylene resin		


	72577	72579	72581
Accuracy	±1℃		
Each Graduation	1℃		
Material	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene Case: Polyethylene resin	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene Case: Brass	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene Case: Brass

	72604	72516
Accuracy	±1℃	
Each Graduation	1℃	
Material	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene Case: Brass	Body: Glass Temperature Sensitive Liquid: Mercury Case: Polyethylene resin

*Stick thermometer is a fully immersive thermometer - it only indicates the correct temperature after temperature gauge is fully immersed. Since it simultaneously measures water temperature and air temperature when not fully immersed, it may display a temperature that is lower than the actual water temperature.



Metal Case for Stick Thermometer



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72729	for 30 cm	341×14×16	44	4 960910 727298	10	SP
72731	for 15 cm	190×14×16	28	4 960910 727311	10	SP

Features

- Case window allows measuring and reading of the scale while thermometer stays in the case


Use

- For protection of glass material stick thermometers

Specifications

Material	Brass
Operating Temperature	-30 - 200°C

Stick Thermometer Alcohol/Mercury Bulk Packaged



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72746	H-1S -20 - 105°C 30 cm	300×6×6	21	4 960910 727465	10	
72747	H-2S 0 - 200°C 30 cm	300×6×6	21	4 960910 727472	10	
72748	H-4S 0 - 100°C 15 cm	153×6×6	11	4 960910 727489	10	
72749	H-5S 0 - 100°C 30 cm	300×6×6	21	4 960910 727496	10	
72750	H-6S -30 - 50°C 30 cm	300×6×6	21	4 960910 727502	10	
72751	H-7S -10 - 65°C 30 cm Blue	300×6×6	21	4 960910 727519	10	
72752	H-8S -20 - 50°C 15 cm	153×6×6	11	4 960910 727526	10	
72754	I-1S -20 - 105°C 30 cm	300×6×6	23	4 960910 727540	10	

Features

- Affordable price with simple packaging
- Rubber stopper to prevent rolling




Use



For melting chocolate over hot water in cooking



For measuring temperature of solution, etc.



For measuring ground temperature




For measuring temperature of cooking oil, etc. (72747)

Specifications

	72746	72747	72748
Accuracy	±1°C		
Each Graduation	1°C		
Material	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene		


	72749	72750	72751
Accuracy	±1°C		
Each Graduation	1°C		
Material	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene		

	72752	72754
Accuracy	±1°C	
Each Graduation	1°C	
Material	Body: Glass Temperature Sensitive Liquid: Colored refined white kerosene	Body: Glass Temperature Sensitive Liquid: Mercury



Packaging:
With hook pin

*Stick thermometer is a fully immersive thermometer - it only indicates the correct temperature after temperature gauge is fully immersed.



Since it simultaneously measures water temperature and air temperature when not fully immersed, it may display a temperature that is lower than the actual water temperature

Stick Thermometer Specifications

Item Code	Description	Size	Measuring Range (°C)																Liquid
			-30	-20	-10	0	10	20	30	40	50	60	65	70	80	90	100	105	
72508/72746	H/H-1S	30 cm																	Red
72510/72747	H-2/H-2S	30 cm																	Red
72511	H-3	30 cm																	Red
72514/72748	H-4/H-4S	15 cm																	Red
72547/72749	H-5/H-5S	30 cm																	Red
72574/72750	H-6/H-6S	30 cm																	Red
72577/72751	H-7/H-7S	30 cm																	Blue
72579/72752	H-8/H-8S	15 cm																	Red
72581	H-9	15 cm × 2																	Red+Blue
72604	H-10	45 cm																	Red
72516/72754	I/I-1S	30 cm																	Mercury

*Mercury products will be discontinued at the end of 2020

Thermometer for Ground Temperature



72627

72623

72639

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72622	O-2 White	190×25×7	20	4 960910 726222	10	SP
72627	O-2 Yellow	190×25×7	20	4 960910 726277	10	SP
72630	O-2 Blue	190×25×7	20	4 960910 726307	10	SP
72623	O-3 Mini A 3 pc-pack (Red, Orange, Purple)	56×17×3	1	4 960910 726239	10	SP
72633	O-3 Mini B 3 pc-pack (Black, Blue, Green)	56×17×3	1	4 960910 726338	10	SP
72624	O-4 White with Air Temperature	245×35×7	36	4 960910 726246	10	SP
72636	O-4 Yellow with Air Temperature	245×35×7	36	4 960910 726369	10	SP
72639	O-4 Blue with Air Temperature	245×35×7	36	4 960910 726390	10	SP

Features

- Use by sticking into the ground or the soil in a pot for temperature control of germination, raising seedlings, and potting
- Growth of plants have a strong relation to ground temperature. This thermometer helps effective cultivation.
- O-3 models are colorful, small three-piece sets
- O-4 models can measure air and ground temperature at the same time

Growing Temp.	15 - 25°C	25 - 30°C
	Morning glory Amaryllis Potato	Tomato Corn Pumpkin
Germination Temp.	15 - 25°C	25 - 30°C
	Tulip Sweet pea Spinach	Zinnia Cosmos Chinese cabbage

Use

- For temperature control of soil in gardening and vegetable cultivation, etc.

Specifications

	72622	72627	72630
Accuracy	±1℃		
Measuring Range	-10 - 50℃		
Each Graduation	1℃		
Material	Body: Polystyrene resin		


	72623	72633
Accuracy	±2℃	
Measuring Range	10 - 50℃	
Each Graduation	2℃	
Material	Body: Yupo paper	

	72624	72636	72639
Accuracy	±1℃		
Measuring Range	Ground Temperature: -10 - 50℃ Air Temperature: -20 - 50℃		
Each Graduation	1℃		
Material	Body: Polystyrene resin		

Salt Hydrometer



72718



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72718	Salt Hydrometer	φ11×205	11	4 960910 727182	5	SP

Features

- Measures the concentration of salt water to separate seeds or unshelled rice
- Color coded to find the ideal gravity for each species of seed


Use

- For separating seeds or unshelled rice

Specifications

Accuracy	±1 Heavy Baume degree
Measuring Range	0 - 35 Heavy Baume degree
Each Graduation	1 Heavy Baume degree
Material	Body: Glass

Soil pH Meter



72724



- *This unit cannot measure liquid acidity.
- *When measuring, please make sure soil has sufficient moisture as if a mud ball was to be made

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72724	A	160×47×47	100	4 960910 727243	6	SP

Features

- Easy operation without battery - simply stick into the soil for a minute to measure
- Cone-shaped end gives the sensor firm contact with the soil and a large measurement area for high accuracy
- Meter stays horizontal for optimum functioning when inserted vertically into soil.

Use

- For measuring soil acidity

Specifications


Accuracy	±pH 0.5
Measuring Range	pH 4 - 7
Each Graduation	pH 0.2
Material	Body: ABS resin

Digital Soil pH Meter



72716

Display Image



①Illuminance

②Soil acidity (pH) } Switch
Temperature (°C)

③Soil moisture

*This unit cannot measure liquid acidity.
 *When measuring, please make sure soil has sufficient moisture as if a mud ball was to be made



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72716	A	322×63×36	117	4 960910 727168	2	

Features

- Digital display soil pH meter with multi-functions measuring ground temperature, soil moisture, and illuminance
- With backlight
- Switch allows easy change between soil acidity (pH) and temperature (°C)

Reverse side



pH is an index of acidity in soil.
Growth of crops depends significantly on soil pH.

Use

- For measurement of soil acidity, ground temperature, soil moisture, illuminance in cultivation environment

Specifications

Measuring Target	Acidity of soil, temperature of soil, moisture of soil, illuminance
Measuring Range	LOW-, LOW, LOW+, NOR-, NOR, NOR+, HIGH-, HIGH, HIGH+
Luminous Intensity (9 levels)	
Moisture of Soil (5 levels)	DRY+, DRY, NOR, WET, WET+
Acidity of Soil (14 levels)	pH 3.5 - 9.0 (minimum pH 0.5, accuracy ±pH 0.5)
Temperature of Soil	-9 - 50°C (minimum 1°C, accuracy ±1°C)
Power Source	1x 9 V battery (Battery included is for trial use only and may not last as long)
Auto Power Off (approx.)	5 minutes after stopped operation
Auto Backlight Off (approx.)	1.5 minutes after stopped operation
Operating Temperature	5 - 40°C
Probe Size	φ6 × 200 mm
Material	Body: ABS resin

Digital Soil EC Meter



72976



72758

Carry case

Carry case



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72976	Digital Soil EC Meter II	φ40×185	98	4 960910 729766	1	
72758	Digital Soil EC Meter	φ37×180	83	4 960910 727588	1	

Features

- Easy-to-read liquid crystal display with large lettering (72976)
- Ideal for detailed measurement with a resolution of 1 μS/cm



- Easy operation with just one push of the button
- Liquid temperature measurement function
- Compact, pocket-sized
- Hold function (only for soil EC Measurement Mode)
- Automatic Temperature Compensation (ATC) function
- IPX5 rating means it can be used safely even if it gets wet
- *Waterproof: Protected from low pressure water jets from any direction

ATC is an abbreviation for Automatic Temperature Compensation, which is a function that compensates for temperature changes in the liquid being measured by changing the measurement value. This allows precise measurement even without conversion.

EC means Electric Conductivity.
If the EC value of soil is too high (above 1,500 μS/cm), crops cannot absorb nutrition effectively and it affects how they grow.

Use

- For soil conditioning in gardening or agricultural works

Specifications

	72976	72758
Measuring Range	Soil conductivity 0 - 1,999 μS/cm Temperature 0 - 60°C	Soil conductivity 0 - 1,999 μS/cm Temperature 0 - 80°C
Accuracy*	Soil conductivity ±20 μS/cm Temperature ±1°C	
Automatic Temperature Compensation (ATC)	Available	
Resolution	1 μS/cm	
Waterproof	IPX5	
Power Source	3x Alkaline batteries LR44 or 3x Silver oxide batteries SR44 (Batteries included are for trial use only and may not last as long)	
Auto Power Off	Approx. 5 minutes	
Material	Body: ABS resin Sensor Part: Glass	

*Accuracy is the repeatability of measurements in the standard solution after calibration in the same standard solution.

Digital pH Meter



72788

Carry case



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72788	Digital pH Meter	φ40×185	110	4 960910 727885	1	B

Features

- Compact size convenient for carrying
- Hold function
- IPX5* rating means it can be used safely even if it gets wet
- *Protected from low pressure water jets from any direction

Use

- For measurement of pH
- For water quality tests in pools, drinking water tests, and fish farming management
- For pH management of soil in agricultural fields. (When measuring soil pH, measure the top clear layer of the solution mixed with a ratio of 1 part soil to 2.5 parts water.)

Specifications

Measuring Range	pH 1.0 - 14.0
Accuracy*	±pH 0.1
Usable Liquid Temperature Range	5 - 35°C
Resolution	pH 0.1
Waterproof	IPX5
Power Source	3x Alkaline batteries LR44 or 3x Silver oxide batteries SR44 (Batteries included are for trial use only and may not last as long)
Auto Power Off	Approx. 8 minutes
Material	Body: ABS resin Sensor Part: Glass

*Accuracy is the repeatability of measurements in the standard solution after calibration in the same standard solution.

Digital Salinity Meter





72799

Carry case

Salinity Measurement

Electric Conductivity Measurement



Can switch from salinity measurement to electric conductivity (EC) measurement with one button



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72799	Digital Salinity Meter	φ40×185	114	4 960910 727991	1	B

Features

- Compact size convenient for carrying
- Hold function
- Automatic Temperature Compensation (ATC) function
- Electric conductivity measurement function
- Liquid temperature measurement function
- IPX5* rating means it can be used safely even if it gets wet
- *Protected from low pressure water jets from any direction

ATC is an abbreviation for Automatic Temperature Compensation, which is a function that compensates for temperature changes in the liquid being measured by changing the measurement value. This allows precise measurement even without conversion.

Use

- For management of fish farming and drinking water
- Measure salinity of liquids

Specifications

Measuring Range	Salinity: 0 - 8.0‰ Electric Conductivity: 0 - 200 mS/cm*1 Temperature: 0 - 60°C
Accuracy*2	Salinity: ±0.2‰ Electric Conductivity: 0 - 1999 μS/cm*1: ±20 μS/cm 2 - 200 mS/cm: ±2 mS/cm Temperature: ±1°C
Automatic Temperature Compensation (ATC)	Available
Resolution	Salinity: 0.1‰ Electric Conductivity: 1 μS/cm Temperature: 0.1°C
Waterproof	IPX5
Power Source	2x AAA Alkaline batteries (Batteries included are for trial use only and may not last as long)
Auto Power Off	Approx. 8 minutes
Material	Body: ABS resin Sensor Part: Glass

*1 Will automatically switch to mS/cm if measurement value exceeds 1999 μS/cm
*2 Accuracy is the repeatability of measurements in the standard solution after calibration in the same standard solution.

Solutions



73033

73034

73035

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73033	Calibration Buffer Solution pH 4.01, pH 7.01 3 Each	148×70×5	23×6	4 960910 730335	5	B
73034	Calibration Buffer Solution pH 10.01, pH 7.01 3 Each	148×70×5	23×6	4 960910 730342	5	B
73035	Conductivity Solution 1413 μS/cm 6 Sachets	148×70×5	23×6	4 960910 730359	5	B

Features

- Disposable type with just the right amount for one-time calibration
- Preparing a beaker is unnecessary since the sensor can be dipped into the pouch as is



Use

- For calibration of pH Meter and EC Measurement

Specifications

	73033	73034	73035
Accuracy*	±pH 0.01	—	—
Volume	1 sachet 20 ml	—	—
Compatible Products	72788	72976/72758	72799

*Accuracy at 25°C

Digital Lux Meter

78747



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78747	Digital Lux Meter	Display Part: 130×72×30 Receiver Part: 106×57×26	210		1	

Features

- Separate light sensor allows sensor to be pointed towards light source while reading LCD display for better accuracy
- Measuring range switch enables switching between three different measurement ranges
- Peak hold function that locks screen at the maximum measured value
- Easy-to-read, large letter LCD screen (17 mm)

Use

- For luminance control at office, factory, or inside greenhouse

Specifications

Measuring Range	0 - 40,000 lux
Resolution	0.1 lux
Sensitivity	0 - 10,000 lux: ±(4%+10 dgt) 10,001 - 40,000 lux: ±(5%+10 dgt)
Repeatability	±2%
Measurement Cycle	Twice/second
Light Receiver	Photodiode sensor
Operation Requirement	Temperature: 0 - 40°C Humidity: Below 70%
Storage Requirement	Temperature: -10 - 50°C Humidity: Below 80%
Power Source	1x 9V Battery (included) (Battery included is for trial use only and may not last as long)
Material	Body: ABS resin Cover: Rubber


Lux Meter

78604



Note

Low luminance fluorescent light wastes electricity. Measure the light's luminance by turning conversion switch on to the right (X10) and directly facing it. If it shows below 13,000 lux, it's time to replace the tube no matter what watt value it usually shows.



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78604	Lux Meter	100×64×24	70		5	

Features

- Instantly finds the brightness of a room
- Illuminometer with solar battery
- Proper luminance reading chart

Use

- For luminance control in a room, etc.

Example of proper luminance (lux)

Gathering/Dinner	300 - 500
Reading/Studying	550 - 1,000
PC/Detail Work	1,000 - 1,500

Specifications

Material	Body: ABS resin
Measuring Range	0 - 15,000 lux
Conversion Switch ×1 (left side) ×10 (right side) 0 - 1,500 lux 0 - 15,000 lux	

Digital UV Light Meter

78642



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
78642	Digital UV Light Meter	Display Part: 130×72×30 Receiver Part: 164×50×32	219		1	

Features

- Ideal for control and confirmation of ultraviolet light intensity
- Separate light sensor allows sensor to be pointed towards light source while reading LCD screen for better accuracy
- Measuring range switch enables switching between three different measurement ranges
- Peak hold function that locks screen at the maximum measured value
- Easy-to-read, large letter LCD screen (17 mm)

Use

- For industrial use facility management
- For control of UV lamps such as UV dryers
- Simple confirmation for products that cut UV light

Specifications

Measuring Range	0 - 20.00 mW/cm ²
Display Mode Range	Range 0 - 400.0 μW/cm ² Range 0 - 4000 μW/cm ² Range 0 - 20.00 mW/cm ²
Resolution	Range 0 - 400.0 μW/cm ² : 0.1 μW/cm ² Range 0 - 4000 μW/cm ² : 1 μW/cm ² Range 0 - 20.00 mW/cm ² : 0.01 mW/cm ²
Accuracy	Range 0 - 400.0 μW/cm ² : ±16.2 μW/cm ² Range 0 - 4000 μW/cm ² : ±162 μW/cm ² Range 0 - 20.00 mW/cm ² : ±1.62 mW/cm ²
Measurement Wavelength	290 - 390 nm (Supports UVA-UVB)
Use Environment	Temperature: 0 - 40°C Humidity: Below 70%
Power Source	1x 9V Battery (included) (Battery included is for trial use only and may not last as long)
Material	Body: ABS resin Cover: Rubber

Digital Noise Meter



78588

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78588	with Maximum Value Holding Function	185×63×35	150	4 960910 785885	1	

Features

- Able to keep displaying maximum value during measurement
- 3 measuring ranges
- Portable, compact size
- Works right out of the box; user friendly

Use

- For checking noise level at construction sites or factories

Specifications

Measuring Range	30 - 130 dB
Resolution	0.1 dB
Accuracy	±1.5 dB (at 94 dB and 1 KHz)
Frequency Range	31.5 Hz - 8 KHz
Frequency Weighting	A/C switchable
Display Mode Range	30 - 70 dB
	60 - 100 dB
	90 - 130 dB
Response Speed	FAST (125 ms) SLOW (1 s)
Operation Requirements	Temperature: 0 - 40°C Humidity: 10 - 90%
Storage Requirements	Temperature: -10 - 60°C Humidity: 10 - 75%
Power Source	1x 9V Battery (included) (Battery included is for trial use only and may not last as long)
Material	Body: ABS resin

Metallic Hourglass



70304

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
70304	for 3-minute	93×35×24	141	4 960910 703049	5	

Features

- Sleek design
- Feel the passing of time with smooth falling sand
- Durable metal frame makes it usable professionally in restaurant or kitchen

Use

- For a variety of time management tasks
- As an interior decoration or accessory
- *Not for use in a sauna

Specifications

Accuracy	Within ±20 seconds
Material	Body: Zinc alloy die cast, glass Sand: Glass

Hourglass



70550

70551

70552

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
70550	for 1-minute	φ45×88	33	4 960910 705500	5	
70551	for 3-minute	φ50×100	43	4 960910 705517		
70552	for 5-minute	φ55×112	53	4 960910 705524		

Features

- Various sizes to choose from - one minute, three minutes, and five minutes
- Nice to have as an interior decoration as well


Use

- For a variety of time management such as brushing teeth, calling time, or training, etc.
- *Not for use in a sauna

Specifications

	70550	70551	70552
Accuracy	Within ±10 secs	Within ±30 secs	Within ±50 secs
Material	Body: Wood, glass Sand: Glass		

17. Outdoor Products



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Pedometer



74132



74133

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74132	Q Black	40×46×21	16	4 960910 741324	5	
74133	Q White	40×46×21	16	4 960910 741331	5	

Features

- Large letters for easy reading

Use

- For health management

Specifications

Display	LCD 5-digit display Minimum 1/Max 99,999
Accuracy	Within ±5%
Power	1x Alkaline battery LR44 (included) (Battery included is for trial use only and may not last as long)
Material	Body: ABS resin

Dry Compass



75602



75603

Features

- Most commonly used dry compass

Use

- For checking directions of East, West, South, and North

Specifications

	75602	75603
Material	Body: Aluminum	Body: Stainless steel, brass
	Display Surface: Glass	

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75602	A-3 Japanese	φ45×13	18	4 960910 756021	10	
75603	B-2 Roman Alphabet	φ45×13	22	4 960910 756038	10	

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Oil-filled Compass



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75590	C Roman Alphabet	φ45×16	39		10	
75592	C-2 Japanese	φ45×15	23		10	

Features

- Oil compass moves the needle slowly and enables a better reading


Use

- For checking directions of East, West, South, and North
- As a compass for orientating (C)


Specifications

	75590	75592
Material	Body: Brass Display Surface: Acetate resin	Body: ABS resin Display Surface: Acrylic resin

■ Using a compass with orienting arrow



Compass Chinese Zodiac



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75604	D	55×55×13	35		10	

Features

- Ideal for finding directions in building sites as you can see map or drawing through the compass


Use

- For checking directions of East, West, South, and North
- For checking directions for Feng Shui

Specifications

Material	Body: Brass Display Surface: Glass
----------	---------------------------------------

Oil-filled Compass for Orienteering



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75612	E	φ50 (84×54) ×10	27		10	
75614	E-2 Round	φ48×12	16		10	

Features

- With neck strap

Use

- As a compass for orienteering
- For checking directions of East, West, South, and North
- For mountain climbing, camping, and hiking

Specifications

	75612	75614
Material	Body: Acrylic resin Display Surface: Acetate resin	

■ How to use E

1. Draw a line between the current location and destination on a map and put the red arrow (A) of compass on the line.
2. Next, turn the rotating bezel to match North on the map.
3. While the compass is still on the map, turn the map to align with Magnetic North. The destination will be in the direction of the red arrow (A).


Oil-filled Compass for Military



■ How to use

Hold the compass horizontally and point the lid to a target. Capture the target through the sight of lid's line and the lens holder.

Look at the dial and read off the scale. That scale is the direction of the target.



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75620	F	φ56×27	66		10	

Features

- Four directions of the compass are luminous to show direction even in the dark

Use

- For checking directions of East, West, South, and North
- As a military compass

Specifications

Material	Body: ABS resin Display surface: Glass
Display	Outer Side: Mil Inner: Degree

Oil-filled Wood Compass Japanese



75662

Features

- Made of high-quality natural material - "KEYAKI" Japanese zelkova
- Floats on water with 10 atm water resistance
- With 1 m neck strap

Use

- For checking directions of East, West, South, and North

Specifications

Material	Body: Wood (Japanese zelkova) Display Surface: Acetate resin
----------	---

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75662	J	57×50×13	20		10	

Other Compass



75686



75672

Features

- I
 - Combined unit of compass and alcohol thermometer
 - Entire luminous surface glows in the dark
 - Use as a key chain or attach to a zipper
- K-2
 - Standard compass that can be used as teaching material

Use


- For checking directions of East, West, South, and North

Specifications

	75686	75672
Temperature Measuring Range	Thermometer: -20 - 60°C	—
Material	Body: Acrylic resin Nameplate: Hard vinyl chloride (noctilucent surface) Thermometer: Glass, paraffin	Body: Aluminum Display Surface: Glass

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75686	I for Zipper	50×28×8.5	9		10	
75672	K-2 Japanese	φ44×11	12		10	

Map Measure



71310

71320

Features

- C
 - Compass to check direction
 - Keyring for portability
- D
 - Six different functions such as thermometer, magnifier, etc.

Use

- For measuring distance on a map

Specifications

	71310	71320
Reduction Scale	Outer(1 division): Outside circle 1:1 (1 cm) Inside circle 1:50,000 (1 km) Inner(1 division): Outside circle 1:20,000 (200 m) Inside circle 1:5,000 (100 m)	
Specification	Direction compass	Direction compass Thermometer: -20 - 50°C Scale: 0 - 70 mm Loupe: Magnification 3X
Material	Body: ABS resin	

■ If the reduction scale of a map and the Map Measure do not fit
 Use 1:1 scale and multiply the reduction scale of the map to find the actual distance
 (Example) In a case that Map Measure indicates 25 cm on a map with 1:17,500 reduction scale, 17,500 X 25=437,500 cm (approx. 4.4 km).

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
71310	C Keyring Model	76×52×11	26		1	
71320	D Multi-function Model	76×54×12	25		10	

18. Magnifying Glasses



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Reading Glass



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75509	A-2 65 mm 2.5x	155×65×12	70	4 960910 755093	5	
75792	A-3 65 mm 3x	182×74×17	83	4 960910 757929		
75793	A-4 75 mm 2.5x	192×83×17	96	4 960910 757936		
75794	A-5 100 mm 2x	228×107×17	178	4 960910 757943		
75517	B-2 75 mm 2x	185×75×13	104	4 960910 755178		
75520	B-3 75 mm 2x and 4x Double Focus	185×85×18	56	4 960910 755208		
75521	B-4 100 mm 2x and 4x Double Focus	235×115×22	128	4 960910 755215		

Features

- Easy-to-hold
- High-quality glass is scratch resistant (Except 75520 and 75521)
- B-3, B-4 models have a lightweight bifocal lens that gives two or four times magnification (75520/75521)



Use

- For reading small letters on a newspaper or dictionary

Specifications

	75509	75517
Lens Diameter (mm)	φ65	φ75
Magnification	2.5x	2x
Material	Body (frame): Brass Body (handle): Vinyl chloride resin	

	75792	75793	75794	75520	75521
Lens Diameter (mm)	φ65	φ75	φ100	φ75	φ100
Magnification	3x	2.5x	2x	2x and 4x	2x and 4x
Material	Body (frame, handle): ABS resin				

- Focal Length = $\frac{\text{Visibility Distance (250 mm)}}{\text{Magnification} - 1}$
- Magnification = $\frac{\text{Visibility Distance (250 mm)}}{\text{Focal Length}} + 1$
- Accuracy Error of Magnification ±20% (not applicable for aspherical lens and power magnifier with 2 or more lenses)

Reading Glass with LED Light

2x and 4x



75751

2x and 4x



75755

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75751	A-6 110 mm 2x and 4x	240×117×24	118	4 960910 757516	5	
75755	A-7 90 mm 2x and 4x	220×97×21	163	4 960910 757554	5	

Features

- Comes with bright LED light
- Easy-to-grip handle (75751)
- Comes with a hands-free stand (75755)



Use

- For reading small letters on a newspaper or dictionary

Specifications

	75751	75755
Lens Diameter (mm)	φ110	φ90
Magnification	2x and 4x	
Material	Body: ABS resin	
Power	2x AAA Alkaline batteries (included)	2x AA Alkaline batteries (included)

(Batteries included are for trial use only and may not last as long)

Magnifier with Light for Reading

3x



75761

3x



75762

10x



75708

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75761	E 50 mm 3x	151×55×31	101	4 960910 757615	5	
75762	F 65 mm 3x	175×68×31	109	4 960910 757622	5	
75708	E-3 28 mm 10x	180×53×48	95	4 960910 757080	5	

Features

- Light for easy reading even in the dark



Use

- For reading small letters on a newspaper or dictionary (75761/75762)
- For looking at stamps, jewelry, or inside clocks, etc. (75708)
- E-3
- How to use:
Put it directly on an object and look through by putting your eye close to the lens
- Scale on the bottom for measurement
- Two lenses are used
Inside lens: Plastic Outside Lens: Glass

Specifications

	75761	75762	75708
Lens Diameter (mm)	φ50	φ65	φ28
Magnification	3x		10x
Material	Body: ABS resin		
Power	2x AA batteries (included) (Batteries included are for trial use only and may not last as long)		2x C batteries (not included)
Light Bulb	2.2V/0.25A		LED

Compact Reading Glass

3x



75557

3.5x



75556

2x



75555

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75557	S-3 30 mm 3x	36×77×5	3	4 960910 755574	10	
75556	S-2 45 mm 3.5x	55×115×8	27	4 960910 755567	10	
75555	S-1 60 mm 2x	70×155×15	35	4 960910 755550	10	

Features

- Pocket-sized for easy carry

Use

- For reading small letters on a newspaper or dictionary

Specifications

	75557	75556	75555
Lens Diameter (mm)	φ30	φ45	φ60
Magnification	3x	3.5x	2x
Material	Body: Acrylic resin	Body: Polyethylene resin	Body: Polypropylene resin

Desk Magnifier

2×



75767

8× and 30×



75727

3.5×



75529

Features

- Convenient for reading data numbers with the center red guide line. Comes with a convenient portable plastic case (75767)
- Combined unit of 8x telescopes and 30x microscopes (75727)
- Can also be used as a paper weight (75529)



Use

- For reading small letters on a newspaper or dictionary (75767/75529)
- For viewing scenery with a telescope, examining minerals or small specimens with a microscope, or for inspection of printed items (75727)

Specifications

	75767	75727	75529
Lens Diameter (mm)	25 × 150	φ11	φ60
Magnification	2x	8x and 30x	3.5x
Material	Body: Acrylic resin	Body: ABS resin, acrylic resin	

Pocket Magnifier

2.5×



75534

3.5×



75535

2 and 4×



75536

Features

- Convenient pocket size for carrying
- Case protecting lens
- N-3 has a bifocal lens (75536)

Use

- For reading small letters on a newspaper or dictionary

Specifications

	75534	75535	75536
Lens Diameter (mm)	65 × 45	φ45	φ65
Magnification	2.5x	3.5x	2x and 4x
Material	Case: Synthetic leather		


Sheet Magnifier

3.5×



75503

3.5×



75505

2×



75506

2×



75522

Features

- Uses a Fresnel lens

— Cross section —



Fresnel lens allows thinness even with a large surface area

- Comes with a convenient, portable plastic case (75502/75505/75506)

Use

- For reading a book, map, or chart, etc.

Specifications

	75503	75505	75506	75522
Magnification	3.5x		2x	
Material	Body: Vinyl chloride resin			

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75503	U-2 3.5x Bookmark Size	140×38	3	4 960910 755031	10	
75505	U-3 3.5x Card Size	85×55	3	4 960910 755055		
75506	U-4 2x Pocket Notebook Size	150×78	7	4 960910 755062		
75522	U-5 2x A4 Size	280×215	40	4 960910 755222		

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery cm/shaku (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Precision Work Magnifier



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75537	O-1 with Tweezer 30 mm 4.5x	110×36×13	27	4 960910 755376	5	
75572	T-3 Watchmaker's Loupe 23 mm 5x	φ36×32	7	4 960910 755727		
75636	X Attachment to Glasses 2.5x	65×74×26	18	4 960910 756366		

Features

- Helps to increase productivity when performing detailed work

Use

- For detailed work such as pulling a thorn out, maintaining bonsai, etc. (75537)
- For repair or inspection of precision parts (75572)
- For assembling work in personal hobby use (75636)

Specifications

	75537	75572	75636
Lens Diameter (mm)	φ30	φ23	28 × 74
Magnification	4.5x	5x	2.5x
Material	Body: Stainless steel, polyethylene resin	Body: Polystyrene resin	Body: ABS resin

High Magnification Model



Features

- High magnification
- Compact size convenient for carrying

Use

- For inspection of jewelry and printing (75543/75564/75565)
- 75570 and 75571 have divisions of 0.1 mm and 0.2 mm respectively for detailed measurement
- As a key chain (75543)

Specifications

	75543	75564	75565
Lens Diameter (mm)	φ10	φ18	φ28
Magnification	15x		10x
Material	Body: Brass Hood: Acrylic resin	Body: Aluminum, vinyl chloride resin	

	75570	75571
Lens Diameter (mm)	φ20	φ28
Magnification	15x	10x
Material	Body: ABS resin, acrylic resin	

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75543	Q 10 mm 15x	φ15×35	10	4 960910 755437	10	
75564	R-1 18 mm 15x	27×85×20	28	4 960910 755642	5	
75565	R-2 28 mm 10x	33×102×20	36	4 960910 755659	1	
75570	T-1 20 mm 15x	φ34×26	14	4 960910 755703	5	
75571	T-2 28 mm 10x	φ34×41	19	4 960910 755710		

Stowed High Magnification Model



Features

- Small, portable, fold-away style with high magnification
- Can increase its magnification by using multiple lenses
75531...7X with two lenses, 10.5X with three lenses
75766...7X with 3X + 4X, 8X with 3X + 5X, 9X with 4X + 5X, 12X with three lenses

Use


- For high-magnification work such as jewelry inspection, or observation, drafting, etc.

Specifications

	75523	75531	75765	75766
Lens Diameter (mm)	φ7/φ13	φ23	φ19	
Magnification	10x/20x	3.5x	10x	3x/4x/5x
Material	Body: Brass	Body: ABS resin	Body: Iron, zinc	Body: Iron, aluminum

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75523	C Double Lens 10x/20x	58×23×16	30	4 960910 755239	5	
75531	D Triplet Lens 3.5x	59×28×15	16	4 960910 755314		
75765	I 10x with Chain	44×27×16	46	4 960910 757653		
75766	J 3x/4x/5x with Chain	44×27×16	47	4 960910 757660		

Pocket Microscope



Features

- Pocket-sized microscope with LED light

Use

- For observation outdoors or inspection of printing, etc.

Specifications

Magnification	60 - 100x (tolerance 20%)
Light	White LED
Luminous Intensity	12,900 mcd
Material	Body: ABS resin Lens: Acrylic resin
Power Source	3x Alkaline batteries LR1130 (included) (Batteries included are for trial use only and may not last as long)

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75753	H 60x - 100x with LED Light	83×33×20	31	4 960910 757530	5	

Stand Magnifier



Features

- Stand model frees up both hands

Use

- For measuring small objects with 25 mm graduation (75763)
- For working on a desk with the adjustable angle lens (75539)

Specifications

	75763	75539
Lens Diameter (mm)	φ25	φ65
Magnification	6x	3x
Material	Body: Aluminum	Body: Brass Base: Cast metal

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75763	G 25 mm 6x	51×38×50	43	4 960910 757639	5	
75539	P-1 65 mm 3x	166×54×60	384	4 960910 755390	2	


JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Binocular



Switch magnification levels by exchanging with a lens stored inside the unit



To replace, simply insert the lens until it clicks



Features

- Both hands are freed by setting it on your head
- Usable with glasses on
- W-2
- Lightweight for comfort
- W-4
- Magnification level can be switched while being worn
- W-3/W-5
- Light for better visibility and night work. Additional lenses for a variety of uses included.

Use

- For handicraft, reading, gardening, assembling a model, pulling a thorn out, etc.

1.5X	For reading (a book, dictionary, phone book, map, document, etc.)
2.5X	For assembling (precision parts, handicrafts, tackles for fishing, etc.)
3.0X	For inspecting (processing of precision parts, plate-making precious metals, etc.)

Specifications

	75646	75656
Lens Diameter (mm)	28 × 75	
Magnification	2.5x	1.5x/2.5x/3.0x
Material	Body: ABS resin	
Power Source	—	2x Lithium batteries CR1220 included (Batteries included are for trial use only and may not last as long)

	75735	75737
Lens Diameter (mm)	29 × 88	100 × 49
Magnification	2.2x/3.3x	1.2x/1.8x/2.5x/3.5x
Material	Body: ABS resin	
Power Source	—	2x AAA batteries included (Batteries included are for trial use only and may not last as long)

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75646	W-2 2.5x	220×200×40	95	4 960910 756465	1	
75650	Replacement Lens 1.5x for W-2	75×28×3.5	8	4 960910 756502		
75651	Replacement Lens 2.5x for W-2	75×28×4.5	10	4 960910 756519		
75652	Replacement Lens 3.0x for W-2	75×28×8	16	4 960910 756526		
75656	W-3 1.5x - 3.0x with Light	230×190×60	100	4 960910 756564	1	
75735	W-4 2.2x/3.3x	230×195×65	129	4 960910 757356		
75737	W-5 1.2x - 3.5x with LED Light	240×195×55	127	4 960910 757370		

Stand Magnifier



Features

- Large glass to use with both eyes. Fixes to a desk for hands-free use.
- Lens turns 360° to adjust at any angle
- Protective sticker so that it will not scratch even when clamp is securely fastened (75659)
- Bifocal so magnification level can be changed without having to switch lenses (75659)

Use



- For precision work or inspection

Specifications

Lens Diameter (mm)	φ123
Magnification	2x (Double Focus 4x)
Material	Lens: Acrylic resin Lens Frame: ABS resin Arm: Iron Clamp: Aluminum, iron

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
75659	Y 123 mm 2x and 4x Double Focus	Overall Length : 940 Arm : 740	725	4 960910 756595	1	

19. Drawing Tools



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

*Acrylic resin has high transparency and is easy to clean.
However, please do not wipe it off with thinner.

Acrylic Straight Rule


77041



75329



77089



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77041	15 cm	160×30×2	11	4 960910 770416	10	
75310	30 cm	309×32×3	33	4 960910 753105		
75329	45 cm	459×43×3	67	4 960910 753297		
77089	30 cm with Grid Scale	311×45×3	48	4 960910 770898		
77097	45 cm with Grid Scale	459×50×3	81	4 960910 770973		

Features

- Improves productivity of layout work and line drawing with grid scale

Use

- Ideal for layout work or line drawing with horizontal lines

Specifications

Material	Acrylic resin
Elasticity Ratio	7 - 8 × 10 ⁻⁵ mm elastic per 1 mm in 1°C change

Acrylic Cutting Rule with Stainless Steel Edge

77085




Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77085	30 cm	310×55×5	110	4 960910 770850	5	
77086	50 cm	510×60×5	165	4 960910 770867		

Features

- Cutter edge has a tough stainless steel plate to prevent the blade from cutting in and enable smooth cutting
- Improves productivity of layout work and line drawing with grid scale

With stainless steel plate



Use

- For line drawing and cutting work

Specifications

Material	Body: Acrylic resin Cutter: Stainless steel
Elasticity Ratio	7 - 8 × 10 ⁻⁵ mm elastic per 1 mm in 1°C change

Acrylic Rule

77070



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77070	30 cm	316×40×3	42	4 960910 770706	10	

Features

- Colored bar makes it easier to read data

Use

- For line drawing and data reading

Specifications

Material	Acrylic resin
Elasticity Ratio	7 - 8 × 10 ⁻⁵ mm elastic per 1 mm in 1°C change

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge
 Japanese zodiac signs With battery cm/shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Black Drawing Scale

77038



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77038	30 cm	310×30×3	27	4 960910 770386	10	

Features

- Upper Graduation: Left base point with 0 - 30 cm straight graduation
- Lower Graduation: Center base point with divided graduation of 15 cm to each side

Use

- For drawing lines

Specifications

Material	Vinyl chloride resin
Elasticity Ratio	5 × 10 ⁻⁵ mm elastic per 1 mm in 1°C change

Acrylic Dot-line Drawing Rule

70726



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70734	15 cm	200×45×3	23	4 960910 707344	10	
70726	30 cm	321×51×5	67	4 960910 707269		

Features

- Easily draw a dotted line and dot-dash line

Use

- For drawing lines, dotted lines and dot-dash lines

Specifications

Material	Acrylic resin
Elasticity Ratio	7 - 8 × 10 ⁻⁵ mm elastic per 1 mm in 1°C change

Acrylic Scale Reduction Rule

70769



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70750	15 cm	210×64×4	39	4 960910 707504	10	
70769	30 cm	370×64×5	80	4 960910 707696		

Features

- Scale with triangular-scale functions
- See through the flat transparent surface while drawing

Use

- For drawing lines and reading sketches


Specifications

Material	Acrylic resin
Elasticity Ratio	7 - 8 × 10 ⁻⁵ mm elastic per 1 mm in 1°C change
Contraction Scale	1/100, 1/200, 1/250 1/300, 1/500, 1/600

Acrylic Protractor

74918

74926



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74918	180-degree Semicircle 15 cm	152×98×2	16	4 960910 749184	10	
74926	360-degree Circle 15 cm	φ152×2	25	4 960910 749269		

Features

- Measures angles to semicircle or full circle

Use


- For measuring angle of sketches

Specifications

Material	Acrylic resin
----------	---------------

Pantagraph

75426



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75426	Aluminum Pantagraph 5x	423×55×35	211	4 960910 754263	5	

Features

- Enlarges an original drawing five times or shrinks it by one fifth
- To start, decide desired magnification of enlargement or reduction, then just simply trace the original drawing to make an enlarged or reduced version


Use

- For enlargement and reduction of illustration, photo, painting, sketch, etc.

Specifications

Material	Arm: Aluminum Fixing: Brass, iron
----------	--------------------------------------

Acrylic Triangle Scale



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77066	18 cm 2 pc-pack	Ⓐ128×128×2 Ⓑ180×104×2	Ⓐ17 Ⓑ19	4 960910 770669	10	
75256	24 cm 2 pc-pack	Ⓐ171×171×2 Ⓑ240×140×2	Ⓐ31 Ⓑ33	4 960910 752566		
75264	30 cm 2 pc-pack	Ⓐ213×213×2 Ⓑ300×174×2	Ⓐ46 Ⓑ54	4 960910 752641		
77062	30 cm 2 pc-pack with Grid Scale	Ⓐ213×213×2 Ⓑ300×174×2	Ⓐ53 Ⓑ63	4 960910 770621		

Features

- Improves productivity of layout work and line drawing with grid scale



Use

- For drafting and line drawing

Specifications

	77066	75256	75264	77062
Material	Acrylic resin			
Elasticity Ratio	7 - 8 × 10 ⁻⁵ mm elastic per 1 mm in 1°C change			
Length of Each Sides	Ⓐ			
	a: 128 mm b: 128 mm c: 180 mm	a: 171 mm b: 171 mm c: 240 mm	a: 213 mm b: 213 mm c: 300 mm	a: 213 mm b: 213 mm c: 300 mm
	Ⓑ			
	a: 104 mm b: 180 mm c: 208 mm	a: 140 mm b: 240 mm c: 277 mm	a: 174 mm b: 300 mm c: 348 mm	a: 174 mm b: 300 mm c: 348 mm


Flexible Rule



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74845	40 cm with Scale	465×7×10	84	4 960910 748453	5	
74853	80 cm with Scale	865×7×10	164	4 960910 748538		

Features

- Flexible rule that can be bent in any shape
- Convenient to use with a bow pen or pen with ink edge



Use

- For making a mold by matching the shape
- For drafting and making a graph

Specifications

	74845	74853
Material	Outside Pipe, Side Cap: Vinyl chloride resin Scale Plate: Iron Middle Plate: Lead	

Curved Rule



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
77003	6 pc-pack	180×58×1	38	4 960910 770034	10	
70947	Middle-size	165×85×2	15	4 960910 709478		

Features

- Draws various curved lines
- Draw a curve by freehand in advance, then match the appropriate curve of the Curved Rule to finish the curved line


Use

- For drawing and checking curved lines

Specifications

	77003	70947
Material	Vinyl chloride resin	Acrylic resin

T-shaped Scale



- Easily draws a horizontal line by aligning "b" to the edge of drafting plate and drawing line with "a"

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
76759	Wood 60 cm	a: 655×65 (45)×6 b: 240×55×9	184	4 960910 767591	5	

Features

- Ideal as teaching material

Use


- For drawing a horizontal line on drafting

Specifications

Material	Body: Wood
----------	------------

Drawing Compass


75396



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75388	A 115 mm	120×13×10	47	4 960910 753884	10	
75396	B 155 mm	150×13×10	60	4 960910 753969	10	

Features

- Draws a large circle by using a joint shaft
- Joint shaft and replacement lead are included (both A and B)



Use

- For drawing circles

Specifications


Material	Brass
Body	Joint's shaft
Tip	

Compass Attachment

70920



Usage Example



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70920	Compass Attachment	42×47×11	6	4 960910 709201	10	

Features

- Uses compass with a pencil, pen, brush, or cutter
- Use by attaching to a drawing compass

Use

- For installing a pencil, pen, brush or cutter, etc. on a compass

Specifications

Usable Size	Maximum diameter of 11.5 mm
Material	Body: ABS resin

Drawing Divider

75450



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75442	A 115 mm	124×13×10	46	4 960910 754423	10	
75450	B 155 mm	154×13×10	59	4 960910 754508	10	

Features

- Gear type opens both shafts equally

Use


- For dividing lines and copying any dimensions

Specifications


Material	Brass
----------	-------

Erasing Shield

70963



70961



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70963	Stainless Steel Erasing Shield	93×60×0.1	4	4 960910 709638	10	
70961	Stainless Steel Mesh Erasing Shield	80×60×0.1	2	4 960910 709614	10	

Features

- Erases only desired area
- Easily see where to erase by looking through the shield (70961)

Use

- For intricate erasing

Specifications

	70963	70961
Material	Stainless steel	


Triangle Scale




70777



74969



74950



74961

For architects qualification exam




74962



70802



70803



74987



74988

Item Code	Description	JIS	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
70777	A-10 10 cm		Length: 120 Cross section: 16×16×16	9	4 960910 707771	10	
74969	A-15 15 cm for Real-estate Surveyors	JIS	Length: 170 Cross section: 16×16×16	13	4 960910 749696	10	
74950	A-30 30 cm for Real-estate Surveyors	JIS	Length: 326 Cross section: 25×25×25	58	4 960910 749504	5	
74961	B-15 15 cm for Architects		Length: 170 Cross section: 16×16×16	13	4 960910 749610	10	
74962	B-30 30 cm for Architects		Length: 326 Cross section: 25×25×25	58	4 960910 749627	5	
70802	C-15 15 cm for Microcopy		Length: 170 Cross section: 16×16×16	13	4 960910 708020	10	
70803	C-30 30 cm for Microcopy		Length: 326 Cross section: 25×25×25	58	4 960910 708037	5	
74987	D-30 30 cm for Architects, Shipbuilders	JIS	Length: 327 Cross section: 25×25×25	60	4 960910 749870	5	
74988	E-30 30 cm for Shipbuilders		Length: 327 Cross section: 25×25×25	60	4 960910 749887	5	

Features

- Convenient for drawing and reading measurements
- 30 cm models comes with a plastic case
- A-10
- Convenient pocket size for portability
- A-15/A-30
- Convenient for drawing and reading required material during a registration process such as an acreage survey map or a building ground plan
- B-15/B-30
- Shows the most essential scales for architectural design
- Most essential drawing and reduction scale for architectural design

City Plan/Area Measurement

1/250

Arrangement Plan/Ground Plan/Elevation Plan

1/100, 1/200, 1/300

Sectional Detail Drawing/Detail Drawing

1/20, 1/30 (double in 1/300), 1/50

■ C-15/C-30

- Reads a reduced copy drawing as a stencil size
- Reduction Scale

A format → A format (70.7%) A format → B format (86.6%)

A3 ▶ A4

A3 ▶ B4

■ D-30


- Convenient for drawing and reading required material in architecture or shipbuilding

■ E-30

- Convenient for drawing and reading required material in shipbuilding

Use

- For drawing and taking readings



Specifications

	70777	74969	74950
Reduction Scale	1/100, 1/200, 1/300 1/400, 1/500, 1/600	1/100, 1/200, 1/250 1/300, 1/500, 1/600	
Length Tolerance	±0.2 mm	±0.3 mm	±0.4 mm
Material	ABS resin		
	74961	74962	
Reduction Scale	1/20, 1/50, 1/100 1/200, 1/250, 1/300		
Length Tolerance	±0.3 mm	±0.4 mm	
Material	ABS resin		
	70802	70803	
Reduction Scale	A format → A format A format → B format	1/50, 1/100, 1/200 1/50, 1/100, 1/200	
Material	ABS resin		

A format means paper size such as A4, A3, A2, etc.
B format means B5, B4, etc.

	74987
Reduction Scale	1/20, 1/25, 1/50 1/75, 1/100, 1/125
Length Tolerance	±0.4 mm
Material	ABS resin
	74988
Reduction Scale	1/10, 1/15, 1/20 1/25, 1/50, 1/75
Length Tolerance	±0.4 mm
Material	ABS resin

*Length tolerance is the accuracy measured at 20°C.

Triangle Rotation Scale



74980



74979



74940



74941

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
74980	15 cm	Length: 185 Cross section: 22.5×22.5×12	61		6	
74979	15 cm/shaku	Length: 185 Cross section: 22.5×22.5×12	61		6	
74940	30 cm	Length: 335.5 Cross section: 22.5×22.5×12	115		6	
74941	30 cm/shaku	Length: 335.5 Cross section: 22.5×22.5×12	115		6	


Features

- Choose six sizes of reduction simply by positioning the unit and turning the knobs located on both sides. No need to turn the unit itself.



Use

- For drawing and reading required material during a registration process such as an acreage survey map or a building ground plan



Specifications



	74980	74979	74940	74941
Length Tolerance	15 cm: ±0.16 mm		30 cm: ±0.19 mm	
Reduction Scale	Upper row	Upper row	Upper row	Upper row
	1/50, 1/100	1/20, 1/50	1/100, 1/200	1/20, 1/50
	1/200, 1/250	1/100, 1/200	1/250, 1/500	1/100, 1/200
	1/500	1/250		1/250
Lower row	Lower row	Lower row	Lower row	Lower row
	1/300	1/30	1/300, 1/600	1/30
Material	Body: Aluminum		Knob: Rubber	

Folding Scale 8-scales



75746

75745




Features

- Folds flat for carrying
- Laminate keeps from fading

Use

- For drawing and reading required material during a registration process such as an acreage survey map or a building ground plan

Fold and use by facing the desired reduction scale outside






Specifications

	75745	75746
Length Tolerance	15 cm: ±0.10 mm	30 cm: ±0.15 mm
Reduction Scale	1/100, 1/150, 1/200, 1/250 1/300, 1/400, 1/500, 1/600	
Material	PET resin	

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
75745	15 cm	170×25×0.9	5		10	
75746	30 cm	320×32×0.9	11		10	


Template [Circle]

66002 ϕ 1-36 mm66004 ϕ 1-36 mm66003 ϕ 1-23 mm66005 ϕ 1-23 mm

Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Packaging
66002	TA-1E Circle with Edge Medium	105×230×1.0	4 960910 660021	5	
66003	TA-4E Circle with Edge Small	70×160×1.0	4 960910 660038		
66004	TB-1 Circle Medium	105×230×0.75	4 960910 660045		
66005	TB-4 Circle Small	70×160×0.75	4 960910 660052		

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- Ring hole helps prevent loss
- Unique edge prevents ink from running off and enables drawing without making the ink bleed (66002/66003)



Use

- For drafting such as design and drawing

Specifications

Material	IR resin
----------	----------

Template [Number/Alphabet]



66013 Character height 3.0/4.0/5.0 mm



66014 Character height 2.5/3.5/4.5 mm



66015 JIS B-type Roman font Character height 3.15/4.5 mm

Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Packaging
66013	TE-5 Number/Alphabet	60×160×0.5	4 960910 660137	5	
66014	TE-6 Number/Alphabet	60×160×0.5	4 960910 660144		
66015	TE-7 Number/Alphabet	60×160×0.5	4 960910 660151		

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- Ring hole helps prevent loss

Use

- For drafting such as design and drawing

Specifications

Material	IR resin
----------	----------

Template [Number]



66016 Middle, tall Character height 2.5/3.0/3.5/4.0/5.0 mm



66017 Middle JIS letter J-type italic font Character height 2.5/3.0/3.5/4.0/5.0 mm



66018 Middle JIS letter B-type Roman font, B-type italic font, J-type italic font Character height 3.0/4.0/3.15/4.5/6.3 mm

Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Packaging
66016	TE-9 Number	60×160×0.5	4 960910 660168	5	
66017	TE-10 Number	60×160×0.5	4 960910 660175		
66018	TE-11 Number	60×160×0.5	4 960910 660182		

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- Ring hole helps prevent loss


Use

- For drafting such as design and drawing

Specifications

Material	IR resin
----------	----------

Template [Oval/Arc/Corner]



66020 Oval 25°/35°/16°/45°/60°



66031 R0.5 - 38.0 mm

Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Packaging
66020	TG-3 Oval	150×300×0.75	4 960910 660205	5	
66031	TP-1 Corner	105×230×0.75	4 960910 660311		

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- Ring hole helps prevent loss (66020)

Use

- For drafting such as design and drawing


Specifications

Material	IR resin
----------	----------

JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens


Template [Sign]



66007




66008



66010



66027



66029

Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Package
66007	TD-1 Furniture Large 1/50	105×230×0.75	4 960910 660076	5	
66008	TD-2 Furniture Small 1/100	70×160×0.75	4 960910 660083		
66010	TD-4 Architecture 1/100 and 1/200	105×230×0.75	4 960910 660106		
66027	TK-1 Finish Mark	70×160×0.75	4 960910 660274		
66029	TL-1 Arrow	105×230×0.75	4 960910 660298		

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- Ring hole helps prevent loss




Use

- For drafting such as design and drawing

Specifications


Material	IR resin
----------	----------

Template [General Shape]




66024

Circle 1-22, Triangle 1-10, Square 1-12, Hexagon 4-12, Isometric 6-20, JIS letter 3.15 mm



66025

Circle 0.5-20, Triangle 1-15, Square 1-15, Hexagon 1-15, Arrow symbol, Alphabet 3.0 mm



66021

Circle 1-17, Triangle 1-10, Square 1-10, Hexagon 2-12, Number 2.5/3.0/3.5, Alphabet 3.5 mm



66022

Circle 1-20, Triangle 2-10, Square 2-12, Hexagon 2-12, Isometric 6-20, Alphabet 3.15 mm

Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Package
66021	TH-1 General Shape Small	70×160×0.75	4 960910 660212	5	
66022	TH-2 General Shape Small	70×160×0.75	4 960910 660229		
66024	TH-4 General Shape Medium	105×230×0.75	4 960910 660243		
66025	TH-5 General Shape Medium	105×230×0.75	4 960910 660250		

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- Ring hole helps prevent loss


Use

- For drafting such as design and drawing

Specifications

Material	IR resin
----------	----------


Template [Other]



66026

66033

For pencil or ball-point pen



Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Package
66026	TJ-1 Nut and Bolt	70×160×0.75	4 960910 660267	5	
66033	TQ-1 Japanese and Roman Letter	60×160×0.5	4 960910 660335		

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- Ring hole helps prevent loss

Use

- For drafting such as design and drawing


Specifications

Material	IR resin
----------	----------

Template[3 pc Card-size Set]

66034

JIS letter, Character height 3.15 mm with isometric



Item Code	Description	Body Size (mm)	JAN Code	Packing Unit	Package
66034	TS-A 3 pc-pack Card-size Set	60×97×0.5	4 960910 660342	5	

Features

- Great durability with IR resin material that makes it hard to break
- Easy color on eyes even during prolonged use
- Because they are cut by NC automatic engraving machine that is controlled by computer, the lag from the indicated line is minimal and the surface is smooth for more accurate drawing
- 3 pc-pack Card-size Set which can be stored in a pocket, pen case, or system notebook, etc.

Use

- For drafting such as design and drawing

Specifications

Material	IR resin
----------	----------

Mechanical Drawing Pencil

77798



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
77798	0.5 mm	φ10×142	17	4 960910 777989	10	

Features

- Ideal for drawing

Use

- For drawing a plan

Specifications

Material _____ Body: Aluminum

Transparent Case




78197



78198

Hole position



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
78197	With Zipper A1	900×630×0.4	300	4 960910 781979	10	
78198	With Zipper A2	670×460×0.4	170	4 960910 781986		

Features

- Clearly shows materials inside from the transparent side. The other side is semi-transparent to prevent papers and sheets from sticking together and to help get them in and out smoothly.
- Both sides have fasteners for better accessibility
- Comes with holes positioned symmetrically for storage



Use

- For presenting, keeping, and filing posters or drawings

Specifications

	78197	78198
Material	Vinyl chloride	
Inner Dimension	870 × 610 mm	640 × 440 mm

Drawing Sheet Case A



77030

■ Paper size

0 step	530 mm
1 step	580 mm
2 step	615 mm (A-1)
3 step	655 mm
4 step	695 mm
5 step	735 mm (B-1)
6 step	775 mm
7 step	845 mm (A-0)

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
77030	7-step Slide	φ86 mm	290	4 960910 770300	10	

Features

- Has a lock function on body and a cap to hold heavy items
- Seven-step expansion allows for various sizes of papers

Use

- For keeping and carrying posters or drawings

Specifications

Material _____ Polypropylene resin

Drawing Brush



70874

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
70874	Drawing Brush	203×75×10	36	4 960910 708747	10	

Features

- Made of soft, high quality horsehair

Use

- For cleaning eraser dust on a desk or drawing

Specifications

Material _____ Wood, horsehair

20. Magnets



Packaging Shrink package Box Vinyl package + header card Card No package
 Sleeve package Bag Clear package Vinyl package

Hand Magnet

Adsorption power
30 N
3 kgf



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73558	A-3	360×115×115	550	4 960910 735583	5	
73559	B-3 with Handle	830×115×115	730	4 960910 735590	5	
73553	A-2	160×98×52	315	4 960910 735538	10	
73554	B-2 with Handle	680×110×52	475	4 960910 735545	10	

Features

- Detachable magnet enables fast, safe picking up of metals such as screws
- Comes with a shaft handle for better accessibility (73559/73554)
- Convenient for sorting empty cans between steel or aluminum for recycling
- Strong aluminum body (73558/73559)
- Detaches easily by pulling up the lever



- Designed to be easy to handle (73558/73559)



Use

- For collecting screws, nails, or other metal pieces, etc.

Specifications

	73558	73559	73553	73554
Material	Body/Adsorption Face: Aluminum Lever: Iron	Body: Polystyrene resin Lever: Iron Adsorption Face: Stainless steel		
Orientation	Anisotropy			
Adsorption Power	30 N (3 kgf)			

Hand Magnet with Casters

Adsorption power
50 N
5 kgf




73556



Features

- Collect metal pieces quickly over a wide area
- Single-handed lever operation
- Turns freely in any direction
- Strong aluminum body



Two-step expansion
Length 715 mm



1,015 mm


Use

- For collecting screws, nails, or other metal pieces, etc.

Specifications

Material	Body: Aluminum, ABS resin
Orientation	Anisotropy
Adsorption Power	50 N (5 kgf)

Magnetic Pick-up Tool



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72290	H-2	133×11×14	28	4 960910 722903	10	
72291	H-3	134×13×13	29	4 960910 722910	10	
72456	H-4 with Light	186×18×18	88	4 960910 724563	5	

Features

- Made with a strong anisotropic magnet
- Telescopic antenna with a clip makes it easy to use, carry, and store (72290/72291)
- Magnetic part can be moved to any direction (72291)
- Comes with a bright, long-lasting white LED light (72456)
- Strong stainless steel shaft (72456)
- Easy-to-hold and non-slip large rubber grip (72456)

Use


- For picking up screws in hard-to-reach places
- For sorting out ferrous and nonferrous metals, and removing metal flakes

Specifications

	72290	72291	72456
Material	Body: Brass		Body: Stainless steel, rubber, brass
Orientation	Anisotropy		
Adsorption Power	10 N (1 kgf)	15 N (1.5 kgf)	20 N (2 kgf)
Antenna Length	645 mm	540 mm	660 mm
Power Source	3x Alkaline batteries LR44 (included) (Batteries included are for trial use only and may not last as long)		

Magnetic Pick-up Tool Flexible

Easily detachable mirror



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73511	H-5 with Light	607×20×20	227	4 960910 735118	5	
73516	H-6 with Light and Mirror	560×18×18	150	4 960910 735163	5	

Features

- Usable even in narrow, winding, and dark places
- Accessible switch for easy turning on and off to extend battery life
- Strong neodymium magnet
- Flexible type that can bend freely
- Strong aluminum grip with colored alumite finish
- Comes with a bright, long-lasting white LED light
- Use as an inspection mirror by attaching the accessory mirror to the end and check places that are hard to see (73516)

Use

- For picking up screws in hard-to-reach places
- For sorting out ferrous and nonferrous metals, and removing metal flakes

Specifications

	73511	73516
Material	Grip: Aluminum Flexible Tube: Iron Magnet: Neodymium	Grip: Aluminum Flexible Tube: Iron Mirror: Glass, ABS resin, polypropylene resin Magnet: Neodymium
Orientation	Anisotropy	
Adsorption Power	20 N (2 kgf)	Tip 10 N (1 kgf) Base 20 N (2 kgf)
Power Source	2x AA Alkaline batteries (included) (Batteries included are for trial use only and may not last as long)	3x Alkaline batteries LR44 (included)
Luminosity	27,000 mcd	

Magnetic Holder



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72008	38 cm	380×49×14	306	4 960910 720084	5	

Features

- Quickly attach and detach a required tool to increase productivity

Use

- Convenient for putting tools in order

Specifications

Material	Body: ABS resin
Orientation	Anisotropy
Withstand Load	1.3 kg

Welding Magnet



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72293	S	120×82×15	293	4 960910 722934	5	
72294	M	156×100×17	598	4 960910 722941	4	
72295	L	190×122×25	1,202	4 960910 722958	3	

Features

- Sticks with strong magnetic force. Convenient 45° and 90° shape
- *Use the angle of 45° and 90° only as a guide. If more precision is needed, fine-adjust.

Use

- For temporary holding in welding works

Specifications

	72293	72294	72295
Material	Body: ABS resin, iron		
Orientation	Anisotropy		
Adsorption Power	80 N (8 kgf)	200 N (20 kgf)	

T-shaped Magnet



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
73520	C ϕ 25	ϕ 25×30	80	4 960910 735200	5	
73539	D ϕ 40	ϕ 40×35	240	4 960910 735392		
73547	E ϕ 50	ϕ 50×35	330	4 960910 735477	3	

Features

- Ideal for various maintenance work with its strong adsorption power

Use

- For holding scales or as an anchor
- As a magnetic hook

Specifications

	73520	73539	73547
Material	Body: Zinc alloy Handle: Iron Magnet: Ferrite		
Orientation	Anisotropy		
Adsorption Power	25 N (2.5 kgf)	150 N (15 kgf)	250 N (25 kgf)
Size of Screw	M6 (1.0pitch)	M8 (1.25pitch)	

Magnetic Chips Circle



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72150	A-1 ϕ 10 6 pc-pack	ϕ 10×5	1.8	4 960910 721500	10	
72151	A-2 ϕ 15 6 pc-pack	ϕ 15×4	3.5	4 960910 721517		
72152	A-3 ϕ 20 3 pc-pack	ϕ 20×4	6.2	4 960910 721524		
72219	A-4 ϕ 25 2 pc-pack	ϕ 25×4	9	4 960910 722194		
72220	A-5 ϕ 30 2 pc-pack	ϕ 30×5	16	4 960910 722200		

Features

- Double-sided tape for use in a variety of applications

Use

- For putting small things on a chalkboard or whiteboard
- For personal hobby use

Specifications

	72150	72151
Material	Ferrite	
Orientation	Isotropy	
Adsorption Power	0.6 N (60 gf)	0.5 N (50 gf)

	72152	72219	72220
Material	Ferrite		
Orientation	Isotropy		
Adsorption Power	0.75 N (75 gf)	1 N (100 gf)	1.4 N (140 gf)

Magnetic Chips Square



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72153	B-1 15 x 16 mm 3 pc-pack	15×16×4	4.6	4 960910 721531	10	
72154	B-2 15 x 20 mm 2 pc-pack	15×20×4	5.6	4 960910 721548		
72155	B-3 19 x 25 mm 2 pc-pack	19×25×4	9.2	4 960910 721555		
72156	B-4 10.5 x 30 mm 2 pc-pack	10.5×30×5	7.6	4 960910 721562		
72221	B-5 20 x 30 mm 2 pc-pack	20×30×5	14	4 960910 722217		

Features

- Double-sided tape for use in a variety of applications

Use

- For putting small things on a chalkboard or whiteboard
- For personal hobby use

Specifications

	72153	72154
Material	Ferrite	
Orientation	Isotropy	
Adsorption Power	0.75 N (75 gf)	

	72155	72156	72221
Material	Ferrite		
Orientation	Isotropy		
Adsorption Power	1 N (100 gf)	0.85 N (85 gf)	1.4 N (140 gf)

Magnetic Chips Square with Yoke



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
73501	E-1 13 x 22 mm 2 pc-pack	13×22×5.5	7	4 960910 735019	10	
73502	E-2 23 x 26 mm 2 pc-pack	23×26×7	21	4 960910 735026		
73503	E-3 30 x 44 mm 2 pc-pack	30×44×7	42	4 960910 735033		

Features

- Strong magnet with yoke
- Double-sided tape for use in a variety of applications

Use

- For putting small things on a chalkboard or whiteboard
- For personal hobby use

Specifications

	73501	73502	73503
Material	Ferrite		
Orientation	Anisotropy		
Adsorption Power	7 N (0.7 kgf)	25 N (2.5 kgf)	32 N (3.2 kgf)

Strong Color Magnets with Yoke

 Adsorption power
1 N
 100 gf



72052

 Adsorption power
3 N
 300 gf



72058

 Adsorption power
4 N
 400 gf


72079

 Adsorption power
4.5 N
 450 gf


72071

 Adsorption power
5 N
 500 gf


72072

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72052	φ20 Red 6 pc-pack	φ20×9	4	4 960910 720527	10	
72053	φ20 White 6 pc-pack	φ20×9	4	4 960910 720534	10	
72077	φ20 Blue 6 pc-pack	φ20×9	4	4 960910 720770	10	
72056	φ20 Yellow 6 pc-pack	φ20×9	4	4 960910 720565	10	
72057	φ25 Red 5 pc-pack	φ25×10	9	4 960910 720572	10	
72058	φ25 White 5 pc-pack	φ25×10	9	4 960910 720589	10	
72078	φ25 Blue 5 pc-pack	φ25×10	9	4 960910 720787	10	
72061	φ25 Yellow 5 pc-pack	φ25×10	9	4 960910 720619	10	
72062	φ30 Red 4 pc-pack	φ30×10	12	4 960910 720626	10	
72063	φ30 White 4 pc-pack	φ30×10	12	4 960910 720633	10	
72079	φ30 Blue 4 pc-pack	φ30×10	12	4 960910 720794	10	
72066	φ30 Yellow 4 pc-pack	φ30×10	12	4 960910 720664	10	
72067	φ40 Red 3 pc-pack	φ40×11	18	4 960910 720671	10	
72068	φ40 White 3 pc-pack	φ40×11	18	4 960910 720688	10	
72080	φ40 Blue 3 pc-pack	φ40×11	18	4 960910 720800	10	
72071	φ40 Yellow 3 pc-pack	φ40×11	18	4 960910 720718	10	
72072	φ50 Red 2 pc-pack	φ50×12	28	4 960910 720725	10	
72073	φ50 White 2 pc-pack	φ50×12	28	4 960910 720732	10	
72081	φ50 Blue 2 pc-pack	φ50×12	28	4 960910 720817	10	
72076	φ50 Yellow 2 pc-pack	φ50×12	28	4 960910 720763	10	

Features

- Strong magnet with yoke



Use

- As a memo holder on a chalkboard, steel object, and refrigerator

Specifications

	72052	72053	72077	72056
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	1 N (100 gf)			


	72057	72058	72078	72061
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	3 N (300 gf)			

	72062	72063	72079	72066
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	4 N (400 gf)			

	72067	72068	72080	72071
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	4.5 N (450 gf)			

	72072	72073	72081	72076
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	5 N (500 gf)			


Strong color magnet cross section



JIS JIS mark With red numbers cm/shaku (Upper side (or Front) metric / Lower side (or Back) shaku) With magnet Vial with luminous sheet Thermometer Double-sided tape Letters in Japanese With stopper Oil Glass lens With edge

Japanese zodiac signs With battery shaku/cm (Upper side (or Front) shaku / Lower side (or Back) metric) With non-slip pad Thermometer/Hygrometer Hygrometer With hanging hole Letters in English With direction arrow With grid scale Plastic lens

Strong Color Magnets with Yoke in Vinyl Bag



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
71824	φ20 Red 6 pc-pack	φ20×9	4	4 960910 718241	10	
71825	φ20 White 6 pc-pack	φ20×9	4	4 960910 718258		
71826	φ20 Blue 6 pc-pack	φ20×9	4	4 960910 718265		
71827	φ20 Yellow 6 pc-pack	φ20×9	4	4 960910 718272		
71828	φ30 Red 6 pc-pack	φ30×10	12	4 960910 718289		
71829	φ30 White 6 pc-pack	φ30×10	12	4 960910 718296		
71830	φ30 Blue 6 pc-pack	φ30×10	12	4 960910 718302		
71831	φ30 Yellow 6 pc-pack	φ30×10	12	4 960910 718319		
71832	φ40 Red 6 pc-pack	φ40×11	18	4 960910 718326		
71833	φ40 White 6 pc-pack	φ40×11	18	4 960910 718333		
71834	φ40 Blue 6 pc-pack	φ40×11	18	4 960910 718340		
71835	φ40 Yellow 6 pc-pack	φ40×11	18	4 960910 718357		

Features

- Strong magnet with yoke


Use

- As a memo holder on a chalkboard, steel object, and refrigerator


Specifications

	71824	71825	71826	71827
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	1 N (100 gf)			
	71828	71829	71830	71831
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	4 N (400 gf)			
	71832	71833	71834	71835
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	4.5 N (450 gf)			

Strong color magnet cross section



Color Magnets



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72010	φ20 Red 5 pc-pack	φ20×9	4	4 960910 720107	10	
72011	φ20 White 5 pc-pack	φ20×9	4	4 960910 720114		
72012	φ20 Blue 5 pc-pack	φ20×9	4	4 960910 720121		
72014	φ20 Yellow 5 pc-pack	φ20×9	4	4 960910 720145		
72015	φ30 Red 3 pc-pack	φ30×9	8	4 960910 720152		
72016	φ30 White 3 pc-pack	φ30×9	8	4 960910 720169		
72017	φ30 Blue 3 pc-pack	φ30×9	8	4 960910 720176		
72019	φ30 Yellow 3 pc-pack	φ30×9	8	4 960910 720190		
72020	φ40 Red 2 pc-pack	φ40×10	14	4 960910 720206		
72021	φ40 White 2 pc-pack	φ40×10	14	4 960910 720213		
72022	φ40 Blue 2 pc-pack	φ40×10	14	4 960910 720220		
72024	φ40 Yellow 2 pc-pack	φ40×10	14	4 960910 720244		

Features

- Convenient memo holder




Use

- As a memo holder on a chalkboard, metal object, and refrigerator

Specifications

	72010	72011	72012	72014
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	0.8 N (80 gf)			
	72015	72016	72017	72019
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	1 N (100 gf)			
	72020	72021	72022	72024
Material	Body (cover): Polystyrene resin Magnet: Ferrite			
Orientation	Isotropy			
Adsorption Power	3 N (300 gf)			

Color magnet cross section



Magnetic Clips Flexible

Adsorption power
10 N
1 kgf



72126

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72126	D White 2 pc-pack	44×36×25	21	4 960910 721265	10	

Features

- Displays memo or price tag at any angle
- Protective tape on the magnetic face protects the surface from getting scratched

Use

- For placing memos, prices and POP displays on a chalkboard, steel object, and refrigerator, etc.

Specifications

Material	Body (clip part): ABS resin Magnet: Ferrite
Orientation	Isotropy
Adsorption Power	10 N (1 kgf)

Magnetic Hanger Square

Withstand load
2 kg



72032



72084




72085

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72032	B Yellow	33×26×15	62	4 960910 720329	10	
72084	B Red	33×26×15	62	4 960910 720848		
72085	B Blue	33×26×15	62	4 960910 720855		

Features

- Magnet with a hook that will hold a bag, key, or any small thing
- Adhesive for sticking to non-metallic surfaces
- Unfixed hook makes it usable on a ceiling as well



Use

- For hanging bags or small articles

Specifications

	72032	72084	72085
Material	Body (cover): Iron Magnet: Ferrite		
Accessories	Steel plate with adhesive		
Orientation	Isotropy		
Withstand Load	2 kg		

Ultra Strong Magnetic Hanger

Maximum withstand load
5 kg



73500




73510

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
73500	Square C	47×50×13	135	4 960910 735002	10	
73510	Circle D	φ76×10	323	4 960910 735101		

Features

- Ultra strong model with an anisotropic magnet
- Protective tape on the magnetic face protects the surface from getting scratched. If stronger magnetic force is required, use without the tape.
- *Load capacity with tape: 3 kg
without tape: 5 kg
- Unfixed hook makes it usable on a ceiling as well (73500)



Use

- For hanging bags or small articles

Specifications

	73500	73510
Material	Body: Iron Magnet: Ferrite	
Orientation	Anisotropy	
Withstand Load	3 - 5 kg	

Magnetic Bar 25 cm

 Adsorption power
4 N
 400 gf


Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72033	Red	250×15×7.5	50	4 960910 720336	10	
72034	Blue	250×15×7.5	50	4 960910 720343		
72035	Yellow	250×15×7.5	50	4 960910 720350		

Features

- Makes it easy to display large paper materials such as maps, graphs, charts, documents and memos



Use

- For displaying maps, graphs and documents

Specifications

	72033	72034	72035
Material	Body (cover): Vinyl chloride resin Magnet: Ferrite		
Orientation	Isotropy		
Adsorption Power	4 N (400 gf)		

Magnet Stick

 Adsorption power
0.2 N
 20 gf


73514

 Adsorption power
0.5 N
 50 gf


73515

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
73514	Pair of Circle A	φ9×90	45	4 960910 735149	10	
73515	Pair of Square B	150×19×6	125	4 960910 735156		

Features

- Pair of NS magnets
- Stick type can be stored in narrow spaces

Use

- As a teaching aid in science class, etc.

Specifications

	73514	73515
Material	Body: High carbon steel	
Adsorption Power	0.2 N (20 gf)	0.5 N (50 gf)

U-shaped Magnet

 Adsorption power
6 N
 600 gf


73530


 Adsorption power
4.5 N
 450 gf

73532


 Adsorption power
2.5 N
 250 gf

73531


 Adsorption power
1 N
 100 gf

73533



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging	
73530	A-1	100×65×8	300	4 960910 735309	5		
73532	A-2	77×57×8	250	4 960910 735323			
73531	B-1	90×52×5	150	4 960910 735316	10		
73533	B-2	62×44×4	50	4 960910 735330			

Features

- NS magnet
- Strong force type (73530/73532)
- Lightweight, compact type (73531/73533)

Use

- As a tool for collecting nails, etc. (73530/73532)
- As a teaching aid in science class, etc. (73531/73533)


Specifications

	73530	73532
Material	Body: High carbon steel	
Adsorption Power	6 N (600 gf)	4.5 N (450 gf)

	73531	73533
Material	Body: High carbon steel	
Adsorption Power	2.5 N (250 gf)	1 N (100 gf)

Steel Sheet 10 x 20 cm 0.2 mm Thick with Adhesive

72200



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72200	Steel Sheet 2 pc-pack	100×200×0.2	13	4 960910 722002	5	

Features

- Non-magnetic surfaces such as wood, glass, and acrylic become magnetic by attaching the sheet
- Easy-to-cut in any desired shape with scissors or cutter
- Sheet type can be attached even to a curved surface

Use

- As a base for affixing magnets


Specifications

Material	Iron
----------	------

Magnetic Sheet 10 x 20 cm 1.2 mm Thick with Adhesive

Adsorption power
0.13
N/cm²
13 gf/cm²

72009



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72009	10 × 20 cm	100×200×1.2	80	4 960910 720091	5	

Features

- Easy-to-cut in any shape with scissors or cutter. Adhere the magnetic sheet to an object and it can be attached to steel, etc.
- Sheet type can be attached even to a curved surface

Use

- For sticking up a poster, calendar, and posting material, etc.

Specifications

Material	Storontium ferrite, chlorinated polyethylene
Orientation	Isotropy
Adsorption Power	0.13 N/cm ² (13 gf/cm ²)

Magnetic Sheet Piece 10 x 20 mm 0.8 mm Thick with Adhesive

Adsorption power
0.11
N/cm²
11 gf/cm²

72182



Size of 1 piece: 10 × 20 mm

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72182	C-1 100 pc-pack	100×200×0.8	51	4 960910 721821	5	

Features

- Adhere a piece of magnetic sheet to an object and it can be attached to steel, etc.
- Already cut-out pieces come in handy for using on small objects

Use

- For sticking up a poster, calendar, or posting material, etc.

Specifications

Material	Storontium ferrite, chlorinated polyethylene
Orientation	Isotropy
Adsorption Power	0.11 N/cm ² (11 gf/cm ²)

Magnetic Sheet 0.8 mm Thick

Adsorption power
0.09
N/cm²
9 gf/cm²



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Packaging
72042	Gloss A Red 10 × 20 cm	100×200×0.8	48	4 960910 720428	5	
72043	Gloss A White 10 × 20 cm	100×200×0.8	48	4 960910 720435		
72044	Gloss A Yellow 10 × 20 cm	100×200×0.8	48	4 960910 720442		
72045	Gloss A Green 10 × 20 cm	100×200×0.8	48	4 960910 720459		
72046	Gloss A Blue 10 × 20 cm	100×200×0.8	48	4 960910 720466		
72047	Mat B Red 10 × 30 cm	100×300×0.8	80	4 960910 720473		
72048	Mat B White 10 × 30 cm	100×300×0.8	80	4 960910 720480		
72049	Mat B Yellow 10 × 30 cm	100×300×0.8	80	4 960910 720497		
72050	Mat B Green 10 × 30 cm	100×300×0.8	80	4 960910 720503		
72051	Mat B Blue 10 × 30 cm	100×300×0.8	80	4 960910 720510		

Features

- Easily cut out any desired shape with scissors or cutter and stick on a chalkboard, steel, or refrigerator, etc.
- Sheet allows attaching even to a curved surface
- Gloss enables it to use as a whiteboard
- Convenient to write on for displays
- Uses are only limited by your ideas, such as sticking on a car, displaying a price of an item, etc.

Use

- For various displays

Specifications

	72042	72043	72044	
Material	Magnet: Storontium ferrite, chlorinated polyethylene Surface: Chlorinated polyvinyl chloride resin			
Orientation	Isotropy			
Adsorption Power	0.09 N/cm ² (9 gf/cm ²)			
	72045	72046	72047	
Material	Magnet: Storontium ferrite, chlorinated polyethylene Surface: Chlorinated polyvinyl chloride resin			
Orientation	Isotropy			
Adsorption Power	0.09 N/cm ² (9 gf/cm ²)			
	72048	72049	72050	72051
Material	Magnet: Storontium ferrite, chlorinated polyethylene Surface: Chlorinated polyvinyl chloride resin			
Orientation	Isotropy			
Adsorption Power	0.09 N/cm ² (9 gf/cm ²)			

Fluorescent Magnetic Sheet Gloss A 10 x 20 cm 0.8 mm Thick

 Adsorption power
0.11
 N/cm²
 11 gf/cm²

72204



Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72204	Yellow	100×200×0.8	55	4 960910 722040	5	

Features

- Stands out with fluorescent color
- Stronger type with semi-anisotropic magnet
- Easily cut out any desired shape with scissors or cutter and stick on a chalkboard, steel, or refrigerator, etc.
- Sheet can be attached even to a curved surface
- Gloss enables it to use as a whiteboard
- Convenient to write on for displays
- Uses are only limited by your ideas, such as sticking on a car, displaying a price of an item, etc.


Use

- For various displays

Specifications

Material	Magnet: Strontium ferrite, chlorinated polyethylene Surface: Chlorinated polyvinyl chloride resin
Orientation	Semi-anisotropic
Adsorption Power	0.11 N/cm ² (11 gf/cm ²)

Magnetic Sheet Mat 10 cm x 10 m 0.8 mm Thick

 Adsorption power
0.09
 N/cm²
 9 gf/cm²


*Please contact us separately about a display

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72215	White Roll	10 cm×10 m t=0.8 mm	3,100	4 960910 722156	1	
74015	Red Roll	10 cm×10 m t=0.8 mm	3,100	4 960910 740150		
74016	Blue Roll	10 cm×10 m t=0.8 mm	3,100	4 960910 740167		

Features

- 10 m roll allows cutting and selling in desired lengths at a store
- Easily cut out any desired shape with scissors or cutter and stick on a chalkboard, steel, or refrigerator, etc.
- Sheet can be attached even to a curved surface
- Convenient to write on for displays
- Uses are only limited by your ideas, such as sticking on a car, displaying a price of an item, etc.


Use

- For various displays

Specifications

	72215	74015	74016
Material	Magnet: Strontium ferrite, chlorinated polyethylene Surface: Chlorinated polyvinyl chloride resin		
Orientation	Isotropy		
Adsorption Power	0.09 N/cm ² (9 gf/cm ²)		

Rubber Magnetic Sheet 10 cm x 10 m 0.8 mm Thick

 Adsorption power
0.09
 N/cm²
 9 gf/cm²


72086

*Please contact us separately about a display

Item Code	Description	Body Size (mm)	Weight (g)	JAN Code	Packing Unit	Package
72086	Black Roll	10 cm×10 m t=0.8 mm	3,000	4 960910 720862	1	

Features


- 10 m roll type allows cutting and selling in desired lengths at a store
- Easily cut out any desired shape with scissors or cutter and stick on a chalkboard, steel, or refrigerator, etc.
- Sheet can be attached even to a curved surface

Use

- For sticking up a poster, calendar, or posting material, etc.

Specifications

Material	Strontium ferrite, chlorinated polyethylene
Orientation	Isotropy
Adsorption Power	0.09 N/cm ² (9 gf/cm ²)



Method of measuring adsorption power

Let a magnet stick to a piece of iron (adsorption area 14×20 mm). Pull it straight up from the adsorption face and read the measurement value when the piece of metal comes off the magnet.

- Adsorption power: 1 gf=0.0098 N
- Load capacity: maximum weight that can be put on a hook.

*Adsorption power and load capacity are listed as references. Please be cautious as they can vary depending on the thickness of iron or coating.

Orientation

Isotropic magnet



Anisotropic magnet



Semi-anisotropic magnet



Ferrite magnet and rubber magnet sheet can be classified roughly into isotropic magnets or anisotropic magnets depending on types of magnetic materials and shapes of crystals.

- An isotropic magnet has a random structure of ferrite (crystal) and its direction is not fixed, so its adsorption is uniformly strong from any direction.
- An anisotropic magnet has a stable structure of ferrite that forms in the same direction and has better magnetic characteristics compared to isotropic magnet.
- Semi-anisotropic magnet has an intermediate character.

Parts List

Carpenter's Square with Fence



99080



Item Code	C. D.	Catalog Printing Page	Description
99080	7	23	Countersunk screws for Carpenter's Square with Fence


Rule Stopper



82415



82873



Item Code	C. D.	Catalog Printing Page	Description
82415	7	32	Stopper screw for Rule Stopper for 15, 30, 60 cm
82873	5	32	Stopper screw for Rule Stopper for 1, 1.5, 2 m

Aluminum Rule Non-Slip Pad



84270

Item Code	C. D.	Catalog Printing Page	Description
84270	0	38	Non-slip pad for Aluminum Rule 30 - 60 cm, 1 m

Aluminum Cutting Rule



85518




99556



84259


Item Code	C. D.	Catalog Printing Page	Description
85518	2	39	Handle, screw set for Aluminum Cutting Rule EX
99556	7	40	Handle, screw set for Aluminum Cutting Rule
84259	5	40	Handle for Aluminum Cutting Rule Light
80741	9	39	Non-slip rubber sheet for Aluminum Cutting Rule EX 60 cm, 1 m
82650	2	39	Non-slip rubber sheet for Aluminum Cutting Rule EX 1.5 cm, 2 m
73930	7	40	Non-slip rubber for Aluminum Cutting Rule

Telescopic Measure One Direction II



Item Code	C. D.	Catalog Printing Page	Description
81102	7	41	Stopper lever 1 red, shaft, screw set for Telescopic Measure One Direction II
81103	4	41	Stopper lever 2 yellow, shaft, screw set for Telescopic Measure One Direction II
81100	3	41	Plastic end A with hook, nut, screw set for Telescopic Measure One Direction II
81101	0	41	Plastic end B, nut, screw set for Telescopic Measure One Direction II

Telescopic Measure One Direction




Item Code	C. D.	Catalog Printing Page	Description
82100	2	41	Stopper lever ① red, shaft, screw set for Telescopic Measure One Direction
82101	9	41	Stopper lever ② yellow, shaft, screw set for Telescopic Measure One Direction
82048	7	41	Upper cap, screw set for Telescopic Measure One Direction
82049	4	41	Lower cap, screw set for Telescopic Measure One Direction

Telescopic Measure Two Directions



Item Code	C. D.	Catalog Printing Page	Description
81551	3	42	Side cap, screw set for Telescopic Measure Two Directions
99755	4	42	Stopper knob ① red for Telescopic Measure Two Directions
99756	1	42	Stopper knob ② yellow for Telescopic Measure Two Directions

Shaku Measure, Ken Measure, Sumiki Shaku Measure




Item Code	C. D.	Catalog Printing Page	Description
99553	6	42/43	Rubber cap for Shaku Measure, Ken Measure, Sumiki Shaku Measure

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)

JAN code number is "4960910 + item code + C.D."

Japanese Sliding Bevel

99559




Item Code	C. D.	Catalog Printing Page	Description
99559	8	48	Nut, center screw set for Japanese Sliding Bevel

Aluminum Sliding Bevel



62546



62547

84730

62548

84730



62547



62548



*The nut and plastic washer can also be used for Welding Guide Rule.

Item Code	C. D.	Catalog Printing Page	Description
84730	9	49	Grip Nut for Aluminum Sliding Bevel
62546	4	49/148	Nut for Aluminum Sliding Bevel and Welding Guide Rule
62547	1	49/148	Plastic washer for Aluminum Sliding Bevel and Welding Guide Rule
62548	8	49	Center screw for Aluminum Sliding Bevel

Protractor

No.30



99506


No.101



99507

Item Code	C. D.	Catalog Printing Page	Description
99505	5	51/52	Nut, washer set for Protractor No.19
99506	2	51	Nut, washer, brass washer set for Protractor No.30
99507	9	51	Nut, center screw set for Protractor No.101
99516	1	51	End nut, iron bolt set for Protractor No.300 Double-blade
99517	8	51	End nut, iron bolt set for Protractor No.600 Double-blade
99518	5	51	End nut, iron bolt set for Protractor No.1000 Double-blade

Vernier Caliper



99523

99563

98911

98912

Item Code	C. D.	Catalog Printing Page	Description
99523	9	53	Stopper knob for Vernier Caliper 150 mm
99563	5	53	Depth probe holding plate, screw set for Vernier Caliper 150 mm
99524	6	53	Stopper knob for Vernier Caliper 200 mm
99564	2	53	Depth probe holding plate, screw set for Vernier Caliper 200 mm
99567	3	53	Depth probe holding plate, screw set for Vernier Caliper 300 mm
98911	5	53	Stopper knob for Vernier Caliper 450, 600 mm
98912	2	53	Fine adjustment knob for Vernier Caliper 450, 600 mm
98913	9	53	Stopper knob for Vernier Caliper 1000 mm
98914	6	53	Fine adjustment knob for Vernier Caliper 1000 mm
99525	3	54	Stopper knob for Mini Vernier Caliper 100 mm
99565	9	54	Depth probe holding plate, screw set for Mini Vernier Caliper 100 mm
82890	2	54	Stopper knob for Mini Vernier Caliper 70 mm

Digital Vernier Caliper



98767

98764

98765

98907

98909


Item Code	C. D.	Catalog Printing Page	Description
98771	5	55	Battery cap, screw set for Digital Vernier Caliper Mini
98764	7	55	Battery cap, screw set for Digital Vernier Caliper 150 - 300 mm
98907	8	55	Battery cap for Digital Vernier Caliper 450, 600 mm
98908	5	55	Battery cap for Digital Vernier Caliper 1000 mm
98765	4	55	Depth probe holding plate, screw set for Digital Vernier Caliper 150 mm and 200 mm
98766	1	55	Depth probe holding plate, screw set for Digital Vernier Caliper 300 mm
98767	8	55	Stopper knob for Digital Vernier Caliper 150 - 300 mm
98909	2	55	Fine adjustment knob for Digital Vernier Caliper 450, 600 mm
98910	8	55	Fine adjustment knob for Digital Vernier Caliper 1000 mm
98774	6	55	Digital part replacement for Digital Vernier Caliper Mini *
98768	5	55	Digital part replacement for Digital Vernier Caliper 150 mm *
98769	2	55	Digital part replacement for Digital Vernier Caliper 200 mm *
98770	8	55	Digital part replacement for Digital Vernier Caliper 300 mm *
98905	4	55	Digital part replacement for Digital Vernier Caliper 450, 600 mm *
98906	1	55	Digital part replacement for Digital Vernier Caliper 1000 mm *

*Please ask about digital unit replacement service

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)


JAN code number is "4960910 + item code + C.D."

Digital Vernier Caliper Carbon Fiber Body



Item Code	C. D.	Catalog Printing Page	Description
98755	5	56	Battery cap for Digital Vernier Caliper Carbon Fiber Body 100 mm
98756	2	56/57	Battery cap for Digital Vernier Caliper Carbon Fiber Body 150 mm and Digital Depth Gauge

Telescopic Leveling Staff



Item Code	C. D.	Catalog Printing Page	Description
76963	2	66	Lock button for Telescopic Leveling Staff
73269	8	66	Lock button for Telescopic Leveling Staff II

Measuring Wheel



77199

Item Code	C. D.	Catalog Printing Page	Description
77199	4	—	Rubber wheel for Measuring Wheel B20-S

Digital Scale with Plate



70120

70121

Item Code	C. D.	Catalog Printing Page	Description
70120	5	81	Stainless steel plate for Digital Scale
70121	2	81	Plastic plate for Digital Scale


Digital Scale with Stand



97217

Item Code	C. D.	Catalog Printing Page	Description
97217	9	82	AC adapter for Digital Scale with Stand 100 kg

Scale



Item Code	C. D.	Catalog Printing Page	Description
70128	1	83	Plate flat type for Scale 200 g - 1 kg
70129	8	83	Plate flat type for Scale 2 kg - 12 kg
70139	7	83	Plate flat type for Scale 20 kg
70140	3	83	Plate flat type for Scale 30 kg
70143	4	83	Plastic cover for Scale 200 g - 1 kg
70144	1	83	Plastic cover for Scale 2 kg - 12 kg
70145	8	83	Plastic cover for Scale 20 kg
70146	5	83	Plastic cover for Scale 30 kg
81521	6	83	Plastic cover for Scale 50 kg
70131	1	83	Plate fixing screw one pair (2 pc-set) for Scale 200 g - 30 kg

Slope Level



47049

Item Code	C. D.	Catalog Printing Page	Description
47049	1	87	Vial cover for Slope Level

Mini Level



84267

Item Code	C. D.	Catalog Printing Page	Description
84267	0	91	Band for Mini Level H

Blue Level Digital



46967

Item Code	C. D.	Catalog Printing Page	Description
46967	9	92	Digital part replacement for Blue Level Digital*
98925	2	92	Battery cap for Blue Level Digital

*Please ask about digital unit replacement service

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)

JAN code number is "4960910 + item code + C.D."

Laser ROBO

Level adjustment tripod adapter



76768

76924

Emitting port protective cap



80826

Battery storage cap



80802

80800

80713

80773

80801

80799

80732

81210

Handle



80733

67823

Toe



80781

Aluminum case



82228

82235

76925


Receiver holder



76659

83832

AC adapter




76791

76962

Item Code	C. D.	Catalog Printing Page	Description
76768	3	97 -	Level adjustment tripod adapter for Laser ROBO Neo, E Sensor and X line
76924	3	109	Level adjustment tripod adapter for Laser ROBO Fine BRIGHT
80826	3	97	Emitting port protective cap for Laser ROBO X line
80802	7	97	Battery storage cap for Laser ROBO X line Green
80801	0	97	Battery storage cap for Laser ROBO X line Red
80800	3	100	Battery storage cap for Laser ROBO Green Neo E Sensor
80799	0	101	Battery storage cap for Laser ROBO Neo E Sensor
80713	6	104	Battery storage cap for Laser ROBO Green Neo AR BRIGHT
80732	7	105	Battery storage cap for Laser ROBO Neo AR BRIGHT
80773	0	106	Battery storage cap for Laser ROBO Green Neo BRIGHT
81210	9	107	Battery storage cap for Laser ROBO Neo BRIGHT
80733	4	104/105	Handle for Laser ROBO Neo AR BRIGHT
67823	1	100 -	Handle for Laser ROBO Neo BRIGHT and E Sensor
80781	5	97 -	Toe for Laser ROBO Neo BRIGHT, E Sensor and X line
82228	3	97	Aluminum case for Laser ROBO X line
82235	1	100 -	Aluminum case for Laser ROBO Neo BRIGHT and E Sensor
76925	0	109	Aluminum case for Laser ROBO Fine BRIGHT
76659	4	110	Holder for Laser Receiver, model II and Plus
83832	1	112	Receiver holder for Rotating Laser H-2, HV-2
76791	1	97 -	AC adapter for Laser ROBO Green, E Sensor and X line
76962	5	109	AC adapter for Laser ROBO Fine 3C

Laser Holder



Item Code	C. D.	Catalog Printing Page	Description of Product
97905	5	111	Fixing screw for Laser Holder
97906	2	111	Aluminum nut large for Laser Holder
97907	9	111	Aluminum nut small for Laser Holder

Auto Level



Item Code	C. D.	Catalog Printing Page	Description
73844	7	112	Storage case for Auto Level SA-24A and 28A
46804	7	112	Protective cap for Auto Level SA-24A and 28A

Tripod



Item Code	C. D.	Catalog Printing Page	Description
83701	0	113	Handle for Tripod with Handle A
98917	7	113	Handle for Tripod with Handle B
98919	1	113	Handle for Tripod with Handle C
81570	4	113	Stopper screw for Tripod with Handle A
81856	9	113	Carrying case for Tripod with Handle A
97531	6	113	Adjustment core for Tripod Spherical Head
97533	0	113	Stopper screw on adjustment core rail for Tripod Spherical Head

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)

JAN code number is "4960910 + item code + C.D."

Handy Ink Line Marker PRO/Jr. Plus



93287



93297



93280

Item Code	C. D.	Catalog Printing Page	Description
93287	6	115	Spring set (with string) for Handy Ink Line Marker PRO Plus Tough Line
93288	3	115	Spring set (with string) for Handy Ink Line Marker Jr. Plus Tough Line
93297	5	115	Spring set (with string) for Handy Ink Line Marker Pro Plus Sharp Line
93298	2	115	Spring set (with string) for Handy Ink Line Marker Jr. Plus Sharp Line
93280	7	116	Spring set (with string) for Handy Ink Line Marker PRO Plus
93281	4	116	Spring set (with string) for Handy Ink Line Marker Jr. Plus

Handy Ink Line Marker Pro/Jr. LITE



93300

Item Code	C. D.	Catalog Printing Page	Description
93300	2	117	Spring set (with string) for Handy Ink Line Marker PRO LITE
93301	9	117	Spring set (with string) for Handy Ink Line Marker Jr. LITE

Handy Ink Line Marker Miniα



80790

Item Code	C. D.	Catalog Printing Page	Description
80790	7	—	Threader for Handy Ink Line Marker Miniα

Handy Ink Line Marker SUMIWAZA



77907



83653

Item Code	C. D.	Catalog Printing Page	Description
77907	5	118	Ratchet ring for Handy Ink Line Marker SUMIWAZA and Mini α
83653	2	118	Thread holding guide for Handy Ink Line Marker SUMIWAZA

Handy Chalk Line Neo



80665

Item Code	C. D.	Catalog Printing Page	Description
80665	8	119	Screw for Handy Chalk Line Neo

Wind-resistant Plumb



77556

Upper fixing screw

77556

Spacer

77559


Spring



77604

Item Code	C. D.	Catalog Printing Page	Description
77553	4	123	Rubber band for Wind-resistant Plumb
77556	5	123	Upper fixing screw, spacer, spring set for Wind-resistant Plumb
77559	6	123	Lower fixing screw, spacer, spring set for Wind-resistant Plumb
77604	3	123	Carrying case for Wind-resistant Plumb

Holder for Wind-resistant Plumb with Quick Arm



77648

Item Code	C. D.	Catalog Printing Page	Description
77648	7	123	Arm for Holder for Wind-resistant Plumb with Quick Arm

Handy Plumb Holder Pro



77811

77926

Item Code	C. D.	Catalog Printing Page	Description
77926	6	124	Pin cover for Handy Plumb Holder Pro Auto-rewind Red
77959	4	124	Pin cover for Handy Plumb Holder Pro Hand-rewind Blue
77811	5	124	Coil Spring for Handy Plumb Holder Pro

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)

JAN code number is "4960910 + item code + C.D."

Handy Plumb Holder Jr.



Item Code	C. D.	Catalog Printing Page	Description
78094	1	124	Pin cover for Handy Plumb Holder Jr.
77956	3	124	Coil Spring for Handy Plumb Holder Jr.

Circular Saw Guide L-Angle Series Handle



83737
L-Angle II
L-Angle Adjust



99608
L-Angle with Support Plate
L-Angle with Horizontal Graduations
L-Angle for Left Hand



99552
L-Angle/L-Angle II
L-Angle Adjust
L-Angle EX



98790
L-Angle EX 45 cm and 60 cm




98791
L-Angle EX 1 m



93310
L-Angle Plus

Item Code	C. D.	Catalog Printing Page	Description
83737	9	—	Handle for L-Angle II and L-Angle Adjust
99608	3	136/137	Handle for L-Angle with Support Plate, with Horizontal Graduations, and for Left Hand
99552	9	132	Handle installing screw for L-Angle II, Adjust, and EX
98790	6	132	Handle screw set for L-Angle EX 45 cm and 60 cm
98791	3	132	Handle screw set for L-Angle EX 1 m
93310	1	133	Handle non-slip rubber, screw set for L-Angle Plus

Circular Saw Guide L-Angle Series



83464
Mini Free Angle II
L-Angle II
L-Angle EX

Item Code	C. D.	Catalog Printing Page	Description
77894	8	136	Support plate for L-Angle with Support Plate 45 cm
77884	9	136	Support plate for L-Angle with Support Plate 60 cm
77893	1	136	Support plate for L-Angle with Support Plate 1 m
84231	1	136	Support plate installing screw for L-Angle with Support Plate
99249	8	135	Cutout positioning stick fixing screw for L-Angle II, Plus, with Support Plate, with Horizontal Graduations, and for Left Hand
80925	3	134/141	Cutout positioning stick fixing screw for L-Angle Adjust and Free Angle Neo
99606	9	136/136	Bracing fitting for L-Angle for L-Angle with Support Plate, with Horizontal Graduations, and for Left-hand 1 m
93316	3	133	Adjustment knob, movable pin, indicator, washer set for L-Angle Plus Shift
93401	6	134	Fine adjustment screw set for L-Angle Plus Adjust
80908	6	138	Stainless steel plate for L-Angle Mini 15 cm and Fit 15 cm
84020	1	137	Stainless steel plate for L-Angle 45 cm, II 45 cm and Adjust 45 cm
85273	0	132	Stainless steel plate for L-Angle EX 45 cm and Plus 45 cm
73877	5	132	Stainless steel plate for L-Angle II 60 cm, Adjust 60 cm, EX 60 cm and Plus 60 cm
84287	8	132	Stainless steel plate for L-Angle II 1 m, Adjust 1 m, EX 1 m and Plus 1 m
93313	2	134	Stainless steel plate for L-Angle Adjust 1.2 m and Plus 1.2 m
47234	1	134/141	Cutout positioning stick for L-Angle Adjust 45 - 60 cm and Free Angle Neo 30 - 45 cm
47235	8	134/141	Cutout positioning stick for L-Angle Adjust 1 - 1.2 m and Free Angle Neo 60 - 1 m
99203	0	135	Cutout positioning stick for Mini Free Angle Justy 23 cm, L-Angle II 45 cm - 60 cm and L-Angle Plus
99232	0	132	Cutout positioning stick for Mini Free Angle, L-Angle II 1 m and EX 1 m
83464	4	132	Non-slip rubber triangle for Mini Free Angle II, L-Angle II and EX
93311	8	133	Upper protective cap for L-Angle Plus
93312	5	133	Lower protective cap for L-Angle Plus

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)

JAN code number is "4960910 + item code + C.D."

Circular Saw Guide T-Slide Series



47358
T-Slide II
T-Slide Double
T-Slide Slim shift



47359
T-Slide II
T-Slide Double



47386
T-Slide Slim shift



47364
T-Slide II





47365
T-Slide Double




47383
T-Slide Slim shift

Item Code	C.D.	Catalog Printing Page	Description
47358	4	139/140	Guide stabilization metal fitting for T-Slide II, Double and Slim-shift
47359	1	139/140	Mounting position adjustment screw for T-slide II and Double
47364	5	139	Slider for T-Slide II
47365	2	140	Slider for T-Slide Double
47383	6	139	Slider for T-Slide Slim-shift
47386	7	139	Mounting position adjustment screw for T-Slide Slim-shift

Circular Saw Guide I-Clamp One-touch




Mounting part A Assembly drawing



Item Code	C.D.	Catalog Printing Page	Description
99246	7	141	Cutout positioning stick fixing screw for I-Clamp One-touch
99241	2	141	Mounting part A for I-Clamp One-touch
99244	3	141	Mounting part B, screw set for I-Clamp One-touch
99243	6	141	Wedge for I-Clamp One-touch
99242	9	141	Spreading plate 2 pc-set for I-Clamp One-touch and Free Angle One-touch
99245	0	141	Edge cap, screw set for I-Clamp One-touch

Circular Saw Guide Free Angle One-touch

Name of each part (Back)



Item Code	C.D.	Catalog Printing Page	Description
78452	9	142	Assist plate, screw set for Free Angle One-touch 1 m
78453	6	142	Assist plate, screw set for Free Angle One-touch 1.2 m
78454	3	142	Front side hanging part with spring for Free Angle One-touch

Circular Saw Guide Free Angle Series



85959
Mini Free Angle II
Mini Free Angle Justy II
Free Angle Neo



99604
Mini Free Angle Quick Adjust
Mini Free Angle Justy Quick Adjust



99602
Free Angle One-touch
Free Angle Multi



99251
Mini Free Angle Justy
Free Angle Series



78237

*Cutout positioning stick for Mini Free Angle II 23 cm/L-Angle II 45 - 60 cm/ L-Angle Plus, cutout positioning stick for Mini Free Angle II/L-Angle II 1 m/EX1 m, and anti-slip rubber triangle for Mini Free Angle II/L-Angle II/EX are listed under the L-Angle Series (P219).

Item Code	C.D.	Catalog Printing Page	Description
85959	3	141	Stopper screw, bolt, metal washer set for Mini Free Angle II, Justy II and Neo
99604	5	143	Stopper screw, bolt, metal washer set for Mini Free Angle Quick Adjust and Justy Quick Adjust
99602	1	142	Stopper screw, bolt, metal washer set for Free Angle One-touch and Multi
99251	1	141	Thin stopper screw, bolt, metal washer set for Mini Free Angle Justy and Free Angle
78237	2	142	Aluminum guide fixing screw for Free Angle Multi
99605	2	143	Cutout positioning stick fixing screw for Mini Free Angle II and Justy II

Stud Finder

80697



Item Code	C.D.	Catalog Printing Page	Description
80620	7	—	Spring for Stud Finder L
80697	9	—	Spring for Stud Finder L with Magnet
80634	4	—	Spring for Stud Finder LL

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)


JAN code number is "4960910 + item code + C.D."

Digital Moisture Meter for Wood



Item Code	C.D.	Catalog Printing Page	Description
96061	9	146	Needle pin 2 pc-pack for Digital Moisture Meter for Wood
96063	3	146	Protective cap for Digital Moisture Meter for Wood


Welding Guide Rule



*The nut and plastic washer can also be used for Aluminum Sliding Bevel as well (P215).

Item Code	C.D.	Catalog Printing Page	Description
83440	8	148	Center screw for Welding Guide Rule
83525	2	148	Magnet for Welding Guide Rule

Dial Gauge




Item Code	C.D.	Catalog Printing Page	Description
81365	6	156	Gauge head for Dial Gauge
81367	0	156	Back cover with lug for Dial Gauge
81369	4	156	Plastic case for Dial Gauge

Dial Indicator



Item Code	C.D.	Catalog Printing Page	Description
81370	0	156	Stem $\phi 6$ for Dial Indicator
81371	7	156	Stem $\phi 8$ for Dial Indicator
81372	4	156	Gauge head spanner for Dial Indicator
81373	1	156	Gauge head for Dial Indicator
81374	8	156	Plastic case for Dial Indicator

Magnetic Stand



Item Code	C.D.	Catalog Printing Page	Description
81375	5	157	Post for Magnetic Stand A and A-2
81376	2	157	Arm for Stand for Magnetic Stand A Standard
81380	9	157	Arm for Magnetic Stand A-2 Fine Adjustment
81377	9	157	Stopper screws complete set with knobs for Magnetic Stand A and A-2
81378	6	157	Gauge installation complete set for Magnetic Stand A and A-2

Large Inspection Mirror



Item Code	C.D.	Catalog Printing Page	Description
84116	1	157	Mirror with frame for Large Inspection Mirror C-1
84117	8	157	Mirror with frame for Large Inspection Mirror C-2

Inspection Mirror



Item Code	C.D.	Catalog Printing Page	Description
84171	0	158	Mirror with frame for Inspection Mirror A-1 and D-1
78946	3	158	Mirror with frame for Inspection Mirror A-2 and D-2
70720	7	158	Mirror with frame for Inspection Mirror A-3 and D-3
84159	8	158	Mirror with frame for Inspection Mirror A-4 and D-4
84160	4	158	Mirror with frame for Magnifying Mirror B-1
84161	1	158	Mirror with frame for Magnifying Mirror B-2
84162	8	158	Mirror with frame for Magnifying Mirror B-3
84163	5	158	Mirror with frame for Magnifying Mirror B-4
80941	3	158	Joint for Inspection Mirror A, D, Magnifying Mirror

Inspection Scope




Item Code	C.D.	Catalog Printing Page	Description
74180	5	159	Battery replacement for Inspection Scope *

*Battery change will be handled as a repair.

Please be aware that we will no longer provide components for discontinued products once the inventory runs out after discontinuation (however, this is limited to three years after discontinuation)


JAN code number is "4960910 + item code + C.D."

Auto Punch with Flat Grip to Prevent Rolling



Item Code	C. D.	Catalog Printing Page	Description
81311	3	160	Tip with superhard chip for Auto Punch M with Flat Grip to Prevent Rolling
81312	0	160	Front spring with guide pin for Auto Punch M with Flat Grip to Prevent Rolling
81313	7	160	Hammer pin for Auto Punch M with Flat Grip to Prevent Rolling
81314	4	160	Rear spring for Auto Punch M with Flat Grip to Prevent Rolling
81315	1	160	Tip with superhard chip for Auto Punch L with Flat Grip to Prevent Rolling
81316	8	160	Front spring with guide pin for Auto Punch L with Flat Grip to Prevent Rolling
81317	5	160	Hammer pin for Auto Punch L with Flat Grip to Prevent Rolling
81318	2	160	Rear spring for Auto Punch L with Flat Grip to Prevent Rolling

Auto Punch



Item Code	C. D.	Catalog Printing Page	Description
73997	0	160	Tip with superhard chip for Auto Punch M
73994	9	160	Front spring and guide pin set for Auto Punch M
74291	8	160	Hammer pin for Auto Punch M
73993	2	160	Rear spring for Auto Punch M
73992	5	160	Tip with superhard chip for Auto Punch L
73996	3	160	Front spring and guide pin set for Auto Punch L
85773	5	160	Hammer pin for Auto Punch L
73995	6	160	Rear spring for Auto Punch L

Suction Lifter



Item Code	C. D.	Catalog Printing Page	Description
81623	7	161	Stopper for Suction Lifter Double A and Single B

Digital Thermometer



Item Code	C. D.	Catalog Printing Page	Description
73047	2	172/173	Sensor probe for Digital Thermometer G and Wireless Thermometer A

Psychrometer



Item Code	C. D.	Catalog Printing Page	Description
46845	0	176	Water tank for Psychrometer E-2

Stick Thermometer




Item Code	C. D.	Catalog Printing Page	Description
73001	4	179	Case for Stick Thermometer 15 cm
73002	1	179	Case for Stick Thermometer 30 cm
73003	8	179	Clear Case for Stick Thermometer H-3 30 cm

Magnifying Glass



Item Code	C. D.	Catalog Printing Page	Description
76507	8	190	Light bulb for Magnifier with Light for Reading E and F

Drawing Divider



Item Code	C. D.	Catalog Printing Page	Description
74458	5	198	Replacement lead for Drawing Divider

Hand Magnet



Item Code	C. D.	Catalog Printing Page	Description
84297	7	204	Handle and screws set for Hand Magnet B-2

■ Japan Calibration Service System (JCSS)

What is JCSS (Japan Calibration Service System)?

JCSS consists of the National Standards Provision System and the Calibration Laboratory Accreditation System introduced by the revised Measurement Law that was enforced in November 1993. Calibration laboratories are assessed and accredited for their technological capabilities and traceability by the National Institute of Technology and Evaluation (NITE) to meet the requirements of certified international standard, ISO/IEC 17025.

What is MRA?

MRA (Mutual Recognition Arrangement) is an international agreement by which two or more countries agree to recognize one another's traceability system. JCSS signed an MRA with APLAC (Asia Pacific Laboratory Accreditation Cooperation) in December 1999, and signed an MRA with ILAC (International Laboratory Accreditation Cooperation) in November 2000. JCSS has been accepted as an accreditation operator conforming to international criteria.

JCSS Calibration Service

(Stainless Steel Rule, Steel Tape Measure, Vernier Caliper, Micrometer)

The Quality Assurance Department at Shinwa Rules Co., Ltd. was registered as a registered calibration laboratory in the "length" field in February 2001 and accredited as an MRA conforming JCSS laboratory in November 2013. Under this program, we are able to issue a JCSS calibration certificate with an MRA accreditation symbol. This certificate is internationally accepted to conform to one of the MRA signatory countries.

Contents of Business

Shinwa Rules Co., Ltd. Quality Assurance Department Registration number 0092

Item / Scope of Service		Maximum Measurement Capability (Minimum Uncertainty of Measurement*)	Remark
Stainless Steel Rule Up to 1,000 mm		0.02 mm	Calibrated by Working Standard Calibratable graduation is 50 mm pitch
Stainless Steel Rule (The base point on the edge) Up to 1,000 mm		0.02 mm	
Stainless Steel Rule from 1,000 mm up to 2,000 mm		0.05 mm	
Stainless Steel Rule (The base point on the edge) from 1,000 mm up to 2,000 mm		0.06 mm	
Stainless Steel Rule (Precision type) Up to 1,000 mm		11 μ m	Calibrated by Laboratory Reference Standard (Our highest rank gauge) Calibratable graduation is 100 mm pitch
Steel Tape Measure Up to 100 m		Up to 5 m: 0.08 mm More than 5 m up to 100 m: 0.08 mm added to the above value in every 5 m increase	Limited to tensile strength of more than 10 N up to 100 N Compact tape measures (with a hook and auto roll up function) are not included. Calibratable graduation is 1 m pitch
Vernier Caliper Up to 300mm	Scale Interval 0.10 mm	0.08 mm	Calibratable graduation is 20, 50, 100, 150, 200, 250, 300 mm **Depth probe zero point deviation" is not applicable
	Scale Interval 0.05 mm	0.06 mm	
	Scale Interval 0.02 mm	0.04 mm	
	Scale Interval 0.01 mm	0.03 mm	
Outside Micrometer Up to 50 mm		3 μ m	Combination of 16-piece set of gauge blocks from 1 - 50 mm

*Uncertainty is based on the assumption that the absolute true value cannot be known, so variation etc. is comprehensively evaluated, and the value is statistically estimated to be within the range thought to include the true value.

Measuring Point


Applicable Calibration		Measuring Point	Additional Measuring Point
Stainless Steel Rule	Up to 2,000 mm	Basic 4 points are at 100 mm and the entire length on the upper and lower graduations. For 100 mm rules, they are at 50 mm and 100 mm on the upper and lower graduations. Please inquire about rules with only one side graduations or ones with graduations on both faces.	Measuring point can be added if requested, which will incur an extra charge to the package price. (Please see the next page for details.)
Stainless Steel Rule (Precision Type)	Up to 1,000 mm	1 point at every 100 mm (one side graduation) 10 points for 1,000 mm rules	
Steel Tape Measure	Up to 5 m	1 point per 1 m. 5 points for the total length of 5 m.	
	From 5 m – 20 m	1 point per 1 m up to 5 m, 1 point per 5 m for 5 m or more For the total length of 20 m, total 8 points at 1,2,3,4,5,10,15,20 m	
	From 20 m – 50 m	1 point per 1 m up to 5 m, 1 point per 5 m for 5 m or more For the total length of 50 m, total 14 points at 1,2,3,4,5,10,15,20...45, 50 m	Since there is no set package available, please inquire for an quote.
	From 50 m – 100 m	Set package is not available. Please specify your requirements.	
Vernier Caliper	70 mm	4 points at 20 mm and 50 mm for inside and outside	Measuring points can be added if requested, which will incur an extra charge to the package price. (Please see the next page for details.)
	100 mm	6 points at 20 mm, 50 mm, and 100 mm for inside and outside	
	150 mm	6 points at 50 mm, 100 mm, and 150 mm for inside and outside	
	200 mm	6 points at 50 mm, 100 mm, and 200 mm for inside and outside	
	300 mm	6 points at 100 mm, 200 mm, and 300 mm for inside and outside	
Micrometer	0 – 25 mm	Total 3 points at 1.25, 11.5, 25 mm	
	25 – 50 mm	Total 3 points at 25.25, 36.5, 50 mm	

JCSS Calibration Certificate



Traceability System Diagram

(Stainless Steel Rule, Steel Tape Measure, Vernier Caliper, and Micrometer)



Calibration Service List

Received Products (JCSS Calibration Certificate only)

This is the price list when we handle a product that you already have and issue a JCSS calibration certificate.

JCSS Calibration Certificate for Stainless Steel Rules

Item Code	C.D.	Description
19010	8	10 cm
19034	4	15 cm
19035	1	30 cm
19036	8	60 cm
19037	5	1 m
19075	7	1.5 m
19076	4	2 m
19044	3	Over 1 m under 2 m
19045	0	Under 1 m

JCSS Calibration Certificate for Precision Stainless Steel Rules

Item Code	C.D.	Description
83702	7	30 cm
83802	4	60 cm
83502	3	1 m

JCSS Calibration Certificate for Steel Tape Measures

Item Code	C.D.	Description
19039	9	under 5 m
19047	4	Over 5 m under 20 m
19048	1	Over 20 m under 50 m
19049	8	Over 50 m under 100 m

JCSS Calibration Certificate for Vernier Calipers

Item Code	C.D.	Description
19060	3	70 mm
19061	0	100 mm
19056	6	150 mm
19057	3	200 mm
19058	0	300 mm

JCSS Calibration Certificate for Micrometers

Item Code	C.D.	Description
19082	5	0 - 25 mm
19083	2	25 - 50 mm

Manufactured Products with Certificate (Product and JCSS Calibration Certificate)

This is the price list when a JCSS calibration certificate is attached at the time a new product is newly purchased. *Please confirm the use of each product on each page

Stainless Steel Rule Hard Chrome Finish *Refer to P30

Item Code	C.D.	Description
19014	6	15 cm
19015	3	30 cm
19016	0	60 cm
19017	7	1 m
19063	4	1.5 m
19064	1	2 m

Stainless Steel Rule Polish Finish *Refer to P30

Item Code	C.D.	Description
19018	4	15 cm
19019	1	30 cm
19020	7	60 cm
19021	4	1 m
19065	8	1.5 m
19066	5	2 m

Vernier Caliper *Refer to P53/54

Item Code	C.D.	Description
19054	2	Mini 70 mm
19055	9	Mini 100 mm
19051	1	150 mm
19052	8	200 mm
19053	5	300 mm

Stainless Steel Pickup Rule Hard Chrome Finish *Refer to P30

Item Code	C.D.	Description
19012	2	10 cm
19022	1	15 cm
19023	8	30 cm
19024	5	60 cm
19025	2	1 m

Flexible Stainless Steel Rule Hard Chrome Finish *Refer to P31

Item Code	C.D.	Description
19026	9	30 cm
19027	6	60 cm
19028	3	1 m
19067	2	1.5 m
19068	9	2 m

Digital Vernier Caliper *Refer to P55

Item Code	C.D.	Description
19084	9	Mini 100 mm
19085	6	150 mm
19086	3	200 mm
19087	0	300 mm

Stainless Steel Rule Hard Chrome Finish with Magnet *Refer to P31

Item Code	C.D.	Description
81741	8	15 cm
80288	9	30 cm
82826	1	60 cm
83249	7	1 m

Stainless Steel Rule Hard Chrome Finish 1 mm Dividing *Made-to-order *Refer to P32

Item Code	C.D.	Description
47032	3	15 cm
81838	5	30 cm
81476	9	60 cm
50027	3	1 m

Digital Vernier Caliper with Solar Panel *Refer to P56

Item Code	C.D.	Description
47293	8	150 mm
81484	4	150 mm

*Only stainless steel body products are calibratable for vernier calipers. (Except for item number 19518 Pocket Vernier Caliper)

Micrometer *Refer to P58

Item Code	C.D.	Description
19080	1	0 - 25 mm
19081	8	25 - 50 mm

Additional Measuring Point (Optional)

The above prices are listed for calibration with basic measuring points. Added measuring points will incur an extra charge.

Item Code	C.D.	Description
84058	4	1 additional measuring point

Calibration Certificate Reissue (Within three years from the date of issue)

A reissue fee will be charged for an additional certificate requested. There will be no fee for reissuing a copy of a JCSS accession certificate.

Item Code	C.D.	Description
96106	7	Reissue of JCSS Calibration Certificate, Private Examination Result

Digital Micrometer *Refer to P58

Item Code	C.D.	Description
19088	7	0 - 25 mm

*Customer's name and address are required to issue a JCSS calibration certificate. Please let us know with your order.

*Calibration certificate and traceability system diagram comes with a product. If a JCSS accession certificate is required, please contact us.

*Please request calibration certificates for products other than the above through suppliers. We will provide a separate estimate (it will be for a general calibration certificate, not a JCSS calibration certificate).

■ Etching

What is Etching?

Etching is an application of a photomechanical process technique and a process of grooving, engraving, and drilling by chemical treatment on the surface of metals, such as stainless steel, iron, and copper. It enables us to process a variety of precision parts or ornaments to match a customer's needs.

Features

1

Fine Processing

Enables fine processing which pressing can not create

2

Finishing

No burrs, residual strain, or work hardening

3

Design Effect

Name plates or metal ornament items can utilize the design effect from the contrast between the metal surface and the etched concave satin finish surface

4

Low Cost

Provides low initial cost without using molds or jigs unlike pressing


5

Early delivery date

Enables the process of multiple pieces at the same time

■ Main Usage Examples

- Filter
- Mesh or perforated plate
- Metal ornament items
- Sales promotion (Clip/Bookmark)
- Spacer, shim plate
- Art and craft work, ornament
- Name plate, name tag, sign, etc.



For etching please contact...

Shinwa Rules Co., Ltd. FE Department

3485 Koike, Tsubame-shi, Niigata-ken, Japan Postal code 959-1276
TEL. +81-256-61-1114 FAX. +81-256-61-1114

■ Sheet Heaters

Shinwa's surface heating element is a thin heating sheet that generates heat by running electricity through a thin metal foil. It is very soft and flexible, which makes it ideal to heat a curved surface or narrow space.

Additionally, making the circuit from etching, it is easy to get the ideal heat distribution that a designer intends. Everything is made-to-order, designed and manufactured, in a way that matches a customer's needs.

Features

1

Free Shape

Making a circuit by etching enables design and manufacture in any required shapes

2

Thin

The minimum thickness of approximately 0.1 mm makes it ideal for weight-saving and simplifying a machine

3

Flexible

The flexibility allows it to be attached to a curved surface

4


Changeable Heat Distribution

Because the distribution and shape of the heater circuit can be changed, calorific value can be uniform or partially changed


5

Quick Start

The shape and small heat capacity help it to heat up quickly



Heat Distribution



Usage Examples Widely being used for medical equipment, motor vehicles, airplanes, rockets, etc.



For sheet heaters please contact...

Shinwa Rules Co., Ltd. FE Department

3485 Koike, Tsubame-shi, Niigata-ken, Japan Postal code 959-1276
TEL. +81-256-61-1114 FAX. +81-256-61-1114
<http://www.shinwasokutei.co.jp/menpatsu1>

Custom-made Items

We produce custom-made items, such as stainless steel rules, carpenter's squares, special scales, etc., based on requested sizes and graduations. Please feel free to contact us about quantity, delivery date, price and more.

Custom-made Stainless Steel Rules

◎Production Examples

●Stainless Steel Rule 15 cm Gold Finish



●Stainless Steel Rule 15 cm One Side Graduation



●Stainless Steel Rule 15 cm with Inch Graduation (for export)



●Special Vertical Graduation



●Other Stainless Steel Rules Special Scales



Manufacturing Range	
Thickness	0.5 - 4.0 mm
Length	Hard Chrome Finish
	Polish Finish
Width	10 mm - 100 mm

3,000 mm
6,000 mm
*Up to 2,000 mm length for items with less than 1.0 mm thickness

Custom-made Carpenter's Squares

◎Production Examples

●Thick Wide Shaku 6 Graduation Fluorescence


■We also create fluorescent graduations on each carpenter's square model. However, surface processing is only for hard chrome finish models

■We produce custom-made carpenter's squares as well with your size request (length, thickness). Because the manufacturing range has to be considered, please contact us for details.

■Left-handed model, slope carpenter's square, inch graduation model for export are also available

■Custom-made items of large carpenter's squares are also available

		Manufacturing Range	
		Hard Chrome Finish	Polish Finish
Length	Long Branch	1,030 mm	2,000 mm
	Short Branch	630 mm	800 mm




Other Custom-made Items

◎Production Examples

●Camera Scale



●Chain friction measuring scale



●Special scale L-shape type



Please contact us for other items, such as artifact measuring gauges, custom-made protractors, main scale of height gauges, computer scales, etc. The graduation printing can be done by an etching treatment or screen printing. Screen printing can be applied to any materials other than stainless steel such as aluminum.

■Inch graduation models can not be manufactured or sold for the domestic market, which manufactures based on the metric system. Items for export will be made based on applicable graduations for each destination.

<Note> Forms and molds of custom-made items will be discarded after **three years** from the last order.


Name Printing

Perfect for business gifts or personal gifts

Types of name printing Etching Treatment Silkscreen Printing Sticker

Carpenter's Square Etching Treatment

●Example: Name printing on 10845 Carpenter's Square
High Quality Thick Corner 1 shaku 5 sun with Square Scale



Space for printing name

"TAKUMI JINGOROU"	shaku 6	80 × 7 mm
"TAKUMI JINGORO"	50 cm, shaku 5	70 × 7 mm


*Name can be printed to other carpenter's squares besides the ones listed above. Please feel free to contact us.

Stainless Steel Rule Etching Treatment or Silkscreen Printing

●Example: Name printing on 13005 Hard Chrome Finish 15 cm



Space for printing name



*Name can be printed on sizes from 10 cm up to 1 m as long as it is located 2 mm away from each edge.

Tape Measure Sticker

●Example: Name printing on 78007 High-touch H-163



High-touch series
Space for printing name

2 m	φ36.5 mm
3.5 m	φ40 mm

●Example: Name printing on 80880 Smart Gear 19 - 5.5 m



Smart Gear series
Space for printing name
φ32 mm

Name Printing on Other Products

Specified symbols or marks can be printed on other Shinwa products besides the ones listed above. Please feel free to contact us.



*May not be applicable to some products due to shape and other restrictions

Individual Paper Box



80 mm
75 mm
45 mm

Tape measure sold separately

Item Code	Description	Packing Unit	JAN Code
67983	80 × 75 × 45 mm White	1	4 960910 679832

<Note> Forms of name printing products will be discarded after two years from the last order.

10000~10999

Item Code	Description	Page
10007	Carpenter's Square Flat Hard Chrome Finish 15 cm	15
10008	Carpenter's Square Flat Hard Chrome Finish 5 sun	15
10011	Carpenter's Square Thick Corner Hard Chrome Finish 50 cm/1 shaku 5 sun	8
10012	Carpenter's Square Thick Corner Hard Chrome Finish 50 cm/1 shaku 6 sun	8
10014	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 50 cm	8
10016	Carpenter's Square Flat Hard Chrome Finish with Square Scale 50 cm	15
10027	Carpenter's Square Thick Corner Hard Chrome Finish 30 cm/1 shaku	8
10028	Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku/30 cm	8
10030	Carpenter's Square Thick Corner Hard Chrome Finish 50 cm	8
10032	Carpenter's Square Flat Hard Chrome Finish 50 cm	15
10033	Carpenter's Square Flat Hard Chrome Finish 50 cm/1 shaku 6 sun	15
10034	Carpenter's Square Wide and Flexible Hard Chrome Finish 50 cm	17
10037	Carpenter's Square Flat Hard Chrome Finish 15 cm/5 sun	15
10038	Carpenter's Square Flat Hard Chrome Finish 5 sun/15 cm	15
10044	Carpenter's Square Flat Hard Chrome Finish 50 cm/1 shaku 5 sun	15
10045	Carpenter's Square Flat Hard Chrome Finish 1 shaku 5 sun/50 cm	15
10046	Carpenter's Square Flat Hard Chrome Finish 1 shaku 6 sun/50 cm	15
10047	Carpenter's Square Flat Hard Chrome Finish 30 cm/1 shaku	15
10048	Carpenter's Square Flat Hard Chrome Finish 1 shaku/30 cm	15
10055	Carpenter's Square Hard Chrome Finish for Two-by-Four 50 cm	17
10056	Carpenter's Square Hard Chrome Finish for Two-by-Four 1 shaku 5 sun	17
10175	Carpenter's Square Hard Chrome Finish with Magnet Flat Corner 50 cm	18
10181	Carpenter's Square Hard Chrome Finish with Magnet Flat Corner 1 shaku 6 sun	18
10286	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 30 cm	8
10294	Carpenter's Square Thick Corner Hard Chrome Finish 30 cm	8
10297	Carpenter's Square Flat Hard Chrome Finish 30 cm	15
10332	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale and Inside Scale 1 shaku 5 sun	9
10340	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale and Inside Scale 1 shaku 6 sun	9
10359	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale and Inside Scale 50 cm	9
10370	Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales 50 cm	9
10371	Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales and Square Scale 1 shaku 5 sun	9
10372	Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales and Square Scale 1 shaku 6 sun	9
10373	Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales and Square Scale 50 cm	9
10405	Carpenter's Square Wide Hard Chrome Finish 50 cm with 6 Scales	13
10414	Carpenter's Square Wide Hard Chrome Finish 50 cm/1 shaku 6 sun with 5 Scales	13
10421	Carpenter's Square Wide Hard Chrome Finish 30 cm with 8 Scales	13
10424	Carpenter's Square Wide Hard Chrome Finish 15 cm with 8 Scales cm Notation	13
10425	Carpenter's Square Hard Chrome Finish with Magnet Wide 30 cm with 8 Scales	18
10435	Carpenter's Square Hard Chrome Finish with Magnet Wide 15 cm with 8 Scales cm Notation	18
10445	Carpenter's Square Hard Chrome Finish with Magnet Wide 50 cm with 6 Scales	18
10450	Carpenter's Square Wide Hard Chrome Finish 50 cm with 8 Scales cm Notation	13
10451	Carpenter's Square Wide Hard Chrome Finish 30 cm with 8 Scales cm Notation	13
10456	Carpenter's Square Wide Hard Chrome Finish 1 shaku 6 sun with 4 Scales	13
10464	Carpenter's Square Wide Hard Chrome Finish 1 shaku with 4 Scales	13
10510	Carpenter's Square Rigid Hard Chrome Finish with Square Scale 30 cm	18
10511	Carpenter's Square Rigid Hard Chrome Finish 30 cm/1 shaku	18
10529	Carpenter's Square Rigid Hard Chrome Finish with Square Scale 1 shaku	18
10545	Carpenter's Square Rigid Hard Chrome Finish 1 shaku	18
10553	Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 5 sun	8
10555	Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 5 sun/50 cm	8
10556	Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 6 sun/50 cm	8
10561	Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 6 sun	8

10588	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	8
10590	Carpenter's Square Flat Hard Chrome Finish with Square Scale 1 shaku 5 sun	15
10592	Carpenter's Square Flat Hard Chrome Finish 1 shaku 5 sun	15
10595	Carpenter's Square Flat Hard Chrome Finish 1 shaku 6 sun	15
10596	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	8
10598	Carpenter's Square Flat Hard Chrome Finish with Square Scale 1 shaku 6 sun	15
10600	Carpenter's Square Wide and Flexible Hard Chrome Finish 1 shaku 6 sun	17
10618	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 1 shaku	8
10620	Carpenter's Square Flat Hard Chrome Finish 1 shaku	15
10626	Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku	8
10634	Carpenter's Square Rigid Hard Chrome Finish 30 cm	18
10638	Carpenter's Square Flat Corner Hard Chrome Finish 50 cm/1 shaku 5 sun	11
10639	Carpenter's Square Flat Corner Hard Chrome Finish 50 cm/1 shaku 6 sun	11
10640	Carpenter's Square Flat Corner Hard Chrome Finish 50 cm	11
10642	Carpenter's Square Flat Corner Hard Chrome Finish 30 cm/1 shaku	11
10643	Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 5 sun	11
10644	Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 5 sun/50 cm	11
10645	Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 6 sun/50 cm	11
10646	Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 6 sun	11
10647	Carpenter's Square Flat Corner Hard Chrome Finish 30 cm	11
10648	Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku	11
10649	Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku/30 cm	11
10650	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale for Left-hander 1 shaku 5 sun	9
10652	Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 30 cm	11
10653	Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 50 cm	11
10654	Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	11
10655	Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	11
10657	Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 1 shaku	11
10669	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale for Left-hander 1 shaku 6 sun	9
10677	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale for Left-hander 50 cm	9
10758	Carpenter's Square Thick Corner Black Color with Square Scale 1 shaku 5 sun	10
10837	Carpenter's Square High Quality Thin Corner Hard Chrome Finish with Square Scale 50 cm	13
10839	Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 50 cm	12
10845	Carpenter's Square High Quality Thin Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	13
10847	Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	12
10855	Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	12
10860	Carpenter's Square High Quality Thin Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	13
10871	Carpenter's Square Thick Corner Black Color with Square Scale 50 cm	10
10876	Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 50 cm Flexible	12
10877	Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun Flexible	12
10878	Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scal 1 shaku 6 sun Flexible	12

11000~11999

Item Code	Description	Page
11002	Carpenter's Square Thick Corner Polish Finish with Square Scale 50 cm	10
11010	Carpenter's Square Thick Corner Polish Finish 50 cm	10
11100	Carpenter's Square Flat Corner White 30 cm	12
11101	Carpenter's Square Flat Corner White 50 cm	12
11102	Carpenter's Square Flat Corner White 1 shaku	12
11103	Carpenter's Square Flat Corner White 1 shaku 6 sun	12
11104	Carpenter's Square Flat Corner White 30 cm/1 shaku	12
11105	Carpenter's Square Flat Corner White 1 shaku/30 cm	12
11106	Carpenter's Square Flat Corner White 50 cm/1 shaku 6 sun	12
11107	Carpenter's Square Flat Corner White 1 shaku 6 sun/50 cm	12

11108	Carpenter's Square Flat Corner White 1 shaku 5 sun	12
11109	Carpenter's Square Flat Corner White 50 cm/1 shaku 5 sun	12
11110	Carpenter's Square Flat Corner White 1 shaku 5 sun/50 cm	12
11160	Carpenter's Square Wide White 30 cm with 8 Scales	14
11161	Carpenter's Square Wide White 50 cm with 8 Scales	14
11170	Carpenter's Square Flat White 15 cm	16
11171	Carpenter's Square Flat White 30 cm	16
11172	Carpenter's Square Flat White 50 cm	16
11173	Carpenter's Square Flat White 5 sun	16
11174	Carpenter's Square Flat White 1 shaku	16
11175	Carpenter's Square Flat White 1 shaku 5 sun	16
11176	Carpenter's Square Flat White 1 shaku 6 sun	16
11177	Carpenter's Square Flat White 15 cm/5 sun	16
11178	Carpenter's Square Flat White 5 sun/15 cm	16
11179	Carpenter's Square Flat White 30 cm/1 shaku	16
11180	Carpenter's Square Flat White 1 shaku/30 cm	16
11181	Carpenter's Square Flat White 50 cm/1 shaku 5 sun	16
11182	Carpenter's Square Flat White 1 shaku 5 sun/50 cm	16
11183	Carpenter's Square Flat White 50 cm/1 shaku 6 sun	16
11184	Carpenter's Square Flat White 1 shaku 6 sun/50 cm	16
11207	Carpenter's Square Wide Polish Finish 50 cm with 6 Scales	14
11215	Carpenter's Square Wide Polish Finish 30 cm with 8 Scales	14
11481	Carpenter's Square Wide Hard Chrome Finish 50 cm with 8 Scales	13
11487	Carpenter's Square Wide Hard Chrome Finish 50 cm with 4 Scales	13
11754	Carpenter's Square Thick Corner Polish Finish Fluorescent with Square Scale 1 shaku 5 sun	10
11762	Carpenter's Square Thick Corner Polish Finish Fluorescent with Square Scale 1 shaku 6 sun	10
11770	Carpenter's Square Thick Corner Polish Finish Fluorescent with Square Scale 50 cm	10
11777	Carpenter's Square Thick Corner Polish Finish Fluorescent 50 cm	10

12000~12999

Item Code	Description	Page
12017	Small Square Grooved Polish Finish with Square Scale 30 x 15 cm	19
12101	Small Square Polish Finish 10 x 5 cm	19
12102	Small Square Polish Finish 3 x 1.5 sun	19
12103	Small Square Polish Finish 15 x 7.5 cm	19
12104	Small Square Polish Finish 5 x 2.5 sun	19
12114	Small Square Flat Polish Finish with Square Scale 30 x 15 cm	19
12130	Small Square Grooved Polish Finish 30 x 15 cm	19
12325	Small Square Flat Polish Finish 30 x 15 cm	19
12416	Small Square Black with Square Scale 30 x 15 cm	19
12427	Carpenter's Square Holder with Magnet	20
12435	Small Square Black 30 x 15 cm	19
12476	Small Square White with Square Scale 30 x 15 cm	19

13000~13999

Item Code	Description	Page
13005	Stainless Steel Rule Hard Chrome Finish 15 cm	30
13013	Stainless Steel Rule Hard Chrome Finish 30 cm	30
13021	Stainless Steel Rule Hard Chrome Finish 60 cm	30
13048	Stainless Steel Rule Hard Chrome Finish 1 m	30
13056	Stainless Steel Rule Hard Chrome Finish 1.5 m	30
13064	Stainless Steel Rule Hard Chrome Finish 2 m	30
13072	Stainless Steel Rule Hard Chrome Finish 3 m	30
13128	Stainless Pickup Rule Hard Chrome Finish 10 cm	30

13131	Stainless Pickup Rule Hard Chrome Finish 15 cm	30
13134	Stainless Pickup Rule Hard Chrome Finish 30 cm	30
13137	Stainless Pickup Rule Hard Chrome Finish 60 cm	30
13140	Stainless Pickup Rule Hard Chrome Finish 1 m	30
13202	Stainless Steel Rule Hard Chrome Finish Metric/Shaku 15 cm Double-left Reference Point	31
13203	Stainless Steel Rule Hard Chrome Finish Metric/Shaku 30 cm Double-left Reference Point	31
13204	Stainless Steel Rule Hard Chrome Finish Metric/Shaku 60 cm Double-left Reference Point	31
13205	Stainless Steel Rule Hard Chrome Finish Metric/Shaku 1 m Double-left Reference Point	31
13210	Stainless Steel Rule Hard Chrome Finish Metric/Shaku 1 m Right Reference Point	31
13242	Stainless Steel Rule Mini Hard Chrome Finish 15 cm	33
13250	Flexible Stainless Steel Rule Hard Chrome Finish 30 cm	31
13269	Flexible Stainless Steel Rule Hard Chrome Finish 60 cm	31
13277	Flexible Stainless Steel Rule Hard Chrome Finish 1 m	31
13285	Flexible Stainless Steel Rule Hard Chrome Finish 1.5 m	31
13293	Flexible Stainless Steel Rule Hard Chrome Finish 2 m	31
13404	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 15 cm	32
13412	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 60 cm	32
13463	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 30 cm	32
13498	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 1 m	32
13501	Stainless Steel Rule Hard Chrome Finish with Magnet 15 cm	31
13528	Stainless Steel Rule Hard Chrome Finish with Magnet 30 cm	31
13536	Stainless Steel Rule Hard Chrome Finish with Magnet 60 cm	31
13544	Stainless Steel Rule Hard Chrome Finish with Magnet 1 m	31

14000~14999

Item Code	Description	Page
14001	Stainless Steel Rule Polish Finish 15 cm	30
14028	Stainless Steel Rule Polish Finish 30 cm	30
14036	Stainless Steel Rule Polish Finish 60 cm	30
14044	Stainless Steel Rule Polish Finish 1 m	30
14050	Molding Rule 2 m 3/1000	34
14052	Stainless Steel Rule Polish Finish 1.5 m	30
14060	Stainless Steel Rule Polish Finish 2 m	30
14079	Stainless Steel Rule Polish Finish 3 m	30
14087	Stainless Steel Rule Polish Finish 4 m	30
14095	Stainless Steel Rule Polish Finish 5 m	30
14109	Stainless Steel Rule Polish Finish 6 m	30
14113	Precision Stainless Steel Rule Hard Chrome Finish with JCSS Certificate 30 cm	33
14114	Precision Stainless Steel Rule Hard Chrome Finish with JCSS Certificate 60 cm	33
14115	Precision Stainless Steel Rule Hard Chrome Finish with JCSS Certificate 1 m	33
14127	Machine Scale 50 mm Upper-left Reference Point	36
14128	Machine Scale 100 mm Upper-left Reference Point	36
14129	Machine Scale 150 mm Upper-left Reference Point	36
14130	Machine Scale 200 mm Upper-left Reference Point	36
14131	Machine Scale 300 mm Upper-left Reference Point	36
14132	Machine Scale 500 mm Upper-left Reference Point	36
14134	Machine Scale 50 mm Upper-right Reference Point	36
14135	Machine Scale 100 mm Upper-right Reference Point	36
14136	Machine Scale 150 mm Upper-right Reference Point	36
14137	Machine Scale 200 mm Upper-right Reference Point	36
14138	Machine Scale 300 mm Upper-right Reference Point	36
14139	Machine Scale 500 mm Upper-right Reference Point	36
14141	Machine Scale 100 mm Upper-central Reference Point	36
14142	Machine Scale 200 mm Upper-central Reference Point	36

14143	Machine Scale 300 mm Upper-central Reference Point	36
14144	Machine Scale 500 mm Upper-central Reference Point	36
14146	Machine Scale 50 mm Lower-left Reference Point	36
14147	Machine Scale 100 mm Lower-left Reference Point	36
14148	Machine Scale 150 mm Lower-left Reference Point	36
14149	Machine Scale 200 mm Lower-left Reference Point	36
14150	Machine Scale 300 mm Lower-left Reference Point	36
14151	Machine Scale 500 mm Lower-left Reference Point	36
14153	Machine Scale 50 mm Lower-right Reference Point	36
14154	Machine Scale 100 mm Lower-right Reference Point	36
14155	Machine Scale 150 mm Lower-right Reference Point	36
14156	Machine Scale 200 mm Lower-right Reference Point	36
14157	Machine Scale 300 mm Lower-right Reference Point	36
14158	Machine Scale 500 mm Lower-right Reference Point	36
14160	Machine Scale 100 mm Lower-central Reference Point	36
14161	Machine Scale 200 mm Lower-central Reference Point	36
14162	Machine Scale 300 mm Lower-central Reference Point	36
14163	Machine Scale 500 mm Lower-central Reference Point	36
14165	Indicator Plate for Machine Scale	36
14249	Stainless Steel Rule Mini Polish Finish 15 cm	33
14900	Molding Rule 60 cm 29/1000	34
14932	Molding Rule 15 cm 6/1000	34
14938	Molding Rule 15 cm 17/1000	34
14939	Molding Rule 15 cm 18/1000	34
14945	Molding Rule 2 m 27/1000	34
14950	Molding Rule 15 cm 27/1000	34

15000~15999

Item Code	Description	Page
15000	Molding Rule 30 cm 2/1000	34
15008	Molding Rule 30 cm 4/1000	34
15016	Molding Rule 30 cm 5/1000	34
15024	Molding Rule 30 cm 6/1000	34
15032	Molding Rule 30 cm 7/1000	34
15040	Molding Rule 30 cm 8/1000	34
15059	Molding Rule 30 cm 9/1000	34
15067	Molding Rule 30 cm 10/1000	34
15075	Molding Rule 30 cm 12/1000	34
15083	Molding Rule 30 cm 13/1000	34
15091	Molding Rule 30 cm 14/1000	34
15105	Molding Rule 30 cm 15/1000	34
15113	Molding Rule 30 cm 16/1000	34
15121	Molding Rule 30 cm 17/1000	34
15148	Molding Rule 30 cm 18/1000	34
15156	Molding Rule 30 cm 20/1000	34
15164	Molding Rule 30 cm 22/1000	34
15172	Molding Rule 30 cm 23/1000	34
15180	Molding Rule 30 cm 24/1000	34
15199	Molding Rule 30 cm 25/1000	34
15202	Molding Rule 30 cm 26/1000	34
15210	Molding Rule 30 cm 27/1000	34
15229	Molding Rule 30 cm 28/1000	34
15237	Molding Rule 30 cm 30/1000	34
15261	Molding Rule 30 cm 11/1000	34

15288	Molding Rule 30 cm 21/1000	34
15296	Molding Rule 30 cm 3/1000	34
15334	Molding Rule 30 cm 19/1000	34
15380	Molding Rule 2 m 24/1000	34

16000~16999

Item Code	Description	Page
16000	Molding Rule 60 cm 2/1000	34
16004	Molding Rule 60 cm 4/1000	34
16012	Molding Rule 60 cm 5/1000	34
16020	Molding Rule 60 cm 6/1000	34
16039	Molding Rule 60 cm 7/1000	34
16047	Molding Rule 60 cm 8/1000	34
16055	Molding Rule 60 cm 9/1000	34
16063	Molding Rule 60 cm 10/1000	34
16071	Molding Rule 60 cm 12/1000	34
16098	Molding Rule 60 cm 13/1000	34
16101	Molding Rule 60 cm 14/1000	34
16128	Molding Rule 60 cm 15/1000	34
16136	Molding Rule 60 cm 16/1000	34
16144	Molding Rule 60 cm 17/1000	34
16152	Molding Rule 60 cm 18/1000	34
16160	Molding Rule 60 cm 19/1000	34
16179	Molding Rule 60 cm 20/1000	34
16187	Molding Rule 60 cm 22/1000	34
16195	Molding Rule 60 cm 23/1000	34
16209	Molding Rule 60 cm 24/1000	34
16217	Molding Rule 60 cm 25/1000	34
16225	Molding Rule 60 cm 26/1000	34
16233	Molding Rule 60 cm 27/1000	34
16241	Molding Rule 60 cm 28/1000	34
16268	Molding Rule 60 cm 30/1000	34
16365	Molding Rule 60 cm 11/1000	34
16373	Molding Rule 60 cm 21/1000	34
16381	Molding Rule 60 cm 3/1000	34

17000~17999

Item Code	Description	Page
17000	Molding Rule 1 m 4/1000	34
17001	Molding Rule 1 m 2/1000	34
17019	Molding Rule 1 m 5/1000	34
17027	Molding Rule 1 m 6/1000	34
17035	Molding Rule 1 m 7/1000	34
17043	Molding Rule 1 m 8/1000	34
17051	Molding Rule 1 m 9/1000	34
17078	Molding Rule 1 m 10/1000	34
17086	Molding Rule 1 m 12/1000	34
17094	Molding Rule 1 m 13/1000	34
17108	Molding Rule 1 m 14/1000	34
17116	Molding Rule 1 m 15/1000	34
17124	Molding Rule 1 m 16/1000	34
17132	Molding Rule 1 m 17/1000	34
17140	Molding Rule 1 m 18/1000	34
17159	Molding Rule 1 m 19/1000	34

17167	Molding Rule 1 m 20/1000	34
17175	Molding Rule 1 m 22/1000	34
17183	Molding Rule 1 m 23/1000	34
17191	Molding Rule 1 m 24/1000	34
17205	Molding Rule 1 m 25/1000	34
17221	Molding Rule 1 m 27/1000	34
17248	Molding Rule 1 m 28/1000	34
17256	Molding Rule 1 m 30/1000	34
17345	Molding Rule 1 m 3/1000	34
17353	Molding Rule 1 m 11/1000	34
17361	Molding Rule 1 m 21/1000	34

18000~18999

Item Code	Description	Page
18003	Molding Rule 15 cm 4/1000	34
18004	Molding Rule 15 cm 5/1000	34
18007	Molding Rule 15 cm 8/1000	34
18015	Molding Rule 15 cm 10/1000	34
18023	Molding Rule 15 cm 12/1000	34
18024	Molding Rule 15 cm 13/1000	34
18031	Molding Rule 15 cm 15/1000	34
18058	Molding Rule 15 cm 20/1000	34
18066	Molding Rule 15 cm 22/1000	34
18074	Molding Rule 15 cm 25/1000	34
18082	Molding Rule 15 cm 30/1000	34
18090	Molding Rule 30 cm 29/1000	34
18499	Molding Rule 2 m 11/1000	34
18500	Molding Rule 2 m 2/1000	34
18503	Molding Rule 2 m 8/1000	34
18511	Molding Rule 2 m 10/1000	34
18538	Molding Rule 2 m 12/1000	34
18546	Molding Rule 2 m 14/1000	34
18554	Molding Rule 2 m 15/1000	34
18562	Molding Rule 2 m 16/1000	34
18570	Molding Rule 2 m 17/1000	34
18589	Molding Rule 2 m 18/1000	34
18597	Molding Rule 2 m 19/1000	34
18600	Molding Rule 2 m 20/1000	34
18619	Molding Rule 2 m 22/1000	34
18627	Molding Rule 2 m 25/1000	34
18635	Molding Rule 2 m 30/1000	34
18678	Molding Rule 2 m 13/1000	34
18686	Molding Rule 2 m 9/1000	34

19000~19999

Item Code	Description	Page
19005	Molding Rule 15 cm 11/1000	34
19006	Molding Rule 15 cm 16/1000	34
19010	JCSS Calibration Certificate for Stainless Steel Rule 10 cm	224
19012	Pickup Rule Hard Chrome Finish 10 cm with JCSS Certificate	224
19014	Stainless Steel Rule Hard Chrome Finish 15 cm with JCSS Certificate	224
19015	Stainless Steel Rule Hard Chrome Finish 30 cm with JCSS Certificate	224
19016	Stainless Steel Rule Hard Chrome Finish 60 cm with JCSS Certificate	224
19017	Stainless Steel Rule Hard Chrome Finish 1 m with JCSS Certificate	224

19018	Stainless Steel Rule Polish Finish 15 cm with JCSS Certificate	224
19019	Stainless Steel Rule Polish Finish 30 cm with JCSS Certificate	224
19020	Stainless Steel Rule Polish Finish 60 cm with JCSS Certificate	224
19021	Stainless Steel Rule Polish Finish 1 m with JCSS Certificate	224
19022	Pickup Rule Hard Chrome Finish 15 cm with JCSS Certificate	224
19023	Pickup Rule Hard Chrome Finish 30 cm with JCSS Certificate	224
19024	Pickup Rule Hard Chrome Finish 60 cm with JCSS Certificate	224
19025	Pickup Rule Hard Chrome Finish 1 m with JCSS Certificate	224
19026	Stainless Steel Rule Hard Chrome Finish 30 cm Flex Rule 15 mm Wide with JCSS Certificate	224
19027	Stainless Steel Rule Hard Chrome Finish 60 cm Flex Rule 15 mm Wide with JCSS Certificate	224
19028	Stainless Steel Rule Hard Chrome Finish 1 m Flex Rule 15 mm Wide with JCSS Certificate	224
19034	JCSS Calibration Certificate for Stainless Steel Rule 15 cm	224
19035	JCSS Calibration Certificate for Stainless Steel Rule 30 cm	224
19036	JCSS Calibration Certificate for Stainless Steel Rule 60 cm	224
19037	JCSS Calibration Certificate for Stainless Steel Rule 1 m	224
19039	JCSS Calibration Certificate for Steel Tape Measure Under 5 m	224
19044	JCSS Calibration Certificate for Stainless Steel Rule Over 1m under 2 m	224
19045	JCSS Calibration Certificate for Stainless Steel Rule Under 1 m	224
19047	JCSS Calibration Certificate for Steel Tape Measure Over 5 m under 20 m	224
19048	JCSS Calibration Certificate for Steel Tape Measure Over 20 m under 50 m	224
19049	JCSS Calibration Certificate for Steel Tape Measure Over 50 m under 100 m	224
19051	Vernier Caliper 150 mm with JCSS Certificate	224
19052	Vernier Caliper 200 mm with JCSS Certificate	224
19053	Vernier Caliper 300 mm with JCSS Certificate	224
19054	Mini Vernier Caliper 70 mm with JCSS Certificate	224
19055	Mini Vernier Caliper 100 mm with JCSS Certificate	224
19056	JCSS Calibration Certificate for Vernier Caliper 150 mm	224
19057	JCSS Calibration Certificate for Vernier Caliper 200 mm	224
19058	JCSS Calibration Certificate for Vernier Caliper 300 mm	224
19060	JCSS Calibration Certificate for Vernier Caliper 70 mm	224
19061	JCSS Calibration Certificate for Vernier Caliper 100 mm	224
19063	Stainless Steel Rule Hard Chrome Finish 1.5 m with JCSS Certificate	224
19064	Stainless Steel Rule Hard Chrome Finish 2 m with JCSS Certificate	224
19065	Stainless Steel Rule Polish Finish 1.5 m with JCSS Certificate	224
19066	Stainless Steel Rule Polish Finish 2 m with JCSS Certificate	224
19067	Stainless Steel Rule Hard Chrome Finish 1.5 m Flex Rule 15 mm Wide with JCSS Certificate	224
19068	Stainless Steel Rule Hard Chrome Finish 2 m Flex Rule 15 mm Wide with JCSS Certificate	224
19075	JCSS Calibration Certificate for Stainless Steel Rule 1.5 m	224
19076	JCSS Calibration Certificate for Stainless Steel Rule 2 m	224
19080	Micrometer 0 - 25 mm with JCSS Certificate	224
19081	Micrometer 25 - 50 mm with JCSS Certificate	224
19082	JCSS Calibration Certificate for Micrometer 0 - 25 mm	224
19083	JCSS Calibration Certificate for Micrometer 25 - 50 mm	224
19084	Digital Vernier Caliper Mini 100 mm with JCSS Certificate	224
19085	Digital Vernier Caliper 150 mm with JCSS Certificate	224
19086	Digital Vernier Caliper 200 mm with JCSS Certificate	224
19087	Digital Vernier Caliper 300 mm with JCSS Certificate	224
19088	Digital Micrometer 0 - 25 mm with JCSS Certificate	224
19300	Depth Gauge Mini	57
19305	Digital Depth Gauge Mini 25 mm	57
19306	Digital Depth Gauge with Hold Function 150 mm	57
19307	Digital Depth Gauge with Hold Function 200 mm	57
19514	Vernier Caliper Plastic Body 70 mm	54
19515	Vernier Caliper Plastic Body 100 mm	54

19518	Pocket Vernier Caliper 100 mm	54
19892	Mini Vernier Caliper 70 mm	54
19894	Mini Vernier Caliper 100 mm	54
19899	Vernier Caliper 150 mm	53
19912	Vernier Caliper 200 mm	53
19913	Vernier Caliper 300 mm	53
19920	Vernier Caliper 450 mm	53
19921	Vernier Caliper 600 mm	53
19922	Vernier Caliper 1000 mm	53
19932	Fiberglass Dial Caliper 150 mm	55
19974	Digital Vernier Caliper with Hold Function Mini 100 mm	55
19975	Digital Vernier Caliper with Hold Function 150 mm	55
19976	Digital Vernier Caliper with Hold Function 200 mm	55
19977	Digital Vernier Caliper with Hold Function 300 mm	55
19978	Digital Vernier Caliper Carbon Fiber Body 100 mm	56
19979	Digital Vernier Caliper Carbon Fiber Body 150 mm	56
19981	Digital Vernier Caliper Carbon Fiber Body with Solar Panel 150 mm	56
19983	Digital Vernier Caliper with Solar Panel 150 mm	56
19984	Digital Vernier Caliper with Solar Panel 200 mm	56
19986	Digital Vernier Caliper with Hold Function 450 mm	55
19987	Digital Vernier Caliper with Hold Function 600 mm	55
19988	Digital Vernier Caliper with Hold Function 1000 mm	55

21000~21999

Item Code	Description	Page
21010	Stainless Steel Rule Hard Chrome Finish H-101A 15 cm	27
21028	Stainless Steel Rule Hard Chrome Finish H-101E 60 cm	27
21085	Stainless Steel Rule Hard Chrome Finish H-101C 30 cm	27
21107	Stainless Steel Rule Hard Chrome Finish H-101F 1 m	27
21148	Stainless Steel Rule Polish Finish S-101A 15 cm	28
21156	Stainless Steel Rule Polish Finish S-101C 30 cm	28
21164	Stainless Steel Rule Polish Finish S-101E 60 cm	28
21172	Stainless Steel Rule Polish Finish S-101F 1 m	28
21566	Stainless Steel Rule Hard Chrome Finish H-102I 3 m	27
21589	Stainless Steel Rule Hard Chrome Finish H-102G 1.5 m	27
21607	Stainless Steel Rule Hard Chrome Finish H-102H 2 m	27
21741	Stainless Steel Rule Polish Finish S-102G 1.5 m	28
21768	Stainless Steel Rule Polish Finish S-102H 2 m	28

22000~22999

Item Code	Description	Page
22004	Stainless Steel Rule Hard Chrome Finish H-201A 15 cm/6"	27
22012	Stainless Steel Rule Hard Chrome Finish H-201C 30 cm/12"	27
22021	Stainless Steel Rule Hard Chrome Finish H-201E 60 cm/24"	27
22039	Stainless Steel Rule Hard Chrome Finish H-201F 1m/36"	27

23000~23999

Item Code	Description	Page
23001	Stainless Steel Rule Hard Chrome Finish H-301A 15 cm/6"	27
23021	Stainless Steel Rule Hard Chrome Finish H-301C 30 cm/12"	27
23029	Stainless Steel Rule Hard Chrome Finish H-301E 60 cm/24"	27
23037	Stainless Steel Rule Hard Chrome Finish H-301F 1 m/36"	27
23159	Stainless Steel Rule Hard Chrome Finish H-302G 1.5 m/60"	27
23167	Stainless Steel Rule Hard Chrome Finish H-302H 2 m/78"	27

23175	Stainless Steel Rule Hard Chrome Finish H-302I 3 m/118"	27
23275	Stainless Steel Rule Polish Finish S-102I 3 m	28
23276	Stainless Steel Rule Polish Finish S-102J 4 m	28
23277	Stainless Steel Rule Polish Finish S-102K 5 m	28
23278	Stainless Steel Rule Polish Finish S-102L 6 m	28

24000~24999

Item Code	Description	Page
24007	Stainless Steel Rule Hard Chrome Finish H-401A 15 cm/6"	28
24015	Stainless Steel Rule Hard Chrome Finish H-401C 30 cm/12"	28
24023	Stainless Steel Rule Hard Chrome Finish H-401E 60 cm/24"	28
24031	Stainless Steel Rule Hard Chrome Finish H-401F 1 m/36"	28
24252	Stainless Steel Rule Hard Chrome Finish H-402G 1.5 m/60"	28
24260	Stainless Steel Rule Hard Chrome Finish H-402H 2 m/78"	28
24540	Stainless Steel Rule Hard Chrome Finish H-3001A 6"/6" Rigid 4R	29
24548	Stainless Steel Rule Hard Chrome Finish H-3001C 12"/12" Rigid 4R	29
24580	Stainless Steel Rule Hard Chrome Finish H-3101A 6"/6" Flexible 4R	29
24591	Stainless Steel Rule Hard Chrome Finish H-3101C 12"/12" Flexible 4R	29
24621	Stainless Steel Rule Hard Chrome Finish H-3102A 6"/6" Flexible 5R	29
24629	Stainless Steel Rule Hard Chrome Finish H-3102C 12"/12" Flexible 5R	29
24737	Stainless Steel Rule Hard Chrome Finish H-3301A 6"/6" Flexible 3R	29
24742	Stainless Steel Rule Hard Chrome Finish H-3301C 12"/12" Flexible 3R	29
24777	Stainless Steel Rule Hard Chrome Finish H-3302A 6"/6" Rigid 3R	29
24785	Stainless Steel Rule Hard Chrome Finish H-3302C 12"/12" Rigid 3R	29

30000~34999

Item Code	Description	Page
30451	Stainless Steel Rule Hard Chrome Finish H-3412A 6"/15 cm Rigid EM	29
30459	Stainless Steel Rule Hard Chrome Finish H-3412C 12"/30 cm Rigid EM	29
32255	Miter Try Square S-1421 20 cm/8"	50
32263	Miter Try Square S-1422 25 cm/10"	50
32271	Miter Try Square S-1423 30 cm/12"	50
32506	Stainless Steel Rafter Square Polish Finish S-1401 24" x 16"	22
32674	Miter Rule 45° 90° Standard Model S-1462 Inch Graduations	46
33421	Aluminum Cutting Rule 1 m	40
33422	Aluminum Cutting Rule 2 m	40
33423	Aluminum Cutting Rule with Handle 1 m	40
33424	Aluminum Cutting Rule with Handle 2 m	40
33919	Sliding Bevel SB-8 8"	48
33921	Sliding Bevel SB-10 10"	48
33950	Divider with Spring SD-6 15 cm	152
33951	Divider with Spring SD-8 20 cm	152
33952	Divider with Spring SD-10 25 cm	152
33953	Divider with Spring SD-12 30 cm	152
33954	Inside Caliper with Spring IC-6 15 cm	153
33955	Inside Caliper with Spring IC-8 20 cm	153
33956	Inside Caliper with Spring IC-10 25 cm	153
33957	Inside Caliper with Spring IC-12 30 cm	153
33958	Outside Caliper with Spring OC-6 15 cm	153
33959	Outside Caliper with Spring OC-8 20 cm	153
33960	Outside Caliper with Spring OC-10 25 cm	153
33961	Outside Caliper with Spring OC-12 30 cm	153
34513	Carpenter's Square Thick Corner Hard Chrome Finish H-1475 20"/45 cm	8
34517	Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale H-1476 20"	8

46000~48999

Item Code	Description	Page
46800	Molding Rule 15 cm 2/1000	34
46804	Protective cap for Auto Level SA-24A and 28A	217
46845	Water tank for Psychrometer E-2	222
46967	Digital part replacement for Blue Level Digital	216
47032	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 15 cm with JCSS Certificate	224
47049	Vial cover for Slope Level	216
47234	Cutout positioning stick for L-Angle Adjust 45 cm - 60 cm and Free Angle Neo 30 cm - 45 cm	219
47235	Cutout positioning stick for L-Angle Adjust 1 - 1.2 m and Free Angle Neo 60 - 1 m	219
47293	Digital Vernier Caliper with Solar Panel 150 mm with JCSS Certificate	224
47358	Guide stabilization metal fitting for T-Slide II, Double and Slim-shift	220
47359	Mounting position adjustment screw for T-Slide II and Double	220
47364	Slider for T-Slide II	220
47365	Slider for T-Slide Double	220
47383	Slider for T-Slide Slim-shift	220
47386	Mounting position adjustment screw for T-Slide Slim-shift	220
48351	Plastic Thermometer 20 cm Blue	168
48352	Plastic Thermometer 20 cm Yellow	168
48356	Plastic Thermometer 25 cm Blue	168
48357	Plastic Thermometer 25 cm Yellow	168
48361	Plastic Thermometer 30 cm Blue	168
48362	Plastic Thermometer 30 cm Yellow	168
48481	Thermometer Wood M-023	168
48705	Thermometer "Petit Thermo Square" Vertical 12 cm White	169
48706	Thermometer "Petit Thermo Square" Vertical 12 cm Yellow	169
48707	Thermometer "Petit Thermo Square" Vertical 12 cm Blue	169
48715	Thermometer "Petit Thermo Square" with Magnet Vertical 13.5 cm White	169
48716	Thermometer "Petit Thermo Square" with Magnet Vertical 13.5 cm Yellow	169
48717	Thermometer "Petit Thermo Square" with Magnet Vertical 13.5 cm Blue	169
48785	Thermometer "Petit Thermo Square" with Magnet Horizontal 13.5 cm White	169
48786	Thermometer "Petit Thermo Square" with Magnet Horizontal 13.5 cm Yellow	169
48787	Thermometer "Petit Thermo Square" with Magnet Horizontal 13.5 cm Blue	169
48795	Thermometer "Petit Thermo Square" Vertical 20 cm White	169
48796	Thermometer "Petit Thermo Square" Vertical 20 cm Yellow	169
48797	Thermometer "Petit Thermo Square" Vertical 20 cm Blue	169
48927	Thermo/Hygrometer White and White	166
48929	Thermo/Hygrometer Black and White	166
48932	Thermo/Hygrometer Blue	166
48975	Thermo/Hygrometer ECO White	166

49000~49999

Item Code	Description	Page
49099	Stainless Steel Rule Hard Chrome Finish H-402I 3 m/118"	28

58000~58999

Item Code	Description	Page
50027	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 1 m with JCSS Certificate	224
58691	Welding Gauge A	149
58695	Undercut Gauge	149
58697	Crack Scale Clear Type	150
58698	Crack Scale Rule Type 15 cm	150
58699	Crack Scale Card Type	150

62000~62999

Item Code	Description	Page
62006	Japanese Try Square with Square Scale 15 cm	46
62009	Japanese Try Square 15 cm	46
62014	Japanese Try Square with Square Scale 13 cm	46
62020	Mini Try Square Brass Base 4.5 cm	50
62021	Mini Try Square Brass Base 6 cm	50
62022	Mini Try Square Brass Base 7.5 cm	50
62023	Mini Try Square Brass Base 9 cm	50
62060	Miter Rule 45° with Graduations	47
62081	Miter Rule 45° 90° Standard Model	46
62103	Miter Rule 45° Standard Model	47
62110	Miter Rule 45° with Right Angle	47
62112	Miter Rule 3D 45° 90° Polycarbonate	47
62113	Miter Rule 3D 45° 90° Aluminum	47
62114	Miter Rule 3D 45° Aluminum	48
62162	Miter Rule 45° with 40 mm Wide Fence	47
62189	Miter Rule 45° 90° with 40 mm Wide Fence	46
62286	Miter Try Square 20 cm	50
62294	Miter Try Square 25 cm	50
62308	Miter Try Square 30 cm	50
62359	Flat Square 30 x 20 cm	22
62480	Protractor Hard Chrome Finish No.19 φ 90 10 cm	51
62490	Protractor Hard Chrome Finish No.19 Double-blade φ 90 10 cm	51
62495	Digital Protractor with Hold Function 20 cm	52
62496	Digital Protractor with Hold Function 30 cm	52
62499	Protractor Polish Finish No.19 φ 90 10 cm	52
62502	Japanese Bevel 25 cm	48
62510	Japanese Bevel 30 cm	48
62529	Japanese Bevel 45 cm	48
62532	Japanese Bevel 60 cm	48
62540	Aluminum Sliding Bevel without Scale 45 cm	49
62541	Aluminum Sliding Bevel without Scale 60 cm	49
62542	Aluminum Sliding Bevel without Scale 90 cm	49
62546	Nut for Aluminum Sliding Bevel and Welding Guide Rule	215
62547	Plastic washer for Aluminum Sliding Bevel and Welding Guide Rule	215
62548	Center screw for Aluminum Sliding Bevel	215
62569	Aluminum Sliding Bevel with Gradient Scale 30 cm	49
62570	Aluminum Sliding Bevel with Gradient Scale 45 cm	49
62571	Aluminum Sliding Bevel with Gradient Scale 60 cm	49
62572	Aluminum Sliding Bevel with Gradient Scale 90 cm	49
62573	Aluminum Sliding Bevel with Gradient Scale 1.2 m	49
62588	Japanese Sliding Bevel 15 cm	48
62596	Japanese Sliding Bevel 25 cm	48
62600	Taper Gauge No.700 A 1 - 15 mm	154
62603	Taper Gauge with Metal Case 1 - 15 mm	154
62605	Taper Gauge No.700 B 15 - 30 mm	154
62610	Taper Gauge No.700 C 30 - 45 mm	154
62612	Taper Gauge with Rule 1 - 15 mm	154
62615	Taper Gauge No.700 D 45 - 60 mm	154
62620	Taper Gauge Double for Clearance, Hole Diameter, Length 1 - 15 mm	154
62660	Aluminum Sliding Bevel with Angle Scale 30 cm	49
62661	Aluminum Sliding Bevel with Angle Scale 45 cm	49
62662	Aluminum Sliding Bevel with Angle Scale 60 cm	49

62774	Protractor Hard Chrome Finish No.30 φ 120	51
62839	Protractor Hard Chrome Finish No.300 Double-blade φ 210 30 cm	51
62847	Protractor Hard Chrome Finish No.1000 φ 320 1 m	51
62855	Protractor Hard Chrome Finish No.600 φ 320 60 cm	51
62868	Protractor Hard Chrome Finish with Groove No.101 φ 120 15 cm	51
62898	Protractor Hard Chrome Finish No.300 φ 210 30 cm	51
62901	Protractor Hard Chrome Finish No.182 φ 90 10 cm	51
62928	Protractor Hard Chrome Finish No.183 Square 10 cm	51
62944	Protractor Hard Chrome Finish No.600 Double-blade φ 320 60 cm	51
62952	Protractor Hard Chrome Finish No.1000 Double-blade φ 320 1 m	51
62987	Protractor Polish Finish Mini φ 40 10 cm	52
62995	Protractor Hard Chrome Finish Mini φ 40 10 cm	51

63000~63999

Item Code	Description	Page
63053	Large Square Rigid Polish Finish 60 x 30 cm	21
63094	Large Square Polish Finish 1 m/3 shaku 3 sun	20
63099	Large Square Rigid Polish Finish 1 m x 60 cm	20
63118	Large Square Polish Finish 1 m x 60 cm	20
63121	Large Square with Brace Polish Finish 1 m x 60 cm	21
63122	Large Square Polish Finish 1 m x 60 cm with 8 Scales	20
63128	Large Square Polish Finish 3 shaku 3 sun x 2 shaku	20
63400	Large Square Hard Chrome Finish 1 m x 60 cm	20
63402	Large Square Hard Chrome Finish 60 x 30 cm	21
63410	Large Square Polish Finish 60 x 30 cm	21
63411	Large Square Polish Finish 2 x 1 shaku	21
63412	Large Square Polish Finish 60 cm/2 shaku	21
63413	Large Square Polish Finish 60 x 30 cm with 8 Scales	21
63509	Large Caliper 30 cm	23
63517	Large Caliper 35 cm	23
63525	Large Caliper 45 cm	23
63541	Large Caliper 60 cm	23
63568	Large Caliper 75 cm	23
63592	Large Caliper 1 m	23
63770	6-folding Stainless Steel Rule Polish Finish 1 m	33

64000~64999

Item Code	Description	Page
64009	Dressmaking Square Hard Chrome Finish 75 x 35 cm	22
64548	Rafter Square 60 x 40 cm	22

65000~65999

Item Code	Description	Page
65030	Aluminum Cutting Rule EX 60 cm/shaku	39
65031	Aluminum Cutting Rule EX with Handle 60 cm/shaku	39
65032	Aluminum Cutting Rule EX 1 m/shaku	39
65033	Aluminum Cutting Rule EX with Handle 1 m/shaku	39
65034	Aluminum Cutting Rule EX 1.5 m/shaku	39
65035	Aluminum Cutting Rule EX with Handle 1.5 m/shaku	39
65036	Aluminum Cutting Rule EX 2 m/shaku	39
65037	Aluminum Cutting Rule EX with Handle 2 m/shaku	39
65038	Aluminum Cutting Rule EX 2.5 m/shaku	39
65065	Aluminum Cutting Rule PROTECT 70 cm/shaku	39
65066	Aluminum Cutting Rule PROTECT 1 m/shaku	39

65067	Aluminum Cutting Rule PROTECT 1.25 m/shaku	39
65068	Aluminum Cutting Rule PROTECT 2 m/shaku	39
65075	Aluminum Cutting Rule Light 1 m	40
65076	Aluminum Cutting Rule Light with Handle 1 m	40
65077	Cut Rail 1 m/shaku	40
65078	Cut Rail 2 m/shaku	40
65086	Aluminum Cutting Rule 60 cm/shaku	40
65088	Aluminum Cutting Rule 1 m/shaku Left Reference Point	40
65090	Aluminum Cutting Rule 1 m/shaku	40
65091	Aluminum Cutting Rule 2 m/shaku	40
65092	Aluminum Cutting Rule 2.5 m/shaku	40
65093	Aluminum Cutting Rule with Handle 1 m/shaku	40
65094	Aluminum Cutting Rule 1.5 m/shaku	40
65096	Aluminum Cutting Rule with Handle 1.5 m/shaku	40
65097	Aluminum Cutting Rule with Handle 2 m/shaku	40
65098	Aluminum Cutting Rule with Handle 60 cm/shaku	40
65105	Telescopic Measure Two Directions C 360 cm	42
65106	Telescopic Measure Two Directions D 400 cm	42
65107	Telescopic Measure Two Directions A 95 cm	42
65108	Telescopic Measure Two Directions AB 190 cm	42
65109	Telescopic Measure Two Directions B 280 cm	42
65132	Shaku Measure 12 shaku	42
65133	Shaku Measure 13 shaku 5 sun	42
65160	Telescopic Measure Two Directions A 3 shaku 2 sun	42
65161	Telescopic Measure Two Directions AB 6 shaku 3 sun	42
65162	Telescopic Measure Two Directions B 9 shaku 3 sun	42
65163	Telescopic Measure Two Directions C 12 shaku	42
65164	Telescopic Measure Two Directions D 13 shaku 5 sun	42
65180	Ken Measure 12 shaku	43
65183	Telescopic Measure One Direction A 3 shaku 2 sun	41
65184	Telescopic Measure One Direction AB 6 shaku 3 sun	41
65185	Telescopic Measure One Direction B 9 shaku 3 sun	41
65186	Telescopic Measure One Direction C 12 shaku	41
65187	Telescopic Measure One Direction D 13 shaku 5 sun	41
65188	Telescopic Measure One Direction E 15 shaku 5 sun	41
65190	Telescopic Measure One Direction II A 3 shaku 2 sun	41
65191	Telescopic Measure One Direction II AB 6 shaku 6 sun	41
65192	Telescopic Measure One Direction II B 9 shaku 3 sun	41
65193	Telescopic Measure One Direction II C 12 shaku	41
65194	Telescopic Measure One Direction II D 13 shaku 5 sun	41
65195	Telescopic Measure One Direction II E 15 shaku 5 sun	41
65204	Molding Rule 2 m 23/1000	34
65205	Molding Rule 2 m 28/1000	34
65260	Aluminum Box Beam Straight Measure 135 cm	43
65262	Aluminum Box Beam Straight Measure 175 cm	43
65264	Aluminum Box Beam Straight Measure 195 cm	43
65266	Aluminum Box Beam Straight Measure 230 cm	43
65331	Aluminum Rule with Non-slip Pad 30 cm	38
65340	Aluminum Rule Rigid 30 cm	37
65358	Aluminum Rule with Non-slip Pad 45 cm	38
65363	Aluminum Rule Rigid 45 cm	37
65374	Aluminum Rule with Non-slip Pad 60 cm	38
65378	Aluminum Rule Rigid 60 cm	37
65382	Aluminum Rule with Non-slip Pad 1 m	38

65387	Aluminum Rule Rigid 1 m	37
65415	Aluminum Rule with Non-slip Pad 30 cm Blue	38
65416	Aluminum Rule with Non-slip Pad 30 cm Pink	38
65417	Aluminum Rule with Non-slip Pad 30 cm Gold	38
65418	Aluminum Rule with Non-slip Pad 30 cm White	38
65423	Aluminum Rule with Non-slip Pad 45 cm Blue	38
65424	Aluminum Rule with Non-slip Pad 45 cm Pink	38
65425	Aluminum Rule with Non-slip Pad 45 cm Gold	38
65426	Aluminum Rule with Non-slip Pad 45 cm White	38
65434	Aluminum Rule with Non-slip Pad 60 cm Blue	38
65435	Aluminum Rule with Non-slip Pad 60 cm Pink	38
65436	Aluminum Rule with Non-slip Pad 60 cm Gold	38
65437	Aluminum Rule with Non-slip Pad 60 cm White	38
65442	Aluminum Rule with Non-slip Pad 1 m Blue	38
65443	Aluminum Rule with Non-slip Pad 1 m Pink	38
65444	Aluminum Rule with Non-slip Pad 1 m Gold	38
65445	Aluminum Rule with Non-slip Pad 1 m White	38
65498	Aluminum Rule 15 cm	38
65501	Aluminum Rule 30 cm	38
65528	Aluminum Rule 45 cm	38
65536	Aluminum Rule 60 cm	38
65544	Aluminum Rule 1 m	38

66000~67999

Item Code	Description	Page
66002	Template with Edge TA-1E Circle Medium	201
66003	Template with Edge TA-4E Circle Small	201
66004	Template TB-1 Circle Medium	201
66005	Template TB-4 Circle Small	201
66007	Template TD-1 Furniture Large 1/50	202
66008	Template TD-2 Furniture Small 1/100	202
66010	Template TD-4 Architecture 1/100 and 1/200	202
66013	Template TE-5 Number/Alphabet	201
66014	Template TE-6 Number/Alphabet	201
66015	Template TE-7 Number/Alphabet	201
66016	Template TE-9 Number	201
66017	Template TE-10 Number	201
66018	Template TE-11 Number	201
66020	Template TG-3 Oval	201
66021	Template TH-1 General Shape Small	202
66022	Template TH-2 General Shape Small	202
66024	Template TH-4 General Shape Medium	202
66025	Template TH-5 General Shape Medium	202
66026	Template TJ-1 Bolt and Nut	202
66027	Template TK-1 Finish Mark	202
66029	Template TL-1 Arrow	202
66031	Template TP-1 Corner	201
66033	Template TQ-1 Japanese and Roman Letter	202
66034	Template TS-A 3 pc-pack Card-size Set	202
67618	Cartridge 100/150 for Screw Pitch Marking Tool Multi	122
67619	Cartridge 200/250/300 for Screw Pitch Marking Tool Multi	122
67823	Handle for Laser ROBO Neo BRIGHT and E Sensor	217
67845	Molding Rule 15 cm 19/1000	34
67983	Individual Paper Box 80 x 75 x 45 mm White	228

70000~70999

Item Code	Description	Page
70008	Scale 100 kg	82
70026	Scale 50 kg	82
70079	Scale for Commercial Use 1 kg	83
70081	Scale for Commercial Use 2 kg	83
70084	Scale for Commercial Use 4 kg	83
70087	Scale for Commercial Use 8 kg	83
70090	Scale for Commercial Use 12 kg	83
70093	Scale for Commercial Use 20 kg	83
70101	Scale for Commercial Use 50 kg	83
70102	Scale for Commercial Use 30 kg	83
70104	Digital Scale 3 kg	81
70105	Digital Scale 6 kg	81
70106	Digital Scale 15 kg	81
70107	Digital Scale 30 kg	81
70108	Digital Scale Remote-reading 100 kg	82
70109	Digital Spring Scale 20 kg	84
70119	AC adapter for Digital Scale	81
70120	Stainless steel plate for Digital Scale	216
70121	Plastic plate for Digital Scale	216
70123	Scale for Commercial Use 200 g	83
70124	Scale for Commercial Use 400 g	83
70128	Plate flat type for Scale 200 g - 1 kg	216
70129	Plate flat type for Scale 2 kg - 12 kg	216
70131	Plate fixing screw one pair (2 pc-set) for Scale 200 g - 30 kg	216
70139	Plate flat type for Scale 20 kg	216
70140	Plate flat type for Scale 30 kg	216
70143	Plastic cover for Scale 200 g - 1 kg	216
70144	Plastic cover for Scale 2 kg - 12 kg	216
70145	Plastic cover for Scale 20 kg	216
70146	Plastic cover for Scale 30 kg	216
70163	Digital Compact Scale Mini 200 g	80
70191	Digital Scale for Commercial Use 3 kg	81
70192	Digital Scale for Commercial Use 6 kg	81
70193	Digital Scale for Commercial Use 15 kg	81
70194	Digital Scale for Commercial Use 30 kg	81
70304	Metallic Hourglass for 3-minute	185
70380	Thermo/Hygrometer P-2 12 cm White	165
70480	Thermo/Hygrometer and Discomfort Index Meter R-1 Green	165
70494	Thermo/Hygrometer Q-1 15 cm Blue	163
70495	Thermo/Hygrometer Q-1 15 cm Gray	163
70496	Thermo/Hygrometer Q-2 10 cm Blue	163
70497	Thermo/Hygrometer Q-2 10 cm Gray	163
70498	Thermo/Hygrometer Q-3 6.5 cm Blue	163
70499	Thermo/Hygrometer Q-3 6.5 cm Gray	163
70500	Thermo/Hygrometer and Discomfort Index Meter R-2 Green	165
70501	Thermo/Hygrometer for Room Conditioning F-2L 15 cm Blue	164
70503	Thermo/Hygrometer for Environmental Safety F-4L 15 cm Blue	164
70505	Thermo/Hygrometer for Heatstroke Warning F-3L II 15 cm White	164
70506	Thermo/Hygrometer for Room Conditioning F-2M 10 cm Blue	164
70507	Thermo/Hygrometer for Heatstroke Warning F-3M 10 cm White	164
70508	Thermo/Hygrometer for Environmental Safety F-4M 10 cm Blue	164
70510	Thermo/Hygrometer W-1 White	165

70514	Thermo/Hygrometer for Room Conditioning F-2S 6.5 cm Blue	164
70515	Thermo/Hygrometer for Heatstroke Warning F-3S 6.5 cm White	164
70516	Thermo/Hygrometer for Environmental Safety 6.5 cm Blue	164
70550	Hourglass for 1-minute	185
70551	Hourglass for 3-minute	185
70552	Hourglass for 5-minute	185
70720	Mirror with frame for Inspection Mirror A-3 and D-3	221
70726	Acrylic Dot-line Drawing Rule 30 cm	196
70734	Acrylic Dot-line Drawing Rule 15 cm	196
70750	Acrylic Scale Reduction Rule 15 cm	196
70769	Acrylic Scale Reduction Rule 30 cm	196
70777	Triangle Scale A-10 10 cm	199
70802	Triangle Scale for Microcopy C-15 15 cm	199
70803	Triangle Scale for Microcopy C-30 30 cm	199
70874	Drawing Brush	203
70920	Compass Attachment	198
70947	Curved Rule Middle-size	197
70961	Stainless Steel Mesh Erasing Shield	198
70963	Stainless Steel Erasing Shield	198

71000~71999

Item Code	Description	Page
71005	Spring Tape Measure 1.5 m	63
71013	Flat Tape 1.5 m	63
71310	Map Measure C Keyring Model	188
71320	Map Measure D Multi-function Model	188
71500	Laser Receiver II Plus with Holder	110
71501	Laser Receiver II Plus for Laser ROBO Green with Holder	110
71502	Laser ROBO Neo 21 E Sensor	101
71503	Laser ROBO Neo 31 E Sensor	101
71505	Laser ROBO Neo 51 E Sensor	101
71506	Laser ROBO Neo 51 AR E Sensor	101
71512	Laser ROBO Neo 21 E Sensor with Receiver and Tripod	101
71513	Laser ROBO Neo 31 E Sensor with Receiver and Tripod	101
71515	Laser ROBO Neo 51 E Sensor with Receiver and Tripod	101
71516	Laser ROBO Neo 51 AR E Sensor with Receiver and Tripod	101
71602	Laser ROBO Green Neo E Sensor 21	100
71603	Laser ROBO Green Neo E Sensor 31	100
71605	Laser ROBO Green Neo E Sensor 51	100
71606	Laser ROBO Green Neo E Sensor 51 AR	100
71607	Laser ROBO X line Red	97
71608	Laser ROBO X line Green	97
71609	Laser ROBO X line-E Red	97
71610	Laser ROBO X line-E Green	97
71612	Laser ROBO Green Neo E Sensor 21 with Receiver and Tripod	100
71613	Laser ROBO Green Neo E Sensor 31 with Receiver and Tripod	100
71615	Laser ROBO Green Neo E Sensor 51 with Receiver and Tripod	100
71616	Laser ROBO Green Neo E Sensor 51 AR with Receiver and Tripod	100
71617	Laser ROBO X line Red with Receiver and Tripod	97
71618	Laser ROBO X line Green with Receiver and Tripod	97
71619	Laser ROBO X line-E Red with Receiver and Tripod	97
71620	Laser ROBO X line-E Green with Receiver and Tripod	97
71760	Bamboo Rule with Hole 30 cm	44
71765	Bamboo Rule with Hole 50 cm	44

71773	Bamboo Rule with Hole 1 m	44
71812	Color Magnets φ 20 Red 10 pc-pack in Vinyl Bag	209
71813	Color Magnets φ 20 White 10 pc-pack in Vinyl Bag	209
71814	Color Magnets φ 20 Blue 10 pc-pack in Vinyl Bag	209
71815	Color Magnets φ 20 Yellow 10 pc-pack in Vinyl Bag	209
71816	Color Magnets φ 30 Red 10 pc-pack in Vinyl Bag	209
71817	Color Magnets φ 30 White 10 pc-pack in Vinyl Bag	209
71818	Color Magnets φ 30 Blue 10 pc-pack in Vinyl Bag	209
71819	Color Magnets φ 30 Yellow 10 pc-pack in Vinyl Bag	209
71820	Color Magnets φ 40 Red 10 pc-pack in Vinyl Bag	209
71821	Color Magnets φ 40 White 10 pc-pack in Vinyl Bag	209
71822	Color Magnets φ 40 Blue 10 pc-pack in Vinyl Bag	209
71823	Color Magnets φ 40 Yellow 10 pc-pack in Vinyl Bag	209
71824	Strong Color Magnets with Yoke φ 20 Red 6 pc-pack in Vinyl Bag	208
71825	Strong Color Magnets with Yoke φ 20 White 6 pc-pack in Vinyl Bag	208
71826	Strong Color Magnets with Yoke φ 20 Blue 6 pc-pack in Vinyl Bag	208
71827	Strong Color Magnets with Yoke φ 20 Yellow 6 pc-pack in Vinyl Bag	208
71828	Strong Color Magnets with Yoke φ 30 Red 6 pc-pack in Vinyl Bag	208
71829	Strong Color Magnets with Yoke φ 30 White 6 pc-pack in Vinyl Bag	208
71830	Strong Color Magnets with Yoke φ 30 Blue 6 pc-pack in Vinyl Bag	208
71831	Strong Color Magnets with Yoke φ 30 Yellow 6 pc-pack in Vinyl Bag	208
71832	Strong Color Magnets with Yoke φ 40 Red 6 pc-pack in Vinyl Bag	208
71833	Strong Color Magnets with Yoke φ 40 White 6 pc-pack in Vinyl Bag	208
71834	Strong Color Magnets with Yoke φ 40 Blue 6 pc-pack in Vinyl Bag	208
71835	Strong Color Magnets with Yoke φ 40 Yellow 6 pc-pack in Vinyl Bag	208
71854	Bamboo Rule Kujira 2 shaku for Kimono	44
71897	Bamboo Rule Kane 1 shaku	44
71900	Bamboo Rule Kane 2 shaku	44
71919	Bamboo Rule Kane 3 shaku	44

72000~72999

Item Code	Description	Page
72008	Magnetic Holder 38 cm	205
72009	Magnetic Sheet 10 x 20 cm 1.2 mm Thick with Adhesive 10 x 20 cm	212
72010	Color Magnets φ 20 Red 5 pc-pack	208
72011	Color Magnets φ 20 White 5 pc-pack	208
72012	Color Magnets φ 20 Blue 5 pc-pack	208
72014	Color Magnets φ 20 Yellow 5 pc-pack	208
72015	Color Magnets φ 30 Red 3 pc-pack	208
72016	Color Magnets φ 30 White 3 pc-pack	208
72017	Color Magnets φ 30 Blue 3 pc-pack	208
72019	Color Magnets φ 30 Yellow 3 pc-pack	208
72020	Color Magnets φ 40 Red 2 pc-pack	208
72021	Color Magnets φ 40 White 2 pc-pack	208
72022	Color Magnets φ 40 Blue 2 pc-pack	208
72024	Color Magnets φ 40 Yellow 2 pc-pack	208
72032	Magnetic Hanger Square B Yellow	210
72033	Magnetic Bar 25 cm Red	211
72034	Magnetic Bar 25 cm Blue	211
72035	Magnetic Bar 25 cm Yellow	211
72036	Magnetic Clips Circle A Green 2 pc-pack	209
72037	Magnetic Clips Circle A Blue 2 pc-pack	209
72038	Magnetic Clips Circle A Yellow 2 pc-pack	209
72039	Magnetic Clips Circle A Red 2 pc-pack	209

72040	Magnetic Clip Square B Small	209
72041	Magnetic Clip Square C Large	209
72042	Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Red	212
72043	Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A White	212
72044	Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Yellow	212
72045	Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Green	212
72046	Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Blue	212
72047	Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Red	212
72048	Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B White	212
72049	Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Yellow	212
72050	Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Green	212
72051	Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Blue	212
72052	Strong Color Magnets with Yoke φ 20 Red 6 pc-pack	207
72053	Strong Color Magnets with Yoke φ 20 White 6 pc-pack	207
72056	Strong Color Magnets with Yoke φ 20 Yellow 6 pc-pack	207
72057	Strong Color Magnets with Yoke φ 25 Red 5 pc-pack	207
72058	Strong Color Magnets with Yoke φ 25 White 5 pc-pack	207
72061	Strong Color Magnets with Yoke φ 25 Yellow 5 pc-pack	207
72062	Strong Color Magnets with Yoke φ 30 Red 4 pc-pack	207
72063	Strong Color Magnets with Yoke φ 30 White 4 pc-pack	207
72066	Strong Color Magnets with Yoke φ 30 Yellow 4 pc-pack	207
72067	Strong Color Magnets with Yoke φ 40 Red 3 pc-pack	207
72068	Strong Color Magnets with Yoke φ 40 White 3 pc-pack	207
72071	Strong Color Magnets with Yoke φ 40 Yellow 3 pc-pack	207
72072	Strong Color Magnets with Yoke φ 50 Red 2 pc-pack	207
72073	Strong Color Magnets with Yoke φ 50 White 2 pc-pack	207
72076	Strong Color Magnets with Yoke φ 50 Yellow 2 pc-pack	207
72077	Strong Color Magnets with Yoke φ 20 Blue 6 pc-pack	207
72078	Strong Color Magnets with Yoke φ 25 Blue 5 pc-pack	207
72079	Strong Color Magnets with Yoke φ 30 Blue 4 pc-pack	207
72080	Strong Color Magnets with Yoke φ 40 Blue 3 pc-pack	207
72081	Strong Color Magnets with Yoke φ 50 Blue 2 pc-pack	207
72084	Magnetic Hanger Square B Red	210
72085	Magnetic Hanger Square B Blue	210
72086	Rubber Magnetic Sheet 10 cm x 10 m 0.8 mm Thick Black Roll	213
72126	Magnetic Clips Flexible D White 2 pc-pack	210
72150	Magnetic Chips Circle A-1 φ 10 6 pc-pack	206
72151	Magnetic Chips Circle A-2 φ 15 6 pc-pack	206
72152	Magnetic Chips Circle A-3 φ 20 3 pc-pack	206
72153	Magnetic Chips Square B-1 15 x 16 mm 3 pc-pack	206
72154	Magnetic Chips Square B-2 15 x 20 mm 2 pc-pack	206
72155	Magnetic Chips Square B-3 19 x 25 mm 2 pc-pack	206
72156	Magnetic Chips Square B-4 10.5 x 30 mm 2 pc-pack	206
72182	Magnetic Sheet Piece 10 x 20 mm 0.8 mm Thick with Adhesive C-1 100 pc-pack	212
72200	Steel Sheet 10 x 20 cm 0.2 mm Thick with Adhesive 2 pc-pack	212
72204	Fluorescent Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick Yellow	213
72215	Magnetic Sheet Mat 10 cm x 10 m 0.8 mm Thick White Roll	213
72219	Magnetic Chips Circle A-4 φ 25 2 pc-pack	206
72220	Magnetic Chips Circle A-5 φ 30 2 pc-pack	206
72221	Magnetic Chips Square B-5 20 x 30 mm 2 pc-pack	206
72290	Magnetic Pick-up Tool H-2	205
72291	Magnetic Pick-up Tool H-3	205
72293	Welding Magnet S	205
72294	Welding Magnet M	205

72295	Welding Magnet L	205
72456	Magnetic Pick-up Tool with Light H-4	205
72508	Stick Thermometer Alcohol H-2 0 - 105°C 30 cm Individually Packaged	179
72510	Stick Thermometer Alcohol H-2 0 - 200°C 30 cm Individually Packaged	179
72511	Stick Thermometer Alcohol H-3 -20 - 105°C 30 cm Individually Packaged	179
72514	Stick Thermometer Alcohol H-4 0 - 100°C 15 cm Individually Packaged	179
72516	Stick Thermometer Mercury I -20 - 105°C 30 cm Individually Packaged	179
72524	Thermometer C	168
72526	Thermometer C-2	168
72532	Thermometer for Refrigerator with Magnet A	174
72547	Stick Thermometer Alcohol H-3 0 - 100°C 30 cm Individually Packaged	179
72571	Thermometer Wood 90 cm	168
72574	Stick Thermometer Alcohol H-6 -30 - 50°C 30 cm Individually Packaged	179
72577	Stick Thermometer Alcohol H-7 -10 - 65°C 30 cm Individually Packaged	179
72579	Stick Thermometer Alcohol H-8 -20 - 50°C 15 cm Individually Packaged	179
72581	Stick Thermometer Alcohol H-9 -10 - 50°C 15 cm x 2 pc-set Individually Packaged	179
72583	Thermometer for Aquarium L	176
72590	Thermometer C-5	168
72591	Thermo/Hygrometer F 15 cm	163
72604	Stick Thermometer Alcohol H-10 -20 - 105°C 45 cm Individually Packaged	179
72605	Thermo/Hygrometer G 15 cm	163
72610	Thermometer V-2 -20 - 60°C φ 3.5 x 13 cm	167
72611	Thermometer V-3 -20 - 100°C φ 6 x 90 cm	167
72615	Thermo/Hygrometer Green	166
72622	Thermometer for Ground Temperature O-2 White	181
72623	Thermometer for Ground Temperature O-3 Mini A 3 pc-pack (Red, Orange, Purple)	181
72624	Thermometer for Ground Temperature with Air Temperature O-4 White	181
72627	Thermometer for Ground Temperature O-2 Yellow	181
72630	Thermometer for Ground Temperature O-2 Blue	181
72633	Thermometer for Ground Temperature O-3 Mini B 3 pc-pack (Black, Blue, Green)	181
72636	Thermometer for Ground Temperature with Air Temperature O-4 Yellow	181
72639	Thermometer for Ground Temperature with Air Temperature O-4 Blue	181
72648	Thermometer for Bath B Blue	175
72651	Thermometer for Bath B-3	175
72667	Thermometer S-3 6.5 cm	166
72668	Hygrometer T-3 6.5 cm	166
72669	Thermo/Hygrometer U-3 6.5 cm	163
72674	Thermometer and Hygrometer Pair ST-4 4.5 cm	167
72675	Thermometer S-5 3.5 cm	166
72689	Thermometer S-1 10 cm	166
72690	Hygrometer T-1 10 cm	166
72691	Thermo/Hygrometer U-1 10 cm	163
72692	Thermometer for Refrigerator with Magnet A-4 Remote-reading	174
72703	Thermometer for Refrigerator A-3 5 cm	174
72706	Psychrometer E-2	176
72709	Maximum and Minimum Thermometer D-7	176
72715	Maximum and Minimum Thermometer D-9	176
72716	Digital Soil pH Meter A	182
72718	Salt Hydrometer	181
72724	Soil pH Meter A	181
72725	Thermometer for Bath B-8	175
72729	Metal Case for Stick Thermometer for 30 cm	179
72731	Metal Case for Stick Thermometer for 15 cm	179
72746	Stick Thermometer Alcohol H-15 -20 - 105°C 30 cm Bulk Packaged	180

72747	Stick Thermometer Alcohol H-25 0 - 200℃ 30 cm Bulk Packaged	180
72748	Stick Thermometer Alcohol H-45 0 - 100℃ 15 cm Bulk Packaged	180
72749	Stick Thermometer Alcohol H-55 0 - 100℃ 30 cm Bulk Packaged	180
72750	Stick Thermometer Alcohol H-65 -30 - 50℃ 30 cm Bulk Packaged	180
72751	Stick Thermometer Alcohol H-75 -10 - 65℃ 30 cm Blue Bulk Packaged	180
72752	Stick Thermometer Alcohol H-85 -20 - 50℃ 15 cm Bulk Packaged	180
72754	Stick Thermometer Mercury I-15 -20 - 105℃ 30 cm Bulk Packaged	180
72758	Digital Soil EC Meter	182
72760	Thermometer for Bath B Pink	175
72762	Tape Measure SMART GEAR with Magnetic Hook 25-5.5 m	62
72788	Digital pH Meter	183
72799	Digital Salinity Meter	183
72947	Digital Thermometer for Indoor and Outdoor E	171
72957	Thermometer "Petit Thermo Twin" for Outside and Inside	169
72960	Thermometer V-1 0 - 100℃ φ 3.5 x 13 cm	167
72967	Thermometer for Frying Oil Chopstick Model	175
72976	Digital Soil EC Meter II	182
72978	Digital Thermometer for Cooking T Pink	174
72979	Digital Thermometer for Cooking T Green	174
72980	Digital Thermometer for Refrigerator T Round-shape	174
72985	Digital Thermo/Hygrometer with Discomfort Index Meter C	171
72989	Digital Thermo/Hygrometer with Solar Panel B Maximum and Minimum	171
72991	Thermometer Aluminum 45 cm	168
72992	Thermometer Aluminum 60 cm	168
72993	Thermometer Aluminum 75 cm	168

73000~73999

Item Code	Description	Page
73001	Case for Stick Thermometer 15 cm	222
73002	Case for Stick Thermometer 30 cm	222
73003	Clear Case for Stick Thermometer H-3 30 cm	222
73009	Infrared Thermometer with Clock Function A Emissivity Adjustable Model	177
73010	Infrared Thermometer with Laser Pointer B	177
73012	Thermometer V-4 0 - 200℃ White φ 8 x 20 cm	167
73013	Thermometer V-4 0 - 200℃ Black φ 8 x 20 cm	167
73014	Infrared Thermometer with Laser Pointer C Emissivity Adjustable Model	178
73017	Infrared Thermometer with Probe D Emissivity Adjustable Model	177
73030	Digital Thermo/Hygrometer Home A Maximum and Minimum White	170
73033	Calibration Buffer Solution pH 4.01, pH 7.01 3 Each	183
73034	Calibration Buffer Solution pH 10.01, pH 7.01 3 Each	183
73035	Conductivity Solution 1413 μS/cm 6 Sachets	183
73036	Infrared Thermometer with Dual Laser Pointer E Emissivity Adjustable Model	178
73038	Infrared Thermometer F	177
73042	Digital Thermometer for Refrigerator A Maximum and Minimum Remote-reading	174
73043	Maximum and Minimum Digital Thermometer D-10 Waterproof	171
73044	Digital Thermo/Hygrometer Home A White with Clear Package	170
73045	Waterproof Digital Thermometer G-1 Maximum and Minimum Remote-reading	172
73046	Waterproof Digital Thermometer for 2 points G-2 Remote-reading	172
73047	Sensor probe for Digital Thermometer G and Wireless Thermometer A	222
73048	Digital Thermo/Hygrometer Home A Blue with Clear Package	170
73049	Digital Thermo/Hygrometer Home A Green with Clear Package	170
73051	Thermometer for Bath B-9 Green and White	175
73052	Thermometer for Bath B-9 White and Pink	175
73054	Digital Thermo/Hygrometer D-1 Blue	171

73055	Digital Thermo/Hygrometer D-1 Orange	171
73056	Digital Thermo/Hygrometer D-2 Blue	171
73057	Digital Thermo/Hygrometer D-2 Orange	171
73059	Divider with Spring A 15 cm	152
73063	Shock-resistant Infrared Thermometer with Dual Laser Pointer G Emissivity Adjustable Model	178
73067	Divider with Spring B 20 cm	152
73080	Waterproof Digital Thermometer with Remote Probe H-1	172
73081	Waterproof Digital Thermometer with Remote Probe H-2	172
73087	Remote Probe Thin Model φ 2.0 x 185 mm for Digital Thermometer H-2	172
73088	Remote Probe Standard Model φ 3.5 x 110 mm for Digital Thermometer H-2	172
73089	Remote Probe Long and Thick Model φ 5.0 x 275 mm for Digital Thermometer H-2	172
73090	Remote Probe Surface Model φ 3.5 x 110 mm for H-2	172
73095	Thermometer for Bath B-10 Pink	175
73096	Thermometer for Bath B-10 Purple	175
73097	Thermometer for Bath B-10 White	175
73098	Digital Thermometer for Bath B	175
73100	Infrared Thermometer for High Temperature with Dual Laser Pointer H Emissivity Adjustable Model	178
73115	Digital Thermo/Hygrometer Smart A	170
73116	Digital Thermometer Smart A	170
73117	Digital Thermometer Smart B for Indoor and Outdoor with Waterproof Outside Sensor	170
73118	Digital Thermometer Smart C Maximum and Minimum for Indoor and Outdoor with Waterproof Outside Sensor	170
73130	Handy Level MEGA-MAG with Magnet 100 mm White	88
73131	Handy Level MEGA-MAG with Magnet 100 mm Black	88
73132	Handy Level MEGA-MAG with Magnet 150 mm White	88
73133	Handy Level MEGA-MAG with Magnet 150 mm Black	88
73150	Circular Saw Guide L-Angle Plus 45 cm/shaku	135
73151	Circular Saw Guide L-Angle Plus 60 cm/shaku	135
73152	Circular Saw Guide L-Angle Plus 1 m/shaku	135
73153	Circular Saw Guide L-Angle Plus 1.2 m/shaku	135
73160	Circular Saw Guide Free Angle Neo 30 cm	141
73161	Circular Saw Guide Free Angle Neo 45 cm	141
73162	Circular Saw Guide Free Angle Neo 60 cm	141
73163	Circular Saw Guide Free Angle Neo 1 m	141
73166	Circular Saw Guide Free Angle Neo 37 cm	141
73180	Circular Saw Guide L-Angle Plus Adjust 45 cm/shaku	134
73181	Circular Saw Guide L-Angle Plus Adjust 60 cm/shaku	134
73182	Circular Saw Guide L-Angle Plus Adjust 1 m/shaku	134
73183	Circular Saw Guide L-Angle Plus Adjust 1.2 m/shaku	134
73241	Wireless Thermometer with Remote Twin Probe A Maximum and Minimum Waterproof	173
73242	Additional Remote Sensor for Wireless Thermometer A	173
73250	One-side Caliper A 15 cm	152
73253	Inside Caliper A 15 cm	153
73261	Inside Caliper B 20 cm	153
73264	Telescopic Leveling Staff II 3 m 3 Steps	66
73265	Telescopic Leveling Staff II 5 m 3 Steps	66
73266	Telescopic Leveling Staff II 5 m 4 Steps	66
73267	Telescopic Leveling Staff II 5 m 5 Steps	66
73268	Telescopic Leveling Staff II 7 m 5 Steps	66
73269	Lock button for Telescopic Leveling Staff II	216
73280	Handy Ink Line Marker Pro Plus Auto-rewind Black	116
73281	Handy Ink Line Marker Pro Plus Auto-rewind Royal Blue	116
73282	Handy Ink Line Marker Jr. Plus Auto-rewind Black	116
73283	Handy Ink Line Marker Jr. Plus Auto-rewind Coral Red	116
73284	Handy Ink Line Marker Jr. Plus Hand-rewind Black	116

73285	Handy Ink Line Marker Jr. Plus Hand-rewind Turquoise Blue	116
73286	Holder for Handy Ink Line Marker Pro/Jr. Plus	117
73287	Handy Ink Line Marker Pro Plus Auto-rewind Tough Line Metal Red	115
73289	Handy Ink Line Marker Jr. Plus Auto-rewind Tough Line Metal Red	115
73290	Handy Ink Line Marker Pro Plus Auto-rewind with Holder Black	116
73291	Handy Ink Line Marker Pro Plus Auto-rewind with Holder Royal Blue	116
73292	Handy Ink Line Marker Jr. Plus Auto-rewind with Holder Black	116
73293	Handy Ink Line Marker Jr. Plus Auto-rewind with Holder Coral Red	116
73297	Handy Ink Line Marker Pro Plus Auto-rewind Sharp Line Metal Blue	115
73298	Handy Ink Line Marker Jr. Plus Auto-rewind Sharp Line Metal Blue	115
73299	Handy Ink Line Marker Jr. Plus Hand-rewind Sharp Line Metal Blue	115
73300	Handy Ink Line Marker Pro LITE Auto-rewind Blue	117
73301	Handy Ink Line Marker Pro LITE Auto-rewind Red	117
73302	Handy Ink Line Marker Jr. LITE Auto-rewind Green	117
73303	Handy Ink Line Marker Jr. LITE Auto-rewind Orange	117
73307	Handy Ink Line Marker Jr. LITE Hand-rewind Mint Green	117
73310	Digital Counter	162
73312	Circular Saw Guide T-Slide Slim-shift 15 cm/shaku	139
73313	Circular Saw Guide T-Slide Slim-shift 30 cm/shaku	139
73314	Circular Saw Guide T-Slide Slim-shift 45 cm/shaku	139
73315	Circular Saw Guide T-Slide Slim-shift 60 cm/shaku	139
73316	Circular Saw Guide T-Slide Slim-shift 90 cm/shaku	139
73318	Outside Caliper A 15 cm	153
73326	Outside Caliper B 20 cm	153
73441	Wireless Thermometer with Remote Twin Probe A Maximum and Minimum External Antenna Type	173
73442	Additional Remote Sensor for Wireless Thermometer A External Antenna Type	173
73500	Ultra Strong Magnetic Hanger Square C	210
73501	Magnetic Chips Square with Yoke E-1 13 x 22 mm 2 pc-pack	206
73502	Magnetic Chips Square with Yoke E-2 23 x 26 mm 2 pc-pack	206
73503	Magnetic Chips Square with Yoke E-3 30 x 44 mm 2 pc-pack	206
73510	Ultra Strong Magnetic Hanger Circle D	210
73511	Magnetic Pick-up Tool Flexible with Light H-5	205
73514	Magnet Stick Pair of Circle A	211
73515	Magnet Stick Pair of Square B	211
73516	Magnetic Pick-up Tool Flexible with Light and Mirror H-6	205
73520	T-shaped Magnet C ϕ 25	206
73530	U-shaped Magnet A-1	211
73531	U-shaped Magnet B-1	211
73532	U-shaped Magnet A-2	211
73533	U-shaped Magnet B-2	211
73539	T-shaped Magnet D ϕ 40	206
73547	T-shaped Magnet E ϕ 50	206
73553	Hand Magnet A-2	204
73554	Hand Magnet with Handle B-2	204
73556	Hand Magnet with Casters C	204
73558	Hand Magnet A-3	204
73559	Hand Magnet with Handle B-3	204
73570	Radius Scale A-1 R 0.5 - 7	153
73571	Radius Scale A-2 R 8 - 15	153
73591	Circular Saw Guide T-Slide Basic 15 cm/shaku	140
73592	Circular Saw Guide T-Slide Basic 30 cm/shaku	140
73593	Circular Saw Guide T-Slide Basic 45 cm/shaku	140
73594	Circular Saw Guide T-Slide Basic 60 cm/shaku	140
73701	Circular Saw Guide T-Slide Double 15 cm/shaku	140

73702	Circular Saw Guide T-Slide Double 30 cm/shaku	140
73703	Circular Saw Guide T-Slide Double 45 cm/shaku	140
73704	Circular Saw Guide T-Slide Double 60 cm/shaku	140
73705	Circular Saw Guide T-Slide Double 90 cm/shaku	140
73711	Circular Saw Guide T-Slide II 15 cm/shaku	139
73712	Circular Saw Guide T-Slide II 30 cm/shaku	139
73713	Circular Saw Guide T-Slide II 45 cm/shaku	139
73714	Circular Saw Guide T-Slide II 60 cm/shaku	139
73715	Circular Saw Guide T-Slide II 90 cm/shaku	139
73746	Digital Thickness Caliper with Handle A 0.01 mm/10 mm	156
73750	Dial Gauge 0.01 mm/10 mm	156
73751	Dial Indicator 0.01 mm/0.8 mm	156
73752	Magnetic Stand A Standard	157
73753	Magnetic Stand A-2 Fine Adjustment	157
73773	Bolt and Nut Gauge	155
73776	Feeler Gauge A 75 mm 9 Leaves	155
73780	Feeler Gauge B 100 mm 9 Leaves	155
73781	Feeler Gauge C 150 mm 9 Leaves	155
73782	Feeler Gauge D 65 mm 25 Leaves	155
73794	Pitch Gauge for Inch Screw Thread 26 Leaves A-2	155
73795	Pitch Gauge for Metric Screw Thread 28 Leaves B-2	155
73796	Feeler Gauge E 100 mm 25 Leaves	155
73797	Feeler Gauge F 150 mm 25 Leaves	155
73798	Marking Tape 30 mm x 50 m Pink	79
73799	Marking Tape 30 mm x 50 m Yellow	79
73800	Marking Tape 30 mm x 50 m Orange	79
73844	Storage case for Auto Level SA-24A and 28A	217
73865	Marking Tape 30 mm x 100 m Pink	79
73877	Stainless steel plate for L-Angle II 60 cm, Adjust 60 cm, EX 60 cm and Plus 60 cm	219
73879	Molding Rule 2 m 5/1000	34
73930	Non-slip rubber for Aluminum Cutting Rule	214
73992	Tip with superhard chip for Auto Punch L	222
73993	Rear spring for Auto Punch M	222
73994	Front spring and guide pin set for Auto Punch M	222
73995	Rear spring for Auto Punch L	222
73996	Front spring and guide pin set for Auto Punch L	222
73997	Tip with superhard chip for Auto Punch M	222

74000~74999

Item Code	Description	Page
74015	Magnetic Sheet Mat 10 cm x 10 m 0.8 mm Thick Red Roll	213
74016	Magnetic Sheet Mat 10 cm x 10 m 0.8 mm Thick Blue Roll	213
74102	Tile Percussion Hammer A-1	146
74103	Tile Percussion Hammer A-2	146
74104	Tile Percussion Hammer A-3	146
74105	Tile Percussion Hammer A-4	146
74106	Tile Percussion Hammer B-1	146
74110	Try Square Aluminum Base without Graduations 20 cm	50
74111	Try Square Aluminum Base without Graduations 25 cm	50
74112	Try Square Aluminum Base without Graduations 30 cm	50
74113	Try Square Aluminum Base without Graduations 35 cm	50
74114	Try Square Aluminum Base without Graduations 40 cm	50
74115	Try Square Aluminum Base without Graduations 45 cm	50
74116	Try Square Aluminum Base without Graduations 50 cm	50

74117	Try Square Aluminum Base without Graduations 60 cm	50
74118	Try Square Aluminum Base without Graduations 70 cm	50
74119	Try Square Aluminum Base without Graduations 90 cm	50
74120	Try Square Aluminum Base without Graduations 1 m	50
74125	Marking Tape 30 mm x 50 m Blue	79
74132	Pedometer Q Black	186
74133	Pedometer Q White	186
74141	Chalk White 10 pc-pack with Plastic Case	130
74142	Chalk Red 10 pc-pack with Plastic Case	130
74143	Chalk Yellow 10 pc-pack with Plastic Case	130
74155	Inspection Mirror with LED Light D-1 Circle 60 mm	158
74156	Inspection Mirror with LED Light D-2 Circle 36 mm	158
74157	Inspection Mirror with LED Light D-3 Oval 50 x 80 mm	158
74158	Inspection Mirror with LED Light D-4 Oval 25 x 50 mm	158
74161	Marking Tape 15 mm x 50 m Pink	79
74162	Marking Tape 15 mm x 50 m Yellow	79
74163	Marking Tape 15 mm x 50 m Orange	79
74164	Marking Tape 15 mm x 50 m Blue	79
74172	Inspection Scope A φ 5.8 Wireless 3.5 Inch LCD	159
74173	Inspection Scope B φ 9 Wireless 3.5 Inch LCD	159
74175	Camera Head for Inspection Scope φ 5.8 x 1 m	159
74176	Camera Head for Inspection Scope φ 9 x 1 m	159
74178	Extension Cable for Inspection Scope 2 m	159
74179	Extension Cable for Inspection Scope 5 m	159
74180	Battery replacement for Inspection Scope	221
74291	Hammer pin for Auto Punch M	222
74444	Scribing Needle D	151
74445	Scribing Needle E	151
74451	Spring Scale with Flat Scale Face 500 g	84
74452	Spring Scale with Flat Scale Face 1 kg	84
74453	Spring Scale with Flat Scale Face 2 kg	84
74458	Replacement lead for Drawing Divider	222
74459	Spring Scale with Flat Scale Face 5 kg	84
74460	Spring Scale with Flat Scale Face 10 kg	84
74461	Spring Scale with Flat Scale Face 20 kg	84
74468	Replacement of Scribing Needle 1 pc for D	151
74469	Replacement of Scribing Needle 1 pc for E	151
74481	Suction Lifter Single A	161
74482	Suction Lifter Single B	161
74483	Suction Lifter Double A	161
74484	Suction Lifter Double B One-touch	161
74487	Spring Scale with Flat Scale Face 30 kg	84
74488	Spring Scale with Flat Scale Face 50 kg	84
74493	Spring Scale with Flat Scale Face 8 kg	84
74499	Spring Scale with Flat Scale Face 15 kg	84
74845	Flexible Rule with Scale 40 cm	197
74853	Flexible Rule with Scale 80 cm	197
74918	Acrylic Protractor 180-degree Semicircle 15 cm	196
74926	Acrylic Protractor 360-degree Circle 15 cm	196
74940	Triangle Rotation Scale 30 cm	200
74941	Triangle Rotation Scale 30 cm/shaku	200
74950	Triangle Scale for Real-estate Surveyors A-30 30 cm	199
74961	Triangle Scale for Architects B-15 15 cm	199
74962	Triangle Scale for Architects B-30 30 cm	199

74969	Triangle Scale for Real-estate Surveyors A-15 15 cm	199
74979	Triangle Rotation Scale 15 cm/shaku	200
74980	Triangle Rotation Scale 15 cm	200
74987	Triangle Scale for Architects, Shipbuilders D-30 30 cm	199
74988	Triangle Scale for Shipbuilders E-30 30 cm	199

75000~75999

Item Code	Description	Page
75078	Counter with Stand A Metallic Model	162
75086	Counter B Metallic Model	162
75089	Counter C Yellow Plastic Model	162
75090	Counter C Blue Plastic Model	162
75256	Acrylic Triangle Scale 24 cm 2 pc-pack	197
75264	Acrylic Triangle Scale 30 cm 2 pc-pack	197
75310	Acrylic Straight Rule 30 cm	195
75329	Acrylic Straight Rule 45 cm	195
75388	Drawing Compasses A 115 mm	198
75396	Drawing Compasses B 155 mm	198
75416	Molding Rule 1 m 29/1000	34
75421	Measuring Wheel E10-S	68
75422	Measuring Wheel E20-S	68
75426	Aluminum Pantagraph 5x	196
75442	Drawing Divider A 115 mm	198
75450	Drawing Divider B 155 mm	198
75503	Sheet Magnifier U-2 3.5x Bookmark Size	191
75505	Sheet Magnifier U-3 3.5x Card Size	191
75506	Sheet Magnifier U-4 2x Pocket Notebook Size	191
75509	Reading Glass A-2 65 mm 2.5x	189
75517	Reading Glass B-2 75 mm 2x	189
75520	Reading Glass B-3 75 mm 2x and 4x Double Focus	189
75521	Reading Glass B-4 100 mm 2x and 4x Double Focus	189
75522	Sheet Magnifier U-5 2x A4 Size	191
75523	Stowed High Magnification Model C Double Lens 10x/20x	193
75529	Desk Magnifier M-1 60 mm 3.5x	191
75531	Stowed High Magnification Model D Triplet Lens 3.5x	193
75534	Pocket Magnifier N-1 65 x 45 mm 2.5x	191
75535	Pocket Magnifier N-2 45 mm 3.5x	191
75536	Pocket Magnifier N-3 65 mm 2x and 4x Double Focus	191
75537	Precision Work Magnifier with Tweezer O-1 30 mm 4.5x	192
75539	Stand Magnifier P-1 65 mm 3x	193
75543	High Magnification Model Q 10 mm 15x	192
75555	Compact Reading Glass S-1 60 mm 2x	190
75556	Compact Reading Glass S-2 45 mm 2x	190
75557	Compact Reading Glass S-3 30 mm 3x	190
75564	High Magnification Model R-1 18 mm 15x	192
75565	High Magnification Model R-2 28 mm 10x	192
75570	High Magnification Model T-1 20 mm 15x	192
75571	High Magnification Model T-2 28 mm 10x	192
75572	Precision Work Magnifier T-3 Watchmaker's Loupe 23 mm 5x	192
75590	Oil-filled Compass C Roman Alphabet	187
75592	Oil-filled Compass C-2 Japanese	187
75602	Dry Compass A-3 Japanese	186
75603	Dry Compass B-2 Roman Alphabet	186
75604	Compass Chinese Zodiac D	187

75612	Oil-filled Compass for Orienteering E	187
75614	Oil-filled Compass for Orienteering E-2 Round	187
75620	Oil-filled Compass for Military F	187
75636	Precision Work Magnifier X Attachment to Glasses 2.5x	192
75646	Binocular W-2 2.5x	194
75650	Replacement Lens for W-2 1.5x	194
75651	Replacement Lens for for W-2 2.5x	194
75652	Replacement Lens for for W-2 3.0x	194
75656	Binocular with Light W-3 1.5x - 3.0x	194
75659	Stand Magnifier Y 123 mm 2x and 4x Double Focus	194
75662	Oil-filled Wood Compass Japanese J	188
75672	Compass K-2 Japanese	188
75686	Compass I for Zipper	188
75708	Magnifier for Reading with Light E-3 28 mm 10x	190
75727	Desk Magnifier L-3 8x and 30x	191
75735	Binocular W-4 2.2x/3.3x	194
75737	Binocular with LED Light W-5 1.2x - 3.5x	194
75745	Folding Scale 8-scales 15 cm	200
75746	Folding Scale 8-scales 30 cm	200
75751	Reading Glass with LED Light A-6 110 mm 2x and 4x	190
75753	Pocket Microscope with LED Light H 60x - 100x	193
75755	Reading Glass with LED Light A-7 90 mm 2x and 4x	190
75756	Inspection Mirror A-3 Oval 50 x 80 mm	158
75757	Inspection Mirror A-4 Oval 25 x 50 mm	158
75758	Inspection Mirror A-1 Circle 60 mm	158
75759	Inspection Mirror A-2 Circle 36 mm	158
75761	Magnifier for Reading with Light E 50 mm 3x	190
75762	Magnifier for Reading with Light F 65 mm 3x	190
75763	Stand Magnifier G 25 mm 6x	193
75765	Stowed High Magnification Model with Chain I 10x	193
75766	Stowed High Magnification Model with Chain J 3x/4x/5x	193
75767	Desk Magnifier K 25 x 150 mm 2x	191
75788	Magnifying Mirror B-3 Oval 50 x 80 mm 2x	158
75789	Magnifying Mirror B-4 Oval 25 x 50 mm 2x	158
75790	Magnifying Mirror B-1 Circle 60 mm 2x	158
75791	Magnifying Mirror B-2 Circle 36 mm 2x	158
75792	Reading Glass A-3 65 mm 3x	189
75793	Reading Glass A-4 75 mm 2.5x	189
75794	Reading Glass A-5 100 mm 2x	189
75796	Large Inspection Mirror C-1 1.2 m Oval 80 x 120 mm	157
75797	Large Inspection Mirror C-2 2.5 m Oval 120 x 150 mm	157
75919	Thermometer Wood 45 cm	168
75920	Thermometer Wood 60 cm	168

76000~76999

Item Code	Description	Page
76037	Mini Level A Circular Model	91
76046	Mini Level D Flat Model	91
76048	Handy Level with Magnet B 100 mm	89
76060	Mini Level H Cube Model	91
76164	Laser Beam Level II 300 mm	93
76165	Laser Beam Level II with Magnet 300 mm	93
76166	Laser Beam Level II 450 mm	93
76167	Laser Beam Level II with Magnet 450 mm	93

76301	Precise I-Beam Level with Magnet 300 mm	88
76302	Precise I-Beam Level with Magnet 380 mm	88
76303	Precise I-Beam Level with Magnet 450 mm	88
76304	Precise I-Beam Level with Magnet 600 mm	88
76305	Precise I-Beam Level with Magnet 750 mm	88
76306	Precise I-Beam Level with Magnet 900 mm	88
76308	Precise I-Beam Level with Magnet 150 mm	88
76310	Precise I-Beam Level with Magnet 230 mm	88
76315	Precise I-Beam Level 150 mm	88
76316	Precise I-Beam Level 230 mm	88
76318	Precise I-Beam Level 300 mm	88
76319	Precise I-Beam Level 380 mm	88
76320	Precise I-Beam Level 450 mm	88
76321	Precise I-Beam Level 600 mm	88
76322	Precise I-Beam Level 750 mm	88
76323	Precise I-Beam Level 900 mm	88
76324	Precise I-Beam Level 1200 mm	88
76326	Blue Level Digital 600 mm	92
76327	Blue Level Digital with Magnet 600 mm	92
76328	Round Shape Vial A φ 11 Clear 2 pc-pack	91
76329	Round Shape Vial B φ 16 Clear 2 pc-pack	91
76330	Blue Level Jr. 100 mm	86
76331	Blue Level Jr. with Magnet 100 mm	86
76332	Slim Level with Magnet on Back Side 200 mm White	90
76334	Blue Level Jr. 150 mm	86
76335	Blue Level Jr. 200 mm	86
76336	Blue Level Jr. with Magnet 150 mm	86
76337	Blue Level Jr. with Magnet 200 mm	86
76339	Post Level with Magnet	91
76340	Slim Level with Magnet 200 mm White	90
76342	Handy Level Light 100 mm	89
76343	Blue Level Digital 350 mm	92
76344	Blue Level Digital with Magnet 350 mm	92
76348	Blue Level Digital 450 mm	92
76349	Blue Level Digital with Magnet 450 mm	92
76355	Slope Level 450 mm	87
76358	Slope Level 300 mm	87
76359	Slope Level 600 mm	87
76370	Blue Level 300 mm	87
76371	Blue Level 450 mm	87
76372	Blue Level 600 mm	87
76373	Blue Level 900 mm	87
76374	Blue Level 1200 mm	87
76375	Blue Level 380 mm	87
76377	Blue Level 1500 mm	87
76378	Blue Level 1800 mm	87
76379	Blue Level with Magnet 300 mm	87
76380	Blue Level with Magnet 450 mm	87
76381	Blue Level with Magnet 600 mm	87
76382	Blue Level with Magnet 900 mm	87
76383	Blue Level with Magnet 1200 mm	87
76384	Blue Level with Magnet 380 mm	87
76385	Blue Level with Magnet 1500 mm	87
76387	Mini Level Revo Clear Cube Model	90

Parts List	Japan Calibration Service System (JCS)
Etching	
Sheet Heaters	
Custom-Made Items	
Name Printing	
Index Item Code ➡ Description	
Index Item Code ➡ Description	

76389	Blue Level with Magnet 1800 mm	87	76826	Digital Angle Meter II with Magnet Dust/Waterproof	92
76390	Blue Level PRO 300 mm	86	76827	Tripod with Handle B	113
76391	Blue Level PRO 380 mm	86	76863	Mini Telescopic Leveling Staff 2 m 2 Steps	65
76393	Blue Level PRO 450 mm	86	76866	Tripod with Handle C	113
76394	Blue Level PRO 600 mm	86	76874	Construction Folding Chalk Board Wood OA 45 x 60 cm	70
76395	Blue Level PRO 900 mm	86	76875	Construction Folding Chalk Board Wood OC 45 x 60 cm	70
76396	Blue Level PRO 1200 mm	86	76876	Construction Folding Chalk Board Wood OD 45 x 60 cm	70
76398	Blue Level PRO 1500 mm	86	76877	Construction Folding Chalk Board Wood OG 45 x 60 cm	70
76400	Blue Level PRO 1800 mm	86	76900	Mini Telescopic Leveling Staff 3 m 3 Steps	65
76403	Blue Level PRO with Magnet 300 mm	86	76901	Auto Level SA-28A with Tripod	112
76404	Blue Level PRO with Magnet 380 mm	86	76909	Construction Flag Nylon Pair of White and Red	68
76405	Blue Level PRO with Magnet 450 mm	86	76911	KONOE MASTER LINE Stick-on Type M-1	77
76407	Blue Level PRO with Magnet 600 mm	86	76912	KONOE MASTER LINE Stick-on Type M-2	77
76408	Blue Level PRO with Magnet 900 mm	86	76913	KONOE MASTER LINE Stick-on Type M-3	77
76409	Blue Level PRO with Magnet 1200 mm	86	76914	KONOE MASTER LINE Stick-on Type M-4	77
76411	Blue Level PRO with Magnet 1500 mm	86	76915	KONOE MASTER LINE Stick-on Type M-5	77
76412	Blue Level PRO with Magnet 1800 mm	86	76916	KONOE MASTER LINE Insert Type M-6	77
76416	Mini Level Revo Lineclip Model	90	76917	KONOE MASTER LINE Insert Type M-7	77
76417	Mini Level Revo for Rule and Square	90	76918	KONOE MASTER LINE Insert Type M-8	77
76418	Mini Level Revo T-shaped Model	90	76919	KONOE MASTER LINE Insert Type M-9	77
76423	Mini Level Revo Keyring Model	90	76920	KONOE MASTER LINE Insert Type M-10	77
76424	Handy Level Revo Single White	89	76923	Laser Holder for Light Weight Steel Framing with Rising/Lowering Motion	111
76425	Handy Level Revo Single Blue	89	76924	Level adjustment tripod adapter for Laser ROBO Fine BRIGHT	217
76426	Handy Level Revo Double	89	76925	Aluminum case for Laser ROBO Fine BRIGHT	217
76427	Handy Level Revo with Magnet Double	89	76926	Cross Fitting for Aluminum Leveling Rod 60 mm Wide	64
76428	Handy Level Revo Triple	89	76927	Surveying Pin Pole (Steel) φ 4 30 cm	68
76429	Handy Level Revo with Magnet Triple	89	76928	Surveying Pin Pole (Steel) φ 4 60 cm	68
76447	Digital Angle Meter with Magnet Mini	92	76930	Telescopic Leveling Staff 5 m 4 Steps	66
76478	Rotating Table for Laser Beam Level	93	76931	Aluminum Leveling Rod 60 mm Wide 30 cm	64
76496	Rotating Laser HV-2	112	76932	Aluminum Leveling Rod 60 mm Wide 50 cm	64
76497	Rotating Laser HV-2 with Tripod	112	76933	Aluminum Leveling Rod 60 mm Wide 70 cm	64
76503	Level for Square	91	76934	Aluminum Leveling Rod 60 mm Wide 1 m	64
76507	Light bulb for Magnifier with Light for Reading E and F	222	76935	Aluminum Leveling Rod 60 mm Wide 1.1 m	64
76530	Round Shape Vial φ 11 Blue 2 pc-pack	91	76936	Aluminum Cross Leveling Rod 60 mm Wide 1 x 1.1 m	64
76531	Round Shape Vial φ 16 Blue 2 pc-pack	91	76938	KONOE NAIL Mini Pack No.01 20 pc-pack	78
76629	Tripod with Handle A	113	76939	KONOE NAIL Mini Pack No.1 20 pc-pack	78
76644	Water Level A with 15 m Hose	93	76940	KONOE NAIL Mini Pack No.2 5 pc-pack	78
76653	Auto Level SA-24A with Tripod	112	76941	KONOE NAIL Mini Pack No.3 5 pc-pack	78
76654	Tripod Spherical Head	113	76942	KONOE NAIL Mini Pack No.4 5 pc-pack	78
76659	Holder for Laser Receiver, model II and Plus	217	76943	KONOE NAIL Mini Pack No.5 5 pc-pack	78
76676	Tripod with Handle 1.5 m	113	76946	KONOE DOUBLE Mini Pack 2 Red 20 pc-pack	78
76690	Tripod Flat Head	113	76947	KONOE DOUBLE Mini Pack 2 Yellow 20 pc-pack	78
76745	Rule Stopper for 15 cm Rule	32	76948	KONOE DOUBLE Mini Pack 2 Blue 20 pc-pack	78
76746	Rule Stopper for 30 cm Rule	32	76949	KONOE DOUBLE Mini Pack 3 Red 5 pc-pack	78
76747	Rule Stopper for 60 cm Rule	32	76950	KONOE DOUBLE Mini Pack 3 Yellow 5 pc-pack	78
76748	Rule Stopper for 1 m Rule	32	76951	KONOE DOUBLE Mini Pack 3 Blue 5 pc-pack	78
76749	Rule Stopper for 1.5 and 2 m Rule	32	76952	Tripod with Handle 3 m	113
76751	Stainless Steel Rule Hard Chrome Finish with Stopper 15 cm	32	76955	Construction Flag Fabric Pair of White and Red	68
76752	Stainless Steel Rule Hard Chrome Finish with Stopper 30 cm	32	76956	Construction Chalk Board Wood B 45 x 60 cm	69
76759	T-shaped Scale Wood 60 cm	197	76957	Construction Chalk Board Wood C 45 x 60 cm	69
76768	Level adjustment tripod adapter for Laser ROBO Neo, E Sensor and X line	217	76962	AC adapter for Laser ROBO Fine 3C	217
76791	AC adapter for Laser ROBO Green, E Sensor and X line	217	76963	Lock button for Telescopic Leveling Staff	216
76793	Laser Safety Glasses	110	76964	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 30 cm	65
76825	Digital Angle Meter II Dust/Waterproof	92	76965	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 50 cm	65

76966	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 70 cm	65
76967	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 1 m	65
76968	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 1 m 2 Folded	65
76969	Fiberglass Leveling Rod Tape 3 m	67
76970	Fiberglass Leveling Rod Tape 5 m	67
76971	Fiberglass Leveling Rod Tape 10 m	67
76973	Telescopic Leveling Staff 5 m 3 Steps	66
76975	Construction Chalk Board Wood A 45 x 60 cm	69
76976	Surveying Pin Pole (Steel) φ 6 30 cm	68
76977	Surveying Pin Pole (Steel) φ 6 50 cm	68
76978	Surveying Pin Pole (Steel) φ 6 60 cm	68
76979	Surveying Pin Pole (Steel) φ 8 1 m	68
76980	Cross Fitting for Plywood Leveling Rod 63 mm Wide	65
76982	Traverse Surveying Pin Pole (Hard Steel) φ 3.2 50 cm	68
76984	Surveying Pole Wood 2 m	67
76985	Surveying Pole Aluminum 2 m Steps	67
76986	KONOE NAIL No.01 100 pc-pack	78
76987	KONOE NAIL No.1 50 pc-pack	78
76988	Surveying Pole Aluminum 2 m	67
76989	KONOE NAIL No.2 20 pc-pack	78
76990	KONOE NAIL No.3 20 pc-pack	78
76991	KONOE NAIL No.4 10 pc-pack	78
76992	KONOE NAIL No.5 10 pc-pack	78
76993	KONOE DOUBLE 2 Red 100 pc-pack	78
76994	KONOE DOUBLE 2 Yellow 100 pc-pack	78
76995	KONOE DOUBLE 2 Blue 100 pc-pack	78
76996	Surveying Pole Aluminum 2 m 10 pc-pack	67

77000~77999

Item Code	Description	Page
77003	Curved Rule 6 pc-pack	197
77030	Drawing Sheet Case A 7-step Slide	203
77031	Construction Chalk Board Wood AS 30 x 45 cm	69
77037	Construction Chalk Board Wood J 45 x 60 cm	70
77038	Black Drawing Scale 30 cm	196
77041	Acrylic Straight Rule 15 cm	195
77045	Eraser for Waterproof Chalkboard	77
77055	Auto Level SA-32A with Tripod	112
77057	Construction Chalk Board Wood B-2 60 x 45 cm	69
77058	Construction Chalk Board Wood C-2 60 x 45 cm	69
77059	Construction Chalk Board Wood D 45 x 60 cm	69
77061	Construction Water-resistant Chalk Board TA 45 x 60 cm	71
77062	Acrylic Triangle Scale with Grid Scale 30 cm 2 pc-pack	197
77064	Chalk for Waterproof Chalkboard	76
77066	Acrylic Triangle Scale 18 cm 2 pc-pack	197
77067	Construction Chalk Board Wood D-2 60 x 45 cm	69
77068	Construction Chalk Board Wood E-2 60 x 45 cm	69
77069	Construction Chalk Board Wood F 45 x 60 cm	69
77070	Acrylic Rule 30 cm	195
77074	Construction Water-resistant Chalk Board TD 45 x 60 cm	71
77075	Construction Water-resistant Chalk Board TD-2 60 x 45 cm	71
77078	Construction Chalk Board Wood G 45 x 60 cm	70
77079	Construction Chalk Board Wood H 45 x 60 cm	70
77085	Acrylic Cutting Rule with Stainless Steel Edge 30 cm	195

77086	Acrylic Cutting Rule with Stainless Steel Edge 50 cm	195
77087	Construction Chalk Board Wood DS 30 x 45 cm	69
77088	Construction Chalk Board Wood DS-2 45 x 30 cm	69
77089	Acrylic Straight Rule with Grid Scale 30 cm	195
77096	Laser ROBO Fine 3C1	109
77097	Acrylic Straight Rule with Grid Scale 45 cm	195
77099	Rotating Table for Fine 3C	110
77196	Molding Rule 15 cm 24/1000	34
77199	Rubber wheel for Measuring Wheel B20-S	216
77258	Auto Punch L	160
77259	Auto Punch M	160
77304	Tripod Short Model	113
77314	Construction Chalk Board Wood K 45 x 60 cm	70
77315	Screw Pitch Marking Tool Multi 5-pitch Switch	122
77317	Auto Punch with Flat Grip to Prevent Rolling M	160
77318	Auto Punch with Flat Grip to Prevent Rolling L	160
77320	Main Block for Screw Pitch Marking Tool Multi	122
77322	Construction Water-resistant Chalk Board TC 45 x 60 cm	71
77323	Replacement Belt 100/150 for Screw Pitch Marking Tool Multi	122
77324	Replacement Belt 200/250/300 for Screw Pitch Marking Tool Multi	122
77326	Replacement Cotton for Screw Pitch Marking Tool Multi 2 pc-pack	122
77328	Construction Water-resistant Chalk Board TB 45 x 60 cm	71
77329	Construction Chalk Board Wood GS 30 x 45 cm	70
77331	Construction White Board CW 45 x 60 cm	73
77332	Construction White Board DW 45 x 60 cm	73
77333	Construction White Board DW-2 60 x 45 cm	73
77334	Construction Chalk Board Wood JS 30 x 45 cm	70
77351	Aluminum Leveling Rod 60 mm Wide 1.5 m	64
77352	Aluminum Leveling Rod 60 mm Wide 2 m	64
77353	Eraser for Chalkboard and Whiteboard	77
77354	Laser ROBO Neo 21 BRIGHT	107
77355	Laser ROBO Neo 21P BRIGHT	107
77357	Construction White Board AW 45 x 60 cm	73
77358	Construction White Board BW 45 x 60 cm	73
77359	Construction White Board GW 45 x 60 cm	74
77360	Laser ROBO Neo 31 BRIGHT	107
77361	Laser ROBO Neo 41 BRIGHT	107
77362	Laser ROBO Neo 51 BRIGHT	107
77365	Construction White Board ASW 30 x 45 cm	73
77366	Construction White Board CSW 30 x 45 cm	73
77367	Construction White Board DSW 30 x 45 cm	73
77368	Construction White Board DSW-2 45 x 30 cm	73
77369	Construction White Board GSW 30 x 45 cm	74
77375	Handy Plumb Holder Pro Auto-rewind Red	124
77376	Handy Plumb Holder Pro with Plumb Bob 400 g Auto-rewind Red	124
77377	Handy Plumb Holder Pro Hand-rewind Blue	124
77378	Replacement Needle for Handy Plumb Holder Pro	124
77381	Replacement Sponge 3 pc-pack for Ink Line Marker Jr. series	121
77385	Construction White Board FW 45 x 60 cm	73
77386	Construction White Board HW 45 x 60 cm	74
77387	Construction White Board JW 45 x 60 cm	74
77388	Laser ROBO Neo 01 BRIGHT	107
77389	Laser ROBO Neo 11P BRIGHT	107
77390	Screw Pitch Marking Tool 100	122

Parts List	Japan Calibration Service System (JCS)
Etching	
Sheet Heaters	
Custom-Made Items	
Name Printing	
Index Item Code ➡ Description	
Index Item Code ➡ Description	

77391	Screw Pitch Marking Tool 150	122	77546	Divider with Super Hard Chip F-2 40 cm	152
77392	Main Block for Screw Pitch Marking Tool 100	122	77548	Dial Plumb 110 cm	123
77393	Main Block for Screw Pitch Marking Tool 150	122	77549	Dial Plumb 175 cm	123
77394	Guide Rule for Screw Pitch Marking Tool/Multi	122	77550	Dial Plumb 200 cm	123
77395	Stopper for Guide Rule for Screw Pitch Marking Tool/Multi	122	77553	Rubber band for Wind-resistant Plumb	218
77396	Replacement Lead for Screw Pitch Marking Tool 10 pc-pack	122	77554	Wind-resistant Plumb Basic	123
77397	Replacement Cotton for Screw Pitch Marking Tool 4 pc-pack	122	77556	Upper fixing screw, spacer, spring set for Wind-resistant Plumb	218
77398	Laser Receiver II with Holder	110	77559	Lower fixing screw, spacer, spring set for Wind-resistant Plumb	218
77399	Laser Receiver II for Laser ROBO Green with Holder	110	77560	Handy Chalk Line 5x Speed Hand-rewind	119
77433	Replacement Anchor Pin for Concrete	121	77562	Replacement Thread 3x Chalk Retentive ϕ 1.0 mm x 20 m for Chalk Line Marker	121
77446	Thread Reel II Auto-rewind Red	120	77575	Dial Plumb 240 cm	123
77450	Handy Ink Line Marker Self Stop Auto-rewind Black	118	77577	Replacement Thread Super Thick 50 m for Chalk Line BIG	121
77451	Replacement Sponge 2 pc-pack for Ink Line Marker Self Stop	121	77578	Replacement Felt 4 pc-pack for Chalk Line BIG	121
77452	Replacement Anchor Pin Mini Black 3 pc-pack	121	77580	Chalk Line BIG Hand-rewind Blue	119
77453	Replacement Anchor Pin 2 pc-pack for Thread Reel II	120	77587	Ink Black for Wet Condition 200 ml	118
77456	Thread Reel II Hand-rewind Green	120	77588	Ink Red for Wet Condition 200 ml	118
77465	Laser ROBO Fine 21 BRIGHT	109	77589	Ink Black 500 ml	118
77466	Laser ROBO Fine 31 BRIGHT	109	77590	Log Scriber	150
77467	Laser ROBO Fine 41 BRIGHT	109	77594	Replacement Thread ϕ 0.8 mm x 15 m for Ink Line Marker	121
77475	Ink Black 200 ml	118	77597	Replacement Scribing Ink Pencil 2 pc-pack for Log Scriber	150
77476	Ink Red 200 ml	118	77598	Replacement Thread 15 m for Handy Plumb Holder	124
77477	Ink White 200 ml	118	77599	Holder for Wind-resistant Plumb with Quick Arm	123
77478	Ink Blue 200 ml	118	77604	Carrying case for Wind-resistant Plumb	218
77480	Motorized Handy Ink Line Marker Black	117	77605	Laser ROBO Neo 21 BRIGHT with Receiver and Tripod	107
77484	Replacement Sponge 3 pc-pack for Ink Line Marker Pro series	121	77606	Laser ROBO Neo 21P BRIGHT with Receiver and Tripod	107
77485	Replacement Sponge 3 pc-pack for Motorized Ink Line Marker and Jr. series	121	77608	Laser ROBO Neo 31 BRIGHT with Receiver and Tripod	107
77486	Replacement Safety Anchor Pin II	121	77609	Laser ROBO Neo 41 BRIGHT with Receiver and Tripod	107
77493	Handy Chalk Line Neo Auto-rewind Thick Thread Yellow	119	77625	Laser ROBO Neo 51 BRIGHT with Receiver and Tripod	107
77494	Handy Chalk Line Neo Hand-rewind Thick Thread Blue	119	77626	Construction White Board Mini with Telescopic Arm MCSW 11 x 14 cm with Itemized Magnetic Sheet	75
77495	Replacement Thread ϕ 1.0 mm x 20 m for Chalk Line Marker	121	77627	Construction White Board Mini with Telescopic Arm MCW 14 x 17 cm with Itemized Magnetic Sheet	75
77501	Handy Plumb Holder Jr. Auto-rewind Red	124	77648	Arm for Holder for Wind-resistant Plumb with Quick Arm	218
77502	Handy Plumb Holder Jr. with Plumb Bob 200 g Auto-rewind Red	124	77649	Disappearing Ink 50 ml	118
77504	Replacement Needle for Handy Plumb Holder Jr.	124	77673	Molding Rule 15 cm 2B/1000	34
77507	Laser ROBO Neo 01 AR BRIGHT	105	77741	Folding Construction White Board OAW 45 x 60 cm	74
77508	Laser ROBO Neo 21 AR BRIGHT	105	77742	Folding Construction White Board OCW 45 x 60 cm	74
77510	Construction Chalk Board Steel SA 45 x 60 cm	72	77743	Folding Construction White Board ODW 45 x 60 cm	74
77511	Construction Chalk Board Steel SC 45 x 60 cm	72	77744	Folding Construction White Board OGW 45 x 60 cm	74
77513	Construction Chalk Board Steel SD 45 x 60 cm	72	77785	Molding Rule 15 cm 2B/1000	34
77514	Construction Chalk Board Steel SD-2 60 x 45 cm	72	77798	Mechanical Drawing Pencil 0.5 mm	203
77516	Divider with Super Hard Chip C-2 10 cm	152	77803	Circular Saw Guide L-Angle for Left-hander 45 cm/shaku	137
77517	Divider C 10 cm	152	77805	Circular Saw Guide L-Angle for Left-hander 60 cm/shaku	137
77518	Divider A 15 cm	152	77807	Circular Saw Guide L-Angle for Left-hander 1 m/shaku	137
77520	Divider with Super Hard Chip A-2 15 cm	152	77811	Coil Spring for Handy Plumb Holder Pro	218
77521	Divider with Super Hard Chip B-2 20 cm	152	77821	Circular Saw Guide I-Clamp One-touch 1.2 m/shaku	141
77523	Construction Chalk Board Steel SG 45 x 60 cm	72	77822	Circular Saw Guide I-Clamp One-touch 1 m/shaku	141
77524	Wind-resistant Plumb II with Magnetic Damper	123	77823	Circular Saw Guide I-Clamp One-touch 2 m/shaku	141
77526	Divider B 20 cm	152	77824	Circular Saw Guide I-Clamp One-touch 2.4 m/shaku	141
77533	Construction Chalk Board Steel SAS 30 x 45 cm	72	77837	Ink Black 15 ml 2 pc-pack	118
77536	Divider D 25 cm	152	77838	Ink Red 15 ml 2 pc-pack	118
77537	Divider E 30 cm	152	77839	Ink White 15 ml 2 pc-pack	118
77539	Construction Chalk Board Steel SDS 30 x 45 cm	72	77840	Folding Square 1.8 m	148
77540	Construction Chalk Board Steel SDS-2 45 x 30 cm	72	77843	Replacement Safety Anchor Pin with Magnet	121
77543	Divider with Super Hard Chip D-2 25 cm	152	77845	Handy Ink Line Marker SUMIWAZA Auto-rewind Brown	118
77545	Divider with Super Hard Chip E-2 30 cm	152	77846	Replacement Sponge 3 pc-pack for Ink Line Marker SUMIWAZA	121

77848	Replacement Cotton 3 pc-pack for Ink Line Marker Pro series	121
77849	Replacement Safety Anchor Pin	121
77858	Circular Saw Guide L-Angle without Handle 50 cm/shaku	137
77862	Replacement Anchor Pin Red 3 pc-pack	121
77864	Replacement Thread ϕ 0.6 mm x 20 m for Ink Line Marker	121
77879	Replacement Thread ϕ 0.7 mm x 15 m for Ink Line Marker Tough Line	121
77880	Replacement Anchor Pin Mini Red 3 pc-pack	121
77882	Replacement Thread ϕ 0.4 mm x 20 m for Ink Line Marker Sharp Line	121
77883	Circular Saw Guide L-Angle with Support Plate 60 cm/shaku	136
77884	Support plate for L-Angle with Support Plate 60 cm	219
77885	Carpenter's Square with Fence 60 cm/shaku	23
77888	Welding Guide Rule with Magnet 1 m	148
77893	Support plate for L-Angle with Support Plate 1 m	219
77894	Support plate for L-Angle with Support Plate 45 cm	219
77899	Circular Saw Guide L-Angle with Support Plate 45 cm/shaku	136
77901	Circular Saw Guide L-Angle with Support Plate 1 m/shaku	136
77907	Ratchet ring for Handy Ink Marker SUMIWAZA and Mini α	218
77919	Circular Saw Guide L-Angle Light 1 m	137
77926	Pin cover for Handy Plumb Holder Pro Auto-rewind Red	218
77927	Handy Chalk Line Hand-rewind Red	119
77929	Replacement Thread ϕ 0.5 mm x 20 m for Chalk Line Marker	121
77932	Replacement Hook 3 pc-pack for Chalk Line	121
77935	Chalk Powder 300 g Yellow	120
77936	Chalk Powder 300 g Red	120
77937	Chalk Powder 300 g Blue	120
77938	Chalk Powder 300 g White	120
77951	Plumb Bob 800 g with Damper	124
77954	Chalk Powder for Outdoor 200 g White	120
77956	Coil Spring for Handy Plumb Holder Jr.	219
77959	Pin cover for Handy Plumb Holder Pro Hand-rewind Blue	218
77962	Chalk Powder for Outdoor 375 g Blue	120
77963	Handy Chalk Line Neo Auto-rewind Thin Thread Orange	119
77964	Handy Chalk Line Neo Hand-rewind Thin Thread Purple	119
77965	Chalk Powder for Outdoor 750 g Blue	120
77966	Circular Saw Guide L-Angle Light 45 cm	137
77967	Circular Saw Guide L-Angle Light 60 cm	137
77968	Chalk Powder for Outdoor 500 g Whiter	120
77970	Profile Gauge A 150 mm	150
77971	Profile Gauge B 300 mm	150
77974	Plumb Bob 100 g with Damper	124
77975	Plumb Bob 600 g with Damper	124
77976	Chalk Powder for Outdoor 1 kg White	120
77979	Plumb Bob 400 g with Damper	124
77981	Plumb Bob 150 g with Damper	124
77982	Plumb Bob 200 g with Damper	124
77983	Plumb Bob 300 g with Damper	124
77984	Profile Gauge C 200 mm	150
77991	Plumb Bob 1000 g	124

78000~79999

Item Code	Description	Page
78002	Tape Measure H-132 Free Type JIS	62
78007	Tape Measure H-163 Free Type JIS	62
78029	Chalk Powder 300 g Pink	120

78030	Chalk Powder 300 g Green	120
78032	Circular Saw Guide L-Angle EX 1 m/shaku	132
78034	Circular Saw Guide L-Angle Fit 15 cm	138
78036	Circular Saw Guide L-Angle Fit 23 cm	138
78052	Circular Saw Guide L-Angle Fit 30 cm	138
78054	Circular Saw Guide L-Angle EX 45 cm/shaku	132
78055	Circular Saw Guide L-Angle EX 60 cm/shaku	132
78079	Circular Saw Guide Mini Free Angle Justy Quick Adjust 23 cm	143
78094	Pin cover for Handy Plumb Holder Jr.	219
78096	Chalk Powder for Outdoor 150 g Blue	120
78108	Circular Saw Guide Triangle AL 15 cm	138
78161	Construction White Board Mini with Telescopic Arm MCSW 11 x 14 cm	75
78162	Construction White Board Mini with Telescopic Arm MCW 14 x 17 cm	75
78174	Laser Range Finder L-Measure40 II Metric/Shaku	111
78176	Circular Saw Guide Mini Free Angle Justy II 23 cm	143
78179	Circular Saw Guide Mini Free Angle II 30 cm	143
78181	Fiberglass Tape Measure FW-50 JIS	63
78184	Fiberglass Tape Measure FW-30 JIS	63
78190	Laser Range Finder L-Measure30 Metric/Shaku	111
78192	Adhesive Leveling Rod Tape 50 mm x 25 m 20 cm Color Interval	67
78193	Adhesive Leveling Rod Tape 50 mm x 25 m 30 cm Color Interval	67
78194	Adhesive Leveling Rod Tape 75 mm x 25 m 20 cm Color Interval	67
78195	Adhesive Leveling Rod Tape 75 mm x 25 m 30 cm Color Interval	67
78196	Adhesive Leveling Rod Tape with Numbering 60 mm x 26 m 20 cm Color Interval	67
78197	Transparent Case with Zipper A1	203
78198	Transparent Case with Zipper A2	203
78217	Circular Saw Guide Mini Free Angle Quick Adjust 30 cm	143
78218	Laser ROBO Neo 01 AR BRIGHT with Receiver and Tripod	105
78219	Laser ROBO Neo 21 AR BRIGHT with Receiver and Tripod	105
78229	Construction Water-resistant Chalk Board TDS 30 x 45 cm	71
78230	Construction Water-resistant Chalk Board TF 45 x 60 cm	71
78232	Circular Saw Guide Free Angle Multi with Guide Rule 30 cm	142
78233	Guide Rule for Circular Saw Guide Free Angle Multi 30 cm	142
78234	Guide Rule for Circular Saw Guide Free Angle Multi 45 cm	142
78235	Guide Rule for Circular Saw Guide Free Angle Multi 60 cm	142
78236	Slider for Circular Saw Guide with Groove	132
78237	Aluminum guide fixing screw for Free Angle Multi	220
78238	Construction Water-resistant Chalk Board TG 45 x 60 cm	71
78240	Laser ROBO Neo 31 AR BRIGHT	105
78241	Laser ROBO Neo 51 AR BRIGHT	105
78243	Laser ROBO Neo 31 AR BRIGHT with Receiver and Tripod	105
78244	Laser ROBO Neo 51 AR BRIGHT with Receiver and Tripod	105
78271	Laser ROBO Green Neo 41 BRIGHT	106
78273	Laser ROBO Green Neo 21P BRIGHT	106
78274	Laser ROBO Green Neo 21 BRIGHT	106
78275	Laser ROBO Green Neo 31 BRIGHT	106
78276	Laser ROBO Green Neo 51 BRIGHT	106
78277	Laser ROBO Green Neo 21 AR BRIGHT	104
78278	Laser ROBO Green Neo 31 AR BRIGHT	104
78279	Laser ROBO Green Neo 51 AR BRIGHT	104
78280	Circular Saw Guide Triangle PC 30 cm	138
78283	Laser ROBO Green Neo 21P BRIGHT with Receiver and Tripod	106
78284	Laser ROBO Green Neo 21 BRIGHT with Receiver and Tripod	106
78285	Laser ROBO Green Neo 31 BRIGHT with Receiver and Tripod	106

Parts List	Japan Calibration Service System (JCS)
Etching	
Sheet Heaters	
Custom-Made Items	
Name Printing	
Index Item Code ➡ Description	
Index Item Code ➡ Description	

78286	Laser ROBO Green Neo 51 AR BRIGHT with Receiver and Tripod	106	78481	Polyester Leveling Line Reel 0.5 mm 500 m Orange	125
78287	Laser ROBO Green Neo 21 AR BRIGHT with Receiver and Tripod	104	78482	Polyester Leveling Line Reel 0.8 mm 270 m Orange	125
78288	Laser ROBO Green Neo 31 AR BRIGHT with Receiver and Tripod	104	78483	Polyester Leveling Line Reel 0.5 mm 500 m Green	125
78289	Laser ROBO Green Neo 51 AR BRIGHT with Receiver and Tripod	104	78485	Polyester Leveling Line Reel 0.8 mm 270 m Green	125
78291	Laser ROBO Green Neo 41 AR BRIGHT with Receiver and Tripod	106	78488	Cotton Leveling Line No.3 0.7 mm 100 m	125
78414	Paint Marker Fine Bullet-tip Black	126	78489	Cotton Leveling Line No.4 0.8 mm 100 m	125
78415	Paint Marker Fine Bullet-tip Red	126	78490	Cotton Leveling Line No.5 0.9 mm 100 m	125
78416	Paint Marker Fine Bullet-tip Yellow	126	78491	Cotton Leveling Line No.6 1.0 mm 100 m	125
78418	Paint Marker Fine Bullet-tip White	126	78493	Cotton Leveling Line No.7 1.1 mm 100 m	125
78419	Paint Marker Fine Bullet-tip Pink	126	78494	Cotton Leveling Line No.8 1.2 mm 100 m	125
78420	Paint Marker Fine Bullet-tip Gold	126	78495	Cotton Leveling Line No.10 1.4 mm 100 m	125
78424	Oil-based Marking Pen Fine Bullet-tip Black	127	78498	Polyester Leveling Line Reel 1.2 mm 120 m Yellow	125
78427	Itemized Magnetic Sheet 6 item-set for Construction White Board Mini MCW 14 x 17 cm	76	78499	Polyester Leveling Line Reel 1.2 mm 120 m Pink	125
78428	Itemized Magnetic Sheet 6 item-set for Construction White Board Mini MCSW 11 x 14 cm	76	78501	Chalk Holder White	130
78429	Oil-based Marking Pen Fine Bullet-tip Red	127	78503	Whiteboard Marking Pen Black	76
78430	Oil-based Marking Pen Fine Chisel-tip Black	127	78504	Whiteboard Marking Pen Red	76
78431	Oil-based Marking Pen Fine Chisel-tip Red	127	78505	Waterproof Chalkboard Marking Pen White	76
78432	Replacement Cartridge for Oil-based Marking Pen Black 2 pc-pack	127	78506	Whiteboard Marking Pen Black Fine-tip with Eraser and Magnet	76
78434	Replacement Cartridge for Oil-based Marking Pen Red 2 pc-pack	127	78507	Marking Mechanical Pencil Type 2.0 mm HB	129
78435	Marking Crayon Pencil Type Black 3 pc-pack	130	78508	Replacement Lead for Marking Mechanical Pencil Type 2.0 mm 2H 6 pc-pack	129
78440	Marking Crayon Pencil Type Red 3 pc-pack	130	78509	Replacement Lead for Marking Mechanical Pencil Type 2.0 mm HB 6 pc-pack	129
78442	Marking Crayon Pencil Type Yellow 3 pc-pack	130	78510	Holder for Paint Marker Fine	126
78443	Marking Crayon Pencil Type White 3 pc-pack	130	78511	Marking Mechanical Pencil Type 2.0 mm 2H	129
78445	Marking Crayon Retractable 4.0 mm Black	128	78515	Paint Marker Fine Bullet-tip Blue	126
78446	Marking Crayon Retractable 4.0 mm Red	128	78516	Paint Marker Fine Bullet-tip Silver	126
78447	Marking Crayon Retractable 4.0 mm Yellow	128	78517	Marking Pencil PRO 2H 3 pc-pack	129
78448	Marking Crayon Retractable 4.0 mm White	128	78518	Marking Pencil PRO H 3 pc-pack	129
78449	Marking Crayon Retractable 4.0 mm Pink	128	78519	Marking Pencil PRO HB 3 pc-pack	129
78450	Circular Saw Guide Free Angle One-touch 1 m	142	78520	Marking Pencil PRO 2B 3 pc-pack	129
78451	Circular Saw Guide Free Angle One-touch 1.2 m	142	78521	Marking Pencil PRO Red Hard 3 pc-pack	129
78452	Assist plate, screw set for Free Angle One-touch 1 m	220	78523	Marking Pencil PRO Red Soft 3 pc-pack	129
78453	Assist plate, screw set for Free Angle One-touch 1.2 m	220	78524	Marking Pencil PRO 4H 3 pc-pack	129
78454	Front side hanging part with spring for Free Angle One-touch	220	78527	Chalk Holder Red	130
78458	Refill Lead for Marking Crayon Retractable 4.0 mm Black 4 pc-pack	128	78528	Chalk Holder Yellow	130
78459	Refill Lead for Marking Crayon Retractable 4.0 mm Red 4 pc-pack	128	78529	Rebar Marker Red 10 pc-pack	79
78460	Refill Lead for Marking Crayon Retractable 4.0 mm Yellow 4 pc-pack	128	78530	Rebar Marker Orange 10 pc-pack	79
78461	Refill Lead for Marking Crayon Retractable 4.0 mm White 4 pc-pack	128	78531	Rebar Marker Yellow 10 pc-pack	79
78462	Refill Lead for Marking Crayon Retractable 4.0 mm Pink 4 pc-pack	128	78532	Rebar Marker White 10 pc-pack	79
78463	Marking Crayon Retractable 7.0 mm Black	127	78533	Rebar Marker Green 10 pc-pack	79
78464	Marking Crayon Retractable 7.0 mm Red	127	78534	Rebar Marker Blue 10 pc-pack	79
78465	Marking Crayon Retractable 7.0 mm White	127	78541	Paint Marker Wide Bullet-tip Black	126
78466	Refill for Marking Crayon Retractable 7.0 mm Black 2 pc-pack	127	78542	Paint Marker Wide Bullet-tip Red	126
78467	Refill for Marking Crayon Retractable 7.0 mm Red 2 pc-pack	127	78543	Blue Slant Tube Vial Model	94
78469	Refill for Marking Crayon Retractable 7.0 mm White 2 pc-pack	127	78544	Blue Slant Dial Model	94
78470	Marking Mechanical Pencil 2.0 mm Black	128	78545	Blue Slant with Magnet Dial Model	94
78471	Marking Mechanical Pencil 2.0 mm Red	128	78546	Blue Slant Revolving Dial Model	94
78472	Marking Mechanical Pencil 2.0 mm White	128	78547	Paint Marker Wide Bullet-tip White	126
78473	Replacement Lead for Marking Mechanical Pencil 2.0 mm Black 6 pc-pack	128	78548	Paint Marker Wide Bullet-tip Pink	126
78474	Replacement Lead for Marking Mechanical Pencil 2.0 mm Red 6 pc-pack	128	78551	Blue Slant Dial Model for Japanese Roof Slope	94
78475	Replacement Lead for Marking Mechanical Pencil 2.0 mm White 6 pc-pack	128	78552	Rebar Marker Pink 10 pc-pack	79
78477	Polyester Leveling Line Reel 0.5 mm 500 m Yellow	125	78563	Leveling Line Yellow 3 mm 30 m	79
78478	Polyester Leveling Line Reel 0.8 mm 270 m Yellow	125	78564	Leveling Line Pink 3 mm 30 m	79
78479	Polyester Leveling Line Reel 0.5 mm 500 m Pink	125	78570	Circular Saw Guide L-Angle with Horizontal Graduations 1 m/shaku	136
78480	Polyester Leveling Line Reel 0.8 mm 270 m Pink	125	78574	Stud Finder Smart 45 mm	144

78575	Stud Sensor Basic	145
78576	Stud Sensor Super	145
78577	Stud Sensor HG	145
78578	Stud Sensor HG-Center Finder	145
78582	Chuck Wrench A 3 mm	160
78584	Chuck Wrench B 5 mm	160
78585	Stud Finder Smart 25 mm	144
78586	Stud Finder Smart 35 mm	144
78587	Chuck Wrench C 6.5 mm	160
78588	Digital Noise Meter with Maximum Value Holding Function	185
78590	Chuck Wrench D 10 mm	160
78592	Stud Finder Smart with Magnet 35 mm	144
78593	Chuck Wrench E 13 mm	160
78594	Replacement Needle 10 pc-pack for Stud Finder Smart 25 mm	145
78595	Replacement Needle 10 pc-pack for Stud Finder Smart 35/45 mm	145
78596	Chuck Wrench A-2 3 mm	160
78597	Chalk Holder Blue	130
78604	Lux Meter	184
78605	Fiberglass Folding Rule 5-folding 1 m	45
78606	Fiberglass Folding Rule 10-folding 1 m	45
78623	Fiberglass Folding Rule 5-folding 1 m/shaku	45
78624	Fiberglass Folding Rule 5-folding 1 m/shaku in Bulk	45
78625	Fiberglass Folding Rule 5-folding 1 m Black	45
78633	Fiberglass Folding Rule 5-folding 1 m Black in Bulk	45
78636	Digital Moisture Meter for Wood with Maximum and Minimum Hold Function	146
78638	Scribing Needle A	151
78642	Digital UV Light Meter	184
78646	Scribing Needle B	151
78650	Replacement of Scribing Needle 2 pc-pack for C	151
78654	Scribing Needle C	151
78657	Stud Sensor EX	145
78665	Deburring Tool with Replacement Blade for S-10/S-20/S-35	161
78666	Replacement Blade 2 pc-pack for Deburring Tool S-10	161
78674	Metal Stud Finder Mini	146
78705	Fiberglass Folding Rule 5-folding 1 m in Bulk	45
78708	Fiberglass Folding Rule 10-folding 1 m in Bulk	45
78747	Digital Lux Meter	184
78833	Fiberglass Folding Rule 10-folding 2 m	45
78841	Fiberglass Folding Rule 10-folding 2 m in Bulk	45
78935	Micrometer 0 - 25 mm	58
78936	Micrometer 25 - 50 mm	58
78946	Mirror with frame for Inspection Mirror A-2 and D-2	221
78966	Angle Level A-600	94
78996	Angle Level A-300	94
78997	Angle Level A-150	94
79052	Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 45 cm/shaku	133
79053	Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 60 cm/shaku	133
79054	Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 1 m/shaku	133
79055	Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 1.2 m/shaku	133
79523	Digital Micrometer 0 - 25 mm	58

80000~89999

Item Code	Description	Page
80288	Stainless Steel Rule Hard Chrome Finish with Magnet 30 cm with JCSS Certificate	224

80620	Spring for Stud Finder L	220
80634	Spring for Stud finder LL	220
80665	Screw for Handy Chalk Line Neo	218
80697	Spring for Stud Finder L with Magnet	220
80713	Battery storage cap for Laser ROBO Green Neo AR BRIGHT	217
80732	Battery storage cap for Laser ROBO Neo AR BRIGHT	217
80733	Handle for Laser ROBO Neo AR BRIGHT	217
80741	Non-slip rubber sheet for Aluminum Cutting Rule EX 60 cm, 1 m	214
80773	Battery storage cap for Laser ROBO Green Neo BRIGHT	217
80781	Toe for Laser ROBO Neo BRIGHT, E Sensor and X line	217
80790	Threader for Handy Ink Line Marker Mini α	218
80799	Battery storage cap for Laser ROBO Neo E Sensor	217
80800	Battery storage cap for Laser ROBO Green Neo E Sensor	217
80801	Battery storage cap for Laser ROBO X line Red	217
80802	Battery storage cap for Laser ROBO X line Green	217
80813	Tape Measure TOUGH GEAR Automatic Stop with Holder 25-5.5 m/shaku	60
80814	Tape Measure TOUGH GEAR Automatic Stop 19-5.5 m JIS	60
80815	Tape Measure TOUGH GEAR Automatic Stop 25-5.5 m JIS	60
80816	Tape Measure TOUGH GEAR Automatic Stop 25-5.5 m/shaku	60
80818	Tape Measure TOUGH GEAR HG with Holder 25-5.5 m/shaku	59
80821	Tape Measure TOUGH GEAR HG 25-5.5 m JIS	59
80822	Tape Measure TOUGH GEAR HG 25-5.5 m/shaku	59
80823	Tape Measure TOUGH GEAR HG with Magnetic Hook 25-5.5 m JIS	59
80824	Tape Measure TOUGH GEAR HG 25-7.5 m JIS	59
80825	One-touch Holder for Measuring Tape	62
80826	Emitting port protective cap for Laser ROBO X line	217
80855	Tape Measure RIGHT GEAR 25-7.5 m/shaku	61
80858	Fabric Safety Cord A Black	147
80859	Fabric Safety Cord A Orange	147
80860	Fabric Safety Cord B Black	147
80861	Fabric Safety Cord B Orange	147
80862	Tape Measure RIGHT GEAR 19-5.5 m JIS	61
80863	Tape Measure RIGHT GEAR 19-5.5 m/shaku	61
80864	Tape Measure RIGHT GEAR 25-5.5 m JIS	61
80865	Tape Measure RIGHT GEAR with Magnetic Hook 25-5.5 m JIS	61
80866	Tape Measure RIGHT GEAR 25-5.5 m/shaku	61
80867	Tape Measure RIGHT GEAR 25-7.5 m JIS	61
80868	Tape Measure RIGHT GEAR with Magnetic Hook 25-7.5 m JIS	61
80870	Tape Measure TOUGH GEAR SD with Holder 25-5.5 m JIS	60
80871	Tape Measure TOUGH GEAR SD with Holder 25-5.5 m/shaku	60
80872	Tape Measure TOUGH GEAR SD with Magnetic Hook and Holder 25-5.5 m JIS	60
80873	Tape Measure TOUGH GEAR SD with Holder 25-7.5 m JIS	60
80874	Tape Measure TOUGH GEAR SD 25-5.5 m JIS	60
80875	Tape Measure TOUGH GEAR SD 25-5.5 m/shaku	60
80876	Tape Measure TOUGH GEAR SD with Magnetic Hook 25-5.5 m JIS	60
80877	Tape Measure TOUGH GEAR SD 25-7.5 m JIS	60
80880	Tape Measure SMART GEAR 19-5.5 m	62
80881	Tape Measure SMART GEAR 19-5.5 m/shaku	62
80882	Tape Measure SMART GEAR 25-5.5 m	62
80883	Tape Measure SMART GEAR 25-5.5 m/shaku	62
80890	Safety Cord A	147
80891	Safety Cord B	147
80908	Stainless steel plate for L-Angle Mini 15 cm and Fit 15 cm	219
80925	Cutout positioning stick fixing screw for L-Angle Adjust and Free Angle Neo	219

80941	Joint for Inspection Mirror A, D, Magnifying Mirror	221
81100	Plastic end A with hook, nut, screw set for Telescopic Measure One Direction II	214
81101	Plastic end B, nut, screw set for Telescopic Measure One Direction II	214
81102	Stopper lever 1 red, shaft, screw set for Telescopic Measure One Direction II	214
81103	Stopper lever 2 yellow, shaft, screw set for Telescopic Measure One Direction II	214
81210	Battery storage cap for Laser ROBO Neo BRIGHT	217
81311	Tip with superhard chip for Auto Punch M with Flat Grip to Prevent Rolling	222
81312	Front spring with guide pin for Auto Punch M with Flat Grip to Prevent Rolling	222
81313	Hammer pin for Auto Punch M with Flat Grip to Prevent Rolling	222
81314	Rear spring for Auto Punch M with Flat Grip to Prevent Rolling	222
81315	Tip with superhard chip for Auto Punch L with Flat Grip to Prevent Rolling	222
81316	Front spring with guide pin for Auto Punch L with Flat Grip to Prevent Rolling	222
81317	Hammer pin for Auto Punch L with Flat Grip to Prevent Rolling	222
81318	Rear spring for Auto Punch L with Flat Grip to Prevent Rolling	222
81365	Gauge head for Dial Gauge	221
81367	Back cover with lug for Dial Gauge	221
81369	Plastic case for Dial Gauge	221
81370	Stem φ 6 for Dial Indicator	221
81371	Stem φ 8 for Dial Indicator	221
81372	Gauge head spanner for Dial Indicator	221
81373	Gauge head for Dial Indicator	221
81374	Plastic case for Dial Indicator	221
81375	Post for Magnetic Stand A and A-2	221
81376	Arm for Stand for Magnetic Stand A Standard	221
81377	Stopper screws complete set with knobs for Magnetic Stand A and A-2	221
81378	Gauge installation complete set for Magnetic Stand A and A-2	221
81380	Arm for Magnetic Stand A-2 Fine Adjustment	221
81476	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 60 cm with JCSS Certificate	224
81484	Digital Vernier Caliper with Solar Panel 200 mm with JCSS Certificate	224
81521	Plastic cover for Scale 50 kg	216
81551	Side cap, screw set for Telescopic Measure Two Directions	214
81570	Stopper screw for Tripod with Handle A	217
81623	Stopper for Suction Lifter Double A and Single B	222
81657	Molding Rule 15 cm 14/1000	34
81737	Molding Rule 60 cm 1/1000	34
81738	Molding Rule 15 cm 1/1000	34
81741	Stainless Steel Rule Hard Chrome Finish with Magnet 15 cm with JCSS Certificate	224
81838	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 30 cm with JCSS Certificate	224
81856	Carrying case for Tripod with Handle A	217
82048	Upper cap, screw set for Telescopic Measure One Direction	214
82049	Lower cap, screw set for Telescopic Measure One Direction	214
82100	Stopper lever ① red, shaft, screw set for Telescopic Measure One Direction	214
82101	Stopper lever ② yellow, shaft, screw set for Telescopic Measure One Direction	214
82228	Aluminum case for Laser ROBO X line	217
82235	Aluminum case for Laser ROBO Neo BRIGHT and E Sensor	217
82415	Stopper screw for Rule Stopper 15, 30, 60 cm	214
82650	Non-slip rubber sheet for Aluminum Cutting Rule EX 1.5 m, 2 m	214
82826	Stainless Steel Rule Hard Chrome Finish with Magnet 60 cm with JCSS Certificate	224
82873	Stopper screw for Rule Stopper 1, 1.5, 2 m	214
82890	Stopper knob for Mini Vernier Caliper 70 mm	215
83249	Stainless Steel Rule Hard Chrome Finish with Magnet 1 m with JCSS Certificate	224
83440	Center screw for Welding Guide Rule	221
83464	Non-slip rubber triangle for Mini Free Angle II, L-Angle II and EX	219
83502	JCSS Calibration Certificate for Precision Stainless Steel Rule 1 m	224

83525	Magnet for Welding Guide Rule	221
83653	Thread holding guide for Handy Ink Line Marker SUMIWAZA	218
83701	Handle for Tripod with Handle A	217
83702	JCSS Calibration Certificate for Precision Stainless Steel Rule 30 cm	224
83737	Handle for L-Angle II and L-Angle Adjust	219
83802	JCSS Calibration Certificate for Precision Stainless Steel Rule 60 cm	224
83803	Molding Rule 2 m 7/1000	34
83832	Receiver holder for Rotating Laser H-2, HV-2	217
84020	Stainless steel plate for L-Angle 45 cm, II 45 cm and Adjust 45 cm	219
84058	1 additional measuring point	224
84116	Mirror with frame for Large Inspection Mirror C-1	221
84117	Mirror with frame for Large Inspection Mirror C-2	221
84159	Mirror with frame for Inspection Mirror A-4 and D-4	221
84160	Mirror with frame for Magnifying Glass B-1	221
84161	Mirror with frame for Magnifying Glass B-2	221
84162	Mirror with frame for Magnifying Glass B-3	221
84163	Mirror with frame for Magnifying Glass B-4	221
84171	Mirror with frame for Inspection Mirror A-1 and D-1	221
84231	Support plate installing screw for L-Angle with Support Plate	219
84259	Handle for Aluminum Cutting Rule Light	214
84267	Band for Mini Level H	216
84270	Non-slip pad for Aluminum Rule 30 - 60 cm, 1 m	214
84287	Stainless steel plate for L-Angle II 1 m, Adjust 1 m, EX 1 m and Plus 1 m	219
84297	Handle and screws set for Hand Magnet B-2	222
84730	Grip Nut for Aluminum Sliding Bevel	215
85273	Stainless steel plate for L-Angle EX 45 cm and Plus 45 cm	219
85518	Handle, screw set for Aluminum Cutting Rule EX	214
85773	Hammer pin for Auto Punch L	222
85959	Stopper screw, bolt, metal washer set for Mini Free Angle II, Justy II and Neo	220

90000~99999

Item Code	Description	Page
90943	Ink Tank for Screw Pitch Marking Tool Multi	122
93280	Spring set (with string) for Handy Ink Line Marker PRO Plus	218
93281	Spring set (with string) for Handy Ink Line Marker Jr. Plus	218
93287	Spring set (with string) for Handy Ink Line Marker PRO Plus Tough Line	218
93288	Spring set (with string) for Handy Ink Line Marker Jr. Plus Tough Line	218
93297	Spring set (with string) for Handy Ink Line Marker PRO Plus Sharp Line	218
93298	Spring set (with string) for Handy Ink Line Marker Jr. Plus Sharp Line	218
93300	Spring set (with string) for Handy Ink Line Marker PRO LITE	218
93301	Spring set (with string) for Handy Ink Line Marker Jr. LITE	218
93310	Handle non-slip rubber, screw set for L-Angle Plus	219
93311	Upper protective cap for L-Angle Plus	219
93312	Lower protective cap for L-Angle Plus	219
93313	Stainless steel plate for L-Angle Adjust 1.2 m and Plus 1.2 m	219
93316	Adjustment knob, movable pin, indicator, washer set for L-Angle Plus Shift	219
93401	Fine adjustment screw set for L-Angle Plus Adjust	219
96061	Needle pin 2 pc-pack for Digital Moisture Meter for Wood	221
96063	Protective cap for Digital Moisture Meter for Wood	221
96106	Reissue of JCSS Calibration Certificate, Private Examination Result	224
97217	AC adapter for Digital Scale with Stand 100 kg	216
97531	Adjustment core for Tripod Spherical Head	217
97533	Stopper screw on adjustment core rail for Tripod Spherical Head	217
97575	Measuring Instrument Set for Steel Fabrication 5 Items	149

97784	Bevel Angle Measuring Gauge 9 Leaves (30° - 50°)	149
97786	Route Interval Measuring Gauge 9 Leaves (4 - 12 mm)	149
97788	Joint Offset Measuring Gauge	149
97790	Flange Bend, Gradient Measuring Gauge	149
97794	Measuring Instrument Set for Steel Fabrication 7 Items	149
97905	Fixing screw for Laser Holder	217
97906	Aluminum nut large for Laser Holder	217
97907	Aluminum nut small for Laser Holder	217
98755	Battery cap for Digital Vernier Caliper Carbon Fiber Body 100 mm	216
98756	Battery cap for Digital Vernier Caliper Carbon Fiber Body 150 mm and Digital Depth Gauge	216
98760	Ornament Carpenter's Square Gold and Silver with Frame	24
98764	Battery cap, screw set for Digital Vernier Caliper 150 - 300 mm	215
98765	Depth probe holding plate, screw set for Digital Vernier Caliper 150 mm and 200 mm	215
98766	Depth probe holding plate, screw set for Digital Vernier Caliper 300 mm	215
98767	Stopper knob for Digital Vernier Caliper 150 - 300 mm	215
98768	Digital part replacement for Digital Vernier Caliper 150 mm	215
98769	Digital part replacement for Digital Vernier Caliper 200 mm	215
98770	Digital part replacement for Digital Vernier Caliper 300 mm	215
98771	Battery cap, screw set for Digital Vernier Caliper Mini	215
98774	Digital part replacement for Digital Vernier Caliper Mini	215
98790	Handle screw set for L-Angle EX 45 cm and 60 cm	219
98791	Handle screw set for L-Angle EX 1 m	219
98905	Digital part replacement for Digital Vernier Caliper 450, 600 mm	215
98906	Digital part replacement for Digital Vernier Caliper 1000 mm	215
98907	Battery cap for Digital Vernier Caliper 450, 600 mm	215
98908	Battery cap for Digital Vernier Caliper 1000 mm	215
98909	Fine adjustment knob for Digital Vernier Caliper 450, 600 mm	215
98910	Fine adjustment knob for Digital Vernier Caliper 1000 mm	215
98911	Stopper knob for Vernier Caliper 450, 600 mm	215
98912	Fine adjustment knob for Vernier Caliper 450, 600 mm	215
98913	Stopper knob for Vernier Caliper 1000 mm	215
98914	Fine adjustment knob for Vernier Caliper 1000 mm	215
98917	Handle for Tripod with Handle B	217
98919	Handle for Tripod with Handle C	217
98925	Battery cap for Blue Level Digital	216
99080	Countersunk screws for Carpenter's Square with Fence	214
99203	Cutout positioning stick for Mini Free Angle Justy 23 cm, L-Angle II 45 cm - 60cm and L-Angle Plus	219
99232	Cutout positioning stick for Mini Free Angle II , L-Angle II 1 m and EX 1 m	219
99241	Mounting part A for I-Clamp One-touch	220
99242	Spreading plate 2 pc-set for I-Clamp One-touch and Free Angle One-touch	220
99243	Wedge for I-Clamp One-touch	220
99244	Mounting part B, screw set for I-Clamp One-touch	220
99245	Edge cap, screw set for I-Clamp One-touch	220
99246	Cutout positioning stick fixing screw for I-Clamp One-touch	220
99249	Cutout positioning stick fixing screw for L-Angle II, Plus, with Support Plate, with Horizontal Graduations, and for Left-hander	219
99251	Thin stopper screw, bolt, metal washer set for Mini Free Angle Justy and Free Angle	220
99505	Nut, washer set for Protractor No.19	215
99506	Nut, washer, brass washer set for Protractor No.30	215
99507	Nut, center screw set for Protractor No.101	215
99516	End nut, iron bolt set for Protractor No.300 Double-blade	215
99517	End nut, iron bolt set for Protractor No.600 Double-blade	215
99518	End nut, iron bolt set for Protractor No.1000 Double-blade	215
99523	Stopper knob for Vernier Caliper 150 mm	215
99524	Stopper knob for Vernier Caliper 200 mm	215

99525	Stopper knob for Mini Vernier Caliper 100 mm	215
99552	Handle installing screw for L-Angle II , Adjust, and EX	219
99553	Rubber cap for Shaku Measure, Ken Measure, Sumiki Shaku Measure	214
99556	Handle, screw set for Aluminum Cutting Rule	214
99559	Nut, center screw set for Japanese Sliding Bevel	215
99563	Depth probe holding plate, screw set for Vernier Caliper 150 mm	215
99564	Depth probe holding plate, screw set for Vernier Caliper 200 mm	215
99565	Depth probe holding plate, screw set for Mini Vernier Caliper 100 mm	215
99567	Depth probe holding plate, screw set for Vernier Caliper 300 mm	215
99602	Stopper screw, bolt, metal washer set for Free Angle One-touch and Multi	220
99604	Stopper screw, bolt, metal washer set for Mini Free Angle Quick Adjust and Justy Quick Adjust	220
99605	Cutout positioning stick fixing screw for Mini Free Angle II and Justy II	220
99606	Bracing fitting for L-Angle for L-Angle with Support Plate, with Horizontal Graduations, and for Left-hander 1 m	219
99608	Handle for L-Angle with Support Plate, with Horizontal Graduations, and for Left-hander	219
99755	Stopper knob ① red for Telescopic Measure Two Directions	214
99756	Stopper knob ② yellow for Telescopic Measure Two Directions	214

Parts List	Japan Calibration Service System (JCS)
Etching	
Sheet Heaters	
Custom-Made Items	
Name Printing	
Index Item Code Description	
Index Item Code Description	

A

Description	Item Code	Page
AC adapter for Digital Scale	70119	81
AC adapter for Digital Scale with Stand 100 kg	97217	216
AC adapter for Laser ROBO Fine 3C	76962	217
AC adapter for Laser ROBO Green, E Sensor and X line	76791	217
Acrylic Cutting Rule with Stainless Steel Edge 30 cm	77085	195
Acrylic Cutting Rule with Stainless Steel Edge 50 cm	77086	195
Acrylic Dot-line Drawing Rule 15 cm	70734	196
Acrylic Dot-line Drawing Rule 30 cm	70726	196
Acrylic Protractor 180-degree Semicircle 15 cm	74918	196
Acrylic Protractor 360-degree Circle 15 cm	74926	196
Acrylic Rule 30 cm	77070	195
Acrylic Scale Reduction Rule 15 cm	70750	196
Acrylic Scale Reduction Rule 30 cm	70769	196
Acrylic Straight Rule 15 cm	77041	195
Acrylic Straight Rule 30 cm	75310	195
Acrylic Straight Rule 45 cm	75329	195
Acrylic Straight Rule with Grid Scale 30 cm	77089	195
Acrylic Straight Rule with Grid Scale 45 cm	77097	195
Acrylic Triangle Scale 18 cm 2 pc-pack	77066	197
Acrylic Triangle Scale 24 cm 2 pc-pack	75256	197
Acrylic Triangle Scale 30 cm 2 pc-pack	75264	197
Acrylic Triangle Scale with Grid Scale 30 cm 2 pc-pack	77062	197
Additional Remote Sensor for Wireless Thermometer A	73242	173
Additional Remote Sensor for Wireless Thermometer A External Antenna Type	73442	173
Adhesive Leveling Rod Tape 50 mm x 25 m 20 cm Color Interval	78192	67
Adhesive Leveling Rod Tape 50 mm x 25 m 30 cm Color Interval	78193	67
Adhesive Leveling Rod Tape 75 mm x 25 m 20 cm Color Interval	78194	67
Adhesive Leveling Rod Tape 75 mm x 25 m 30 cm Color Interval	78195	67
Adhesive Leveling Rod Tape with Numbering 60 mm x 26 m 20 cm Color Interval	78196	67
Adjustment core for Tripod Spherical Head	97531	217
Adjustment knob, movable pin, indicator, washer set for L-Angle Plus Shift	93316	219
Aluminum Box Beam Straight Measure 135 cm	65260	43
Aluminum Box Beam Straight Measure 175 cm	65262	43
Aluminum Box Beam Straight Measure 195 cm	65264	43
Aluminum Box Beam Straight Measure 230 cm	65266	43
Aluminum case for Laser ROBO Fine BRIGHT	76925	217
Aluminum case for Laser ROBO Neo BRIGHT and E Sensor	82235	217
Aluminum case for Laser ROBO X line	82228	217
Aluminum Cross Leveling Rod 60 mm Wide 1 x 1.1 m	76936	64
Aluminum Cutting Rule 1 m	33421	40
Aluminum Cutting Rule 1 m/shaku	65090	40
Aluminum Cutting Rule 1 m/shaku Left Reference Point	65088	40
Aluminum Cutting Rule 1.5 m/shaku	65094	40
Aluminum Cutting Rule 2 m	33422	40
Aluminum Cutting Rule 2 m/shaku	65091	40
Aluminum Cutting Rule 2.5 m/shaku	65092	40
Aluminum Cutting Rule 60 cm/shaku	65086	40
Aluminum Cutting Rule EX 1 m/shaku	65032	39
Aluminum Cutting Rule EX 1.5 m/shaku	65034	39
Aluminum Cutting Rule EX 2 m/shaku	65036	39
Aluminum Cutting Rule EX 2.5 m/shaku	65038	39
Aluminum Cutting Rule EX 60 cm/shaku	65030	39

Aluminum Cutting Rule EX with Handle 1 m/shaku	65033	39
Aluminum Cutting Rule EX with Handle 1.5 m/shaku	65035	39
Aluminum Cutting Rule EX with Handle 2 m/shaku	65037	39
Aluminum Cutting Rule EX with Handle 60 cm/shaku	65031	39
Aluminum Cutting Rule Light 1 m	65075	40
Aluminum Cutting Rule Light with Handle 1 m	65076	40
Aluminum Cutting Rule PROTECT 1 m/shaku	65066	39
Aluminum Cutting Rule PROTECT 1.25 m/shaku	65067	39
Aluminum Cutting Rule PROTECT 2 m/shaku	65068	39
Aluminum Cutting Rule PROTECT 70 cm/shaku	65065	39
Aluminum Cutting Rule with Handle 1 m	33423	40
Aluminum Cutting Rule with Handle 1 m/shaku	65093	40
Aluminum Cutting Rule with Handle 1.5 m/shaku	65096	40
Aluminum Cutting Rule with Handle 2 m	33424	40
Aluminum Cutting Rule with Handle 2 m/shaku	65097	40
Aluminum Cutting Rule with Handle 60 cm/shaku	65098	40
Aluminum guide fixing screw for Free Angle Multi	78237	220
Aluminum Leveling Rod 60 mm Wide 1 m	76934	64
Aluminum Leveling Rod 60 mm Wide 1.1 m	76935	64
Aluminum Leveling Rod 60 mm Wide 1.5 m	77351	64
Aluminum Leveling Rod 60 mm Wide 2 m	77352	64
Aluminum Leveling Rod 60 mm Wide 30 cm	76931	64
Aluminum Leveling Rod 60 mm Wide 50 cm	76932	64
Aluminum Leveling Rod 60 mm Wide 70 cm	76933	64
Aluminum nut large for Laser Holder	97906	217
Aluminum nut small for Laser Holder	97907	217
Aluminum Pantagraph 5x	75426	196
Aluminum Rule 1 m	65544	38
Aluminum Rule 15 cm	65498	38
Aluminum Rule 30 cm	65501	38
Aluminum Rule 45 cm	65528	38
Aluminum Rule 60 cm	65536	38
Aluminum Rule Rigid 1 m	65387	37
Aluminum Rule Rigid 30 cm	65340	37
Aluminum Rule Rigid 45 cm	65363	37
Aluminum Rule Rigid 60 cm	65378	37
Aluminum Rule with Non-slip Pad 1 m	65382	38
Aluminum Rule with Non-slip Pad 1 m Blue	65442	38
Aluminum Rule with Non-slip Pad 1 m Gold	65444	38
Aluminum Rule with Non-slip Pad 1 m Pink	65443	38
Aluminum Rule with Non-slip Pad 1 m White	65445	38
Aluminum Rule with Non-slip Pad 30 cm	65331	38
Aluminum Rule with Non-slip Pad 30 cm Blue	65415	38
Aluminum Rule with Non-slip Pad 30 cm Gold	65417	38
Aluminum Rule with Non-slip Pad 30 cm Pink	65416	38
Aluminum Rule with Non-slip Pad 30 cm White	65418	38
Aluminum Rule with Non-slip Pad 45 cm	65358	38
Aluminum Rule with Non-slip Pad 45 cm Blue	65423	38
Aluminum Rule with Non-slip Pad 45 cm Gold	65425	38
Aluminum Rule with Non-slip Pad 45 cm Pink	65424	38
Aluminum Rule with Non-slip Pad 45 cm White	65426	38
Aluminum Rule with Non-slip Pad 60 cm	65374	38
Aluminum Rule with Non-slip Pad 60 cm Blue	65434	38
Aluminum Rule with Non-slip Pad 60 cm Gold	65436	38

Aluminum Rule with Non-slip Pad 60 cm Pink	65435	38
Aluminum Rule with Non-slip Pad 60 cm White	65437	38
Aluminum Sliding Bevel with Angle Scale 30 cm	62660	49
Aluminum Sliding Bevel with Angle Scale 45 cm	62661	49
Aluminum Sliding Bevel with Angle Scale 60 cm	62662	49
Aluminum Sliding Bevel with Gradient Scale 1.2 m	62573	49
Aluminum Sliding Bevel with Gradient Scale 30 cm	62569	49
Aluminum Sliding Bevel with Gradient Scale 45 cm	62570	49
Aluminum Sliding Bevel with Gradient Scale 60 cm	62571	49
Aluminum Sliding Bevel with Gradient Scale 90 cm	62572	49
Aluminum Sliding Bevel without Scale 45 cm	62540	49
Aluminum Sliding Bevel without Scale 60 cm	62541	49
Aluminum Sliding Bevel without Scale 90 cm	62542	49
Angle Level A-150	78997	94
Angle Level A-300	78996	94
Angle Level A-600	78966	94
Arm for Holder for Wind-resistant Plumb with Quick Arm	77648	218
Arm for Magnetic Stand A-2 Fine Adjustment	81380	221
Arm for Stand for Magnetic Stand A Standard	81376	221
Assist plate, screw set for Free Angle One-touch 1 m	78452	220
Assist plate, screw set for Free Angle One-touch 1.2 m	78453	220
Auto Level SA-24A with Tripod	76653	112
Auto Level SA-28A with Tripod	76901	112
Auto Level SA-32A with Tripod	77055	112
Auto Punch L	77258	160
Auto Punch M	77259	160
Auto Punch with Flat Grip to Prevent Rolling L	77318	160
Auto Punch with Flat Grip to Prevent Rolling M	77317	160

B

Description	Item Code	Page
Back cover with lug for Dial Gauge	81367	221
Bamboo Rule Kane 1 shaku	71897	44
Bamboo Rule Kane 2 shaku	71900	44
Bamboo Rule Kane 3 shaku	71919	44
Bamboo Rule Kujira 2 shaku for Kimono	71854	44
Bamboo Rule with Hole 1 m	71773	44
Bamboo Rule with Hole 30 cm	71760	44
Bamboo Rule with Hole 50 cm	71765	44
Band for Mini Level H	84267	216
Battery cap for Blue Level Digital	98925	216
Battery cap for Digital Vernier Caliper 1000 mm	98908	215
Battery cap for Digital Vernier Caliper 450, 600 mm	98907	215
Battery cap for Digital Vernier Caliper Carbon Fiber Body 100 mm	98755	216
Battery cap for Digital Vernier Caliper Carbon Fiber Body 150 mm and Digital Depth Gauge	98756	216
Battery cap, screw set for Digital Vernier Caliper 150 - 300 mm	98764	215
Battery cap, screw set for Digital Vernier Caliper Mini	98771	215
Battery replacement for Inspection Scope	74180	221
Battery storage cap for Laser ROBO Green Neo AR BRIGHT	80713	217
Battery storage cap for Laser ROBO Green Neo BRIGHT	80773	217
Battery storage cap for Laser ROBO Green Neo E Sensor	80800	217
Battery storage cap for Laser ROBO Neo AR BRIGHT	80732	217
Battery storage cap for Laser ROBO Neo BRIGHT	81210	217
Battery storage cap for Laser ROBO Neo E Sensor	80799	217

Battery storage cap for Laser ROBO X line Green	80802	217
Battery storage cap for Laser ROBO X line Red	80801	217
Bevel Angle Measuring Gauge 9 Leaves (30° - 50°)	97784	149
Binocular W-2 2.5x	75646	194
Binocular W-4 2.2x/3.3x	75735	194
Binocular with LED Light W-5 1.2x - 3.5x	75737	194
Binocular with Light W-3 1.5x - 3.0x	75656	194
Black Drawing Scale 30 cm	77038	196
Blue Level 1200 mm	76374	87
Blue Level 1500 mm	76377	87
Blue Level 1800 mm	76378	87
Blue Level 300 mm	76370	87
Blue Level 380 mm	76375	87
Blue Level 450 mm	76371	87
Blue Level 600 mm	76372	87
Blue Level 900 mm	76373	87
Blue Level Digita with Magnet 450 mm	76349	92
Blue Level Digital 350 mm	76343	92
Blue Level Digital 450 mm	76348	92
Blue Level Digital 600 mm	76326	92
Blue Level Digital with Magnet 350 mm	76344	92
Blue Level Digital with Magnet 600 mm	76327	92
Blue Level Jr. 100 mm	76330	86
Blue Level Jr. 150 mm	76334	86
Blue Level Jr. 200 mm	76335	86
Blue Level Jr. with Magnet 100 mm	76331	86
Blue Level Jr. with Magnet 150 mm	76336	86
Blue Level Jr. with Magnet 200 mm	76337	86
Blue Level PRO 1200 mm	76396	86
Blue Level PRO 1500 mm	76398	86
Blue Level PRO 1800 mm	76400	86
Blue Level PRO 300 mm	76390	86
Blue Level PRO 380 mm	76391	86
Blue Level PRO 450 mm	76393	86
Blue Level PRO 600 mm	76394	86
Blue Level PRO 900 mm	76395	86
Blue Level PRO with Magnet 1200 mm	76409	86
Blue Level PRO with Magnet 1500 mm	76411	86
Blue Level PRO with Magnet 1800 mm	76412	86
Blue Level PRO with Magnet 300 mm	76403	86
Blue Level PRO with Magnet 380 mm	76404	86
Blue Level PRO with Magnet 450 mm	76405	86
Blue Level PRO with Magnet 600 mm	76407	86
Blue Level PRO with Magnet 900 mm	76408	86
Blue Level with Magnet 1200 mm	76383	87
Blue Level with Magnet 1500 mm	76385	87
Blue Level with Magnet 1800 mm	76389	87
Blue Level with Magnet 300 mm	76379	87
Blue Level with Magnet 380 mm	76384	87
Blue Level with Magnet 450 mm	76380	87
Blue Level with Magnet 600 mm	76381	87
Blue Level with Magnet 900 mm	76382	87
Blue Slant Dial Model	78544	94
Blue Slant Dial Model for Japanese Roof Slope	78551	94

Blue Slant Revolving Dial Model	78546	94
Blue Slant Tube Vial Model	78543	94
Blue Slant with Magnet Dial Model	78545	94
Bolt and Nut Gauge	73773	155
Bracing fitting for L-Angle for L-Angle with Support Plate, with Horizontal Graduations, and for Left-hander 1 m	99606	219

C

Description	Item Code	Page
Calibration Buffer Solution pH 10.01, pH 7.01 3 Each	73034	183
Calibration Buffer Solution pH 4.01, pH 7.01 3 Each	73033	183
Camera Head for Inspection Scope φ 5.8 x 1 m	74175	159
Camera Head for Inspection Scope φ 9 x 1 m	74176	159
Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku	10648	11
Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 5 sun	10643	11
Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 5 sun/50 cm	10644	11
Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 6 sun	10646	11
Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku 6 sun/50 cm	10645	11
Carpenter's Square Flat Corner Hard Chrome Finish 1 shaku/30 cm	10649	11
Carpenter's Square Flat Corner Hard Chrome Finish 30 cm	10647	11
Carpenter's Square Flat Corner Hard Chrome Finish 30 cm/1 shaku	10642	11
Carpenter's Square Flat Corner Hard Chrome Finish 50 cm	10640	11
Carpenter's Square Flat Corner Hard Chrome Finish 50 cm/1 shaku 5 sun	10638	11
Carpenter's Square Flat Corner Hard Chrome Finish 50 cm/1 shaku 6 sun	10639	11
Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 1 shaku	10657	11
Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	10654	11
Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	10655	11
Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 30 cm	10652	11
Carpenter's Square Flat Corner Hard Chrome Finish with Square Scale 50 cm	10653	11
Carpenter's Square Flat Corner White 1 shaku	11102	12
Carpenter's Square Flat Corner White 1 shaku 5 sun	11108	12
Carpenter's Square Flat Corner White 1 shaku 5 sun/50 cm	11110	12
Carpenter's Square Flat Corner White 1 shaku 6 sun	11103	12
Carpenter's Square Flat Corner White 1 shaku 6 sun/50 cm	11107	12
Carpenter's Square Flat Corner White 1 shaku/30 cm	11105	12
Carpenter's Square Flat Corner White 30 cm	11100	12
Carpenter's Square Flat Corner White 30 cm/1 shaku	11104	12
Carpenter's Square Flat Corner White 50 cm	11101	12
Carpenter's Square Flat Corner White 50 cm/1 shaku 5 sun	11109	12
Carpenter's Square Flat Corner White 50 cm/1 shaku 6 sun	11106	12
Carpenter's Square Flat Hard Chrome Finish 1 shaku	10620	15
Carpenter's Square Flat Hard Chrome Finish 1 shaku 5 sun	10592	15
Carpenter's Square Flat Hard Chrome Finish 1 shaku 5 sun/50 cm	10045	15
Carpenter's Square Flat Hard Chrome Finish 1 shaku 6 sun	10595	15
Carpenter's Square Flat Hard Chrome Finish 1 shaku 6 sun/50 cm	10046	15
Carpenter's Square Flat Hard Chrome Finish 1 shaku/30 cm	10048	15
Carpenter's Square Flat Hard Chrome Finish 15 cm	10007	15
Carpenter's Square Flat Hard Chrome Finish 15 cm/5 sun	10037	15
Carpenter's Square Flat Hard Chrome Finish 30 cm	10297	15
Carpenter's Square Flat Hard Chrome Finish 30 cm/1 shaku	10047	15
Carpenter's Square Flat Hard Chrome Finish 5 sun	10008	15
Carpenter's Square Flat Hard Chrome Finish 5 sun/15 cm	10038	15
Carpenter's Square Flat Hard Chrome Finish 50 cm	10032	15
Carpenter's Square Flat Hard Chrome Finish 50 cm/1 shaku 5 sun	10044	15
Carpenter's Square Flat Hard Chrome Finish 50 cm/1 shaku 6 sun	10033	15

Carpenter's Square Flat Hard Chrome Finish with Square Scale 1 shaku 5 sun	10590	15
Carpenter's Square Flat Hard Chrome Finish with Square Scale 1 shaku 6 sun	10598	15
Carpenter's Square Flat Hard Chrome Finish with Square Scale 50 cm	10016	15
Carpenter's Square Flat White 1 shaku	11174	16
Carpenter's Square Flat White 1 shaku 5 sun	11175	16
Carpenter's Square Flat White 1 shaku 5 sun/50 cm	11182	16
Carpenter's Square Flat White 1 shaku 6 sun	11176	16
Carpenter's Square Flat White 1 shaku 6 sun/50 cm	11184	16
Carpenter's Square Flat White 1 shaku/30 cm	11180	16
Carpenter's Square Flat White 15 cm	11170	16
Carpenter's Square Flat White 15 cm/5 sun	11177	16
Carpenter's Square Flat White 30 cm	11171	16
Carpenter's Square Flat White 30 cm/1 shaku	11179	16
Carpenter's Square Flat White 5 sun	11173	16
Carpenter's Square Flat White 5 sun/15 cm	11178	16
Carpenter's Square Flat White 50 cm	11172	16
Carpenter's Square Flat White 50 cm/1 shaku 5 sun	11181	16
Carpenter's Square Flat White 50 cm/1 shaku 6 sun	11183	16
Carpenter's Square Hard Chrome Finish for Two-by-Four 1 shaku 5 sun	10056	17
Carpenter's Square Hard Chrome Finish for Two-by-Four 50 cm	10055	17
Carpenter's Square Hard Chrome Finish with Magnet Flat Corner 1 shaku 6 sun	10181	18
Carpenter's Square Hard Chrome Finish with Magnet Flat Corner 50 cm	10175	18
Carpenter's Square Hard Chrome Finish with Magnet Wide 15 cm with 8 Scales cm Notation	10435	18
Carpenter's Square Hard Chrome Finish with Magnet Wide 30 cm with 8 Scales	10425	18
Carpenter's Square Hard Chrome Finish with Magnet Wide 50 cm with 6 Scales	10445	18
Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scal 1 shaku 6 sun Flexible	10878	12
Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	10847	12
Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun Flexible	10877	12
Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	10855	12
Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 50 cm	10839	12
Carpenter's Square High Quality Thick Corner Hard Chrome Finish with Square Scale 50 cm Flexible	10876	12
Carpenter's Square High Quality Thin Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	10845	13
Carpenter's Square High Quality Thin Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	10860	13
Carpenter's Square High Quality Thin Corner Hard Chrome Finish with Square Scale 50 cm	10837	13
Carpenter's Square Holder with Magnet	12427	20
Carpenter's Square Rigid Hard Chrome Finish 1 shaku	10545	18
Carpenter's Square Rigid Hard Chrome Finish 30 cm	10634	18
Carpenter's Square Rigid Hard Chrome Finish 30 cm/1 shaku	10511	18
Carpenter's Square Rigid Hard Chrome Finish with Square Scale 1 shaku	10529	18
Carpenter's Square Rigid Hard Chrome Finish with Square Scale 30 cm	10510	18
Carpenter's Square Thick Corner Black Color with Square Scale 1 shaku 5 sun	10758	10
Carpenter's Square Thick Corner Black Color with Square Scale 50 cm	10871	10
Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku	10626	8
Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 5 sun	10553	8
Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 5 sun/50 cm	10555	8
Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 6 sun	10561	8
Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku 6 sun/50 cm	10556	8
Carpenter's Square Thick Corner Hard Chrome Finish 1 shaku/30 cm	10028	8
Carpenter's Square Thick Corner Hard Chrome Finish 30 cm	10294	8
Carpenter's Square Thick Corner Hard Chrome Finish 30 cm/1 shaku	10027	8
Carpenter's Square Thick Corner Hard Chrome Finish 50 cm	10030	8
Carpenter's Square Thick Corner Hard Chrome Finish 50 cm/1 shaku 5 sun	10011	8
Carpenter's Square Thick Corner Hard Chrome Finish 50 cm/1 shaku 6 sun	10012	8
Carpenter's Square Thick Corner Hard Chrome Finish H-1475 20/45 cm	34513	8

Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales 50 cm	10370	9
Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales and Square Scale 1 shaku 5 sun	10371	9
Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales and Square Scale 1 shaku 6 sun	10372	9
Carpenter's Square Thick Corner Hard Chrome Finish with Inside Scales and Square Scale 50 cm	10373	9
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 1 shaku	10618	8
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 1 shaku 5 sun	10588	8
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 1 shaku 6 sun	10596	8
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 30 cm	10286	8
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale 50 cm	10014	8
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale and Inside Scale 1 shaku 5 sun	10332	9
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale and Inside Scale 1 shaku 6 sun	10340	9
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale and Inside Scale 50 cm	10359	9
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale for Left-hander 1 shaku 5 sun	10650	9
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale for Left-hander 1 shaku 6 sun	10669	9
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale for Left-hander 50 cm	10677	9
Carpenter's Square Thick Corner Hard Chrome Finish with Square Scale H-1476 20"	34517	8
Carpenter's Square Thick Corner Polish Finish 50 cm	11010	10
Carpenter's Square Thick Corner Polish Finish Fluorescent 50 cm	11777	10
Carpenter's Square Thick Corner Polish Finish Fluorescent with Square Scale 1 shaku 5 sun	11754	10
Carpenter's Square Thick Corner Polish Finish Fluorescent with Square Scale 1 shaku 6 sun	11762	10
Carpenter's Square Thick Corner Polish Finish Fluorescent with Square Scale 50 cm	11770	10
Carpenter's Square Thick Corner Polish Finish with Square Scale 50 cm	11002	10
Carpenter's Square Wide and Flexible Hard Chrome Finish 1 shaku 6 sun	10600	17
Carpenter's Square Wide and Flexible Hard Chrome Finish 50 cm	10034	17
Carpenter's Square Wide Hard Chrome Finish 1 shaku 6 sun with 4 Scales	10456	13
Carpenter's Square Wide Hard Chrome Finish 1 shaku with 4 Scales	10464	13
Carpenter's Square Wide Hard Chrome Finish 15 cm with 8 Scales cm Notation	10424	13
Carpenter's Square Wide Hard Chrome Finish 30 cm with 8 Scales	10421	13
Carpenter's Square Wide Hard Chrome Finish 30 cm with 8 Scales cm Notation	10451	13
Carpenter's Square Wide Hard Chrome Finish 50 cm with 4 Scales	11487	13
Carpenter's Square Wide Hard Chrome Finish 50 cm with 6 Scales	10405	13
Carpenter's Square Wide Hard Chrome Finish 50 cm with 8 Scales	11481	13
Carpenter's Square Wide Hard Chrome Finish 50 cm with 8 Scales cm Notation	10450	13
Carpenter's Square Wide Hard Chrome Finish 50 cm/1 shaku 6 sun with 5 Scales	10414	13
Carpenter's Square Wide Polish Finish 30 cm with 8 Scales	11215	14
Carpenter's Square Wide Polish Finish 50 cm with 6 Scales	11207	14
Carpenter's Square Wide White 30 cm with 8 Scales	11160	14
Carpenter's Square Wide White 50 cm with 8 Scales	11161	14
Carpenter's Square with Fence 60 cm/shaku	77885	23
Carrying case for Tripod with Handle A	81856	217
Carrying case for Wind-resistant Plumb	77604	218
Cartridge 100/150 for Screw Pitch Marking Tool Multi	67618	122
Cartridge 200/250/300 for Screw Pitch Marking Tool Multi	67619	122
Case for Stick Thermometer 15 cm	73001	222
Case for Stick Thermometer 30 cm	73002	222
Center screw for Aluminum Sliding Bevel	62548	215
Center screw for Welding Guide Rule	83440	221
Chalk for Waterproof Chalkboard	77064	76
Chalk Holder Blue	78597	130
Chalk Holder Red	78527	130
Chalk Holder White	78501	130
Chalk Holder Yellow	78528	130
Chalk Line BIG Hand-rewind Blue	77580	119
Chalk Powder 300 g Blue	77937	120

Chalk Powder 300 g Green	78030	120
Chalk Powder 300 g Pink	78029	120
Chalk Powder 300 g Red	77936	120
Chalk Powder 300 g White	77938	120
Chalk Powder 300 g Yellow	77935	120
Chalk Powder for Outdoo 500 g Whiter	77968	120
Chalk Powder for Outdoor 1 kg White	77976	120
Chalk Powder for Outdoor 150 g Blue	78096	120
Chalk Powder for Outdoor 200 g White	77954	120
Chalk Powder for Outdoor 375 g Blue	77962	120
Chalk Powder for Outdoor 750 g Blue	77965	120
Chalk Red 10 pc-pack with Plastic Case	74142	130
Chalk White 10 pc-pack with Plastic Case	74141	130
Chalk Yellow 10 pc-pack with Plastic Case	74143	130
Chuck Wrench A 3 mm	78582	160
Chuck Wrench A-2 3 mm	78596	160
Chuck Wrench B 5 mm	78584	160
Chuck Wrench C 6.5 mm	78587	160
Chuck Wrench D 10 mm	78590	160
Chuck Wrench E 13 mm	78593	160
Circular Saw Guide Free Angle Multi with Guide Rule 30 cm	78232	142
Circular Saw Guide Free Angle Neo 1 m	73163	141
Circular Saw Guide Free Angle Neo 30 cm	73160	141
Circular Saw Guide Free Angle Neo 37 cm	73166	141
Circular Saw Guide Free Angle Neo 45 cm	73161	141
Circular Saw Guide Free Angle Neo 60 cm	73162	141
Circular Saw Guide Free Angle One-touch 1 m	78450	142
Circular Saw Guide Free Angle One-touch 1.2 m	78451	142
Circular Saw Guide I-Clamp One-touch 1 m/shaku	77822	141
Circular Saw Guide I-Clamp One-touch 1.2 m/shaku	77821	141
Circular Saw Guide I-Clamp One-touch 2 m/shaku	77823	141
Circular Saw Guide I-Clamp One-touch 2.4 m/shaku	77824	141
Circular Saw Guide L-Angle EX 1 m/shaku	78032	132
Circular Saw Guide L-Angle EX 45 cm/shaku	78054	132
Circular Saw Guide L-Angle EX 60 cm/shaku	78055	132
Circular Saw Guide L-Angle Fit 15 cm	78034	138
Circular Saw Guide L-Angle Fit 23 cm	78036	138
Circular Saw Guide L-Angle Fit 30 cm	78052	138
Circular Saw Guide L-Angle for Left-hander 1 m/shaku	77807	137
Circular Saw Guide L-Angle for Left-hander 45 cm/shaku	77803	137
Circular Saw Guide L-Angle for Left-hander 60 cm/shaku	77805	137
Circular Saw Guide L-Angle Light 1 m	77919	137
Circular Saw Guide L-Angle Light 45 cm	77966	137
Circular Saw Guide L-Angle Light 60 cm	77967	137
Circular Saw Guide L-Angle Plus 1 m/shaku	73152	135
Circular Saw Guide L-Angle Plus 1.2 m/shaku	73153	135
Circular Saw Guide L-Angle Plus 45 cm/shaku	73150	135
Circular Saw Guide L-Angle Plus 60 cm/shaku	73151	135
Circular Saw Guide L-Angle Plus Adjust 1 m/shaku	73182	134
Circular Saw Guide L-Angle Plus Adjust 1.2 m/shaku	73183	134
Circular Saw Guide L-Angle Plus Adjust 45 cm/shaku	73180	134
Circular Saw Guide L-Angle Plus Adjust 60 cm/shaku	73181	134
Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 1 m/shaku	79054	133
Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 1.2 m/shaku	79055	133

Parts List	Japan Calibration Service System (JCS)	Etching	Sheet Heaters	Custom-Made Items	Name Printing	Index Item Code ➡ Description	Index Description ➡ Item Code
------------	--	---------	---------------	-------------------	---------------	--	--

Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 45 cm/shaku	79052	133	Color Magnets φ 40 Red 2 pc-pack	72020	208
Circular Saw Guide L-Angle Plus Shift with Gradient Scale Cutting Function 60 cm/shaku	79053	133	Color Magnets φ 40 White 2 pc-pack	72021	208
Circular Saw Guide L-Angle with Horizontal Graduations 1 m/shaku	78570	136	Color Magnets φ 40 White 10 pc-pack in Vinyl Bag	71821	209
Circular Saw Guide L-Angle with Support Plate 1 m/shaku	77901	136	Color Magnets φ 40 Yellow 10 pc-pack in Vinyl Bag	71823	209
Circular Saw Guide L-Angle with Support Plate 45 cm/shaku	77899	136	Color Magnets φ 40 Yellow 2 pc-pack	72024	208
Circular Saw Guide L-Angle with Support Plate 60 cm/shaku	77883	136	Infrared Thermometer with Clock Function A Emissivity Adjustable Model	73009	177
Circular Saw Guide L-Angle without Handle 50 cm/shaku	77858	137	Compact Reading Glass S-1 60 mm 2x	75555	190
Circular Saw Guide Mini Free Angle II 30 cm	78179	143	Compact Reading Glass S-2 45 mm 2x	75556	190
Circular Saw Guide Mini Free Angle Justy II 23 cm	78176	143	Compact Reading Glass S-3 30 mm 3x	75557	190
Circular Saw Guide Mini Free Angle Justy Quick Adjust 23 cm	78079	143	Compass Attachment	70920	198
Circular Saw Guide Mini Free Angle Quick Adjust 30 cm	78217	143	Compass Chinese Zodiac D	75604	187
Circular Saw Guide Triangle AL 15 cm	78108	138	Compass I for Zipper	75686	188
Circular Saw Guide Triangle PC 30 cm	78280	138	Compass K-2 Japanese	75672	188
Circular Saw Guide T-Slide II 15 cm/shaku	73711	139	Conductivity Solution 1413 μ S/cm 6 Sachets	73035	183
Circular Saw Guide T-Slide II 30 cm/shaku	73712	139	Construction Chalk Board Steel SA 45 x 60 cm	77510	72
Circular Saw Guide T-Slide II 45 cm/shaku	73713	139	Construction Chalk Board Steel SAS 30 x 45 cm	77533	72
Circular Saw Guide T-Slide II 60 cm/shaku	73714	139	Construction Chalk Board Steel SC 45 x 60 cm	77511	72
Circular Saw Guide T-Slide II 90 cm/shaku	73715	139	Construction Chalk Board Steel SD 45 x 60 cm	77513	72
Circular Saw Guide T-Slide Basic 15 cm/shaku	73591	140	Construction Chalk Board Steel SD-2 60 x 45 cm	77514	72
Circular Saw Guide T-Slide Basic 30 cm/shaku	73592	140	Construction Chalk Board Steel SDS 30 x 45 cm	77539	72
Circular Saw Guide T-Slide Basic 45 cm/shaku	73593	140	Construction Chalk Board Steel SDS-2 45 x 30 cm	77540	72
Circular Saw Guide T-Slide Basic 60 cm/shaku	73594	140	Construction Chalk Board Steel SG 45 x 60 cm	77523	72
Circular Saw Guide T-Slide Double 15 cm/shaku	73701	140	Construction Chalk Board Wood A 45 x 60 cm	76975	69
Circular Saw Guide T-Slide Double 30 cm/shaku	73702	140	Construction Chalk Board Wood AS 30 x 45 cm	77031	69
Circular Saw Guide T-Slide Double 45 cm/shaku	73703	140	Construction Chalk Board Wood B 45 x 60 cm	76956	69
Circular Saw Guide T-Slide Double 60 cm/shaku	73704	140	Construction Chalk Board Wood B-2 60 x 45 cm	77057	69
Circular Saw Guide T-Slide Double 90 cm/shaku	73705	140	Construction Chalk Board Wood C 45 x 60 cm	76957	69
Circular Saw Guide T-Slide Slim-shift 15 cm/shaku	73312	139	Construction Chalk Board Wood C-2 60 x 45 cm	77058	69
Circular Saw Guide T-Slide Slim-shift 30 cm/shaku	73313	139	Construction Chalk Board Wood D 45 x 60 cm	77059	69
Circular Saw Guide T-Slide Slim-shift 45 cm/shaku	73314	139	Construction Chalk Board Wood D-2 60 x 45 cm	77067	69
Circular Saw Guide T-Slide Slim-shift 60 cm/shaku	73315	139	Construction Chalk Board Wood DS 30 x 45 cm	77087	69
Circular Saw Guide T-Slide Slim-shift 90 cm/shaku	73316	139	Construction Chalk Board Wood DS-2 45 x 30 cm	77088	69
Clear Case for Stick Thermometer H-3 30 cm	73003	222	Construction Chalk Board Wood E-2 60 x 45 cm	77068	69
Coil Spring for Handy Plumb Holder Jr.	77956	219	Construction Chalk Board Wood F 45 x 60 cm	77069	69
Coil Spring for Handy Plumb Holder Pro	77811	218	Construction Chalk Board Wood G 45 x 60 cm	77078	70
Color Magnets φ 20 Blue 10 pc-pack in Vinyl Bag	71814	209	Construction Chalk Board Wood GS 30 x 45 cm	77329	70
Color Magnets φ 20 Blue 5 pc-pack	72012	208	Construction Chalk Board Wood H 45 x 60 cm	77079	70
Color Magnets φ 20 Red 10 pc-pack in Vinyl Bag	71812	209	Construction Chalk Board Wood J 45 x 60 cm	77037	70
Color Magnets φ 20 Red 5 pc-pack	72010	208	Construction Chalk Board Wood JS 30 x 45 cm	77334	70
Color Magnets φ 20 White 5 pc-pack	72011	208	Construction Chalk Board Wood K 45 x 60 cm	77314	70
Color Magnets φ 20 White 10 pc-pack in Vinyl Bag	71813	209	Construction Flag Fabric Pair of White and Red	76955	68
Color Magnets φ 20 Yellow 10 pc-pack in Vinyl Bag	71815	209	Construction Flag Nylon Pair of White and Red	76909	68
Color Magnets φ 20 Yellow 5 pc-pack	72014	208	Construction Folding Chalk Board Wood OA 45 x 60 cm	76874	70
Color Magnets φ 30 Blue 10 pc-pack in Vinyl Bag	71818	209	Construction Folding Chalk Board Wood OC 45 x 60 cm	76875	70
Color Magnets φ 30 Blue 3 pc-pack	72017	208	Construction Folding Chalk Board Wood OD 45 x 60 cm	76876	70
Color Magnets φ 30 Red 10 pc-pack in Vinyl Bag	71816	209	Construction Folding Chalk Board Wood OG 45 x 60 cm	76877	70
Color Magnets φ 30 Red 3 pc-pack	72015	208	Construction Water-resistant Chalk Board TA 45 x 60 cm	77061	71
Color Magnets φ 30 White 3 pc-pack	72016	208	Construction Water-resistant Chalk Board TB 45 x 60 cm	77328	71
Color Magnets φ 30 White 10 pc-pack in Vinyl Bag	71817	209	Construction Water-resistant Chalk Board TC 45 x 60 cm	77322	71
Color Magnets φ 30 Yellow 10 pc-pack in Vinyl Bag	71819	209	Construction Water-resistant Chalk Board TD 45 x 60 cm	77074	71
Color Magnets φ 30 Yellow 3 pc-pack	72019	208	Construction Water-resistant Chalk Board TD-2 60 x 45 cm	77075	71
Color Magnets φ 40 Blue 10 pc-pack in Vinyl Bag	71822	209	Construction Water-resistant Chalk Board TDS 30 x 45 cm	78229	71
Color Magnets φ 40 Blue 2 pc-pack	72022	208	Construction Water-resistant Chalk Board TF 45 x 60 cm	78230	71
Color Magnets φ 40 Red 10 pc-pack in Vinyl Bag	71820	209	Construction Water-resistant Chalk Board TG 45 x 60 cm	78238	71

Construction White Board ASW 30 x 45 cm	77365	73
Construction White Board AW 45 x 60 cm	77357	73
Construction White Board BW 45 x 60 cm	77358	73
Construction White Board CSW 30 x 45 cm	77366	73
Construction White Board CW 45 x 60 cm	77331	73
Construction White Board DSW 30 x 45 cm	77367	73
Construction White Board DSW-2 45 x 30 cm	77368	73
Construction White Board DW 45 x 60 cm	77332	73
Construction White Board DW-2 60 x 45 cm	77333	73
Construction White Board FW 45 x 60 cm	77385	73
Construction White Board GSW 30 x 45 cm	77369	74
Construction White Board GW 45 x 60 cm	77359	74
Construction White Board HW 45 x 60 cm	77386	74
Construction White Board JW 45 x 60 cm	77387	74
Construction White Board Mini with Telescopic Arm MCSW 11 x 14 cm	78161	75
Construction White Board Mini with Telescopic Arm MCSW 11 x 14 cm with Itemized Magnetic Sheet	77626	75
Construction White Board Mini with Telescopic Arm MCW 14 x 17 cm	78162	75
Construction White Board Mini with Telescopic Arm MCW 14 x 17 cm with Itemized Magnetic Sheet	77627	75
Cotton Leveling Line No.10 1.4 mm 100 m	78495	125
Cotton Leveling Line No.3 0.7 mm 100 m	78488	125
Cotton Leveling Line No.4 0.8 mm 100 m	78489	125
Cotton Leveling Line No.5 0.9 mm 100 m	78490	125
Cotton Leveling Line No.6 1.0 mm 100 m	78491	125
Cotton Leveling Line No.7 1.1 mm 100 m	78493	125
Cotton Leveling Line No.8 1.2 mm 100 m	78494	125
Counter B Metallic Model	75086	162
Counter C Blue Plastic Model	75090	162
Counter C Yellow Plastic Model	75089	162
Counter with Stand A Metallic Model	75078	162
Countersunk screws for Carpenter's Square with Fence	99080	214
Crack Scale Card Type	58699	150
Crack Scale Clear Type	58697	150
Crack Scale Rule Type 15 cm	58698	150
Cross Fitting for Aluminum Leveling Rod 60 mm Wide	76926	64
Cross Fitting for Plywood Leveling Rod 63 mm Wide	76980	65
Curved Rule 6 pc-pack	77003	197
Curved Rule Middle-size	70947	197
Cut Rail 1 m/shaku	65077	40
Cut Rail 2 m/shaku	65078	40
Cutout positioning stick fixing screw for L-Clamp One-touch	99246	220
Cutout positioning stick fixing screw for L-Angle Adjust and Free Angle Neo	80925	219
Cutout positioning stick fixing screw for L-Angle II, Plus, with Support Plate, with Horizontal Graduations, and for Left-hander	99249	219
Cutout positioning stick fixing screw for Mini Free Angle II and Justy II	99605	220
Cutout positioning stick for L-Angle Adjust 1 - 1.2 m and Free Angle Neo 60 - 1 m	47235	219
Cutout positioning stick for L-Angle Adjust 45 cm - 60 cm and Free Angle Neo 30 cm - 45 cm	47234	219
Cutout positioning stick for Mini Free Angle Justy 23 cm, L-Angle II 45 cm - 60cm and L-Angle Plus	99203	219
Cutout positioning stick for Mini Free Angle II, L-Angle II 1 m and EX 1 m	99232	219

D

Description	Item Code	Page
Deburring Tool with Replacement Blade for S-10/S-20/S-35	78665	161
Depth Gauge Mini	19300	57
Depth probe holding plate, screw set for Digital Vernier Caliper 150 mm and 200 mm	98765	215
Depth probe holding plate, screw set for Digital Vernier Caliper 300 mm	98766	215

Depth probe holding plate, screw set for Mini Vernier Caliper 100 mm	99565	215
Depth probe holding plate, screw set for Vernier Caliper 150 mm	99563	215
Depth probe holding plate, screw set for Vernier Caliper 200 mm	99564	215
Depth probe holding plate, screw set for Vernier Caliper 300 mm	99567	215
Desk Magnifier K 25 x 150 mm 2x	75767	191
Desk Magnifier L-3 8x and 30x	75727	191
Desk Magnifier M-1 60 mm 3.5x	75529	191
Dial Gauge 0.01 mm/10 mm	73750	156
Dial Indicator 0.01 mm/0.8 mm	73751	156
Dial Plumb 110 cm	77548	123
Dial Plumb 175 cm	77549	123
Dial Plumb 200 cm	77550	123
Dial Plumb 240 cm	77575	123
Digital Angle Meter II Dust/Waterproof	76825	92
Digital Angle Meter II with Magnet Dust/Waterproof	76826	92
Digital Angle Meter with Magnet Mini	76447	92
Digital Compact Scale Mini 200 g	70163	80
Digital Counter	73310	162
Digital Depth Gauge Mini 25 mm	19305	57
Digital Depth Gauge with Hold Function 150 mm	19306	57
Digital Depth Gauge with Hold Function 200 mm	19307	57
Digital Lux Meter	78747	184
Digital Micrometer 0 - 25 mm	79523	58
Digital Micrometer 0 - 25 mm with JCSS Certificate	19088	224
Digital Moisture Meter for Wood with Maximum and Minimum Hold Function	78636	146
Digital Noise Meter with Maximum Value Holding Function	78588	185
Digital part replacement for Blue Level Digital	46967	216
Digital part replacement for Digital Vernier Caliper 1000 mm	98906	215
Digital part replacement for Digital Vernier Caliper 150 mm	98768	215
Digital part replacement for Digital Vernier Caliper 200 mm	98769	215
Digital part replacement for Digital Vernier Caliper 300 mm	98770	215
Digital part replacement for Digital Vernier Caliper 450, 600 mm	98905	215
Digital part replacement for Digital Vernier Caliper Mini	98774	215
Digital pH Meter	72788	183
Digital Protractor with Hold Function 20 cm	62495	52
Digital Protractor with Hold Function 30 cm	62496	52
Digital Salinity Meter	72799	183
Digital Scale 15 kg	70106	81
Digital Scale 3 kg	70104	81
Digital Scale 30 kg	70107	81
Digital Scale 6 kg	70105	81
Digital Scale for Commercial Use 3 kg	70191	81
Digital Scale for Commercial Use 6 kg	70192	81
Digital Scale for Commercial Use 15 kg	70193	81
Digital Scale for Commercial Use 30 kg	70194	81
Digital Scale Remote-reading 100 kg	70108	82
Digital Soil EC Meter	72758	182
Digital Soil EC Meter II	72976	182
Digital Soil pH Meter A	72716	182
Digital Spring Scale 20 kg	70109	84
Digital Thermo/Hygrometer D-1 Blue	73054	171
Digital Thermo/Hygrometer D-1 Orange	73055	171
Digital Thermo/Hygrometer D-2 Blue	73056	171
Digital Thermo/Hygrometer D-2 Orange	73057	171

Parts List	Digital Thermo/Hygrometer Home A Blue with Clear Package	73048	170
	Digital Thermo/Hygrometer Home A Green with Clear Package	73049	170
	Digital Thermo/Hygrometer Home A Maximum and Minimum White	73030	170
	Digital Thermo/Hygrometer Home A White with Clear Package	73044	170
Japan Calibration Service System (JCSS)	Digital Thermo/Hygrometer Smart A	73115	170
	Digital Thermo/Hygrometer with Discomfort Index Meter C	72985	171
	Digital Thermo/Hygrometer with Solar Panel B Maximum and Minimum	72989	171
	Digital Thermometer for Bath B	73098	175
Etching	Digital Thermometer for Cooking T Green	72979	174
	Digital Thermometer for Cooking T Pink	72978	174
	Digital Thermometer for Indoor and Outdoor E	72947	171
	Digital Thermometer for Refrigerator A Maximum and Minimum Remote-reading	73042	174
Sheet Heaters	Digital Thermometer for Refrigerator T Round-shape	72980	174
	Digital Thermometer Smart A	73116	170
	Digital Thermometer Smart B for Indoor and Outdoor with Waterproof Outside Sensor	73117	170
	Digital Thermometer Smart C Maximum and Minimum for Indoor and Outdoor with Waterproof Outside Sensor	73118	170
Custom-Made Items	Digital Thickness Caliper with Handle A 0.01 mm/10 mm	73746	156
	Digital UV Light Meter	78642	184
	Digital Vernier Caliper 150 mm with JCSS Certificate	19085	224
	Digital Vernier Caliper 200 mm with JCSS Certificate	19086	224
Name Printing	Digital Vernier Caliper 300 mm with JCSS Certificate	19087	224
	Digital Vernier Caliper Carbon Fiber Body 100 mm	19978	56
	Digital Vernier Caliper Carbon Fiber Body 150 mm	19979	56
	Digital Vernier Caliper Carbon Fiber Body with Solar Panel 150 mm	19981	56
Index Item Code ➔ Description	Digital Vernier Caliper Mini 100 mm with JCSS Certificate	19084	224
	Digital Vernier Caliper with Hold Function 1000 mm	19988	55
	Digital Vernier Caliper with Hold Function 150 mm	19975	55
	Digital Vernier Caliper with Hold Function 200 mm	19976	55
Index Description ➔ Item Code	Digital Vernier Caliper with Hold Function 300 mm	19977	55
	Digital Vernier Caliper with Hold Function 450 mm	19986	55
	Digital Vernier Caliper with Hold Function 600 mm	19987	55
	Digital Vernier Caliper with Hold Function Mini 100 mm	19974	55
Index Description ➔ Item Code	Digital Vernier Caliper with Solar Panel 150 mm	19983	56
	Digital Vernier Caliper with Solar Panel 150 mm with JCSS Certificate	47293	224
	Digital Vernier Caliper with Solar Panel 200 mm	19984	56
	Digital Vernier Caliper with Solar Panel 200 mm with JCSS Certificate	81484	224
Index Description ➔ Item Code	Disappearing Ink 50 ml	77649	118
	Divider A 15 cm	77518	152
	Divider B 20 cm	77526	152
	Divider C 10 cm	77517	152
Index Description ➔ Item Code	Divider D 25 cm	77536	152
	Divider E 30 cm	77537	152
	Divider with Spring A 15 cm	73059	152
	Divider with Spring B 20 cm	73067	152
Index Description ➔ Item Code	Divider with Spring SD-10 25 cm	33952	152
	Divider with Spring SD-12 30 cm	33953	152
	Divider with Spring SD-6 15 cm	33950	152
	Divider with Spring SD-8 20 cm	33951	152
Index Description ➔ Item Code	Divider with Super Hard Chip A-2 15 cm	77520	152
	Divider with Super Hard Chip B-2 20 cm	77521	152
	Divider with Super Hard Chip C-2 10 cm	77516	152
	Divider with Super Hard Chip D-2 25 cm	77543	152
Index Description ➔ Item Code	Divider with Super Hard Chip E-2 30 cm	77545	152
	Divider with Super Hard Chip F-2 40 cm	77546	152

Drawing Brush	70874	203
Drawing Compasses A 115 mm	75388	198
Drawing Compasses B 155 mm	75396	198
Drawing Divider A 115 mm	75442	198
Drawing Divider B 155 mm	75450	198
Drawing Sheet Case A 7-step Slide	77030	203
Dressmaking Square Hard Chrome Finish 75 x 35 cm	64009	22
Dry Compass A-3 Japanese	75602	186
Dry Compass B-2 Roman Alphabet	75603	186

E

Description	Item Code	Page
Edge cap, screw set for I-Clamp One-touch	99245	220
Emitting port protective cap for Laser ROBO X line	80826	217
End nut, iron bolt set for Protractor No.1000 Double-blade	99518	215
End nut, iron bolt set for Protractor No.300 Double-blade	99516	215
End nut, iron bolt set for Protractor No.600 Double-blade	99517	215
Eraser for Chalkboard and Whiteboard	77353	77
Eraser for Waterproof Chalkboard	77045	77
Extension Cable for Inspection Scope 2 m	74178	159
Extension Cable for Inspection Scope 5 m	74179	159

F

Description	Item Code	Page
Fabric Safety Cord A Black	80858	147
Fabric Safety Cord A Orange	80859	147
Fabric Safety Cord B Black	80860	147
Fabric Safety Cord B Orange	80861	147
Feeler Gauge A 75 mm 9 Leaves	73776	155
Feeler Gauge B 100 mm 9 Leaves	73780	155
Feeler Gauge C 150 mm 9 Leaves	73781	155
Feeler Gauge D 65 mm 25 Leaves	73782	155
Feeler Gauge E 100 mm 25 Leaves	73796	155
Feeler Gauge F 150 mm 25 Leaves	73797	155
Fiberglass Dial Caliper 150 mm	19932	55
Fiberglass Folding Rule 10-folding 1 m	78606	45
Fiberglass Folding Rule 10-folding 1 m in Bulk	78708	45
Fiberglass Folding Rule 10-folding 2 m	78833	45
Fiberglass Folding Rule 10-folding 2 m in Bulk	78841	45
Fiberglass Folding Rule 5-folding 1 m	78605	45
Fiberglass Folding Rule 5-folding 1 m Black	78625	45
Fiberglass Folding Rule 5-folding 1 m Black in Bulk	78633	45
Fiberglass Folding Rule 5-folding 1 m in Bulk	78705	45
Fiberglass Folding Rule 5-folding 1 m/shaku	78623	45
Fiberglass Folding Rule 5-folding 1 m/shaku in Bulk	78624	45
Fiberglass Leveling Rod Tape 10 m	76971	67
Fiberglass Leveling Rod Tape 3 m	76969	67
Fiberglass Leveling Rod Tape 5 m	76970	67
Fiberglass Tape Measure FW-30 JIS	78184	63
Fiberglass Tape Measure FW-50 JIS	78181	63
Fine adjustment knob for Digital Vernier Caliper 1000 mm	98910	215
Fine adjustment knob for Digital Vernier Caliper 450, 600 mm	98909	215
Fine adjustment knob for Vernier Caliper 1000 mm	98914	215
Fine adjustment knob for Vernier Caliper 450, 600 mm	98912	215

Fine adjustment screw set for L-Angle Plus Adjust	93401	219
Fixing screw for Laser Holder	97905	217
Flange Bend, Gradient Measuring Gauge	97790	149
Flat Square 30 x 20 cm	62359	22
Flat Tape 1.5 m	71013	63
Flexible Rule with Scale 40 cm	74845	197
Flexible Rule with Scale 80 cm	74853	197
Flexible Stainless Steel Rule Hard Chrome Finish 1 m	13277	31
Flexible Stainless Steel Rule Hard Chrome Finish 1.5 m	13285	31
Flexible Stainless Steel Rule Hard Chrome Finish 2 m	13293	31
Flexible Stainless Steel Rule Hard Chrome Finish 30 cm	13250	31
Flexible Stainless Steel Rule Hard Chrome Finish 60 cm	13269	31
Fluorescent Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick Yellow	72204	213
Folding Construction White Board OAW 45 x 60 cm	77741	74
Folding Construction White Board OCW 45 x 60 cm	77742	74
Folding Construction White Board ODW 45 x 60 cm	77743	74
Folding Construction White Board OGW 45 x 60 cm	77744	74
Folding Scale 8-scales 15 cm	75745	200
Folding Scale 8-scales 30 cm	75746	200
Folding Square 1.8 m	77840	148
Front side hanging part with spring for Free Angle One-touch	78454	220
Front spring and guide pin set for Auto Punch L	73996	222
Front spring and guide pin set for Auto Punch M	73994	222
Front spring with guide pin for Auto Punch L with Flat Grip to Prevent Rolling	81316	222
Front spring with guide pin for Auto Punch M with Flat Grip to Prevent Rolling	81312	222

G

Description	Item Code	Page
Gauge head for Dial Gauge	81365	221
Gauge head for Dial Indicator	81373	221
Gauge head spanner for Dial Indicator	81372	221
Gauge installation complete set for Magnetic Stand A and A-2	81378	221
Grip Nut for Aluminum Sliding Bevel	84730	215
Guide Rule for Circular Saw Guide Free Angle Multi 30 cm	78233	142
Guide Rule for Circular Saw Guide Free Angle Multi 45 cm	78234	142
Guide Rule for Circular Saw Guide Free Angle Multi 60 cm	78235	142
Guide Rule for Screw Pitch Marking Tool/Multi	77394	122
Guide stabilization metal fitting for T-Slide II , Double and Slim-shift	47358	220

H

Description	Item Code	Page
Hammer pin for Auto Punch L	85773	222
Hammer pin for Auto Punch L with Flat Grip to Prevent Rolling	81317	222
Hammer pin for Auto Punch M	74291	222
Hammer pin for Auto Punch M with Flat Grip to Prevent Rolling	81313	222
Hand Magnet A-2	73553	204
Hand Magnet A-3	73558	204
Hand Magnet with Casters C	73556	204
Hand Magnet with Handle B-2	73554	204
Hand Magnet with Handle B-3	73559	204
Handle and screws set for Hand Magnet B-2	84297	222
Handle for Aluminum Cutting Rule Light	84259	214
Handle for L-Angle II and L-Angle Adjust	83737	219
Handle for L-Angle with Support Plate, with Horizontal Graduations, and for Left-hander	99608	219

Handle for Laser ROBO Neo AR BRIGHT	80733	217
Handle for Laser ROBO Neo BRIGHT and E Sensor	67823	217
Handle for Tripod with Handle A	83701	217
Handle for Tripod with Handle B	98917	217
Handle for Tripod with Handle C	98919	217
Handle installing screw for L-Angle II , Adjust, and EX	99552	219
Handle non-slip rubber, screw set for L-Angle Plus	93310	219
Handle screw set for L-Angle EX 1 m	98791	219
Handle screw set for L-Angle EX 45 cm and 60 cm	98790	219
Handle, screw set for Aluminum Cutting Rule	99556	214
Handle, screw set for Aluminum Cutting Rule EX	85518	214
Handy Chalk Line 5x Speed Hand-rewind	77560	119
Handy Chalk Line Hand-rewind Red	77927	119
Handy Chalk Line Neo Auto-rewind Thick Thread Yellow	77493	119
Handy Chalk Line Neo Auto-rewind Thin Thread Orange	77963	119
Handy Chalk Line Neo Hand-rewind Thick Thread Blue	77494	119
Handy Chalk Line Neo Hand-rewind Thin Thread Purple	77964	119
Handy Ink Line Marker Jr. LITE Auto-rewind Green	73302	117
Handy Ink Line Marker Jr. LITE Auto-rewind Orange	73303	117
Handy Ink Line Marker Jr. LITE Hand-rewind Mint Green	73307	117
Handy Ink Line Marker Jr. Plus Auto-rewind Black	73282	116
Handy Ink Line Marker Jr. Plus Auto-rewind Coral Red	73283	116
Handy Ink Line Marker Jr. Plus Auto-rewind Sharp Line Metal Blue	73298	115
Handy Ink Line Marker Jr. Plus Auto-rewind Tough Line Metal Red	73289	115
Handy Ink Line Marker Jr. Plus Auto-rewind with Holder Black	73292	116
Handy Ink Line Marker Jr. Plus Auto-rewind with Holder Coral Red	73293	116
Handy Ink Line Marker Jr. Plus Hand-rewind Black	73284	116
Handy Ink Line Marker Jr. Plus Hand-rewind Sharp Line Metal Blue	73299	115
Handy Ink Line Marker Jr. Plus Hand-rewind Turquoise Blue	73285	116
Handy Ink Line Marker Pro LITE Auto-rewind Blue	73300	117
Handy Ink Line Marker Pro LITE Auto-rewind Red	73301	117
Handy Ink Line Marker Pro Plus Auto-rewind Black	73280	116
Handy Ink Line Marker Pro Plus Auto-rewind Royal Blue	73281	116
Handy Ink Line Marker Pro Plus Auto-rewind Sharp Line Metal Blue	73297	115
Handy Ink Line Marker Pro Plus Auto-rewind Tough Line Metal Red	73287	115
Handy Ink Line Marker Pro Plus Auto-rewind with Holder Black	73290	116
Handy Ink Line Marker Pro Plus Auto-rewind with Holder Royal Blue	73291	116
Handy Ink Line Marker Self Stop Auto-rewind Black	77450	118
Handy Ink Line Marker SUMIWAZA Auto-rewind Brown	77845	118
Handy Level Light 100 mm	76342	89
Handy Level MEGA-MAG with Magnet 100 mm Black	73131	88
Handy Level MEGA-MAG with Magnet 100 mm White	73130	88
Handy Level MEGA-MAG with Magnet 150 mm Black	73133	88
Handy Level MEGA-MAG with Magnet 150 mm White	73132	88
Handy Level Revo Double	76426	89
Handy Level Revo Single Blue	76425	89
Handy Level Revo Single White	76424	89
Handy Level Revo Triple	76428	89
Handy Level Revo with Magnet Double	76427	89
Handy Level Revo with Magnet Triple	76429	89
Handy Level with Magnet B 100 mm	76048	89
Handy Plumb Holder Jr. Auto-rewind Red	77501	124
Handy Plumb Holder Jr. with Plumb Bob 200 g Auto-rewind Red	77502	124
Handy Plumb Holder Pro Auto-rewind Red	77375	124

Handy Plumb Holder Pro Hand-rewind Blue	77377	124
Handy Plumb Holder Pro with Plumb Bob 400 g Auto-rewind Red	77376	124
High Magnification Model Q 10 mm 15x	75543	192
High Magnification Model R-1 18 mm 15x	75564	192
High Magnification Model R-2 28 mm 10x	75565	192
High Magnification Model T-1 20 mm 15x	75570	192
High Magnification Model T-2 28 mm 10x	75571	192
Holder for Handy Ink Line Marker Pro/Jr. Plus	73286	117
Holder for Laser Receiver, model II and Plus	76659	217
Holder for Paint Marker Fine	78510	126
Holder for Wind-resistant Plumb with Quick Arm	77599	123
Hourglass for 1-minute	70550	185
Hourglass for 3-minute	70551	185
Hourglass for 5-minute	70552	185
Hygrometer T-1 10 cm	72690	166
Hygrometer T-3 6.5 cm	72668	166

Description	Item Code	Page
Indicator Plate for Machine Scale	14165	36
Individual Paper Box 80 x 75 x 45 mm White	67983	228
Infrared Thermometer F	73038	177
Infrared Thermometer for High Temperature with Dual Laser Pointer H Emissivity Adjustable Model	73100	178
Infrared Thermometer with Laser Pointer B	73010	177
Infrared Thermometer with Laser Pointer C Emissivity Adjustable Model	73014	178
Ink Black 15 ml 2 pc-pack	77837	118
Ink Black 200 ml	77475	118
Ink Black 500 ml	77589	118
Ink Black for Wet Condition 200 ml	77587	118
Ink Blue 200 ml	77478	118
Ink Red 15 ml 2 pc-pack	77838	118
Ink Red 200 ml	77476	118
Ink Red for Wet Condition 200 ml	77588	118
Ink Tank for Screw Pitch Marking Tool Multi	90943	122
Ink White 15 ml 2 pc-pack	77839	118
Ink White 200 ml	77477	118
Inside Caliper A 15 cm	73253	153
Inside Caliper B 20 cm	73261	153
Inside Caliper with Spring IC-10 25 cm	33956	153
Inside Caliper with Spring IC-12 30 cm	33957	153
Inside Caliper with Spring IC-6 15 cm	33954	153
Inside Caliper with Spring IC-8 20 cm	33955	153
Inspection Mirror A-1 Circle 60 mm	75758	158
Inspection Mirror A-2 Circle 36 mm	75759	158
Inspection Mirror A-3 Oval 50 x 80 mm	75756	158
Inspection Mirror A-4 Oval 25 x 50 mm	75757	158
Inspection Mirror with LED Light D-1 Circle 60 mm	74155	158
Inspection Mirror with LED Light D-2 Circle 36 mm	74156	158
Inspection Mirror with LED Light D-3 Oval 50 x 80 mm	74157	158
Inspection Mirror with LED Light D-4 Oval 25 x 50 mm	74158	158
Inspection Scope A φ 5.8 Wireless 3.5 Inch LCD	74172	159
Inspection Scope B φ 9 Wireless 3.5 Inch LCD	74173	159
Itemized Magnetic Sheet 6 item-set for Construction White Board Mini MCSW 11 x 14 cm	78428	76
Itemized Magnetic Sheet 6 item-set for Construction White Board Mini MCW 14 x 17 cm	78427	76

J

Description	Item Code	Page
Japanese Bevel 25 cm	62502	48
Japanese Bevel 30 cm	62510	48
Japanese Bevel 45 cm	62529	48
Japanese Bevel 60 cm	62532	48
Japanese Sliding Bevel 15 cm	62588	48
Japanese Sliding Bevel 25 cm	62596	48
Japanese Try Square 15 cm	62009	46
Japanese Try Square with Square Scale 13 cm	62014	46
Japanese Try Square with Square Scale 15 cm	62006	46
JCSS Calibration Certificate for Micrometer 0 - 25 mm	19082	224
JCSS Calibration Certificate for Micrometer 25 - 50 mm	19083	224
JCSS Calibration Certificate for Precision Stainless Steel Rule 1 m	83502	224
JCSS Calibration Certificate for Precision Stainless Steel Rule 30 cm	83702	224
JCSS Calibration Certificate for Precision Stainless Steel Rule 60 cm	83802	224
JCSS Calibration Certificate for Stainless Steel Rule 1 m	19037	224
JCSS Calibration Certificate for Stainless Steel Rule 1.5 m	19075	224
JCSS Calibration Certificate for Stainless Steel Rule 10 cm	19010	224
JCSS Calibration Certificate for Stainless Steel Rule 15 cm	19034	224
JCSS Calibration Certificate for Stainless Steel Rule 2 m	19076	224
JCSS Calibration Certificate for Stainless Steel Rule 30 cm	19035	224
JCSS Calibration Certificate for Stainless Steel Rule 60 cm	19036	224
JCSS Calibration Certificate for Stainless Steel Rule Over 1m under 2 m	19044	224
JCSS Calibration Certificate for Stainless Steel Rule Under 1 m	19045	224
JCSS Calibration Certificate for Steel Tape Measure Over 20 m under 50 m	19048	224
JCSS Calibration Certificate for Steel Tape Measure Over 5 m under 20 m	19047	224
JCSS Calibration Certificate for Steel Tape Measure Over 50 m under 100 m	19049	224
JCSS Calibration Certificate for Steel Tape Measure Under 5 m	19039	224
JCSS Calibration Certificate for Vernier Caliper 100 mm	19061	224
JCSS Calibration Certificate for Vernier Caliper 150 mm	19056	224
JCSS Calibration Certificate for Vernier Caliper 200 mm	19057	224
JCSS Calibration Certificate for Vernier Caliper 300 mm	19058	224
JCSS Calibration Certificate for Vernier Caliper 70 mm	19060	224
Joint for Inspection Mirror A, D, Magnifying Mirror	80941	221
Joint Offset Measuring Gauge	97788	149

K

Description	Item Code	Page
Ken Measure 12 shaku	65180	43
KONOE DOUBLE 2 Blue 100 pc-pack	76995	78
KONOE DOUBLE 2 Red 100 pc-pack	76993	78
KONOE DOUBLE 2 Yellow 100 pc-pack	76994	78
KONOE DOUBLE Mini Pack 2 Blue 20 pc-pack	76948	78
KONOE DOUBLE Mini Pack 2 Red 20 pc-pack	76946	78
KONOE DOUBLE Mini Pack 2 Yellow 20 pc-pack	76947	78
KONOE DOUBLE Mini Pack 3 Blue 5 pc-pack	76951	78
KONOE DOUBLE Mini Pack 3 Red 5 pc-pack	76949	78
KONOE DOUBLE Mini Pack 3 Yellow 5 pc-pack	76950	78
KONOE MASTER LINE Insert Type M-10	76920	77
KONOE MASTER LINE Insert Type M-6	76916	77
KONOE MASTER LINE Insert Type M-7	76917	77
KONOE MASTER LINE Insert Type M-8	76918	77
KONOE MASTER LINE Insert Type M-9	76919	77

KONOE MASTER LINE Stick-on Type M-1	76911	77
KONOE MASTER LINE Stick-on Type M-2	76912	77
KONOE MASTER LINE Stick-on Type M-3	76913	77
KONOE MASTER LINE Stick-on Type M-4	76914	77
KONOE MASTER LINE Stick-on Type M-5	76915	77
KONOE NAIL Mini Pack No.01 20 pc-pack	76938	78
KONOE NAIL Mini Pack No.1 20 pc-pack	76939	78
KONOE NAIL Mini Pack No.2 5 pc-pack	76940	78
KONOE NAIL Mini Pack No.3 5 pc-pack	76941	78
KONOE NAIL Mini Pack No.4 5 pc-pack	76942	78
KONOE NAIL Mini Pack No.5 5 pc-pack	76943	78
KONOE NAIL No.01 100 pc-pack	76986	78
KONOE NAIL No.1 50 pc-pack	76987	78
KONOE NAIL No.2 20 pc-pack	76989	78
KONOE NAIL No.3 20 pc-pack	76990	78
KONOE NAIL No.4 10 pc-pack	76991	78
KONOE NAIL No.5 10 pc-pack	76992	78

L

Description	Item Code	Page
Large Caliper 1 m	63592	23
Large Caliper 30 cm	63509	23
Large Caliper 35 cm	63517	23
Large Caliper 45 cm	63525	23
Large Caliper 60 cm	63541	23
Large Caliper 75 cm	63568	23
Large Inspection Mirror C-1 1.2 m Oval 80 x 120 mm	75796	157
Large Inspection Mirror C-2 2.5 m Oval 120 x 150 mm	75797	157
Large Square Hard Chrome Finish 1 m x 60 cm	63400	20
Large Square Hard Chrome Finish 60 x 30 cm	63402	21
Large Square Polish Finish 1 m x 60 cm	63118	20
Large Square Polish Finish 1 m x 60 cm with 8 Scales	63122	20
Large Square Polish Finish 1 m/3 shaku 3 sun	63094	20
Large Square Polish Finish 2 x 1 shaku	63411	21
Large Square Polish Finish 3 shaku 3 sun x 2 shaku	63128	20
Large Square Polish Finish 60 cm/2 shaku	63412	21
Large Square Polish Finish 60 x 30 cm	63410	21
Large Square Polish Finish 60 x 30 cm with 8 Scales	63413	21
Large Square Rigid Polish Finish 1 m x 60 cm	63099	20
Large Square Rigid Polish Finish 60 x 30 cm	63053	21
Large Squire with Brace Polish Finish 1 m x 60 cm	63121	21
Laser Beam Level II 300 mm	76164	93
Laser Beam Level II 450 mm	76166	93
Laser Beam Level II with Magnet 300 mm	76165	93
Laser Beam Level II with Magnet 450 mm	76167	93
Laser Holder for Light Weight Steel Framing with Rising/Lowering Motion	76923	111
Laser Range Finder L-Measure30 Metric/Shaku	78190	111
Laser Range Finder L-Measure40 II Metric/Shaku	78174	111
Laser Receiver II for Laser ROBO Green with Holder	77399	110
Laser Receiver II Plus for Laser ROBO Green with Holder	71501	110
Laser Receiver II Plus with Holder	71500	110
Laser Receiver II with Holder	77398	110
Laser ROBO Fine 21 BRIGHT	77465	109
Laser ROBO Fine 31 BRIGHT	77466	109

Laser ROBO Fine 3C1	77096	109
Laser ROBO Fine 41 BRIGHT	77467	109
Laser ROBO Green Neo 21 AR BRIGHT	78277	104
Laser ROBO Green Neo 21 AR BRIGHT with Receiver and Tripod	78287	104
Laser ROBO Green Neo 21 BRIGHT	78274	106
Laser ROBO Green Neo 21 BRIGHT with Receiver and Tripod	78284	106
Laser ROBO Green Neo 21P BRIGHT	78273	106
Laser ROBO Green Neo 21P BRIGHT with Receiver and Tripod	78283	106
Laser ROBO Green Neo 31 AR BRIGHT	78278	104
Laser ROBO Green Neo 31 AR BRIGHT with Receiver and Tripod	78288	104
Laser ROBO Green Neo 31 BRIGHT	78275	106
Laser ROBO Green Neo 31 BRIGHT with Receiver and Tripod	78285	106
Laser ROBO Green Neo 41 BRIGHT	78271	106
Laser ROBO Green Neo 41 BRIGHT with Receiver and Tripod	78291	106
Laser ROBO Green Neo 51 AR BRIGHT	78279	104
Laser ROBO Green Neo 51 AR BRIGHT with Receiver and Tripod	78289	104
Laser ROBO Green Neo 51 BRIGHT	78276	106
Laser ROBO Green Neo 51 BRIGHT with Receiver and Tripod	78286	106
Laser ROBO Green Neo E Sensor 21	71602	100
Laser ROBO Green Neo E Sensor 21 with Receiver and Tripod	71612	100
Laser ROBO Green Neo E Sensor 31	71603	100
Laser ROBO Green Neo E Sensor 31 with Receiver and Tripod	71613	100
Laser ROBO Green Neo E Sensor 51	71605	100
Laser ROBO Green Neo E Sensor 51 AR	71606	100
Laser ROBO Green Neo E Sensor 51 AR with Receiver and Tripod	71616	100
Laser ROBO Green Neo E Sensor 51 with Receiver and Tripod	71615	100
Laser ROBO Neo 01 AR BRIGHT	77507	105
Laser ROBO Neo 01 AR BRIGHT with Receiver and Tripod	78218	105
Laser ROBO Neo 01 BRIGHT	77388	107
Laser ROBO Neo 11P BRIGHT	77389	107
Laser ROBO Neo 21 AR BRIGHT	77508	105
Laser ROBO Neo 21 AR BRIGHT with Receiver and Tripod	78219	105
Laser ROBO Neo 21 BRIGHT	77354	107
Laser ROBO Neo 21 BRIGHT with Receiver and Tripod	77605	107
Laser ROBO Neo 21 E Sensor	71502	101
Laser ROBO Neo 21 E Sensor with Receiver and Tripod	71512	101
Laser ROBO Neo 21P BRIGHT	77355	107
Laser ROBO Neo 21P BRIGHT with Receiver and Tripod	77606	107
Laser ROBO Neo 31 AR BRIGHT	78240	105
Laser ROBO Neo 31 AR BRIGHT with Receiver and Tripod	78243	105
Laser ROBO Neo 31 BRIGHT	77360	107
Laser ROBO Neo 31 BRIGHT with Receiver and Tripod	77608	107
Laser ROBO Neo 31 E Sensor	71503	101
Laser ROBO Neo 31 E Sensor with Receiver and Tripod	71513	101
Laser ROBO Neo 41 BRIGHT	77361	107
Laser ROBO Neo 41 BRIGHT with Receiver and Tripod	77609	107
Laser ROBO Neo 51 AR BRIGHT	78241	105
Laser ROBO Neo 51 AR BRIGHT with Receiver and Tripod	78244	105
Laser ROBO Neo 51 AR E Sensor	71506	101
Laser ROBO Neo 51 AR E Sensor with Receiver and Tripod	71516	101
Laser ROBO Neo 51 BRIGHT	77362	107
Laser ROBO Neo 51 BRIGHT with Receiver and Tripod	77625	107
Laser ROBO Neo 51 E Sensor	71505	101
Laser ROBO Neo 51 E Sensor with Receiver and Tripod	71515	101

Parts List	Japan Calibration Service System (JCS)	Etching	Sheet Heaters	Custom-Made Items	Name Printing	Index Description ➡ Item Code	Index Description ➡ Item Code
------------	--	---------	---------------	-------------------	---------------	-------------------------------	-------------------------------

Laser ROBO X line Green	71608	97
Laser ROBO X line Green with Receiver and Tripod	71618	97
Laser ROBO X line Red	71607	97
Laser ROBO X line Red with Receiver and Tripod	71617	97
Laser ROBO X line-E Green	71610	97
Laser ROBO X line-E Green with Receiver and Tripod	71620	97
Laser ROBO X line-E Red	71609	97
Laser ROBO X line-E Red with Receiver and Tripod	71619	97
Laser Safety Glasses	76793	110
Level adjustment tripod adapter for Laser ROBO Fine BRIGHT	76924	217
Level adjustment tripod adapter for Laser ROBO Neo, E Sensor and X line	76768	217
Level for Square	76503	91
Leveling Line Pink 3 mm 30 m	78564	79
Leveling Line Yellow 3 mm 30 m	78563	79
Light bulb for Magnifier with Light for Reading E and F	76507	222
Lock button for Telescopic Leveling Staff	76963	216
Lock button for Telescopic Leveling Staff II	73269	216
Log Scriber	77590	150
Lower cap, screw set for Telescopic Measure One Direction	82049	214
Lower fixing screw, spacer, spring set for Wind-resistant Plumb	77559	218
Lower protective cap for L-Angle Plus	93312	219
Lux Meter	78604	184

M

Description	Item Code	Page
Machine Scale 100 mm Lower-central Reference Point	14160	36
Machine Scale 100 mm Lower-left Reference Point	14147	36
Machine Scale 100 mm Lower-right Reference Point	14154	36
Machine Scale 100 mm Upper-central Reference Point	14141	36
Machine Scale 100 mm Upper-left Reference Point	14128	36
Machine Scale 100 mm Upper-right Reference Point	14135	36
Machine Scale 150 mm Lower-left Reference Point	14148	36
Machine Scale 150 mm Lower-right Reference Point	14155	36
Machine Scale 150 mm Upper-left Reference Point	14129	36
Machine Scale 150 mm Upper-right Reference Point	14136	36
Machine Scale 200 mm Lower-central Reference Point	14161	36
Machine Scale 200 mm Lower-left Reference Point	14149	36
Machine Scale 200 mm Lower-right Reference Point	14156	36
Machine Scale 200 mm Upper-central Reference Point	14142	36
Machine Scale 200 mm Upper-left Reference Point	14130	36
Machine Scale 200 mm Upper-right Reference Point	14137	36
Machine Scale 300 mm Lower-central Reference Point	14162	36
Machine Scale 300 mm Lower-left Reference Point	14150	36
Machine Scale 300 mm Lower-right Reference Point	14157	36
Machine Scale 300 mm Upper-central Reference Point	14143	36
Machine Scale 300 mm Upper-left Reference Point	14131	36
Machine Scale 300 mm Upper-right Reference Point	14138	36
Machine Scale 50 mm Lower-left Reference Point	14146	36
Machine Scale 50 mm Lower-right Reference Point	14153	36
Machine Scale 50 mm Upper-left Reference Point	14127	36
Machine Scale 50 mm Upper-right Reference Point	14134	36
Machine Scale 500 mm Lower-central Reference Point	14163	36
Machine Scale 500 mm Lower-left Reference Point	14151	36
Machine Scale 500 mm Lower-right Reference Point	14158	36

Machine Scale 500 mm Upper-central Reference Point	14144	36
Machine Scale 500 mm Upper-left Reference Point	14132	36
Machine Scale 500 mm Upper-right Reference Point	14139	36
Magnet for Welding Guide Rule	83525	221
Magnet Stick Pair of Circle A	73514	211
Magnet Stick Pair of Square B	73515	211
Magnetic Bar 25 cm Blue	72034	211
Magnetic Bar 25 cm Red	72033	211
Magnetic Bar 25 cm Yellow	72035	211
Magnetic Chips Circle A-1 φ 10 6 pc-pack	72150	206
Magnetic Chips Circle A-2 φ 15 6 pc-pack	72151	206
Magnetic Chips Circle A-3 φ 20 3 pc-pack	72152	206
Magnetic Chips Circle A-4 φ 25 2 pc-pack	72219	206
Magnetic Chips Circle A-5 φ 30 2 pc-pack	72220	206
Magnetic Chips Square B-1 15 x 16 mm 3 pc-pack	72153	206
Magnetic Chips Square B-2 15 x 20 mm 2 pc-pack	72154	206
Magnetic Chips Square B-3 19 x 25 mm 2 pc-pack	72155	206
Magnetic Chips Square B-4 10.5 x 30 mm 2 pc-pack	72156	206
Magnetic Chips Square B-5 20 x 30 mm 2 pc-pack	72221	206
Magnetic Chips Square with Yoke E-1 13 x 22 mm 2 pc-pack	73501	206
Magnetic Chips Square with Yoke E-2 23 x 26 mm 2 pc-pack	73502	206
Magnetic Chips Square with Yoke E-3 30 x 44 mm 2 pc-pack	73503	206
Magnetic Clip Square B Small	72040	209
Magnetic Clip Square C Large	72041	209
Magnetic Clips Circle A Blue 2 pc-pack	72037	209
Magnetic Clips Circle A Green 2 pc-pack	72036	209
Magnetic Clips Circle A Red 2 pc-pack	72039	209
Magnetic Clips Circle A Yellow 2 pc-pack	72038	209
Magnetic Clips Flexible D White 2 pc-pack	72126	210
Magnetic Hanger Square B Blue	72085	210
Magnetic Hanger Square B Red	72084	210
Magnetic Hanger Square B Yellow	72032	210
Magnetic Holder 38 cm	72008	205
Magnetic Pick-up Tool Flexible with Light and Mirror H-6	73516	205
Magnetic Pick-up Tool Flexible with Light H-5	73511	205
Magnetic Pick-up Tool H-2	72290	205
Magnetic Pick-up Tool H-3	72291	205
Magnetic Pick-up Tool with Light H-4	72456	205
Magnetic Sheet 10 x 20 cm 1.2 mm Thick with Adhesive 10 x 20 cm	72009	212
Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Blue	72046	212
Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Green	72045	212
Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Red	72042	212
Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A White	72043	212
Magnetic Sheet Gloss 10 x 20 cm 0.8 mm Thick A Yellow	72044	212
Magnetic Sheet Mat 10 cm x 10 m 0.8 mm Thick Blue Roll	74016	213
Magnetic Sheet Mat 10 cm x 10 m 0.8 mm Thick Red Roll	74015	213
Magnetic Sheet Mat 10 cm x 10 m 0.8 mm Thick White Roll	72215	213
Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Blue	72051	212
Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Green	72050	212
Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Red	72047	212
Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B White	72048	212
Magnetic Sheet Mat 10 x 30 cm 0.8 mm Thick B Yellow	72049	212
Magnetic Sheet Piece 10 x 20 mm 0.8 mm Thick with Adhesive C-1 100 pc-pack	72182	212
Magnetic Stand A Standard	73752	157

Magnetic Stand A-2 Fine Adjustment	73753	157
Magnifier for Reading with Light E 50 mm 3x	75761	190
Magnifier for Reading with Light E-3 28 mm 10x	75708	190
Magnifier for Reading with Light F 65 mm 3x	75762	190
Magnifying Mirror B-1 Circle 60 mm 2x	75790	158
Magnifying Mirror B-2 Circle 36 mm 2x	75791	158
Magnifying Mirror B-3 Oval 50 x 80 mm 2x	75788	158
Magnifying Mirror B-4 Oval 25 x 50 mm 2x	75789	158
Main Block for Screw Pitch Marking Tool 100	77392	122
Main Block for Screw Pitch Marking Tool 150	77393	122
Main Block for Screw Pitch Marking Tool Multi	77320	122
Map Measure C Keyring Model	71310	188
Map Measure D Multi-function Model	71320	188
Marking Crayon Pencil Type Black 3 pc-pack	78435	130
Marking Crayon Pencil Type Red 3 pc-pack	78440	130
Marking Crayon Pencil Type White 3 pc-pack	78443	130
Marking Crayon Pencil Type Yellow 3 pc-pack	78442	130
Marking Crayon Retractable 4.0 mm Black	78445	128
Marking Crayon Retractable 4.0 mm Pink	78449	128
Marking Crayon Retractable 4.0 mm Red	78446	128
Marking Crayon Retractable 4.0 mm White	78448	128
Marking Crayon Retractable 4.0 mm Yellow	78447	128
Marking Crayon Retractable 7.0 mm Black	78463	127
Marking Crayon Retractable 7.0 mm Red	78464	127
Marking Crayon Retractable 7.0 mm White	78465	127
Marking Mechanical Pencil 2.0 mm Black	78470	128
Marking Mechanical Pencil 2.0 mm Red	78471	128
Marking Mechanical Pencil 2.0 mm White	78472	128
Marking Mechanical Pencil Type 2.0 mm 2H	78511	129
Marking Mechanical Pencil Type 2.0 mm HB	78507	129
Marking Pencil PRO 2B 3 pc-pack	78520	129
Marking Pencil PRO 2H 3 pc-pack	78517	129
Marking Pencil PRO 4H 3 pc-pack	78524	129
Marking Pencil PRO H 3 pc-pack	78518	129
Marking Pencil PRO HB 3 pc-pack	78519	129
Marking Pencil PRO Red Hard 3 pc-pack	78521	129
Marking Pencil PRO Red Soft 3 pc-pack	78523	129
Marking Tape 15 mm x 50 m Blue	74164	79
Marking Tape 15 mm x 50 m Orange	74163	79
Marking Tape 15 mm x 50 m Pink	74161	79
Marking Tape 15 mm x 50 m Yellow	74162	79
Marking Tape 30 mm x 100 m Pink	73865	79
Marking Tape 30 mm x 50 m Blue	74125	79
Marking Tape 30 mm x 50 m Orange	73800	79
Marking Tape 30 mm x 50 m Pink	73798	79
Marking Tape 30 mm x 50 m Yellow	73799	79
Maximum and Minimum Digital Thermometer D-10 Waterproof	73043	171
Maximum and Minimum Thermometer D-7	72709	176
Maximum and Minimum Thermometer D-9	72715	176
Measuring Instrument Set for Steel Fabrication 5 Items	97575	149
Measuring Instrument Set for Steel Fabrication 7 Items	97794	149
Measuring Wheel E10-S	75421	68
Measuring Wheel E20-S	75422	68
Mechanical Drawing Pencil 0.5 mm	77798	203

Metal Case for Stick Thermometer for 15 cm	72731	179
Metal Case for Stick Thermometer for 30 cm	72729	179
Metal Stud Finder Mini	78674	146
Metallic Hourglass for 3-minute	70304	185
Micrometer 0 - 25 mm	78935	58
Micrometer 0 - 25 mm with JCSS Certificate	19080	224
Micrometer 25 - 50 mm	78936	58
Micrometer 25 - 50 mm with JCSS Certificate	19081	224
Mini Level A Circular Model	76037	91
Mini Level D Flat Model	76046	91
Mini Level H Cube Model	76060	91
Mini Level Revo Clear Cube Model	76387	90
Mini Level Revo for Rule and Square	76417	90
Mini Level Revo Keyring Model	76423	90
Mini Level Revo Lineclip Model	76416	90
Mini Level Revo T-shaped Model	76418	90
Mini Telescopic Leveling Staff 2 m 2 Steps	76863	65
Mini Telescopic Leveling Staff 3 m 3 Steps	76900	65
Mini Try Square Brass Base 4.5 cm	62020	50
Mini Try Square Brass Base 6 cm	62021	50
Mini Try Square Brass Base 7.5 cm	62022	50
Mini Try Square Brass Base 9 cm	62023	50
Mini Vernier Caliper 100 mm	19894	54
Mini Vernier Caliper 100 mm with JCSS Certificate	19055	224
Mini Vernier Caliper 70 mm	19892	54
Mini Vernier Caliper 70 mm with JCSS Certificate	19054	224
Mirror with frame for Inspection Mirror A-1 and D-1	84171	221
Mirror with frame for Inspection Mirror A-2 and D-2	78946	221
Mirror with frame for Inspection Mirror A-3 and D-3	70720	221
Mirror with frame for Inspection Mirror A-4 and D-4	84159	221
Mirror with frame for Large Inspection Mirror C-1	84116	221
Mirror with frame for Large Inspection Mirror C-2	84117	221
Mirror with frame for Magnifying Glass B-1	84160	221
Mirror with frame for Magnifying Glass B-2	84161	221
Mirror with frame for Magnifying Glass B-3	84162	221
Mirror with frame for Magnifying Glass B-4	84163	221
Miter Rule 3D 45° 90° Aluminum	62113	47
Miter Rule 3D 45° 90° Polycarbonate	62112	47
Miter Rule 3D 45° Aluminum	62114	48
Miter Rule 45° 90° Standard Model	62081	46
Miter Rule 45° 90° Standard Model S-1462 Inch Graduations	32674	46
Miter Rule 45° 90° with 40 mm Wide Fence	62189	46
Miter Rule 45° Standard Model	62103	47
Miter Rule 45° with 40 mm Wide Fence	62162	47
Miter Rule 45° with Graduations	62060	47
Miter Rule 45° with Right Angle	62110	47
Miter Try Square 20 cm	62286	50
Miter Try Square 25 cm	62294	50
Miter Try Square 30 cm	62308	50
Miter Try Square S-1421 20 cm/8"	32255	50
Miter Try Square S-1422 25 cm/10"	32263	50
Miter Try Square S-1423 30 cm/12"	32271	50
Molding Rule 1 m 10/1000	17078	34
Molding Rule 1 m 11/1000	17353	34

Parts List	Molding Rule 1 m 12/1000	17086	34	Molding Rule 2 m 14/1000	18546	34
	Molding Rule 1 m 13/1000	17094	34	Molding Rule 2 m 15/1000	18554	34
	Molding Rule 1 m 14/1000	17108	34	Molding Rule 2 m 16/1000	18562	34
Japan Calibration Service System (JCS)	Molding Rule 1 m 15/1000	17116	34	Molding Rule 2 m 17/1000	18570	34
	Molding Rule 1 m 16/1000	17124	34	Molding Rule 2 m 18/1000	18589	34
	Molding Rule 1 m 17/1000	17132	34	Molding Rule 2 m 19/1000	18597	34
Etching	Molding Rule 1 m 18/1000	17140	34	Molding Rule 2 m 2/1000	18500	34
	Molding Rule 1 m 19/1000	17159	34	Molding Rule 2 m 20/1000	18600	34
	Molding Rule 1 m 2/1000	17001	34	Molding Rule 2 m 22/1000	18619	34
Sheet Heaters	Molding Rule 1 m 20/1000	17167	34	Molding Rule 2 m 23/1000	65204	34
	Molding Rule 1 m 21/1000	17361	34	Molding Rule 2 m 24/1000	15380	34
	Molding Rule 1 m 22/1000	17175	34	Molding Rule 2 m 25/1000	18627	34
Custom-Made Items	Molding Rule 1 m 23/1000	17183	34	Molding Rule 2 m 27/1000	14945	34
	Molding Rule 1 m 24/1000	17191	34	Molding Rule 2 m 28/1000	65205	34
	Molding Rule 1 m 25/1000	17205	34	Molding Rule 2 m 3/1000	14050	34
Name Printing	Molding Rule 1 m 27/1000	17221	34	Molding Rule 2 m 30/1000	18635	34
	Molding Rule 1 m 28/1000	17248	34	Molding Rule 2 m 5/1000	73879	34
	Molding Rule 1 m 29/1000	75416	34	Molding Rule 2 m 7/1000	83803	34
Index Item Code ➡ Description	Molding Rule 1 m 3/1000	17345	34	Molding Rule 2 m 8/1000	18503	34
	Molding Rule 1 m 30/1000	17256	34	Molding Rule 2 m 9/1000	18686	34
	Molding Rule 1 m 4/1000	17000	34	Molding Rule 30 cm 10/1000	15067	34
Index Description ➡ Item Code	Molding Rule 1 m 5/1000	17019	34	Molding Rule 30 cm 11/1000	15261	34
	Molding Rule 1 m 6/1000	17027	34	Molding Rule 30 cm 12/1000	15075	34
	Molding Rule 1 m 7/1000	17035	34	Molding Rule 30 cm 13/1000	15083	34
	Molding Rule 1 m 8/1000	17043	34	Molding Rule 30 cm 14/1000	15091	34
	Molding Rule 1 m 9/1000	17051	34	Molding Rule 30 cm 15/1000	15105	34
	Molding Rule 15 cm 1/1000	81738	34	Molding Rule 30 cm 16/1000	15113	34
	Molding Rule 15 cm 10/1000	18015	34	Molding Rule 30 cm 17/1000	15121	34
	Molding Rule 15 cm 11/1000	19005	34	Molding Rule 30 cm 18/1000	15148	34
	Molding Rule 15 cm 12/1000	18023	34	Molding Rule 30 cm 19/1000	15334	34
	Molding Rule 15 cm 13/1000	18024	34	Molding Rule 30 cm 2/1000	15000	34
	Molding Rule 15 cm 14/1000	81657	34	Molding Rule 30 cm 20/1000	15156	34
	Molding Rule 15 cm 15/1000	18031	34	Molding Rule 30 cm 21/1000	15288	34
	Molding Rule 15 cm 16/1000	19006	34	Molding Rule 30 cm 22/1000	15164	34
	Molding Rule 15 cm 17/1000	14938	34	Molding Rule 30 cm 23/1000	15172	34
	Molding Rule 15 cm 18/1000	14939	34	Molding Rule 30 cm 24/1000	15180	34
	Molding Rule 15 cm 19/1000	67845	34	Molding Rule 30 cm 25/1000	15199	34
	Molding Rule 15 cm 2/1000	46800	34	Molding Rule 30 cm 26/1000	15202	34
	Molding Rule 15 cm 20/1000	18058	34	Molding Rule 30 cm 27/1000	15210	34
	Molding Rule 15 cm 22/1000	18066	34	Molding Rule 30 cm 28/1000	15229	34
	Molding Rule 15 cm 23/1000	77785	34	Molding Rule 30 cm 29/1000	18090	34
	Molding Rule 15 cm 24/1000	77196	34	Molding Rule 30 cm 3/1000	15296	34
	Molding Rule 15 cm 25/1000	18074	34	Molding Rule 30 cm 30/1000	15237	34
	Molding Rule 15 cm 27/1000	14950	34	Molding Rule 30 cm 4/1000	15008	34
	Molding Rule 15 cm 28/1000	77673	34	Molding Rule 30 cm 5/1000	15016	34
	Molding Rule 15 cm 30/1000	18082	34	Molding Rule 30 cm 6/1000	15024	34
	Molding Rule 15 cm 4/1000	18003	34	Molding Rule 30 cm 7/1000	15032	34
	Molding Rule 15 cm 5/1000	18004	34	Molding Rule 30 cm 8/1000	15040	34
	Molding Rule 15 cm 6/1000	14932	34	Molding Rule 30 cm 9/1000	15059	34
	Molding Rule 15 cm 8/1000	18007	34	Molding Rule 60 cm 1/1000	81737	34
	Molding Rule 2 m 10/1000	18511	34	Molding Rule 60 cm 10/1000	16063	34
	Molding Rule 2 m 11/1000	18499	34	Molding Rule 60 cm 11/1000	16365	34
	Molding Rule 2 m 12/1000	18538	34	Molding Rule 60 cm 12/1000	16071	34
	Molding Rule 2 m 13/1000	18678	34	Molding Rule 60 cm 13/1000	16098	34

Molding Rule 60 cm 14/1000	16101	34
Molding Rule 60 cm 15/1000	16128	34
Molding Rule 60 cm 16/1000	16136	34
Molding Rule 60 cm 17/1000	16144	34
Molding Rule 60 cm 18/1000	16152	34
Molding Rule 60 cm 19/1000	16160	34
Molding Rule 60 cm 2/1000	16000	34
Molding Rule 60 cm 20/1000	16179	34
Molding Rule 60 cm 21/1000	16373	34
Molding Rule 60 cm 22/1000	16187	34
Molding Rule 60 cm 23/1000	16195	34
Molding Rule 60 cm 24/1000	16209	34
Molding Rule 60 cm 25/1000	16217	34
Molding Rule 60 cm 26/1000	16225	34
Molding Rule 60 cm 27/1000	16233	34
Molding Rule 60 cm 28/1000	16241	34
Molding Rule 60 cm 29/1000	14900	34
Molding Rule 60 cm 3/1000	16381	34
Molding Rule 60 cm 30/1000	16268	34
Molding Rule 60 cm 4/1000	16004	34
Molding Rule 60 cm 5/1000	16012	34
Molding Rule 60 cm 6/1000	16020	34
Molding Rule 60 cm 7/1000	16039	34
Molding Rule 60 cm 8/1000	16047	34
Molding Rule 60 cm 9/1000	16055	34
Motorized Handy Ink Line Marker Black	77480	117
Mounting part A for I-Clamp One-touch	99241	220
Mounting part B, screw set for I-Clamp One-touch	99244	220
Mounting position adjustment screw for T-Slide II and Double	47359	220
Mounting position adjustment screw for T-Slide Slim-shift	47386	220

N

Description	Item Code	Page
Needle pin 2 pc-pack for Digital Moisture Meter for Wood	96061	221
Non-slip pad for Aluminum Rule 30 - 60 cm, 1 m	84270	214
Non-slip rubber for Aluminum Cutting Rule	73930	214
Non-slip rubber sheet for Aluminum Cutting Rule EX 1.5 m, 2 m	82650	214
Non-slip rubber sheet for Aluminum Cutting Rule EX 60 cm, 1 m	80741	214
Non-slip rubber triangle for Mini Free Angle II, L-Angle II and EX	83464	219
Nut for Aluminum Sliding Bevel and Welding Guide Rule	62546	215
Nut, center screw set for Japanese Sliding Bevel	99559	215
Nut, center screw set for Protractor No.101	99507	215
Nut, washer set for Protractor No.19	99505	215
Nut, washer, brass washer set for Protractor No.30	99506	215

O

Description	Item Code	Page
Oil-based Marking Pen Fine Bullet-tip Black	78424	127
Oil-based Marking Pen Fine Bullet-tip Red	78429	127
Oil-based Marking Pen Fine Chisel-tip Black	78430	127
Oil-based Marking Pen Fine Chisel-tip Red	78431	127
Oil-filled Compass C Roman Alphabet	75590	187
Oil-filled Compass C-2 Japanese	75592	187
Oil-filled Compass for Military F	75620	187

Oil-filled Compass for Orienteering E	75612	187
Oil-filled Compass for Orienteering E-2 Round	75614	187
Oil-filled Wood Compass Japanese J	75662	188
1 additional measuring point	84058	224
One-side Caliper A 15 cm	73250	152
One-touch Holder for Measuring Tape	80825	62
Ornament Carpenter's Square Gold and Silver with Frame	98760	24
Outside Caliper A 15 cm	73318	153
Outside Caliper B 20 cm	73326	153
Outside Caliper with Spring OC-10 25 cm	33960	153
Outside Caliper with Spring OC-12 30 cm	33961	153
Outside Caliper with Spring OC-6 15 cm	33958	153
Outside Caliper with Spring OC-8 20 cm	33959	153

P

Description	Item Code	Page
Paint Marker Fine Bullet-tip Black	78414	126
Paint Marker Fine Bullet-tip Blue	78515	126
Paint Marker Fine Bullet-tip Gold	78420	126
Paint Marker Fine Bullet-tip Pink	78419	126
Paint Marker Fine Bullet-tip Red	78415	126
Paint Marker Fine Bullet-tip Silver	78516	126
Paint Marker Fine Bullet-tip White	78418	126
Paint Marker Fine Bullet-tip Yellow	78416	126
Paint Marker Wide Bullet-tip Black	78541	126
Paint Marker Wide Bullet-tip Pink	78548	126
Paint Marker Wide Bullet-tip Red	78542	126
Paint Marker Wide Bullet-tip White	78547	126
Pedometer Q Black	74132	186
Pedometer Q White	74133	186
Pickup Rule Hard Chrome Finish 1 m with JCSS Certificate	19025	224
Pickup Rule Hard Chrome Finish 10 cm with JCSS Certificate	19012	224
Pickup Rule Hard Chrome Finish 15 cm with JCSS Certificate	19022	224
Pickup Rule Hard Chrome Finish 30 cm with JCSS Certificate	19023	224
Pickup Rule Hard Chrome Finish 60 cm with JCSS Certificate	19024	224
Pin cover for Handy Plumb Holder Jr.	78094	219
Pin cover for Handy Plumb Holder Pro Auto-rewind Red	77926	218
Pin cover for Handy Plumb Holder Pro Hand-rewind Blue	77959	218
Pitch Gauge for Inch Screw Thread 26 Leaves A-2	73794	155
Pitch Gauge for Metric Screw Thread 28 Leaves B-2	73795	155
Plastic case for Dial Gauge	81369	221
Plastic case for Dial Indicator	81374	221
Plastic cover for Scale 2 kg - 12 kg	70144	216
Plastic cover for Scale 20 kg	70145	216
Plastic cover for Scale 200 g - 1 kg	70143	216
Plastic cover for Scale 30 kg	70146	216
Plastic cover for Scale 50 kg	81521	216
Plastic end A with hook, nut, screw set for Telescopic Measure One Direction II	81100	214
Plastic end B, nut, screw set for Telescopic Measure One Direction II	81101	214
Plastic plate for Digital Scale	70121	216
Plastic Thermometer 20 cm Blue	48351	168
Plastic Thermometer 20 cm Yellow	48352	168
Plastic Thermometer 25 cm Blue	48356	168
Plastic Thermometer 25 cm Yellow	48357	168

Parts List	Plastic Thermometer 30 cm Blue	48361	168
	Plastic Thermometer 30 cm Yellow	48362	168
	Plastic washer for Aluminum Sliding Bevel and Welding Guide Rule	62547	215
	Plate fixing screw one pair (2 pc-set) for Scale 200 g - 30 kg	70131	216
Japan Calibration Service System (JCSS)	Plate flat type for Scale 2 kg - 12 kg	70129	216
	Plate flat type for Scale 20 kg	70139	216
	Plate flat type for Scale 200 g - 1 kg	70128	216
	Plate flat type for Scale 30 kg	70140	216
Etching	Plumb Bob 100 g with Damper	77974	124
	Plumb Bob 1000 g	77991	124
	Plumb Bob 150 g with Damper	77981	124
	Plumb Bob 200 g with Damper	77982	124
Sheet Heaters	Plumb Bob 300 g with Damper	77983	124
	Plumb Bob 400 g with Damper	77979	124
	Plumb Bob 600 g with Damper	77975	124
	Plumb Bob 800 g with Damper	77951	124
Custom-Made Items	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 1 m	76967	65
	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 1 m 2 Folded	76968	65
	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 30 cm	76964	65
	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 50 cm	76965	65
Name Printing	Plywood Leveling Rod 63 mm Wide with Aluminum Frame 70 cm	76966	65
	Pocket Magnifier N-1 65 x 45 mm 2.5x	75534	191
	Pocket Magnifier N-2 45 mm 3.5x	75535	191
	Pocket Magnifier N-3 65 mm 2x and 4x Double Focus	75536	191
Index Item Code ➡ Description	Pocket Microscope with LED Light H 60x - 100x	75753	193
	Pocket Vernier Caliper 100 mm	19518	54
	Polyester Leveling Line Reel 0.5 mm 500 m Green	78483	125
	Polyester Leveling Line Reel 0.5 mm 500 m Orange	78481	125
Index Item Code ➡ Description	Polyester Leveling Line Reel 0.5 mm 500 m Pink	78479	125
	Polyester Leveling Line Reel 0.5 mm 500 m Yellow	78477	125
	Polyester Leveling Line Reel 0.8 mm 270 m Green	78485	125
	Polyester Leveling Line Reel 0.8 mm 270 m Orange	78482	125
Index Item Code ➡ Description	Polyester Leveling Line Reel 0.8 mm 270 m Pink	78480	125
	Polyester Leveling Line Reel 0.8 mm 270 m Yellow	78478	125
	Polyester Leveling Line Reel 1.2 mm 120 m Pink	78499	125
	Polyester Leveling Line Reel 1.2 mm 120 m Yellow	78498	125
Index Item Code ➡ Description	Post for Magnetic Stand A and A-2	81375	221
	Post Level with Magnet	76339	91
	Precise I-Beam Level 1200 mm	76324	88
	Precise I-Beam Level 150 mm	76315	88
Index Item Code ➡ Description	Precise I-Beam Level 230 mm	76316	88
	Precise I-Beam Level 300 mm	76318	88
	Precise I-Beam Level 380 mm	76319	88
	Precise I-Beam Level 450 mm	76320	88
Index Item Code ➡ Description	Precise I-Beam Level 600 mm	76321	88
	Precise I-Beam Level 750 mm	76322	88
	Precise I-Beam Level 900 mm	76323	88
	Precise I-Beam Level with Magnet 150 mm	76308	88
Index Item Code ➡ Description	Precise I-Beam Level with Magnet 230 mm	76310	88
	Precise I-Beam Level with Magnet 300 mm	76301	88
	Precise I-Beam Level with Magnet 380 mm	76302	88
	Precise I-Beam Level with Magnet 450 mm	76303	88
Index Item Code ➡ Description	Precise I-Beam Level with Magnet 600 mm	76304	88
	Precise I-Beam Level with Magnet 750 mm	76305	88

Precise I-Beam Level with Magnet 900 mm	76306	88
Precision Stainless Steel Rule Hard Chrome Finish with JCSS Certificate 1 m	14115	33
Precision Stainless Steel Rule Hard Chrome Finish with JCSS Certificate 30 cm	14113	33
Precision Stainless Steel Rule Hard Chrome Finish with JCSS Certificate 60 cm	14114	33
Precision Work Magnifier T-3 Watchmaker's Loupe 23 mm 5x	75572	192
Precision Work Magnifier with Tweezer O-1 30 mm 4.5x	75537	192
Precision Work Magnifier X Attachment to Glasses 2.5x	75636	192
Profile Gauge A 150 mm	77970	150
Profile Gauge B 300 mm	77971	150
Profile Gauge C 200 mm	77984	150
Protective cap for Auto Level SA-24A and 28A	46804	217
Protective cap for Digital Moisture Meter for Wood	96063	221
Protractor Hard Chrome Finish Mini ϕ 40 10 cm	62995	51
Protractor Hard Chrome Finish No.1000 Double-blade ϕ 320 1 m	62952	51
Protractor Hard Chrome Finish No.1000 ϕ 320 1 m	62847	51
Protractor Hard Chrome Finish No.182 ϕ 90 10 cm	62901	51
Protractor Hard Chrome Finish No.183 Square 10 cm	62928	51
Protractor Hard Chrome Finish No.19 Double-blade ϕ 90 10 cm	62490	51
Protractor Hard Chrome Finish No.19 ϕ 90 10 cm	62480	51
Protractor Hard Chrome Finish No.30 ϕ 120	62774	51
Protractor Hard Chrome Finish No.300 Double-blade ϕ 210 30 cm	62839	51
Protractor Hard Chrome Finish No.300 ϕ 210 30 cm	62898	51
Protractor Hard Chrome Finish No.600 Double-blade ϕ 320 60 cm	62944	51
Protractor Hard Chrome Finish No.600 ϕ 320 60 cm	62855	51
Protractor Hard Chrome Finish with Groove No.101 ϕ 120 15 cm	62868	51
Protractor Polish Finish Mini ϕ 40 10 cm	62987	52
Protractor Polish Finish No.19 ϕ 90 10 cm	62499	52
Psychrometer E-2	72706	176

R

Description	Item Code	Page
Radius Scale A-1 R 0.5 - 7	73570	153
Radius Scale A-2 R 8 - 15	73571	153
Rafter Square 60 x 40 cm	64548	22
Ratchet ring for Handy Ink Marker SUMIWAZA and Mini α	77907	218
Reading Glass A-2 65 mm 2.5x	75509	189
Reading Glass A-3 65 mm 3x	75792	189
Reading Glass A-4 75 mm 2.5x	75793	189
Reading Glass A-5 100 mm 2x	75794	189
Reading Glass B-2 75 mm 2x	75517	189
Reading Glass B-3 75 mm 2x and 4x Double Focus	75520	189
Reading Glass B-4 100 mm 2x and 4x Double Focus	75521	189
Reading Glass with LED Light A-6 110 mm 2x and 4x	75751	190
Reading Glass with LED Light A-7 90 mm 2x and 4x	75755	190
Rear spring for Auto Punch L	73995	222
Rear spring for Auto Punch L with Flat Grip to Prevent Rolling	81318	222
Rear spring for Auto Punch M	73993	222
Rear spring for Auto Punch M with Flat Grip to Prevent Rolling	81314	222
Rebar Marker Blue 10 pc-pack	78534	79
Rebar Marker Green 10 pc-pack	78533	79
Rebar Marker Orange 10 pc-pack	78530	79
Rebar Marker Pink 10 pc-pack	78552	79
Rebar Marker Red 10 pc-pack	78529	79
Rebar Marker White 10 pc-pack	78532	79

Rebar Marker Yellow 10 pc-pack	78531	79
Receiver holder for Rotating Laser H-2, HV-2	83832	217
Refill for Marking Crayon Retractable 7.0 mm Black 2 pc-pack	78466	127
Refill for Marking Crayon Retractable 7.0 mm Red 2 pc-pack	78467	127
Refill for Marking Crayon Retractable 7.0 mm White 2 pc-pack	78469	127
Refill Lead for Marking Crayon Retractable 4.0 mm Black 4 pc-pack	78458	128
Refill Lead for Marking Crayon Retractable 4.0 mm Pink 4 pc-pack	78462	128
Refill Lead for Marking Crayon Retractable 4.0 mm Red 4 pc-pack	78459	128
Refill Lead for Marking Crayon Retractable 4.0 mm White 4 pc-pack	78461	128
Refill Lead for Marking Crayon Retractable 4.0 mm Yellow 4 pc-pack	78460	128
Reissue of JCSS Calibration Certificate, Private Examination Result	96106	224
Remote Probe Long and Thick Model ϕ 5.0 x 275 mm for Digital Thermometer H-2	73089	172
Remote Probe Standard Model ϕ 3.5 x 110 mm for Digital Thermometer H-2	73088	172
Remote Probe Surface Model ϕ 3.5 x 110 mm for H-2	73090	172
Remote Probe Thin Model ϕ 2.0 x 185 mm for Digital Thermometer H-2	73087	172
Replacement Anchor Pin 2 pc-pack for Thread Reel II	77453	120
Replacement Anchor Pin for Concrete	77433	121
Replacement Anchor Pin Mini Black 3 pc-pack	77452	121
Replacement Anchor Pin Mini Red 3 pc-pack	77880	121
Replacement Anchor Pin Red 3 pc-pack	77862	121
Replacement Belt 100/150 for Screw Pitch Marking Tool Multi	77323	122
Replacement Belt 200/250/300 for Screw Pitch Marking Tool Multi	77324	122
Replacement Blade 2 pc-pack for Deburring Tool S-10	78666	161
Replacement Cartridge for Oil-based Marking Pen Black 2 pc-pack	78432	127
Replacement Cartridge for Oil-based Marking Pen Red 2 pc-pack	78434	127
Replacement Cotton 3 pc-pack for Ink Line Marker Pro series	77848	121
Replacement Cotton for Screw Pitch Marking Tool 4 pc-pack	77397	122
Replacement Cotton for Screw Pitch Marking Tool Multi 2 pc-pack	77326	122
Replacement Felt 4 pc-pack for Chalk Line BIG	77578	121
Replacement Hook 3 pc-pack for Chalk Line	77932	121
Replacement lead for Drawing Divider	74458	222
Replacement Lead for Marking Mechanical Pencil 2.0 mm Black 6 pc-pack	78473	128
Replacement Lead for Marking Mechanical Pencil 2.0 mm Red 6 pc-pack	78474	128
Replacement Lead for Marking Mechanical Pencil 2.0 mm White 6 pc-pack	78475	128
Replacement Lead for Marking Mechanical Pencil Type 2.0 mm 2H 6 pc-pack	78508	129
Replacement Lead for Marking Mechanical Pencil Type 2.0 mm HB 6 pc-pack	78509	129
Replacement Lead for Screw Pitch Marking Tool 10 pc-pack	77396	122
Replacement Lens for for W-2 2.5x	75651	194
Replacement Lens for for W-2 3.0x	75652	194
Replacement Lens for W-2 1.5x	75650	194
Replacement Needle 10 pc-pack for Stud Finder Smart 25 mm	78594	145
Replacement Needle 10 pc-pack for Stud Finder Smart 35/45 mm	78595	145
Replacement Needle for Handy Plumb Holder Jr.	77504	124
Replacement Needle for Handy Plumb Holder Pro	77378	124
Replacement of Scribing Needle 1 pc for D	74468	151
Replacement of Scribing Needle 1 pc for E	74469	151
Replacement of Scribing Needle 2 pc-pack for C	78650	151
Replacement Safety Anchor Pin	77849	121
Replacement Safety Anchor Pin II	77486	121
Replacement Safety Anchor Pin with Magnet	77843	121
Replacement Scribing Ink Pencil 2 pc-pack for Log Scriber	77597	150
Replacement Sponge 2 pc-pack for Ink Line Marker Self Stop	77451	121
Replacement Sponge 3 pc-pack for Ink Line Marker Jr. series	77381	121
Replacement Sponge 3 pc-pack for Ink Line Marker Pro series	77484	121

Replacement Sponge 3 pc-pack for Ink Line Marker SUMIWAZA	77846	121
Replacement Sponge 3 pc-pack for Motorized Ink Line Marker and Jr. series	77485	121
Replacement Thread 15 m for Handy Plumb Holder	77598	124
Replacement Thread 3x Chalk Retentive ϕ 1.0 mm x 20 m for Chalk Line Marker	77562	121
Replacement Thread Super Thick 50 m for Chalk Line BIG	77577	121
Replacement Thread ϕ 0.4 mm x 20 m for Ink Line Marker Sharp Line	77882	121
Replacement Thread ϕ 0.5 mm x 20 m for Chalk Line Marker	77929	121
Replacement Thread ϕ 0.6 mm x 20 m for Ink Line Marker	77864	121
Replacement Thread ϕ 0.7 mm x 15 m for Ink Line Marker Tough Line	77879	121
Replacement Thread ϕ 0.8 mm x 15 m for Ink Line Marker	77594	121
Replacement Thread ϕ 1.0 mm x 20 m for Chalk Line Marker	77495	121
Rotating Laser HV-2	76496	112
Rotating Laser HV-2 with Tripod	76497	112
Rotating Table for Fine 3C	77099	110
Rotating Table for Laser Beam Level	76478	93
Round Shape Vial A ϕ 11 Clear 2 pc-pack	76328	91
Round Shape Vial B ϕ 16 Clear 2 pc-pack	76329	91
Round Shape Vial ϕ 11 Blue 2 pc-pack	76530	91
Round Shape Vial ϕ 16 Blue 2 pc-pack	76531	91
Route Interval Measuring Gauge 9 Leaves (4 - 12 mm)	97786	149
Rubber band for Wind-resistant Plumb	77553	218
Rubber cap for Shaku Measure, Ken Measure, Sumiki Shaku Measure	99553	214
Rubber Magnetic Sheet 10 cm x 10 m 0.8 mm Thick Black Roll	72086	213
Rubber wheel for Measuring Wheel B20-5	77199	216
Rule Stopper for 1 m Rule	76748	32
Rule Stopper for 1.5 and 2 m Rule	76749	32
Rule Stopper for 15 cm Rule	76745	32
Rule Stopper for 30 cm Rule	76746	32
Rule Stopper for 60 cm Rule	76747	32

S

Description	Item Code	Page
Safety Cord A	80890	147
Safety Cord B	80891	147
Salt Hydrometer	72718	181
Scale 100 kg	70008	82
Scale 50 kg	70026	82
Scale for Commercial Use 1 kg	70079	83
Scale for Commercial Use 12 kg	70090	83
Scale for Commercial Use 2 kg	70081	83
Scale for Commercial Use 20 kg	70093	83
Scale for Commercial Use 200 g	70123	83
Scale for Commercial Use 30 kg	70102	83
Scale for Commercial Use 4 kg	70084	83
Scale for Commercial Use 400 g	70124	83
Scale for Commercial Use 50 kg	70101	83
Scale for Commercial Use 8 kg	70087	83
Screw for Handy Chalk Line Neo	80665	218
Screw Pitch Marking Tool 100	77390	122
Screw Pitch Marking Tool 150	77391	122
Screw Pitch Marking Tool Multi 5-pitch Switch	77315	122
Scribing Needle A	78638	151
Scribing Needle B	78646	151
Scribing Needle C	78654	151

Parts List	
Japan Calibration Service System (JCS)	
Etching	
Sheet Heaters	
Custom-Made Items	
Name Printing	
Index Item Code ➡ Description	
Index Item Code ➡ Description	

Scribing Needle D	74444	151	Spring set (with string) for Handy Ink Line Marker Jr. Plus Tough Line	93288	218
Scribing Needle E	74445	151	Spring set (with string) for Handy Ink Line Marker PRO LITE	93300	218
Sensor probe for Digital Thermometer G and Wireless Thermometer A	73047	222	Spring set (with string) for Handy Ink Line Marker PRO Plus	93280	218
Shaku Measure 12 shaku	65132	42	Spring set (with string) for Handy Ink Line Marker PRO Plus Sharp Line	93297	218
Shaku Measure 13 shaku 5 sun	65133	42	Spring set (with string) for Handy Ink Line Marker PRO Plus Tough Line	93287	218
Sheet Magnifier U-2 3.5x Bookmark Size	75503	191	Spring Tape Measure 1.5 m	71005	63
Sheet Magnifier U-3 3.5x Card Size	75505	191	Stainless Pickup Rule Hard Chrome Finish 1 m	13140	30
Sheet Magnifier U-4 2x Pocket Notebook Size	75506	191	Stainless Pickup Rule Hard Chrome Finish 10 cm	13128	30
Sheet Magnifier U-5 2x A4 Size	75522	191	Stainless Pickup Rule Hard Chrome Finish 15 cm	13131	30
Shock-resistant Infrared Thermometer with Dual Laser Pointer G Emissivity Adjustable Model	73063	178	Stainless Pickup Rule Hard Chrome Finish 30 cm	13134	30
Side cap, screw set for Telescopic Measure Two Directions	81551	214	Stainless Pickup Rule Hard Chrome Finish 60 cm	13137	30
6-folding Stainless Steel Rule Polish Finish 1 m	63770	33	Stainless Steel Erasing Shield	70963	198
Slider for Circular Saw Guide with Groove	78236	132	Stainless Steel Mesh Erasing Shield	70961	198
Slider for T-Slide II	47364	220	Stainless steel plate for Digital Scale	70120	216
Slider for T-Slide Double	47365	220	Stainless steel plate for L-Angle 45 cm, II 45 cm and Adjust 45 cm	84020	219
Slider for T-Slide Slim-shift	47383	220	Stainless steel plate for L-Angle II 1 m, Adjust 1 m, EX 1 m and Plus 1 m	84287	219
Sliding Bevel SB-10 10"	33921	48	Stainless steel plate for L-Angle II 60 cm, Adjust 60 cm, EX 60 cm and Plus 60 cm	73877	219
Sliding Bevel SB-8 8"	33919	48	Stainless steel plate for L-Angle Adjust 1.2 m and Plus 1.2 m	93313	219
Slim Level with Magnet 200 mm White	76340	90	Stainless steel plate for L-Angle EX 45 cm and Plus 45 cm	85273	219
Slim Level with Magnet on Back Side 200 mm White	76332	90	Stainless steel plate for L-Angle Mini 15 cm and Fit 15 cm	80908	219
Slope Level 300 mm	76358	87	Stainless Steel Rafter Square Polish Finish S-1401 24" x 16"	32506	22
Slope Level 450 mm	76355	87	Stainless Steel Rule Hard Chrome Finish 1 m	13048	30
Slope Level 600 mm	76359	87	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 1 m	13498	32
Small Square Black 30 x 15 cm	12435	19	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 15 cm	13404	32
Small Square Black with Square Scale 30 x 15 cm	12416	19	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 30 cm	13463	32
Small Square Flat Polish Finish 30 x 15 cm	12325	19	Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 60 cm	13412	32
Small Square Flat Polish Finish with Square Scale 30 x 15 cm	12114	19	Stainless Steel Rule Hard Chrome Finish 1.5 m	13056	30
Small Square Grooved Polish Finish 30 x 15 cm	12130	19	Stainless Steel Rule Hard Chrome Finish 15 cm	13005	30
Small Square Grooved Polish Finish with Square Scale 30 x 15 cm	12017	19	Stainless Steel Rule Hard Chrome Finish 2 m	13064	30
Small Square Polish Finish 10 x 5 cm	12101	19	Stainless Steel Rule Hard Chrome Finish 3 m	13072	30
Small Square Polish Finish 15 x 7.5 cm	12103	19	Stainless Steel Rule Hard Chrome Finish 30 cm	13013	30
Small Square Polish Finish 3 x 1.5 sun	12102	19	Stainless Steel Rule Hard Chrome Finish 60 cm	13021	30
Small Square Polish Finish 5 x 2.5 sun	12104	19	Stainless Steel Rule Hard Chrome Finish H-101A 15 cm	21010	27
Small Square White with Square Scale 30 x 15 cm	12476	19	Stainless Steel Rule Hard Chrome Finish H-101C 30 cm	21085	27
Soil pH Meter A	72724	181	Stainless Steel Rule Hard Chrome Finish H-101E 60 cm	21028	27
Infrared Thermometer with Dual Laser Pointer E Emissivity Adjustable Model	73036	178	Stainless Steel Rule Hard Chrome Finish H-101F 1 m	21107	27
Infrared Thermometer with Probe D Emissivity Adjustable Model	73017	177	Stainless Steel Rule Hard Chrome Finish H-102G 1.5 m	21589	27
Spreading plate 2 pc-set for I-Clamp One-touch and Free Angle One-touch	99242	220	Stainless Steel Rule Hard Chrome Finish H-102H 2 m	21607	27
Spring for Stud Finder L	80620	220	Stainless Steel Rule Hard Chrome Finish H-102I 3 m	21566	27
Spring for Stud Finder L with Magnet	80697	220	Stainless Steel Rule Hard Chrome Finish H-201A 15 cm/6"	22004	27
Spring for Stud finder LL	80634	220	Stainless Steel Rule Hard Chrome Finish H-201C 30 cm/12"	22012	27
Spring Scale with Flat Scale Face 1 kg	74452	84	Stainless Steel Rule Hard Chrome Finish H-201E 60 cm/24"	22021	27
Spring Scale with Flat Scale Face 10 kg	74460	84	Stainless Steel Rule Hard Chrome Finish H-201F 1 m/36"	22039	27
Spring Scale with Flat Scale Face 15 kg	74499	84	Stainless Steel Rule Hard Chrome Finish H-3001A 6"/6" Rigid 4R	24540	29
Spring Scale with Flat Scale Face 2 kg	74453	84	Stainless Steel Rule Hard Chrome Finish H-3001C 12"/12" Rigid 4R	24548	29
Spring Scale with Flat Scale Face 20 kg	74461	84	Stainless Steel Rule Hard Chrome Finish H-301A 15 cm/6"	23001	27
Spring Scale with Flat Scale Face 30 kg	74487	84	Stainless Steel Rule Hard Chrome Finish H-301C 30 cm/12"	23021	27
Spring Scale with Flat Scale Face 5 kg	74459	84	Stainless Steel Rule Hard Chrome Finish H-301E 60 cm/24"	23029	27
Spring Scale with Flat Scale Face 50 kg	74488	84	Stainless Steel Rule Hard Chrome Finish H-301F 1 m/36"	23037	27
Spring Scale with Flat Scale Face 500 g	74451	84	Stainless Steel Rule Hard Chrome Finish H-302G 1.5 m/60"	23159	27
Spring Scale with Flat Scale Face 8 kg	74493	84	Stainless Steel Rule Hard Chrome Finish H-302H 2 m/78"	23167	27
Spring set (with string) for Handy Ink Line Marker Jr. LITE	93301	218	Stainless Steel Rule Hard Chrome Finish H-302I 3 m/118"	23175	27
Spring set (with string) for Handy Ink Line Marker Jr. Plus	93281	218	Stainless Steel Rule Hard Chrome Finish H-3101A 6"/6" Flexible 4R	24580	29
Spring set (with string) for Handy Ink Line Marker Jr. Plus Sharp Line	93298	218	Stainless Steel Rule Hard Chrome Finish H-3101C 12"/12" Flexible 4R	24591	29

Stainless Steel Rule Hard Chrome Finish H-3102A 6'/6" Flexible 5R	24621	29
Stainless Steel Rule Hard Chrome Finish H-3102C 12'/12" Flexible 5R	24629	29
Stainless Steel Rule Hard Chrome Finish H-3301A 6'/6" Flexible 3R	24737	29
Stainless Steel Rule Hard Chrome Finish H-3301C 12'/12" Flexible 3R	24742	29
Stainless Steel Rule Hard Chrome Finish H-3302A 6'/6" Rigid 3R	24777	29
Stainless Steel Rule Hard Chrome Finish H-3302C 12'/12" Rigid 3R	24785	29
Stainless Steel Rule Hard Chrome Finish H-3412A 6'/15 cm Rigid EM	30451	29
Stainless Steel Rule Hard Chrome Finish H-3412C 12'/30 cm Rigid EM	30459	29
Stainless Steel Rule Hard Chrome Finish H-401A 15 cm/6"	24007	28
Stainless Steel Rule Hard Chrome Finish H-401C 30 cm/12"	24015	28
Stainless Steel Rule Hard Chrome Finish H-401E 60 cm/24"	24023	28
Stainless Steel Rule Hard Chrome Finish H-401F 1 m/36"	24031	28
Stainless Steel Rule Hard Chrome Finish H-402G 1.5 m/60"	24252	28
Stainless Steel Rule Hard Chrome Finish H-402H 2 m/78"	24260	28
Stainless Steel Rule Hard Chrome Finish H-402I 3 m/118"	49099	28
Stainless Steel Rule Hard Chrome Finish Metric/Shaku 1 m Double-left Reference Point	13205	31
Stainless Steel Rule Hard Chrome Finish Metric/Shaku 1 m Right Reference Point	13210	31
Stainless Steel Rule Hard Chrome Finish Metric/Shaku 15 cm Double-left Reference Point	13202	31
Stainless Steel Rule Hard Chrome Finish Metric/Shaku 30 cm Double-left Reference Point	13203	31
Stainless Steel Rule Hard Chrome Finish Metric/Shaku 60 cm Double-left Reference Point	13204	31
Stainless Steel Rule Hard Chrome Finish with Magnet 1 m	13544	31
Stainless Steel Rule Hard Chrome Finish with Magnet 1 m with JCSS Certificate	83249	224
Stainless Steel Rule Hard Chrome Finish with Magnet 15 cm	13501	31
Stainless Steel Rule Hard Chrome Finish with Magnet 15 cm with JCSS Certificate	81741	224
Stainless Steel Rule Hard Chrome Finish with Magnet 30 cm	13528	31
Stainless Steel Rule Hard Chrome Finish with Magnet 30 cm with JCSS Certificate	80288	224
Stainless Steel Rule Hard Chrome Finish with Magnet 60 cm	13536	31
Stainless Steel Rule Hard Chrome Finish with Magnet 60 cm with JCSS Certificate	82826	224
Stainless Steel Rule Hard Chrome Finish with Stopper 15 cm	76751	32
Stainless Steel Rule Hard Chrome Finish with Stopper 30 cm	76752	32
Stainless Steel Rule Hard Chrome Finish 1 m Flex Rule 15 mm Wide with JCSS Certificate	19028	224
Stainless Steel Rule Hard Chrome Finish 1 m with JCSS Certificate	19017	224
Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 1 m with JCSS Certificate	50027	224
Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 15 cm with JCSS Certificate	47032	224
Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 30 cm with JCSS Certificate	81838	224
Stainless Steel Rule Hard Chrome Finish 1 mm Dividing 60 cm with JCSS Certificate	81476	224
Stainless Steel Rule Hard Chrome Finish 1.5 m Flex Rule 15 mm Wide with JCSS Certificate	19067	224
Stainless Steel Rule Hard Chrome Finish 1.5 m with JCSS Certificate	19063	224
Stainless Steel Rule Hard Chrome Finish 15 cm with JCSS Certificate	19014	224
Stainless Steel Rule Hard Chrome Finish 2 m Flex Rule 15 mm Wide with JCSS Certificate	19068	224
Stainless Steel Rule Hard Chrome Finish 2 m with JCSS Certificate	19064	224
Stainless Steel Rule Hard Chrome Finish 30 cm Flex Rule 15 mm Wide with JCSS Certificate	19026	224
Stainless Steel Rule Hard Chrome Finish 30 cm with JCSS Certificate	19015	224
Stainless Steel Rule Hard Chrome Finish 60 cm Flex Rule 15 mm Wide with JCSS Certificate	19027	224
Stainless Steel Rule Hard Chrome Finish 60 cm with JCSS Certificate	19016	224
Stainless Steel Rule Mini Hard Chrome Finish 15 cm	13242	33
Stainless Steel Rule Mini Polish Finish 15 cm	14249	33
Stainless Steel Rule Polish Finish 1 m	14044	30
Stainless Steel Rule Polish Finish 1 m with JCSS Certificate	19021	224
Stainless Steel Rule Polish Finish 1.5 m	14052	30
Stainless Steel Rule Polish Finish 1.5 m with JCSS Certificate	19065	224
Stainless Steel Rule Polish Finish 15 cm	14001	30
Stainless Steel Rule Polish Finish 15 cm with JCSS Certificate	19018	224
Stainless Steel Rule Polish Finish 2 m	14060	30

Stainless Steel Rule Polish Finish 2 m with JCSS Certificate	19066	224
Stainless Steel Rule Polish Finish 3 m	14079	30
Stainless Steel Rule Polish Finish 30 cm	14028	30
Stainless Steel Rule Polish Finish 30 cm with JCSS Certificate	19019	224
Stainless Steel Rule Polish Finish 4 m	14087	30
Stainless Steel Rule Polish Finish 5 m	14095	30
Stainless Steel Rule Polish Finish 6 m	14109	30
Stainless Steel Rule Polish Finish 60 cm	14036	30
Stainless Steel Rule Polish Finish 60 cm with JCSS Certificate	19020	224
Stainless Steel Rule Polish Finish S-101A 15 cm	21148	28
Stainless Steel Rule Polish Finish S-101C 30 cm	21156	28
Stainless Steel Rule Polish Finish S-101E 60 cm	21164	28
Stainless Steel Rule Polish Finish S-101F 1 m	21172	28
Stainless Steel Rule Polish Finish S-102G 1.5 m	21741	28
Stainless Steel Rule Polish Finish S-102H 2 m	21768	28
Stainless Steel Rule Polish Finish S-102I 3 m	23275	28
Stainless Steel Rule Polish Finish S-102J 4 m	23276	28
Stainless Steel Rule Polish Finish S-102K 5 m	23277	28
Stainless Steel Rule Polish Finish S-102L 6 m	23278	28
Stand Magnifier G 25 mm 6x	75763	193
Stand Magnifier P-1 65 mm 3x	75539	193
Stand Magnifier Y 123 mm 2x and 4x Double Focus	75659	194
Steel Sheet 10 x 20 cm 0.2 mm Thick with Adhesive 2 pc-pack	72200	212
Stem ϕ 6 for Dial Indicator	81370	221
Stem ϕ 8 for Dial Indicator	81371	221
Stick Thermometer Alcohol H-10 -20 - 105°C 45 cm Individually Packaged	72604	179
Stick Thermometer Alcohol H-15 -20 - 105°C 30 cm Bulk Packaged	72746	180
Stick Thermometer Alcohol H-2 0 - 105°C 30 cm Individually Packaged	72508	179
Stick Thermometer Alcohol H-2 0 - 200°C 30 cm Individually Packaged	72510	179
Stick Thermometer Alcohol H-2S 0 - 200°C 30 cm Bulk Packaged	72747	180
Stick Thermometer Alcohol H-3 -20 - 105°C 30 cm Individually Packaged	72511	179
Stick Thermometer Alcohol H-4 0 - 100°C 15 cm Individually Packaged	72514	179
Stick Thermometer Alcohol H-4S 0 - 100°C 15 cm Bulk Packaged	72748	180
Stick Thermometer Alcohol H-5 0 - 100°C 30 cm Individually Packaged	72547	179
Stick Thermometer Alcohol H-5S 0 - 100°C 30 cm Bulk Packaged	72749	180
Stick Thermometer Alcohol H-6 -30 - 50°C 30 cm Individually Packaged	72574	179
Stick Thermometer Alcohol H-6S -30 - 50°C 30 cm Bulk Packaged	72750	180
Stick Thermometer Alcohol H-7 -10 - 65°C 30 cm Individually Packaged	72577	179
Stick Thermometer Alcohol H-7S -10 - 65°C 30 cm Blue Bulk Packaged	72751	180
Stick Thermometer Alcohol H-8 -20 - 50°C 15 cm Individually Packaged	72579	179
Stick Thermometer Alcohol H-8S -20 - 50°C 15 cm Bulk Packaged	72752	180
Stick Thermometer Alcohol H-9 -10 - 50°C 15 cm x 2 pc-set Individually Packaged	72581	179
Stick Thermometer Mercury I -20 - 105°C 30 cm Individually Packaged	72516	179
Stick Thermometer Mercury I-15 -20 - 105°C 30 cm Bulk Packaged	72754	180
Stopper for Guide Rule for Screw Pitch Marking Tool/Multi	77395	122
Stopper for Suction Lifter Double A and Single B	81623	222
Stopper knob ① red for Telescopic Measure Two Directions	99755	214
Stopper knob ② yellow for Telescopic Measure Two Directions	99756	214
Stopper knob for Digital Vernier Caliper 150 - 300 mm	98767	215
Stopper knob for Mini Vernier Caliper 100 mm	99525	215
Stopper knob for Mini Vernier Caliper 70 mm	82890	215
Stopper knob for Vernier Caliper 1000 mm	98913	215
Stopper knob for Vernier Caliper 150 mm	99523	215
Stopper knob for Vernier Caliper 200 mm	99524	215

Parts List	Stopper knob for Vernier Caliper 450, 600 mm	98911	215
	Stopper lever ① red, shaft, screw set for Telescopic Measure One Direction	82100	214
	Stopper lever 1 red, shaft, screw set for Telescopic Measure One Direction II	81102	214
	Stopper lever ② yellow, shaft, screw set for Telescopic Measure One Direction	82101	214
	Stopper lever 2 yellow, shaft, screw set for Telescopic Measure One Direction II	81103	214
	Stopper screw for Rule Stopper 1, 1.5, 2 m	82873	214
	Stopper screw for Rule Stopper 15, 30, 60 cm	82415	214
	Stopper screw for Tripod with Handle A	81570	217
	Stopper screw on adjustment core rail for Tripod Spherical Head	97533	217
	Stopper screw, bolt, metal washer set for Free Angle One-touch and Multi	99602	220
Japan Calibration Service System (JCS)	Stopper screw, bolt, metal washer set for Mini Free Angle II, Justy II and Neo	85959	220
	Stopper screw, bolt, metal washer set for Mini Free Angle Quick Adjust and Justy Quick Adjust	99604	220
	Stopper screws complete set with knobs for Magnetic Stand A and A-2	81377	221
	Storage case for Auto Level SA-24A and 28A	73844	217
	Stowed High Magnification Model C Double Lens 10x/20x	75523	193
	Stowed High Magnification Model D Triplet Lens 3.5x	75531	193
	Stowed High Magnification Model with Chain I 10x	75765	193
	Stowed High Magnification Model with Chain J 3x/4x/5x	75766	193
	Strong Color Magnets with Yoke φ 20 Blue 6 pc-pack	72077	207
	Strong Color Magnets with Yoke φ 20 Red 6 pc-pack	72052	207
Etching	Strong Color Magnets with Yoke φ 20 White 6 pc-pack	72053	207
	Strong Color Magnets with Yoke φ 20 Yellow 6 pc-pack	72056	207
	Strong Color Magnets with Yoke φ 25 Blue 5 pc-pack	72078	207
	Strong Color Magnets with Yoke φ 25 Red 5 pc-pack	72057	207
	Strong Color Magnets with Yoke φ 25 White 5 pc-pack	72058	207
	Strong Color Magnets with Yoke φ 25 Yellow 5 pc-pack	72061	207
	Strong Color Magnets with Yoke φ 30 Blue 4 pc-pack	72079	207
	Strong Color Magnets with Yoke φ 30 Blue 6 pc-pack in Vinyl Bag	71830	208
	Strong Color Magnets with Yoke φ 30 Red 4 pc-pack	72062	207
	Strong Color Magnets with Yoke φ 30 White 4 pc-pack	72063	207
Sheet Heaters	Strong Color Magnets with Yoke φ 30 White 6 pc-pack in Vinyl Bag	71829	208
	Strong Color Magnets with Yoke φ 30 Yellow 4 pc-pack	72066	207
	Strong Color Magnets with Yoke φ 30 Yellow 6 pc-pack in Vinyl Bag	71831	208
	Strong Color Magnets with Yoke φ 40 Blue 3 pc-pack	72080	207
	Strong Color Magnets with Yoke φ 40 Red 3 pc-pack	72067	207
	Strong Color Magnets with Yoke φ 40 Red 6 pc-pack in Vinyl Bag	71832	208
	Strong Color Magnets with Yoke φ 40 White 3 pc-pack	72068	207
	Strong Color Magnets with Yoke φ 40 White 6 pc-pack in Vinyl Bag	71833	208
	Strong Color Magnets with Yoke φ 40 Yellow 3 pc-pack	72071	207
	Strong Color Magnets with Yoke φ 50 Blue 2 pc-pack	72081	207
Custom-Made Items	Strong Color Magnets with Yoke φ 50 Red 2 pc-pack	72072	207
	Strong Color Magnets with Yoke φ 50 White 2 pc-pack	72073	207
	Strong Color Magnets with Yoke φ 50 Yellow 2 pc-pack	72076	207
	Strong Color Magnets with Yoke φ 20 Blue 6 pc-pack in Vinyl Bag	71826	208
	Strong Color Magnets with Yoke φ 20 Red 6 pc-pack in Vinyl Bag	71824	208
	Strong Color Magnets with Yoke φ 20 White 6 pc-pack in Vinyl Bag	71825	208
	Strong Color Magnets with Yoke φ 20 Yellow 6 pc-pack in Vinyl Bag	71827	208
	Strong Color Magnets with Yoke φ 30 Red 6 pc-pack in Vinyl Bag	71828	208
	Strong Color Magnets with Yoke φ 40 Blue 6 pc-pack in Vinyl Bag	71834	208
	Strong Color Magnets with Yoke φ 40 Yellow 6 pc-pack in Vinyl Bag	71835	208
Name Printing	Stud Finder Smart 25 mm	78585	144
	Stud Finder Smart 35 mm	78586	144
	Stud Finder Smart 45 mm	78574	144
	Stud Finder Smart with Magnet 35 mm	78592	144
	Stud Sensor Basic	78575	145
	Stud Sensor EX	78657	145
	Stud Sensor HG	78577	145
	Stud Sensor HG-Center Finder	78578	145
	Stud Sensor Super	78576	145
	Suction Lifter Double A	74483	161
Index Item Code ➔ Description	Suction Lifter Double B One-touch	74484	161
	Suction Lifter Single A	74481	161
	Suction Lifter Single B	74482	161
	Support plate for L-Angle with Support Plate 1 m	77893	219
	Support plate for L-Angle with Support Plate 45 cm	77894	219
	Support plate for L-Angle with Support Plate 60 cm	77884	219
	Support plate installing screw for L-Angle with Support Plate	84231	219
	Surveying Pin Pole (Steel) φ 4 30 cm	76927	68
	Surveying Pin Pole (Steel) φ 4 60 cm	76928	68
	Surveying Pin Pole (Steel) φ 6 30 cm	76976	68
Index Item Code ➔ Description	Surveying Pin Pole (Steel) φ 6 50 cm	76977	68
	Surveying Pin Pole (Steel) φ 6 60 cm	76978	68
	Surveying Pin Pole (Steel) φ 8 1 m	76979	68
	Surveying Pole Aluminum 2 m	76988	67
	Surveying Pole Aluminum 2 m 10 pc-set	76996	67
	Surveying Pole Aluminum 2 m Steps	76985	67
	Surveying Pole Wood 2 m	76984	67

T

Description	Item Code	Page
Tape Measure H-132 Free Type JIS	78002	62
Tape Measure H-163 Free Type JIS	78007	62
Tape Measure RIGHT GEAR 19-5.5 m JIS	80862	61
Tape Measure RIGHT GEAR 19-5.5 m/shaku	80863	61
Tape Measure RIGHT GEAR 25-5.5 m JIS	80864	61
Tape Measure RIGHT GEAR 25-5.5 m/shaku	80866	61
Tape Measure RIGHT GEAR 25-7.5 m JIS	80867	61
Tape Measure RIGHT GEAR 25-7.5 m/shaku	80855	61
Tape Measure RIGHT GEAR with Magnetic Hook 25-5.5 m JIS	80865	61
Tape Measure RIGHT GEAR with Magnetic Hook 25-7.5 m JIS	80868	61
Tape Measure SMART GEAR 19-5.5 m	80880	62
Tape Measure SMART GEAR 19-5.5 m/shaku	80881	62
Tape Measure SMART GEAR 25-5.5 m	80882	62
Tape Measure SMART GEAR 25-5.5 m/shaku	80883	62
Tape Measure SMART GEAR with Magnetic Hook 25-5.5 m	72762	62
Tape Measure TOUGH GEAR Automatic Stop 19-5.5 m JIS	80814	60
Tape Measure TOUGH GEAR Automatic Stop 25-5.5 m JIS	80815	60
Tape Measure TOUGH GEAR Automatic Stop 25-5.5 m/shaku	80816	60
Tape Measure TOUGH GEAR Automatic Stop with Holder 25-5.5 m/shaku	80813	60
Tape Measure TOUGH GEAR HG 25-5.5 m JIS	80821	59
Tape Measure TOUGH GEAR HG 25-5.5 m/shaku	80822	59
Tape Measure TOUGH GEAR HG 25-7.5 m JIS	80824	59
Tape Measure TOUGH GEAR HG with Holder 25-5.5 m/shaku	80818	59
Tape Measure TOUGH GEAR HG with Magnetic Hook 25-5.5 m JIS	80823	59
Tape Measure TOUGH GEAR SD 25-5.5 m JIS	80874	60
Tape Measure TOUGH GEAR SD 25-5.5 m/shaku	80875	60
Tape Measure TOUGH GEAR SD 25-7.5 m JIS	80877	60
Tape Measure TOUGH GEAR SD with Holder 25-5.5 m JIS	80870	60

Tape Measure TOUGH GEAR SD with Holder 25-5.5 m/shaku	80871	60
Tape Measure TOUGH GEAR SD with Holder 25-7.5 m JIS	80873	60
Tape Measure TOUGH GEAR SD with Magnetic Hook 25-5.5 m JIS	80876	60
Tape Measure TOUGH GEAR SD with Magnetic Hook and Holder 25-5.5 m JIS	80872	60
Taper Gauge Double for Clearance, Hole Diameter, Length 1 - 15 mm	62620	154
Taper Gauge No.700 A 1 - 15 mm	62600	154
Taper Gauge No.700 B 15 - 30 mm	62605	154
Taper Gauge No.700 C 30 - 45 mm	62610	154
Taper Gauge No.700 D 45 - 60 mm	62615	154
Taper Gauge with Metal Case 1 - 15 mm	62603	154
Taper Gauge with Rule 1 - 15 mm	62612	154
Telescopic Leveling Staff 5 m 3 Steps	76973	66
Telescopic Leveling Staff 5 m 4 Steps	76930	66
Telescopic Leveling Staff II 3 m 3 Steps	73264	66
Telescopic Leveling Staff II 5 m 3 Steps	73265	66
Telescopic Leveling Staff II 5 m 4 Steps	73266	66
Telescopic Leveling Staff II 5 m 5 Steps	73267	66
Telescopic Leveling Staff II 7 m 5 Steps	73268	66
Telescopic Measure One Direction II A 3 shaku 2 sun	65190	41
Telescopic Measure One Direction II AB 6 shaku 6 sun	65191	41
Telescopic Measure One Direction A 3 shaku 2 sun	65183	41
Telescopic Measure One Direction AB 6 shaku 3 sun	65184	41
Telescopic Measure One Direction B 9 shaku 3 sun	65185	41
Telescopic Measure One Direction C 12 shaku	65186	41
Telescopic Measure One Direction D 13 shaku 5 sun	65187	41
Telescopic Measure One Direction E 15 shaku 5 sun	65188	41
Telescopic Measure One Direction II B 9 shaku 3 sun	65192	41
Telescopic Measure One Direction II C 12 shaku	65193	41
Telescopic Measure One Direction II D 13 shaku 5 sun	65194	41
Telescopic Measure One Direction II E 15 shaku 5 sun	65195	41
Telescopic Measure Two Directions A 3 shaku 2 sun	65160	42
Telescopic Measure Two Directions A 95 cm	65107	42
Telescopic Measure Two Directions AB 190 cm	65108	42
Telescopic Measure Two Directions AB 6 shaku 3 sun	65161	42
Telescopic Measure Two Directions B 280 cm	65109	42
Telescopic Measure Two Directions B 9 shaku 3 sun	65162	42
Telescopic Measure Two Directions C 12 shaku	65163	42
Telescopic Measure Two Directions C 360 cm	65105	42
Telescopic Measure Two Directions D 13 shaku 5 sun	65164	42
Telescopic Measure Two Directions D 400 cm	65106	42
Template TB-1 Circle Medium	66004	201
Template TB-4 Circle Small	66005	201
Template TD-1 Furniture Large 1/50	66007	202
Template TD-2 Furniture Small 1/100	66008	202
Template TD-4 Architecture 1/100 and 1/200	66010	202
Template TE-10 Number	66017	201
Template TE-11 Number	66018	201
Template TE-5 Number/Alphabet	66013	201
Template TE-6 Number/Alphabet	66014	201
Template TE-7 Number/Alphabet	66015	201
Template TE-9 Number	66016	201
Template TG-3 Oval	66020	201
Template TH-1 General Shape Small	66021	202
Template TH-2 General Shape Small	66022	202

Template TH-4 General Shape Medium	66024	202
Template TH-5 General Shape Medium	66025	202
Template TJ-1 Bolt and Nut	66026	202
Template TK-1 Finish Mark	66027	202
Template TL-1 Arrow	66029	202
Template TP-1 Corner	66031	201
Template TQ-1 Japanese and Roman Letter	66033	202
Template TS-A 3 pc-pack Card-size Set	66034	202
Template with Edge TA-1E Circle Medium	66002	201
Template with Edge TA-4E Circle Small	66003	201
Thermo/Hygrometer and Discomfort Index Meter R-1 Green	70480	165
Thermo/Hygrometer and Discomfort Index Meter R-2 Green	70500	165
Thermo/Hygrometer Black and White	48929	166
Thermo/Hygrometer Blue	48932	166
Thermo/Hygrometer ECO White	48975	166
Thermo/Hygrometer F 15 cm	72591	163
Thermo/Hygrometer for Environmental Safety 6.5 cm Blue	70516	164
Thermo/Hygrometer for Environmental Safety F-4L 15 cm Blue	70503	164
Thermo/Hygrometer for Environmental Safety F-4M 10 cm Blue	70508	164
Thermo/Hygrometer for Heatstroke Warning F-3L II 15 cm White	70505	164
Thermo/Hygrometer for Heatstroke Warning F-3M 10 cm White	70507	164
Thermo/Hygrometer for Heatstroke Warning F-3S 6.5 cm White	70515	164
Thermo/Hygrometer for Room Conditioning F-2L 15 cm Blue	70501	164
Thermo/Hygrometer for Room Conditioning F-2M 10 cm Blue	70506	164
Thermo/Hygrometer for Room Conditioning F-2S 6.5 cm Blue	70514	164
Thermo/Hygrometer G 15 cm	72605	163
Thermo/Hygrometer Green	72615	166
Thermo/Hygrometer P-2 12 cm White	70380	165
Thermo/Hygrometer Q-1 15 cm Blue	70494	163
Thermo/Hygrometer Q-1 15 cm Gray	70495	163
Thermo/Hygrometer Q-2 10 cm Blue	70496	163
Thermo/Hygrometer Q-2 10 cm Gray	70497	163
Thermo/Hygrometer Q-3 6.5 cm Blue	70498	163
Thermo/Hygrometer Q-3 6.5 cm Gray	70499	163
Thermo/Hygrometer U-1 10 cm	72691	163
Thermo/Hygrometer U-3 6.5 cm	72669	163
Thermo/Hygrometer W-1 White	70510	165
Thermo/Hygrometer White and White	48927	166
Thermometer "Petit Thermo Square" Vertical 12 cm Blue	48707	169
Thermometer "Petit Thermo Square" Vertical 12 cm White	48705	169
Thermometer "Petit Thermo Square" Vertical 12 cm Yellow	48706	169
Thermometer "Petit Thermo Square" Vertical 20 cm Blue	48797	169
Thermometer "Petit Thermo Square" Vertical 20 cm White	48795	169
Thermometer "Petit Thermo Square" Vertical 20 cm Yellow	48796	169
Thermometer "Petit Thermo Square" with Magnet Horizontal 13.5 cm Blue	48787	169
Thermometer "Petit Thermo Square" with Magnet Horizontal 13.5 cm White	48785	169
Thermometer "Petit Thermo Square" with Magnet Horizontal 13.5 cm Yellow	48786	169
Thermometer "Petit Thermo Square" with Magnet Vertical 13.5 cm Blue	48717	169
Thermometer "Petit Thermo Square" with Magnet Vertical 13.5 cm White	48715	169
Thermometer "Petit Thermo Square" with Magnet Vertical 13.5 cm Yellow	48716	169
Thermometer "Petit Thermo Twin" for Outside and Inside	72957	169
Thermometer Aluminum 45 cm	72991	168
Thermometer Aluminum 60 cm	72992	168
Thermometer Aluminum 75 cm	72993	168

Parts List	Japan Calibration Service System (JCS)	Etching	Sheet Heaters	Custom-Made Items	Name Printing	Index Item Code Description ➡	Index Description Item Code ➡
------------	--	---------	---------------	-------------------	---------------	--	--

Thermometer and Hygrometer Pair ST-4 4.5 cm	72674	167
Thermometer C	72524	168
Thermometer C-2	72526	168
Thermometer C-5	72590	168
Thermometer for Aquarium L	72583	176
Thermometer for Bath B Blue	72648	175
Thermometer for Bath B Pink	72760	175
Thermometer for Bath B-10 Pink	73095	175
Thermometer for Bath B-10 Purple	73096	175
Thermometer for Bath B-10 White	73097	175
Thermometer for Bath B-3	72651	175
Thermometer for Bath B-8	72725	175
Thermometer for Bath B-9 Green and White	73051	175
Thermometer for Bath B-9 White and Pink	73052	175
Thermometer for Frying Oil Chopstick Model	72967	175
Thermometer for Ground Temperature O-2 Blue	72630	181
Thermometer for Ground Temperature O-2 White	72622	181
Thermometer for Ground Temperature O-2 Yellow	72627	181
Thermometer for Ground Temperature O-3 Mini A 3 pc-pack (Red, Orange, Purple)	72623	181
Thermometer for Ground Temperature O-3 Mini B 3 pc-pack (Black, Blue, Green)	72633	181
Thermometer for Ground Temperature with Air Temperature O-4 Blue	72639	181
Thermometer for Ground Temperature with Air Temperature O-4 White	72624	181
Thermometer for Ground Temperature with Air Temperature O-4 Yellow	72636	181
Thermometer for Refrigerator A-3 5 cm	72703	174
Thermometer for Refrigerator with Magnet A	72532	174
Thermometer for Refrigerator with Magnet A-4 Remote-reading	72692	174
Thermometer S-1 10 cm	72689	166
Thermometer S-3 6.5 cm	72667	166
Thermometer S-5 3.5 cm	72675	166
Thermometer V-1 0 - 100°C ϕ 3.5 x 13 cm	72960	167
Thermometer V-2 -20 - 60°C ϕ 3.5 x 13 cm	72610	167
Thermometer V-3 -20 - 100°C ϕ 6 x 90 cm	72611	167
Thermometer V-4 0 - 200°C Black ϕ 8 x 20 cm	73013	167
Thermometer V-4 0 - 200°C White ϕ 8 x 20 cm	73012	167
Thermometer Wood 45 cm	75919	168
Thermometer Wood 60 cm	75920	168
Thermometer Wood 90 cm	72571	168
Thermometer Wood M-023	48481	168
Thin stopper screw, bolt, metal washer set for Mini Free Angle Justy and Free Angle	99251	220
Thread holding guide for Handy Ink Line Marker SUMIWAZA	83653	218
Thread Reel II Auto-rewind Red	77446	120
Thread Reel II Hand-rewind Green	77456	120
Threader for Handy Ink Line Marker Mini α	80790	218
Tile Percussion Hammer A-1	74102	146
Tile Percussion Hammer A-2	74103	146
Tile Percussion Hammer A-3	74104	146
Tile Percussion Hammer A-4	74105	146
Tile Percussion Hammer B-1	74106	146
Tip with superhard chip for Auto Punch L	73992	222
Tip with superhard chip for Auto Punch L with Flat Grip to Prevent Rolling	81315	222
Tip with superhard chip for Auto Punch M	73997	222
Tip with superhard chip for Auto Punch M with Flat Grip to Prevent Rolling	81311	222
Toe for Laser ROBO Neo BRIGHT, E Sensor and X line	80781	217
Transparent Case with Zipper A1	78197	203

Transparent Case with Zipper A2	78198	203
Traverse Surveying Pin Pole (Hard Steel) ϕ 3.2 50 cm	76982	68
Triangle Rotation Scale 15 cm	74980	200
Triangle Rotation Scale 15 cm/shaku	74979	200
Triangle Rotation Scale 30 cm	74940	200
Triangle Rotation Scale 30 cm/shaku	74941	200
Triangle Scale A-10 10 cm	70777	199
Triangle Scale for Architects B-15 15 cm	74961	199
Triangle Scale for Architects B-30 30 cm	74962	199
Triangle Scale for Architects, Shipbuilders D-30 30 cm	74987	199
Triangle Scale for Microcopy C-15 15 cm	70802	199
Triangle Scale for Microcopy C-30 30 cm	70803	199
Triangle Scale for Real-estate Surveyors A-15 15 cm	74969	199
Triangle Scale for Real-estate Surveyors A-30 30 cm	74950	199
Triangle Scale for Shipbuilders E-30 30 cm	74988	199
Tripod Flat Head	76690	113
Tripod Short Model	77304	113
Tripod Spherical Head	76654	113
Tripod with Handle 1.5 m	76676	113
Tripod with Handle 3 m	76952	113
Tripod with Handle A	76629	113
Tripod with Handle B	76827	113
Tripod with Handle C	76866	113
Try Square Aluminum Base without Graduations 1 m	74120	50
Try Square Aluminum Base without Graduations 20 cm	74110	50
Try Square Aluminum Base without Graduations 25 cm	74111	50
Try Square Aluminum Base without Graduations 30 cm	74112	50
Try Square Aluminum Base without Graduations 35 cm	74113	50
Try Square Aluminum Base without Graduations 40 cm	74114	50
Try Square Aluminum Base without Graduations 45 cm	74115	50
Try Square Aluminum Base without Graduations 50 cm	74116	50
Try Square Aluminum Base without Graduations 60 cm	74117	50
Try Square Aluminum Base without Graduations 70 cm	74118	50
Try Square Aluminum Base without Graduations 90 cm	74119	50
T-shaped Magnet C ϕ 25	73520	206
T-shaped Magnet D ϕ 40	73539	206
T-shaped Magnet E ϕ 50	73547	206
T-shaped Scale Wood 60 cm	76759	197

U

Description	Item Code	Page
Ultra Strong Magnetic Hanger Circle D	73510	210
Ultra Strong Magnetic Hanger Square C	73500	210
Undercut Gauge	58695	149
Upper cap, screw set for Telescopic Measure One Direction	82048	214
Upper fixing screw, spacer, spring set for Wind-resistant Plumb	77556	218
Upper protective cap for L-Angle Plus	93311	219
U-shaped Magnet A-1	73530	211
U-shaped Magnet A-2	73532	211
U-shaped Magnet B-1	73531	211
U-shaped Magnet B-2	73533	211

V

Description	Item Code	Page
Vernier Caliper 1000 mm	19922	53
Vernier Caliper 150 mm	19899	53
Vernier Caliper 150 mm with JCSS Certificate	19051	224
Vernier Caliper 200 mm	19912	53
Vernier Caliper 200 mm with JCSS Certificate	19052	224
Vernier Caliper 300 mm	19913	53
Vernier Caliper 300 mm with JCSS Certificate	19053	224
Vernier Caliper 450 mm	19920	53
Vernier Caliper 600 mm	19921	53
Vernier Caliper Plastic Body 100 mm	19515	54
Vernier Caliper Plastic Body 70 mm	19514	54
Vial cover for Slope Level	47049	216

W

Description	Item Code	Page
Water Level A with 15 m Hose	76644	93
Water tank for Psychrometer E-2	46845	222
Waterproof Chalkboard Marking Pen White	78505	76
Waterproof Digital Thermometer for 2 points G-2 Remote-reading	73046	172
Waterproof Digital Thermometer G-1 Maximum and Minimum Remote-reading	73045	172
Waterproof Digital Thermometer with Remote Probe H-1	73080	172
Waterproof Digital Thermometer with Remote Probe H-2	73081	172
Wedge for I-Clamp One-touch	99243	220
Welding Gauge A	58691	149
Welding Guide Rule with Magnet 1 m	77888	148
Welding Magnet L	72295	205
Welding Magnet M	72294	205
Welding Magnet S	72293	205
Whiteboard Marking Pen Black	78503	76
Whiteboard Marking Pen Black Fine-tip with Eraser and Magnet	78506	76
Whiteboard Marking Pen Red	78504	76
Wind-resistant Plumb II with Magnetic Damper	77524	123
Wind-resistant Plumb Basic	77554	123
Wireless Thermometer with Remote Twin Probe A Maximum and Minimum External Antenna Type	73441	173
Wireless Thermometer with Remote Twin Probe A Maximum and Minimum Waterproof	73241	173



JAG-MAR Sp. z o.o. | ul. Złota 36 | 62-800 Kalisz | tel. 62 766 31 01 | www.jag-mar.pl | biuro@jag-mar.pl



7778 33ZJ18 J